
CONSTRUCTION DRAWINGS FOR: 101 & 115 REDFORD PLACE DRIVE

ROLESVILLE, NORTH CAROLINA

- OWNER:
 REDFORD 101, LLC
 1000 CRESCENT GREEN, SUITE 101
 CARY, NC 27518
- DEVELOPER:
 ROGERS ROAD 3415, LLC
 (JONATHAN BOES)
 1000 CRESCENT GREEN
 CARY, NC 27518
 (O) 919.247.0497
- ENGINEER:
 PABST DESIGN GROUP, PA
 404-B GLENWOOD AVE.
 RALEIGH, NC 27603
 (O) 919.848.4399
 (F) 919.848.4395
- ARCHITECT: REDFOOT STUDIO ARCHITECTURE, PC 2515 SAXAPAHAW BETHLEHEM CHURCH RD GRAHAM, NC 27253 (O) 919.931.7134
- SURVEYOR:
 NEWCOMB LAND SURVEYORS, PLLC
 7008 HARPS MILL RD STE 105
 RALEIGH, NC 27615
 (O) 919.847.1800
- GENERAL CONTRACTOR
 CHAMBLISS & RABIL CONTRACTORS INC.
 (CHRIS DOUGHERTY)
 3614 HAWORTH DR
 RALEIGH, NC 27609
 (O) 919.355.0567
 (C) 252.883.8739
 (F) 252.442.9487



	INDEX TO PLANS
C-0.0	COVER SHEET
	BOUNDARY & TOPOGRAPHIC SURVEY
C-1.0	EXISTING CONDITION & DEMOLITION PLAN
C-2.0	SITE LAYOUT PLAN
C-3.0	UTILITY PLAN
C-4.0	GRADING & STORM DRAINAGE PLAN
C-5.0	EROSION CONTROL PLAN (PHASE 1)
C-5.1	EROSION CONTROL PLAN (PHASE 2)
C-6.0	BIORETENTION PLAN & PROFILE
C-6.1	UNDERGROUND DETENTION PLAN & PROFILE
C-6.2	BMP DETAIL SHEET
C-7.0	ROAD IMPROVEMENT PLAN - REDFORD PLACE DR
D-1.0	SITE DETAIL SHEET
D-1.1	SITE DETAIL SHEET
D-1.2	SITE DETAIL SHEET
D-2.0	UTILITY DETAIL SHEET
D-2.1	UTILITY DETAIL SHEET
D-2.2	UTILITY DETAIL SHEET
D-3.0	STORM DRAINAGE DETAIL SHEET
D-4.0	EROSION CONTROL DETAIL SHEET
D-4.1	EROSION CONTROL DETAIL SHEET
D-4.2	EROSION CONTROL DETAIL SHEET
L-1.0	LANDSCAPE PLAN
L-1.1	LANDSCAPE DETAIL SHEET
SLI-1.0	LIGHTING PLAN
A1.0	BUILDING ELEVATIONS
A1.1	BUILDING ELEVATIONS

MUNICIPAL CONTACT LIST • PLANNING - TOWN OF ROLESVILLE PLANNING DEPARTMENT DANNY JOHNSON - PLANNING DIRECTOR **502 SOUTHTOWN CIRCLE** ROLESVILLE, NC 27571 (O) 919.554.6517 • STREETS AND HIGHWAYS - NCDOT **DIVISION 5, DISTRICT 1** SEAN BRENNAN - SENIOR ASSISTANT DISTRICT ENGINEER 4009 DISTRICT DRIVE **RALEIGH, 27607** (O) 919.733.7759 spbrennan@ncdot.gov WAKE COUNTY INSPECTIONS & PERMITS DEPARTMENT **KENNETH DORMAN - BUILDING INSPECTOR** (C) 919.524.4623 **EMERSON PRIVETTE - TRADES INSPECTOR** (C) 919.524.4598 (O) 919.856.6118 EROSION CONTROL & STORMWATER - WAKE COUNTY WAKE COUNTY GOVERNMENT - WATER QUALITY **JEEVAN NEUPANE** P.O. BOX 550 RALEIGH, NC 27602 (O) 919.819.8907 jeevan.neupane@wakegov.com WATER AND SEWER - CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT TIM BEASLEY - DEPARTMENT REVIEW 222 W. HARGETT STREET RALEIGH, NC 27601 (O) 919.996.2176 timothy.beasley@raleighnc.gov WATER AND SEWER - TOWN OF ROLESVILLE COLEJENEST & STONE, PA LEWIS HARDEE, PE, PLS - PROJECT MANAGER 131 1/2 S WILMINGTON STREET, SUITE 200

RALEIGH, NC 27601 (O) 919.645.5964

(C) 252.908.5722

EROSION CONTROL, STORMWATER AND FLOODPLAIN MANAGEMENT
APPROVED
EROSION CONTROL S
STORMWATER MGMT. S
FLOOD STUDY S
DATE
WAKE COUNTY NORTH CAROLINA ENVIRONMENTAL CONSULTANT SIGNATURE

ISSUED FOR CONSTRUCTION

NOTE(s):
ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, WAKE COUNTY AND NCDOT STANDARDS AND SPECIFICATIONS.

1 REVISED PER TOR COMMENTS
2 REVISED PER TOR COMMENTS
3 REVISED PER TOR COMMENTS
4 REVISED PER WAKE CO COMMENTS
4 REVISED PER CLIENT

SHEET **C-0.0**

PROJECT NUMBER
449-19

DATE: 7.31.2019

PROJECT ENGINEER:
PDP


PROJECT CADD DESIGNER:

5 REDFORD PLACE DRIVE ROLESVILLE, WAKE COUNTY, NORTH CAROLINA CONSTRUCTION DRAWINGS

CONSTRUCTION BRAWINGS

COVER SHEET

101 & 115



REFERENCES:

WILL BOOK 2772, PAGE 00-E BOOK OF MAPS 1992, PAGE 41 BOOK OF MAPS 2003, PAGE 435 *OTHERS SHOWN HEREON

LEGEND and NOMENCLATURE

SYM	BOLS	LINETYPE	<u>S</u>
0	Ex. iron pipe/rod or nail	— x —	- Fence
	Ex. concrete monument	ou	 Overhead utility
•	New iron pipe	W	- Water
0	Calculated point	SS	- Sanitary sewer
	Cable pedestal	SD	- Storm drain
	Telephone pedestal	4 D D D E \ (1.4	TIONIO
E	Electric pedestal	ABBREVIA	TIONS
E	Fiber-optic marker	DB	Deed Book
S	Traffic signal box	PB or BM	Plat Book / Book of Maps
0	Water meter	FFE	Finished floor elevation
D	Fire hydrant	PG	Page
\bowtie	Valve (water or gas)	S.F.	Square feet
(S) (9)	Sanitary sewer manhole	AC.	Acres
0	Sanitary sewer cleanout	R/W	Right-of-way
\boxtimes	HVAC	NCSR	North Carolina State Route
0	Drainage inlet (w/ grate)	NCDOT	North Carolina Dept. of Transportation
0	Storm drain manhole	COV.	Covered
റ്	Utility pole	EX.	Existing
^	Lamp post	RCP	Reinforced concrete pipe
-Ã-	Signal pole	PVC	Polyvinyl chloride pipe
Ÿ	Guy wire	P/L	Property line
~	Guy wile	AG	Above ground

Sign post

1) All distances are horizontal ground distances in u.s. survey feet unless otherwise noted

Below ground

- 2) This survey does not include nor depict any environmental evaluations.
- 3) Field survey performed June 29 & July 11, 2019.
- 4) Surveyor has made no investigation or independent search for easements of record, encumbrances, restrictive covenants, ownership title evidence or any other facts that an accurate and current title search may disclose.
- 5) The locations of underground utilities as shown hereon are based on aboveground structures and aboveground visual evidence. Locations of underground utilities/structures may vary from location shown hereon. Additional buried utilities/structures may be encountered. No excavations were made during the progress of this survey to locate buried
- 6) Subject properties are not located within a special flood hazard zone per FEMA Flood Insurance Rate Map (FIRM) #3720175800J, effective date May 2, 2006.
- 7) The State Plane Coordinates for this project were produced with RTK GPS observations and processed using the North Carolina VRS network. The network positional accuracy of the derived positional information is ±0.07'.

Horizontal Datum = NAD 83 / 2011 Vertical Datum = NAVD 88

THIS SURVEY IS OF AN EXISTING PARCEL OR PARCELS OF LAND OR ONE OR MORE EXISTING EASEMENTS AND DOES NOT CREATE A NEW STREET OR CHANGE

l, Justin L. Luther, certify that this plat was drawn under my supervision from an actual survey made under my supervision from references as noted on said plat; that the boundaries not surveyed are clearly indicated as drawn from information as indicated under references; that the ratio of precision or positional accuracy as calculated is greater than 1:10,000; that this plat was prepared in accordance with G.S. 47-30 as amended.

Witness my original signature, license number and seal this day of ________, 2019.

Professional Land Surveyor (L-5107)






INV.: +/-421.9'

CURB INLET (RIM: 423.74' INV.IN: 420.89' INV.OUT: 420.99'

101 REDFORD




BOUNDARY & TOPOGRAPHIC SURVEY

WAKE FOREST TOWNSHIP WAKE COUNTY


PROPERTIES OF MYRTLE R. WALL, HEIRS

NORTH CAROLINA

NC GRID NORTH (NAD 83/2011)



NEWCOMB land surveyors, pllc, 7008 Harps Mill Road, Ste. 105, Raleigh, NC 27615, (919) 847-1800, NC License #P-0203



DEMOLITION NOTES


- . THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL LOCAL AND STATE PERMITS REQUIRED FOR DEMOLITION WORK.
 - 2. THE CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE OWNER AND/OR ENGINEER FOR ANY AND ALL INJURIES AND/OR DAMAGES TO PERSONNEL, EQUIPMENT AND/OR EXISTING FACILITIES IN THE DEMOLITION AND
 - . EXISTING CONDITIONS AS DEPICTED ON THESE PLANS ARE GENERAL AND ILLUSTRATIVE IN NATURE AND DO NOT INCLUDE MECHANICAL, ELECTRICAL AND MISCELLANEOUS STRUCTURES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO EXAMINE THE SITE AND BE FAMILIAR WITH EXISTING CONDITIONS PRIOR TO BIDDING ON THE DEMOLITION WORK FOR THIS PROJECT. IF CONDITIONS **ENCOUNTERED DURING EXAMINATION ARE SIGNIFICANTLY DIFFERENT THAN** THOSE SHOWN, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY.
 - 4. ALL EXISTING ABOVE AND BELOW GROUND STRUCTURES WITHIN THE LIMITS OF NEW CONSTRUCTION SHALL BE RAZED UNLESS NOTED OTHERWISE WITHIN THIS CONSTRUCTION SET, ARCHITECTURAL PLANS AND/OR PROJECT SPECIFICATIONS. THIS INCLUDES FOUNDATION SLABS, WALLS, AND FOOTINGS
 - . ALL DEMOLITION WASTE AND CONSTRUCTION DEBRIS SHALL BE REMOVED BY THE CONTRACTOR AND DISPOSED OF IN A STATE APPROVED WASTE SITE AND IN ACCORDANCE WITH ALL LOCAL AND STATE CODES AND PERMIT REQUIREMENTS
 - 6. ALL UTILITY REMOVAL, RELOCATION, CUTTING, CAPPING AND/OR ABANDONMENT SHALL BE COORDINATED WITH THE APPROPRIATE UTILITY
 - . THE BURNING OF CLEARED MATERIAL AND DEBRIS SHALL NOT BE ALLOWED UNLESS CONTRACTOR GETS WRITTEN AUTHORIZATION FROM THE LOCAL
- 8. MUNICIPAL AND UTILITY CONTACTS ARE LISTED ON COVER SHEET C-0.0.
- 9. EROSION AND SEDIMENTATION CONTROL MEASURES AROUND AREAS OF DEMOLITION SHALL BE INSTALLED PRIOR TO INITIATION OF DEMOLITION
- 10.ASBESTOS OR HAZARDOUS MATERIALS, IF FOUND ON SITE, SHALL BE REMOVED BY A LICENSED HAZARDOUS MATERIALS CONTRACTOR. CONTRACTOR SHALL NOTIFY OWNER IMMEDIATELY IF HAZARDOUS MATERIALS ARE
- 11.CONTRACTOR SHALL PROTECT ALL CORNER PINS, MONUMENTS, PROPERTY CORNERS, AND BENCHMARKS DURING DEMOLITION ACTIVITIES. IF DISTURBED, CONTRACTOR SHALL HAVE DISTURBED ITEMS RESET BY A LICENSED SURVEYOR AT NO ADDITIONAL COST TO THE OWNER.
- 12.CONTRACTOR SHALL ADHERE TO ALL LOCAL, STATE, FEDERAL, AND OSHA REGULATIONS WHEN OPERATING DEMOLITION EQUIPMENT AROUND UTILITIES.
- 13.CONTRACTOR SHALL PROTECT AT ALL TIMES ADJACENT STRUCTURES AND ITEMS FROM DAMAGE DUE TO DEMOLITION ACTIVITIES.
- 14.ALL DEMOLITION WORK SHALL BE PERFORMED WITH "DUE CARE AND DILIGENCE" SO AS TO PREVENT THE ARBITRARY DESTRUCTION OR INTERRUPTION OF CONCEALED UTILITIES WHICH ARE INTENDED TO REMAIN IN USE AND THE ROUTING OF WHICH COULD NOT BE PREDETERMINED UNTIL DEMOLITION WAS STARTED. ALL SUCH DISCOVERIES OF UTILITIES DURING THE DEMOLITION PROCESS WHICH ARE IN A LOCATION DIFFERENT FROM THAT INDICATED OR ARE UNIDENTIFIED, SHALL BE REPORTED TO THE OWNER, ENGINEER AND ARCHITECT BEFORE REMOVAL FOR FINAL DISPOSITION.
- 15.ALL UTILITIES OR STRUCTURES NOT DESIGNATED FOR REMOVAL OR MODIFICATION ARE TO REMAIN AND BE PROTECTED FROM DAMAGE.
- 16.EXISTING PAVEMENT, CURB AND GUTTER, SIDEWALK, ETC. NOT INDICATED FOR REMOVAL. WHICH IS DAMAGED DURING DEMOLITION/CONSTRUCTION. SHALL BE REPAIRED OR REPLACED TO MATCH ORIGINAL CONDITION.
- 17.SALVAGEABLE FILL MATERIALS FROM SITE DEMOLITION DETERMINED TO BE ACCEPTABLE BY AN INDEPENDENT SOILS TESTING LABORATORY SHALL BE UTILIZED FOR FILL MATERIAL WHERE APPROPRIATE.
- 18.ANY NOTE, OR REFERENCE TO ANY ELEMENT, WHICH DOES NOT SPECIFY ACTION BY THE CONTRACTOR SHALL BE CONSTRUED AS INFORMATION ONLY.
- 19.ALL PIPE INSTALLATION, WHEN REQUIRED BY PIPE DEPTHS AND EXCAVATION, SHALL BE PERFORMED WITH THE USE OF TRENCH BOXES. ALL EXCAVATIONS. UTILITY AND GRADING WORK, SHALL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL RULES AND REGULATIONS.
- 20.THE GENERAL CONTRACTOR SHALL PROVIDE ALL SAFETY AND SECURITY FENCING. BARRIERS. PROTECTION MATERIAL AND METHODS AS REQUIRED TO COMPLETE ANY OFF SITE WORK IN A SAFE AND TIMELY MANNER.
- 21.CONTRACTOR SHALL REFER TO OTHER PLANS WITHIN THIS CONSTRUCTION
- 22.UNLESS OTHERWISE NOTED, ALL EXISTING VEGETATION TO REMAIN AND TO BE UNDISTURBED FOR THE DURATION OF CONSTRUCTION. IF DAMAGES OCCUR TO EXISTING VEGETATION, PLANTS SHALL BE REPLACED IN KIND.
- 23.ANY EXISTING PRIVATE SERVICE NOT TO BE USED (LABELED TO BE REMOVED) SHALL BE ABANDONED PER CORPUD STANDARDS (PU HANDBOOK, PAGE 67 AND

GRAPHIC SCALE

(IN FEET)

1 inch = 30 ft.

24.ANY EXISTING WELLS AND/OR SEPTIC SYSTEMS SHALL BE ABANDONED IN ACCORDANCE WITH WAKE COUNTY HEALTH DEPARTMENT STANDARDS.



REDF(

WINGS


OÖ

R R R

DRAWING

PROJECT NUMBER

C-1.0



SITE DATA TABLE ROGERS ROAD 3415, LLC **DEVELOPER:** JONATHAN BOES 1000 CRESCENT GREEN **CARY, NC 27518** TEL: (919) 247-0497 REDFORD 101, LLC 1000 CRESCENT GREEN, SUITE 101 **CARY, NC 27518** PROPERTY ADDRESS: 101 & 115 REDFORD PLACE DRIVE ROLESVILLE, NC 27571 PIN(s): 1758-89-7617 & 1758-89-8410 DEED: BOOK: 2038 PAGE: 017 & BOOK: 1013 PAGE: 0-E PLAT: | BOOK: 1992 PAGE: 00041 EXISTING ZONING: RESIDENTIAL I DISTRICT (R-I) PROPOSED ZONING: COMMERCIAL OUTLYING CONDITIONAL USE DISTRICT (CO-CZ) **EXISTING LAND USE:** 101 REDFORD PLACE DR: VACANT 115 REDFORD PLACE DR: SINGLE FAMILY PROPOSED LAND USE: MIXED-USE (RETAIL, MEDICAL, & DENTAL) LOT AREA: 1.62 ACRES (COMBINED) WATERSHED OVERLAY: ADDITIONAL OVERLAY: NONE WATERSHED: LOWER NEUSE RIVER RIVER BASIN: NEUSE RIVER WETLAND/STREAM | PER THE NATIONAL WETLANDS INVENTORY, NO DATA: WETLANDS EXIST. PER WAKE COUNTY SOILS MAP AND USGS QUAD MAP, NO STREAMS EXIST. PROPOSED GROSS 19,890 SF (3 STORIES, 6,630 SF PER FLOOR) FLOOR AREA: BUILDING HEIGHT: 46'-8" (TOP OF FRAMING/MASONRY) TOTAL DISTURBED | 82,545 SF; 1.89 ACRES EXISTING IMPERVIOUS | OFF-SITE: 556 SF (TO BE REMOVED) ON-SITE: 11,775 SF PROPOSED IMPERVIOUS | OFF-SITE: 2,995 SF (NET INCREASE - 2,439 SF) ON-SITE: 43,209 SF (61.2% OF THE SITE AREA) REDFORD PLACE DRIVE THOROUGHFARE STREETSCAPE BUFFER: MAIN STREET | 10' D (STREET FRONT) STREETSCAPE BUFFER: LANDSCAPE BUFFER | EAST (AGAINST SCHOOL): 10' C (SPATIAL DEFINITION) EAST (AGAINST CEMETERY): 25' B (SEMI-OPAQUE) BETWEEN LAND USES: SOUTH: 25' B (SEMI-OPAQUE) PROJECT SETBACKS: FRONT YARD: 20 FT MIN. SIDE YARD: 15 FT MIN. **CORNER YARD: 25 FT MIN. REAR YARD: 35 FT MIN.** REQUIRED PARKING: COMMERCIAL SHOPPING CENTER = 5.5 SPACES / 1,000 SF FLOOR = 4,500 SF / 1,000 = 4.5 x 5.5 = 24.75 SPACES

ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, WAKE COUNTY AND NCDOT STANDARDS AND SPECIFICATIONS.

FOR EACH EMPLOYEE

TOTAL REQUIRED = 114 SPACES

= 65 SPACES

RESTAURANT = 1.2 SPACES / 100 SF FLOOR AREA

 $= 2,000 \text{ SF} / 100 = 20 \times 1.2 = 24 \text{ SPACES}$

MEDICAL = 6 SPACES / DOCTOR OR DENTIST PLUS 1

3 DOCTORS AND 3 DENTISTS & 29 EMPLOYEES

- 2. ALL DIMENSIONS ARE TO EDGE OF PAVEMENT, EDGE OF SIDEWALK, FACE OF CURB, CENTERLINE OF COLUMN AND FACE OF BUILDING WALL, UNLESS OTHERWISE NOTED. ALL RADII DIMENSIONS TO BACK OF CURB.
- ALL PAINT STRIPING, PAVEMENT MARKINGS, AND SIGNAGE SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" OR
- 4. VERIFY ALL SETBACKS WITH LOCAL CODES.
- 5. A SEPARATE PERMIT AND APPROVAL IS REQUIRED FOR SIGNS.
- 6. ALL CURB RAMPS SHALL HAVE A DETECTABLE WARNING COMPLYING WITH SECTIONS 4.7.7 AND 4.29.2 OF THE ADA ACCESSIBILITY GUIDELINES
- CONTRACTOR SHALL PROVIDE ALL LABOR AND MATERIALS FOR THE INSTALLATION OF TRAFFIC SIGNAGE AND PAVEMENT MARKINGS AS SHOWI ON THE CONSTRUCTION PLANS.
- CONTRACTOR SHALL REFER TO OTHER PLANS WITHIN THIS CONSTRUCTION SET FOR OTHER PERTINENT INFORMATION.
- 9. DETECTABLE WARNINGS ARE REQUIRED AT ANY CROSSWALK, OR ISLAND CUT THRU, WHERE THERE IS NO CHANGE IN ELEVATION (I.E. RAMP NOT
- 10. ALL HVAC UNITS MUST BE SCREENED FROM THE PUBLIC ROW.

GRAPHIC SCALE

(IN FEET)

1 inch = 30 ft.


C-2.0PROJECT NUMBER

DRAWING

449-19

DR. ORD

00 ONSTRUC SITE L **REDF**(



STANDARD CITY OF RALEIGH UTILITY NOTES:

ALL MATERIALS & CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH CITY OF RALEIGH DESIGN STANDARDS, DETAILS & SPECIFICATIONS (REFERENCE: CORPUD HANDBOOK, CURRENT EDITION)

a. A DISTANCE OF 100' SHALL BE MAINTAINED BETWEEN SANITARY SEWER & ANY PRIVATE OR PUBLIC WATER SUPPLY SOURCE SUCH AS AN IMPOUNDED RESERVOIR USED AS A SOURCE OF DRINKING WATER. IF ADEQUATE LATERAL SEPARATION CANNOT BE ACHIEVED, FERROUS SANITARY SEWER PIPE SHALL BE SPECIFIED & INSTALLED TO WATERLINE SPECIFICATIONS. HOWEVER, THE MINIMUM SEPARATION SHALL NOT BE LESS THAN 25' FROM A PRIVATE WELL OR 50' FROM A PUBLIC WELL.

b. WHEN INSTALLING WATER &/OR SEWER MAINS, THE HORIZONTAL SEPARATION BETWEEN UTILITIES SHALL BE 10'. IF THIS SEPARATION CANNOT BE MAINTAINED DUE TO EXISTING CONDITIONS, THE VARIATION ALLOWED IS THE WATER MAIN IN A SEPARATE TRENCH WITH THE ELEVATION OF THE WATER MAIN AT LEAST 18" ABOVE THE TOP OF THE SEWER & MUST BE APPROVED BY THE PUBLIC UTILITIES DIRECTOR. ALL DISTANCES ARE MEASURED FROM OUTSIDE DIAMETER TO OUTSIDE

c. WHERE IT IS IMPOSSIBLE TO OBTAIN PROPER SEPARATION, OR ANYTIME A SANITARY SEWER PASSES OVER A WATERMAIN, DIP MATERIALS OR STEEL ENCASEMENT EXTENDED 10' ON EACH SIDE OF CROSSING MUST BE SPECIFIED & INSTALLED TO WATERLINE SPECIFICATIONS

d. 5.0' MINIMUM HORIZONTAL SEPARATION IS REQUIRED BETWEEN ALL SANITARY SEWER & STORM SEWER FACILITIES, UNLESS DIP MATERIAL IS SPECIFIED FOR SANITARY SEWER.

e. MAINTAIN 18" MIN. VERTICAL SEPARATION AT ALL WATERMAIN & RCP STORM DRAIN CROSSINGS; MAINTAIN 24" MIN. VERTICAL SEPARATION AT ALL SANITARY SEWER & RCP STORM DRAIN CROSSINGS. WHERE ADEQUATE SEPARATIONS CANNOT BE ACHIEVED, SPECIFY DIP MATERIALS & A CONCRETE CRADLE HAVING 6" MIN. CLEARANCE (PER CORPUD DETAILS W-41 & S-49).

f. ALL OTHER UNDERGROUND UTILITIES SHALL CROSS WATER & SEWER FACILITIES WITH 18" MIN. VERTICAL SEPARATION REQUIRED.

ANY NECESSARY FIELD REVISIONS ARE SUBJECT TO REVIEW & APPROVAL OF AN AMENDED PLAN &/OR PROFILE BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT PRIOR TO CONSTRUCTION.

CONTRACTOR SHALL MAINTAIN CONTINUOUS WATER & SEWER SERVICE TO **EXISTING RESIDENCES & BUSINESSES THROUGHOUT CONSTRUCTION OF** PROJECT. ANY NECESSARY SERVICE INTERRUPTIONS SHALL BE PRECEDED BY A 24 HOUR ADVANCE NOTICE TO THE CITY OF RALEIGH PUBLIC UTILITIES

3.0' MINIMUM COVER IS REQUIRED ON ALL WATER MAINS & SEWER FORCEMAINS. 4.0' MINIMUM COVER IS REQUIRED ON ALL REUSE MAINS.

IT IS THE DEVELOPER'S RESPONSIBILITY TO ABANDON OR REMOVE **EXISTING WATER & SEWER SERVICES NOT BEING USED IN REDEVELOPMENT** OF A SITE UNLESS OTHERWISE DIRECTED BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT. THIS INCLUDES ABANDONING TAP AT MAIN & REMOVAL OF SERVICE FROM ROW OR EASEMENT PER CORPUD HANDBOOK

INSTALL 2" COPPER* WATER SERVICES WITH METERS LOCATED AT ROW OR WITHIN A 2'x2' WATERLINE EASEMENT IMMEDIATELY ADJACENT. NOTE: IT IS THE APPLICANT'S RESPONSIBILITY TO PROPERLY SIZE THE WATER SERVICE FOR EACH CONNECTION TO PROVIDE ADEQUATE FLOW & PRESSURE.

INSTALL 4" PVC* SEWER SERVICES @ 1.0% MINIMUM GRADE WITH CLEANOUTS LOCATED AT ROW OR EASEMENT LINE & SPACED EVERY 75

PRESSURE REDUCING VALVES ARE REQUIRED ON ALL WATER SERVICES **EXCEEDING 80 PSI; BACKWATER VALVES ARE REQUIRED ON ALL SANITARY** SEWER SERVICES HAVING BUILDING DRAINS LOWER THAN 1.0' ABOVE THE

10. ALL ENVIRONMENTAL PERMITS APPLICABLE TO THE PROJECT MUST BE OBTAINED FROM NCDWQ, USACE &/OR FEMA FOR ANY RIPARIAN BUFFER, WETLAND &/OR FLOODPLAIN IMPACTS (RESPECTIVELY) PRIOR TO

11. NCDOT / RAILROAD ENCROACHMENT AGREEMENTS ARE REQUIRED FOR ANY UTILITY WORK (INCLUDING MAIN EXTENSIONS & SERVICE TAPS) WITHIN STATE OR RAILROAD ROW PRIOR TO CONSTRUCTION.

12. GREASE INTERCEPTOR / OIL WATER SEPARATOR SIZING CALCULATIONS & INSTALLATION SPECIFICATIONS SHALL BE APPROVED BY THE CORPUD FOG PROGRAM COORDINATOR PRIOR TO ISSUANCE OF A BUILDING PERMIT. **CONTACT TIM BEASLEY AT (919) 996 - 2334 OR** TIMOTHY.BEASLEY@RALEIGHNC.GOV FOR MORE INFORMATION.

13. CROSS-CONNECTION CONTROL PROTECTION DEVICES ARE REQUIRED BASED ON DEGREE OF HEALTH HAZARD INVOLVED AS LISTED IN APPENDIX-B OF THE RULES GOVERNING PUBLIC WATER SYSTEMS IN NORTH CAROLINA. THESE GUIDELINES ARE THE MINIMUM REQUIREMENTS. THE DEVICES SHALL MEET AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE) STANDARDS OR BE ON THE UNIVERSITY OF SOUTHERN CALIFORNIA APPROVAL LIST. THE DEVICES SHALL BE INSTALLED AND TESTED (BOTH INITIAL AND PERIODIC TESTING THEREAFTER) IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS OR THE LOCAL CROSS-CONNECTION CONTROL PROGRAM, WHICHEVER IS MORE STRINGENT. CONTACT JOANIE HARTLEY AT (919) 996-5923 OR JOANIE.HARTLEY@RALEIGHNC.GOV FOR MORE INFORMATION.

GRAPHIC SCALE

(IN FEET)

1 inch = 30 ft.

DR.

S

NO O


REDF

ōF.

- 0 ε 4 c 9

> **DRAWING** C-3.0

PROJECT NUMBER 449-19



ALL SITE WORK SHALL BE DONE IN ACCORDANCE WITH THE PLANS PREPARED BY PABST DESIGN GROUP, PA, THE CURRENT REQUIREMENTS OF THE TOWN OF ROLESVILLE, THE APPLICABLE SECTIONS OF THE NCDOT STANDARD SPECIFICATIONS FOR ROADWAY CONSTRUCTION, AND ALL OTHER PERTINENT

THE CONTRACTOR SHALL COMPLY AT ALL TIMES WITH APPLICABLE FEDERAL STATE AND LOCAL LAWS, PROVISIONS, AND POLICIES GOVERNING SAFETY AND HEALTH, INCLUDING THE FEDERAL CONSTRUCTION SAFETY ACT (PUBLIC LAW 91-54), FEDERAL REGISTER, CHAPTER XVII, PART 1926 OF TITLE 29 REGULATIONS, OCCUPATIONAL SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION, AND SUBSEQUENT PUBLICATIONS UPDATING THESE

. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING THE AREAS AND CONDITIONS UNDER WHICH THE PROJECT IS TO BE CONSTRUCTED PRIOR TO THE SUBMISSION OF A BID. SUBMISSION OF A BID SHALL BE CONSTRUED TO MEAN THE CONTRACTOR HAS REVIEWED THE SITE AND IS FAMILIAR WITH

BEFORE EXCAVATION, ALL UNDERGROUND UTILITIES SHALL BE LOCATED IN THE FIELD BY THE PROPER AUTHORITIES. THE CONTRACTOR SHALL NOTIFY N.C. "ONE CALL" AT 1-800-632-4949. THE LOCATION OF ALL UTILITIES AND UNDERGROUND STRUCTURES ARE APPROXIMATE AND MAY NOT ALL BE SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXISTENCE AND EXACT LOCATION OF ALL UTILITIES AND UNDERGROUND

5. ALL EXISTING TREES, VEGETATION, PAVEMENTS, CONCRETE FOUNDATIONS, STRUCTURES AND ORGANIC TOPSOIL SHALL BE STRIPPED AND REMOVED

6. ALL AREAS NOT PAVED SHALL BE TOPSOILED, SEEDED, MULCHED OR LANDSCAPED UNLESS OTHERWISE NOTED IN THE CONSTRUCTION DRAWINGS,

. CONTRACTOR SHALL BE FINANCIALLY RESPONSIBLE FOR DISPOSAL OF ALL WASTE MATERIALS OFF SITE. THIS RESPONSIBILITY SHALL INCLUDE ALL REQUIRED APPROVALS AND CONDITIONS DICTATED BY THE TOWN OF

8. ALL OPEN STORM DRAIN PIPES SHALL BE PROTECTED WITH STONE FILTER PROTECTION AFTER STOPPAGE OF WORK EACH DAY.

9. CONTRACTOR SHALL ADHERE TO ALL TERMS AND CONDITIONS AS OUTLINED IN THE GENERAL NPDES PERMIT FOR STORMWATER DISCHARGE ASSOCIATED

10.IF AN OFFSITE SOIL SPOIL OR BORROW SITE IS UTILIZED, THEN THE DISTURBED AREA FOR THE SPOIL/BORROW SITE MUST BE INCLUDED IN THE LAND-DISTURBANCE PLAN AND PERMIT UNLESS THE SPOIL/BORROW SITE ALREADY HAS A LAND-DISTURBANCE PERMIT.

11.CONTRACTOR TO PROVIDE SHOP DRAWINGS ON ALL STORM SEWER

12.BOUNDARY AND LOCATION SURVEY PROVIDED BY NEWCOMB LAND SURVEYORS, PLLC, DATED JULY 15, 2019.

13.TOPOGRAPHIC SURVEY PROVIDED BY NEWCOMB LAND SURVEYORS, PLLC,

14.CONTRACTOR SHALL REFER TO OTHER PLANS WITHIN THIS CONSTRUCTION SET FOR OTHER PERTINENT INFORMATION.

. CONTRACTOR SHALL FIELD VERIFY EXISTING TOPOGRAPHY IN RELATION TO THE PROPOSED GRADES TO ENSURE DRAINAGE IN THE DIRECTION INDICATED

2. INITIATE CONSTRUCTION SEQUENCE BEFORE BEGINNING CLEARING AND

3. STRIP TOPSOIL TO FULL DEPTH IN AREAS TO BE GRADED.

4. MAXIMUM GRADED SLOPE SHALL NOT EXCEED 2:1, UNLESS OTHERWISE NOTED


5. AREAS TO BE GRADED SHALL BE CLEARED OF ALL EXISTING VEGETATION. CONTRACTOR TO PROTECT VEGETATION LOCATED BEYOND GRADING LIMITS.

GEOTECHNICAL RECOMMENDATIONS.

ALL 2:1 SLOPES TO BE STABILIZED WITH EXCELSIOR DOUBLE NET BLANKET PER MANUFACTURER'S RECOMMENDATIONS. SLOPES TO BE SODDED w/ BERMUDA. CONTACT ACF ENVIRONMENTAL FOR SPECIFICATIONS AT

ALL PROPOSED ROADS SHALL NOT EXCEED 12% RUNNING GRADE. ALL PROPOSED ROADS SHALL NOT EXCEED 1/4"/1' CROSS SLOPE WITHIN

TOTAL DISTURBED AREA = ±1.89Ac.



DRIV

NE CENTRAL

REDFC

8


101

N DRAV DRAIN

CONS-RADING 8

DRAWING

C-4.0 PROJECT NUMBER



CONSTRUCTION SEQUENCE PHASE - 1

- 1. AFTER SITE PLAN/CONSTRUCTION PLAN APPROVAL HAS BEEN OBTAINED, CONTACT JEEVAN NEUPANE w/ WAKE COUNTY WATERSHED MANAGEMENT STAFF AT (919) 819-8907 AND PABST DESIGN GROUP AT 919-848-4399, TO SCHEDULE A PRE-CONSTRUCTION MEETING. OBTAIN LAND-DISTURBING PERMIT AND PLACARD, AND POST THE PLACARD ON SITE. THIS MUST BE DONE PRIOR TO BEGINNING WORK
- 2. OBTAIN AN APPROVED (STAMPED) S&E CONTROL PLAN AND KEEP IT ON SITE, EITHER IN THE INSPECTION BOX, CONSTRUCTION OFFICE, OR WITH THE CONTRACTOR
- 3. CONTRACTOR SHALL VERIFY LOCATION AND DEPTH OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION TO AVOID CONFLICT DURING GRADING OPERATION. CONTRACTOR SHALL CALL 1-800-632-4949 N.C. "ONE CALL" PRIOR TO DIGGING TO LOCATE ALL EXISTING UNDERGROUND UTILITIES ON SITE.
- EROSION AND SEDIMENT CONTROL MEASURES TO BE INSTALLED PRIOR TO DEMOLITION OF EXISTING STRUCTURES.
- 5. INSTALL TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE WITH SILT FENCE OUTLETS, SKIMMER BASIN AND REMAINING S&E MEASURES SPECIFIED ON THE PLAN, TREE PROTECTION FENCE AND INLET PROTECTION AROUND EXISTING DRAINAGE INLETS AS SHOWN ON PLANS. REMOVE LARGE AREA OF EXISTING GRAVEL ON SITE BEFORE INSTALLATION OF DIVERSION DITCH 1. ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE WAKE COUNTY STANDARDS AND SPECIFICATIONS. ADD BYPASS DRAIN LINE.
- 6. ADD (2) BYPASS DRAIN LINES, SHOWN ON PLANS, THIS SHEET AND C-5.1. IF BYPASS DRAIN LINES OR 12" HDPE PIPE UNDER TEMPORARY CONSTRUCTION ENTRANCE ARE DAMAGED DURING CONSTRUCTION TRAFFIC, CONTRACTOR TO REPAIR OR REPLACE AS NEEDED.
- 7. CALL JEEVAN NEUPANE (919) 819-8907 FOR AN ONSITE INSPECTION BY THE WATERSHED MANAGER TO OBTAIN A CERTIFICATE OF COMPLIANCE.
- 8. REMOVE ANY NON-SEDIMENT UPLAND MATERIALS THAT MAY WASH INTO THE BASI (E.G., LIMBS, DEBRIS, TRASH, BUILDING MATERIALS, ETC.) STABILIZE UPLAND AREAS THAT MAY CONTRIBUTE SIGNIFICANT AMOUNTS OF ERODED SOIL TO THE TRAP/BASIN AS QUICKLY AS POSSIBLE, TO AVOID FREQUENT DREDGING AND MAINTENANCE.
- 9. BEGIN CLEARING, GRUBBING AND ROUGH GRADING OF SITE AS SPECIFIED ON PLAN.
- 10. CONTRACTOR TO MAINTAIN EXISTING SEDIMENT AND EROSION CONTROL DEVICES AS SHOWN ON APPROVED PERMITTED PLANS.
- 11. SEDIMENT AND EROSION CONTROL DEVICES ARE TO BE INSPECTED AND MAINTAINED AFTER EVERY RAIN AND ONCE PER WEEK.
- 12. IF A STOCKPILE IS NECESSARY DUE TO EXCAVATION, A DOUBLE ROW OF SILT FENCE IS REQUIRED 10 FEET APART AT THE LIMITS OF THE STOCKPILE AREA.
- 13. CUT AND FILL SLOPES WILL BE STABILIZED WITHIN, PER STABILIZATION TIMEFRAMES, UPON COMPLETION OF ANY PHASE OF GRADING. (SEE STABILIZATION CRITERIA ON THIS SHEET AND SHEET D-4.2)
- 14. AS THE SITE IS BROUGHT TO GRADE, INSTALL ALL STORM SEWER AND INLET PROTECTION ON PROPOSED INLETS AS INDICATED ON THIS PLAN AND SHEET C-4.0, WHILE ENSURING GRADES MAINTAIN DRAINAGE TO THE SKIMMER BASIN UNTIL IT IS REMOVED.
- 15. CONTRACTOR TO RE-ESTABLISH TEMPORARY DIVERSION DITCHES, IF NEEDED, TO ENSURE POSITIVE DRAINAGE AT THE END OF EACH WORKING DAY.
- 16. STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH VEGETATION AND PAVING. ESTABLISH GROUND COVER ON DENUDED AREAS WITHIN FOURTEEN DAYS (14) DAYS OF COMPLETION OF ANY PHASE OF GRADING. (SEE STABILIZATION CRITERIA ON THIS SHEET AND SHEET D-4.2)
- 17. IF IT IS DETERMINED DURING CONSTRUCTION THAT SIGNIFICANT SEDIMENT IS LEAVING THE SITE, DESPITE PROPER IMPLEMENTATION AND MAINTENANCE, THE CONTRACTOR IS OBLIGATED TO TAKE ADDITIONAL CORRECTIVE ACTION.
- 18. THE CONTRACTOR SHALL INSPECT AND MAINTAIN THE EROSION CONTROL DEVICES SO THEY CONTINUE TO FUNCTION PROPERLY.
- 19. PERFORM REGULAR MAINTENANCE ON THE SEDIMENT TRAP FOR OPTIMUM PERFORMANCE. CHECK SPILLWAY FOR ACCUMULATED DEBRIS, EROSION, AND DISPLACEMENT OF ROCK. REMOVE SEDIMENT FROM THE TRAP WHEN SEDIMENT ACCUMULATES TO THE CLEAN OUT LEVEL (50 PERCENT OF WET STORAGE DEPTH). USE PUMP FOR THIS WHEN NECESSARY, PUMP OUT THROUGH A SILT SACK. STABILIZE OR USE SILT FENCING TO ADDRESS UPSLOPE AREAS THAT ARE CONTRIBUTING EXCESSIVE VOLUMES OF SEDIMENT TO THE TRAP AND INCREASING MAINTENANCE NEEDS. MAINTAIN ORIGINAL DIMENSIONS OF TRAP (GRADE, DEPTH, ETC.) THROUGHOUT LIFE OF PRACTICE.
- 20. SEE PHASE 2 EROSION CONTROL MEASURES AND CONTINUATION OF EROSION CONTROL CONSTRUCTION SEQUENCE ON SHEET C-5.1.

GRADING NOTES

- CONTRACTOR SHALL FIELD VERIFY EXISTING TOPOGRAPHY IN RELATION TO THE PROPOSED GRADES TO ENSURE DRAINAGE IN THE DIRECTION INDICATED
- INITIATE CONSTRUCTION SEQUENCE BEFORE BEGINNING CLEARING AND GRUBBING ON-SITE OPERATIONS.
- S. CONTRACTOR TO PROTECT VEGETATION LOCATED BEYOND CONSTRUCTION
- STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES. STOCKPILE HEIGHT SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2:1 OR FLATTER.

TOTAL DISTURBED AREA = ±1.89 AC

ISSUED FOR CONSTRUCTION

NOTE(s):

1 inch = 30 ft.

NOTE(s):
ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, WAKE COUNTY AND NCDOT STANDARDS AND SPECIFICATIONS.

DESIGN GROUP, Ingineering | Consulting

ENGINEER:

CONSTRUCTION DRAWINGS
SION CONTROL PLAN - PHASE 1

DRI

(T)

REDF

SEAL:

SEAL

D PER TOR COMMENTS 8/28/19

D PER WAKE CO COMMENTS 11/20/19

D PER WAKE CO COMMENTS 12/19/19

1 REVISED PER TOR COMMENTS
2 REVISED PER WAKE CO COMM
3 REVISED PER WAKE CO COMM


TABLE

TABLE

TO STATE

SHEET **C-5.0**

PROJECT NUMBER **449-19**



CONSTRUCTION SEQUENCE PHASE 2

- REFER TO SHEET C-5.0 IN THIS PLAN SET FOR PHASE 1 E&S OPERATIONS PRIOR TO BEGINNING THIS CONSTRUCTION SEQUENCE AND INSTALLATION OF MEASURES ON THIS PLAN SHEET.
- DURING CONTINUED CONSTRUCTION, ADJUST THE TEMPORARY DIVERSION DITCHES AND GRADES AS NECESSARY, STAY AS CLOSE TO THE ORIGINAL LOCATION AS POSSIBLE, TO MAINTAIN POSITIVE DRAINAGE AND CROSS SECTION PER THE DETAIL E6 ON SHEET D-4.0.
- INSTALL TEMPORARY 12" PIPE FROM DBCB-E2 TO THE SKIMMER BASIN AND CB-B1 TO EX CB-A1. INSTALL PLUG IN PIPE AT STRUCTURES DBCB-E2 AND CB-B2 PLUGS SHALL REMAIN INSTALLED UNTIL PDG APPROVES THE SCM DEVICE AND ALL STORM LINES ARE FREE OF SILT/TRASH.
- CONTINUE BRINGING THE SITE TO FINAL GRADES AND INSTALLING UTILITIES AS NECESSARY. SKIMMER BASIN MUST REMAIN IN OPERATION UNTIL SUCH TIME THAT THE SITE UPSTREAM OF THE DEVICE IS STABILIZED. ONCE ENOUGH OF TH SITE IS STABILIZED AND THE STORM CONVEYANCE HAS BEEN INSTALLED, BEGIN THE BASIN REMOVAL SEQUENCE PER THE NOTES ON THIS SHEET.
- ONCE BASIN IS REMOVED CONTINUE GRADING OPERATION PROGRESSING **TOWARD DESIGN GRADE.**
- CUT AND FILL SLOPES WILL BE STABILIZED WITHIN 14 DAYS OF ANY PHASE OF GRADING. (SEE STABILIZATION CRITERIA ON THIS SHEET AND D-4.2).
- INSTALL CURB AND GUTTER, CABC STONE, PAVEMENT AND SIDEWALK IN ALL HARDSCAPE AREAS
- CONTACT PDG TO INSPECT SCM DEVICES FOR ACCEPTANCE. ONCE APPROVED
- UNPLUG STRUCTURES DBCB-E2 AND CB-B1.
- STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH **VEGETATION AND PAVING. ESTABLISH GROUND COVER ON DENUDED AREAS** WITHIN FOURTEEN DAYS (14) DAYS OF COMPLETION OF PROJECT.
- 10. REMOVE BYPASS DRAIN LINES FROM CB-B1 TO EX CB-A1 AND FROM DBCB-E2 TO SKIMMER BASIN. FOLLOWING THE REMOVAL OF BYPASS DRAIN LINE FROM CB-B TO EX CB-A1, COMPLETE DRIVEWAY CONSTRUCTION.
- 11. IF IT IS DETERMINED DURING CONSTRUCTION THAT SIGNIFICANT SEDIMENT IS LEAVING THE SITE, DESPITE PROPER IMPLEMENTATION AND MAINTENANCE, TH CONTRACTOR IS OBLIGATED TO TAKE ADDITIONAL CORRECTIVE ACTION.
- 12. THE CONTRACTOR SHALL INSPECT AND MAINTAIN THE EROSION CONTROL DEVICES SO THEY CONTINUE TO FUNCTION PROPERLY.
- 13. FINE GRADE THE FINAL PORTION OF THE SITE. SEED OR OTHERWISE STABILIZE ANY RESULTING BARE AREAS.
- 14. MAINTAIN ALL REMAINING SOIL AND EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
- 15. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CALL ENVIRONMENTAL CONSULTANT FOR AN INSPECTION.
- 16. IF SITE IS APPROVED, REMOVE TEMPORARY DIVERSIONS, SILT FENCE, ETC., AND SEED OUT OR STABILIZE ANY RESULTING BARE AREAS. ALL REMAINING PERMANENT EROSION CONTROL DEVICES, SUCH AS VELOCITY DISSIPATORS, SHOULD NOW BE INSTALLED.
- 17. WHEN VEGETATION HAS BECOME ESTABLISHED, CALL FOR A FINAL SITE INSPECTION BY JEEVAN NEUPANE WITH WAKE COUNTY WATERSHED MANAGEMENT STAFF AT (919) 819-8907. IF SITE IS APPROVED, OBTAIN A CERTIFICATE OF COMPLETION.

EROSION CONTROL MAINTENANCE SCHEDULE

- ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUN-OFF PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS
- SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT REACHES HALF CAPACITY OF THE FENCE. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER.
- 3. ALL SEEDED ARES WILL BE FERTILIZED, RESEEDED AS NECESSARY, AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO
- MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER. 4. AFTER CONSTRUCTION, THE DEVELOPER WILL MAINTAIN ALL PERMANENT
- 5. SILT FENCE OUTLETS WILL BE ADDED ALONG THE SILT FENCE AT ALL LOW POINTS AS NEEDED BASED ON FIELD CONDITIONS.

BASIN REMOVAL SEQUENCE

- 1. SCHEDULE A SITE MEETING WITH THE ENVIRONMENTAL ENGINEER/CONSULTAN $^{ extsf{T}}$ TO DETERMINE IF A BASIN CAN BE REMOVED. INSTALL SILT FENCING OR OTHER TEMPORARY EROSION CONTROL MEASURES AS NEEDED PRIOR TO REMOVAL OF
- 2. REMOVE BASIN(S) AND ASSOCIATED TEMPORARY DIVERSION DITCHES. IF CULVERT PIPES NEED TO BE EXTENDED, PERFORM THIS OPERATION AT THIS TIMI FINE GRADE AREA IN PREPARATION FOR SEEDING.
- 3. PERFORM SEEDBED PREPARATION, SEED, MULCH AND ASPHALT TACK ANY RESULTING BARE AREAS IMMEDIATELY.
- 4. INSTALL VELOCITY DISSIPATORS AND/OR LEVEL SPREADERS AS REQUIRED ON THE EROSION CONTROL PLAN.
- 5. WHEN SITE IS FULLY STABILIZED, CALL ENVIRONMENTAL ENGINEER/CONSULTANT FOR APPROVAL OF REMOVING REMAINING TEMPORARY EROSION CONTROL MEASURES AND ADVICE ON WHEN SITE CAN BE ISSUED A CERTIFICATE OF COMPLETION.

NOTE: A MEETING SHOULD ALSO BE SCHEDULED WITH THE ENVIRONMENTAL ENGINEER/CONSULTANT TO DETERMINE WHEN A BASIN MAY BE CONVERTED FOR STORMWATER USE. SOME MUNICIPALITIES MAY ALSO REQUIRE THIS.

TRU CONS.

REDF

| - | α | α | **4** | Ω

> DRAWING C-5.1

PROJECT NUMBER


DRAWING SHEET

C-6.0PROJECT NUMBER


449-19

CLEANOUT TEMPORARY PONDING LEVEL - 417.00' EL. 416.00' RISER STRUCTURE (SEE DETAIL THIS FILL SOIL MEDIA (3' DEEP) SHEET) MIX:85-88% SAND _6" PVC 8-12% FINES (SOLID) 3-5% ORGANIC – INV. 414.00 15" HDPE EL. 414.00 _INV. 413.91' - 6"x 6"TEE EL. 413.00 FLOWABLE FILL 10" #57 STONE - NON-WOVEN 6" PERFERATED -**GEO-TEXTILE PVC UNDERDRAIN** FILTER FABRIC **PIPE 0.50% MIN.**

BIORETENTION w/ IWS TYP. DETAIL



RISER STRUCTURE DETAIL



JOINT DETAIL

TRASH RACK DETAIL NTS

25' LANDSCAPE BUFFER - 25 B ─TC 418.43´ FL 417.93

BIORETENTION PLAN VIEW

S 23°57'49" E 293.47'

TC 420.04

TC 419.80 TC 419.44

FL 419.30 | FL 418.94

¯_FL 419.54*P*=

3' x 5' RIP RAP

DISSIPATER PAD

FL 419.12

OUTLET

FES-D1

√(WITH TRASH GUARD. SEE

★ SHEET C-6.2 FOR DETAIL)

MAINTENANCE AND

√ ACCESS ESMT.

PROPOSED


/ BIORETENTION

6" PERF. PVC

PROPOSED 84" CMP UNDERGROUND / DETENTION PIPE (SEE SHEET C-6.1)

_35' REAR SETBACK _

SCALE 1" = 20'



BIORETENTION PROFILE VIEW

SCALE 1" = 20'

KEY	
FL	FLOW LINE
тс	TOP OF CURB
ТР	TOP OF PAVEMENT
TS	TOP OF SIDEWALK
LP	LOW POINT
FFE	FINISHED FLOOR ELEV.

STORM CHART													
Line ID Line Size Material Invert Dn Invert Up Line Length Line Slope Grnd/Rim Elev Dn Grnd/Rim Elev													
	(in)		(ft)	(ft)	(ft)	(%)	(ft)	(ft)					
FES-E1 TO DBCB-E2	15	Cir	416.25	416.66	70.385	0.58	416.25	419.76					
DBCB-E2 TO CB-E3	15	Cir	416.76	418.60	140.058	1.31	419.76	421.60					
UG TO CB-B1	15	Cir	413.72	414.12	39.649	1.01	418.00	417.16					
UG TO CB-C1	15	Cir	413.72	415.23	75.373	2.00	418.00	418.73					
UG TO RS-D1	15	Cir	413.72	413.91	15.306	1.24	418.00	417.00					
POA TO EX CB-A1	15	Cir	407.26	407.50	25.275	0.95	410.65	410.65					
EX CB-A1 TO UG*	15	Cir	407.60	408.14	68.324	0.79	410.65	418.00					
*NOTE: PIPE IS WITHI	N PUBLIC F	RIGHT-OF	WAY AND	SHALL BE (CLASS IV OR	GREATER RO	CP.						

- 2. RISER STRUCTURE SHALL BE LOCATED SUCH THAT DIRECT ACCESS FROM THE EMBANKMENT CAN BE ACHIEVED.
- 3. PEAK ROOF TRASH RACK TO BE PROVIDED w/ A MINIMUM SLOPE OF 2:1
- 4. TRASH RACK SHALL PROVIDE AN ACCESS HATCH w/ A MINIMUM CLEAR SPACE OPENING OF 2' x 3'.
- 5. TRASH RACK SHALL BE MOUNTED TO THE TOP OF THE RISER STRUCTURE. MOUNTING OF BOLTS IN SHEAR IS NOT ALLOWABLE.

TRASH RACK NOTES


- 1. CONTRACTOR TO PROVIDE FABRICATED ALUMINUM PEAK (MINIMUM OF 2:1) ROOF STYLE TRASH RACK. (MUST HAVE ACCEPTED DESIGN LIFE OF 75
- 2. ALUMINUM TRASH RACK SHALL BE BOLTED TO THE TOP OF THE RISER STRUCTURE. AT NO INSTANCE SHALL THE BOLTS BE IN SHEAR. BOLTS SHALL BE STAINLESS STEEL.
- 3. CONTRACTOR TO PROVIDE A MINIMUM 24" x 36" ACCESS HATCH ALIGNED DIRECTLY OVER THE STEPS INSIDE THE STRUCTURE. HATCHES SHALL BE SECURED W/ A LOCK AND CHAIN. MAXIMUM WEIGHT OF OF HATCH OPENING SHALL BE 75 POUNDS.
- 4. CONTRACTOR SHALL SUBMIT TO THE ENGINEER OF RECORD SHOP DRAWINGS FOR FINAL APPROVAL

SEASONAL HIGH WATER TABLE NOTE


IN ACCORDANCE WITH THE DESIGN REQUIREMENTS OF THE NORTH CAROLINA STATE BMP MANUAL, THE SHWT MUST BE A MINIMUM OF 2' BELOW THE BIORETENTION DEVICE. A FIELD INVESTIGATION WAS PERFORMED TO DETERMINE THE SHWT AT THE DEVICE LOCATION. ACCORDING TO THE REPORT OF FINDINGS, BY FRED D. SMITH SOIL CONSULTING, DATED MARCH 10, 2017, THE SHWT TABLE IN THE AREA WHERE THE BIORETENTION IS PROPOSED WAS CONFIRMED TO NOT BE PRESENT WITHIN A MINIMUM OF 70" BELOW EXISTING GRADE, WHICH EXTENDS TO 2' BELOW THE PROPOSED DEVICE. THUS, THE SHWT IS A MINIMUM OF 2' BELOW THE DEVICE.

ISSUED FOR CONSTRUCTION

ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE AND NCDOT STANDARDS AND SPECIFICATIONS.



PRECAST STRUCTURE DETAIL



ISSUED FOR CONSTRUCTION

ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE AND NCDOT STANDARDS AND SPECIFICATIONS

STORM CHART													
Line ID Line Size Material Invert Dn Invert Up Line Length Line Slope Grnd/Rim Elev Dn Grnd/Rim Elev													
	(in)		(ft)	(ft)	(ft)	(%)	(ft)	(ft)					
FES-E1 TO DBCB-E2	15	Cir	416.25	416.66	70.385	0.58	416.25	419.76					
DBCB-E2 TO CB-E3	15	Cir	416.76	418.60	140.058	1.31	419.76	421.60					
UG TO CB-B1	15	Cir	413.72	414.12	39.649	1.01	418.00	417.16					
UG TO CB-C1	15	Cir	413.72	415.23	75.373	2.00	418.00	418.73					
UG TO RS-D1	15	Cir	413.72	413.91	15.306	1.24	418.00	417.00					
POA TO EX CB-A1	15	Cir	407.26	407.50	25.275	0.95	410.65	410.65					
EX CB-A1 TO UG*	15	Cir	407.60	408.14	68.324	0.79	410.65	418.00					
*NOTE: PIPE IS WITHII	N PUBLIC R	GHT-OF-\	VAY AND S	HALL BE CL	ASS IV OR GE	REATER RCP							

ELEVATION

84"Ø UNDERGROUND DETENTION SYSTEM - 628050-010

101 & 115 REDFORD PLACE DRIVE (449-19)

ROLESVILLE, NC

SITE DESIGNATION: UG

RISER LADDER DETAIL

NOT TO SCALE

CANTECH

PROPOSAL DRAWING

CINTECH

STANDARD DETENTION PLAN VIEW DETAIL

PROJECT No.: SEQ. No.: DATE: 628050 010 8/27/2019

DESIGNED: DRAWN:

4. CONCRETE STRENGTH = 4,000 psi

5. REINFORCING STEEL = ASTM A615, GRADE 60

6. PROVIDE ADDITIONAL REINFORCING AROUNI

OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.

84"Ø UNDERGROUND DETENTION SYSTEM - 628050-010

101 & 115 REDFORD PLACE DRIVE (449-19)

ROLESVILLE, NC

SITE DESIGNATION: UG

MANHOLE CAP DETAIL

ALL FABRICATION OF THE PRODUCT SHALL OCCUR WITHIN THE UNITED STATES.

MATERIAL SPECIFICATION

C&NTECH*

CWNTECH

PROPOSAL DRAWING

PROJECT NUMBER

DRAWING

SHEET

C-6.1

DRIVE

)RD


REDFC


101

DR.

CONSTRUC RGROUND DET

ISSUED FOR CONSTRUCTION





Trash Guard Plus® Installation Instructions

Trash Guard Plus® can be installed in a variety of catch basin configurations (or field conditions). In general the Trash Guard Plus[®] is mounted on the catch basin wall, centered over the outlet pipe.

Before installing Trash Guard Plus®, A hydraulic calculation should be performed to determine maximum flow rate based on depth of the catch basin and size of Trash Guard Plus® used. This calculated model will determine maximum flow rate with no obstructions or varying amounts of trash build up, and determine drainage area required to support the cal-culated flow rate. Allowable trash build up and drainage area required for trash build up will determine maintenance frequency.

If catch basin conditions allow and increased flow rate and additional vertical capacity are desired, a model can be calculated to determine flow rate when extending Trash Guard Plus® from one inch to seven inches from the catch basin wall. As above, this calculated model will determine maximum flow rate with no obstructions or varying amounts of trash build up. Contact Trash Guard Plus® for assistance in determining flow rate and drainage areas under varying field conditions.

The following instructions are organized in sections described as follows:

☐ Section 1 – Trash Guard Plus® installed on a flat perpendicular wall with a flat bottom


☐ Section 2 – Bottom Plate installed on an inverted bottom

☐ Section 3 – Trash Guard Plus® installed on a flat perpendicular wall with an inverted bottom

☐ Section 4 – Trash Guard Plus® installed on tiered brick wall escalating width from top to bottom with an inverted or flat bottom.

☐ Section 5 – Trash Guard Plus® installed on concaved wall reasonable flat at top and bottom with an inverted or flat bottom.

☐ Section 6 – Trash Guard Plus® installed extended front wall increase flow capacity with an inverted or flat bottom.



WARNING: Improper installation of the Trash Guard Plus® or failure to keep the area around the Trash Guard Plus® free from sediment, debris and litter after installation may result in clogging of the storm water drainage system and increase the risk of flooding during times of heavy rainfall. It is important to clear sediment, debris and litter from around the Trash Guard Plus® at least four (4) times a year and more frequently in areas with large amounts of vegetation or litter. Please contact your local Trash Guard Plus® distributor with any questions regarding theinstallation or regular maintenance requirements of the Trash Guard Plus®.

Section 1 (Diagram I)

- ☐ Items Included:
- Trash Guard Plus® (Chosen Size) Seven Plastic Anchors
- Seven Flat Washers
- Seven 1.75" x .25" Stainless Steel Phillips Screws

☐ Tools Needed:

- Cordless Hammer Drill 5/16" Masonry Drill Bit
- Phillips Screwdriver

Installation Instructions

Can be attached with or without retaining rails.

1. Place Trash Guard Plus over outlet pipe.

2. Drill 5/16" hole top and bottom each side. 3. Insert plastic anchor and attach washer and phillips screws as shown in diagram.

Section 2 (Diagram A & B)

- ☐ Items Included for **A**: Bottom Plate with plastic netting
- attached Seven Plastic Anchors Seven Flat Washers
- Seven 1.75" x .25" Stainless Steel Phillips
- Screws ☐ Tools Needed:
- Cordless Hammer Drill • 5/16" Masonry Drill Bit
- Phillips Screwdriver

Installation Instructions For A Installation Instructions For B

1. Place bottom plate over inverted bottom with level sides. (Front and Back) 2. Drill 5/16" holes as shown in diagram. 3. Insert plastic wall anchors as shown in

diagram A. 4. Attach with washer and screw as shown.

Items Included for **B**: Bottom Plate with

- plastic netting attached Seven Plastic Anchors Seven Flat Washers
- Seven 1.75" x .25" Stainless Steel
- Phillips Screws Stainless Steel All
- Thread Rod Cut to Size Expansion Article • Fourteen Hex Nuts & Flat Washers Four Expansion Anchors Plastic Netting (if excess amount)
- on plate is not enough) Two Tie Wraps ☐ Tools Needed:
- Cordless Hammer Drill 5/16" Masonry Drill Bit for Plastic
- 1/2" Masonry Drill Bit for **Expansion Anchors**

Phillips Screwdriver

- 1. Follow instructions A if one side is level.
- 2. Drill 1/2" holes to accommodate expansion anchors. 3. Cut stainless steel rod to desired length. (Allow 1" inside
- expansion anchor and 1" through bottom plate) 4. Attach washers and hex nuts as shown in diagram.
- 5. Attach netting as shown in diagram.

Section 3 (Diagram C) Installation Instructions

1. Follow instruction for Section 2 A or B.

2. Follow instruction for Section 1

- ☐ Items Included: Can be attached with or without Same as Section 2 A or B retaining rails. Trash Guard Plus®
- (Chosen Size) Seven Plastic Anchors
- Seven Flat Washers • Seven 1.75" x .25" Stainless Steel Phillips Screws

☐ Tools Needed:

Same as Section 2 A or B

Section 4 (Diagram D & G) ☐ Items Included:

- Same as Section 2 A or B If inverted bottom
- Trash Guard® Plus (Chosen Size)
- Plastic Netting for Sides (Length Determined by Trash Guard Plus Size
- Fourteen Plastic Anchors
- Fourteen Flat Washers
- Fourteen 1.75" x .25" Stainless Steel Phillips Screws
- 3'Stainless Steel All-Tread Rod
- Seven Stainless Steel Hex Nuts and Seven
- Flat Washers and two Expansion Anchors Seven Tie Wraps

☐ Tools Needed:

- Cordless Hammer Drill 5/16" Masonry Drill Bit
- Phillips Screwdriver

Additional

 1/2" Masonry Drill Bit Hacksaw

Installation Instructions Can be attached with or without retaining rails. 1. Attach bottom plate to floor directly

under area where Trash Guard Plus® will sit.

(Use either A or B bottom instructions) 2. Drill the 5/16" holes on each side of Trash Guard Plus® near top and insert plastic anchors.

3. Drill 1/2" holes on each side of Trash Guard® near bottom insert expansion anchors. 4. Cut two sections from all thread Rod the length required for Trash Guard Plus® or retaining rails to hang perpendicular with top attached to wall (allow 1" inside anchors and 1" through Trash Guard Plus®

Flange or retaining rails) 5. Secure Trash Guard Plus® or retaining rails to top as shown in diagram.

9. Continue process until netting is attached to wall top and bottom.

6. Secure rods to expansion anchors and Trash Guard Plus® or retaining rails as shown in insert. 7. Attach plastic netting to Trash Guard Plus® flange or retaining rails with tie wraps as shown in insert. 8. Cut mesh from top tier of bricks and secure with plastic anchor, screw and washer as shown in insert.

Items Included: Same As Section 1 • Same As Section 2 A or B if inverted bottom

Plastic Netting for concave wall

Section 5 (Diagram F)

- Seven Stainless Steel Screws, Flat Washers and Plastic Anchors
- Tools Needed: Same As Section 2 A or B

Installation Instructions

- 1. Follow Instructions In Section 1 and Section 2 A or B if
- 2. Attach Plastic Netting To Trash Guard Plus® Flange or
- rails with Tie Wraps As Shown In Insert 3. Bend & Form Netting To Concaved Wall As Shown In Insert
- 4. Drill 5/16" Holes to Secure Netting To Wall
- 5. Secure Plastic Netting To Wall With Phillips Head Screws,

Plastic Anchors & Washers As Shown In Insert.


Section 6 (Diagram H)


Items Included: Same As Section 4


- Additional
- Top Expansion Strip
- Seven Phillip Head Screws, Flat Washers and Plastic Anchors
- Seven Hex Nuts and Flat Washers
- Two Additional Expansion Anchors
- **Tools Needed:**


Same As Section 4

- **Installation Instructions**
- 1. Follow Instructions In Section 4 2. Drill 1/2" holes each side of Trash Guard Plus® or retaining rails. Insert expansion anchors.
- 3. Cut four sections from all thread rod the expansion width desired. (allow 1" inside anchors & 1" through Trash Guard Plus® Flange or retaining rails.
- 4. Secure Rods to anchors & Trash Guard Plus® Flange or retaining rails as shown in insert.
- 5. Attach Plastic netting to Trash Guard Plus® Flange or retaining rails with tie wraps as shown in insert
- 6. Attach plastic netting to wall with phillips head screws, plastic anchors & washers as shown in insert. 7. Attach top expansion strip to wall with phillips head screws,









DRIVE

JRD

REDFC

8

DRAWINGS


ONSTRUC BMP DI


Ö

C-6.2

DRAWING

PROJECT NUMBER





S1 24" CURB AND GUTTER (S2) HANDICAP SIGN DETAILS

24" CONCRETE SPILL CURB & GUTTER

2. NEW SPACES SHALL NOT USE GROUND-

3. ACCESSIBLE SPACES ARE REQUIRED TO

NOT NECESSARY NOR REQUIRED.

4. STRIPING IS WHITE ON DARK PAVEMENT;

BE STRIPED OFF ONLY; BLUE COLORING IS

BLACK ON LIGHT PAVEMENT. (N.C.D.O.T.)

PAINTED SYMBOLS.

S3 CONCRETE PAVEMENT SECTION

SUBGRADE COMPACTED TO 95%

IN THE UPPER 12".

STANDARD PROCTOR AND 100%

(S5) HEAVY DUTY - ASPHALT PAVEMENT SECTION

SCARIFY 6" SUBGRADE

AND RECOMPACT 97%

STANDARD PROCTOR

1-18 STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C. ROADWAY STANDARD DRAWING FOR

EXISTING CURB AND GUTTER

S7 TYPE 2A MOD SIDEWALK RAMP

ISSUED FOR CONSTRUCTION

DRIVE

PLACE

ORD

REDFC

8

101

DRAWINGS . SHEET

CTION

CONSTRUC SITE DI

D-1.0 PROJECT NUMBER


449-19

S6 NCDOT CURB RAMP

1-18 STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR

EXISTING CURB AND GUTTER



1-18 STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR

CONCRETE CURB, GUTTER AND CURB & GUTTER

S11 NCDOT 30' CURB AND GUTTER

ROADWAY STANDARD DRAWING FOR

CONCRETE CURB, GUTTER AND CURB & GUTTER

1-18 STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

NO. REVISED PER TOR COMMENTS 8/28/19

SEAL.

D-1.1

PROJECT NUMBER

449-19

<u>PLAN</u>

CONCRETE FLUME

NOT TO SCALE

S12 24" CONCRETE FLUME DETAIL

GENERAL NOTES:

1-18 STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR

CONCRETE CURB, GUTTER AND CURB & GUTTER

2. CONCRETE SHALL BE 3000 psi.

1. FINISH ALL CONCRETE WITH CURING COMPOUND.

DRIVE

JRD


REDFC

115

8

DRAWINGS . SHEET

CONSTRUC SITE DI BICYCLE PARKING RACK




S14 PAVEMENT MARKINGS (TURN LANES)

DRIVE DRAWINGS. ORD CONSTRUC SITE DE REDFC 8 101

D-1.2 PROJECT NUMBER


449-19

ISSUED FOR CONSTRUCTION





КW




(U6) STANDARD TAPPING SLEEVE & VALVE


CITY OF RALEIGH

DEPARTMENT OF PUBLIC UTILITIES


TYPICAL REDUCED PRESSURE ZONE


BACKFLOW PREVENTER ASSEMBLY





5 1/2"-5 5/8"





NOTE: 2'x 2'x 6" CONCRETE PAD REQUIRED ON ALL

VALVE BOX COVER

> **VALVE** BOX

I) VALVE BOX NOT TO CONTACT WATER MAIN

2) ALL TRAFFIC CASTINGS MUST BE CLASS 35 OR

3) FOR ANY VALVES OVER 10' DEEP, A VALVE STEM EXTENSION MUST BE USED TO BRING TO A DEPTH O

NO MORE THAN 5', EXTENSION MUST BE A MINIMUM

4) TOTAL VALVE BOX WEIGHT: MINIMUM OF 85 LBS

CASTING

VALVES. NO PRECAST CONCRETE DOUGHNUT

SEE STANDARD W-18 FOR COVER DETAILS.

STANDARD VALVE BOX TOP SECTION TO BE SLIDE SECTION

USE 5" SOIL PIPE

STAB-IN C.I. OR D.I.

STANDARD VALVE BOX

BOTTOM SECTION

PIPE GASKET

BACKFILL

TAMPED _____

OF I" SOLID STOCK.

CITY OF RALEIGH


DEPARTMENT OF PUBLIC UTILITIES

VALVE BOX INSTALLATION


BACKFILL

FOR EXTENSIONS

APPROVED METHOD FOR EXTENSION OF VALVE BOX



VALVE BOX DROP LID 4" SKIRT



ONSTRUC UTILITY REDF(101

DRAWING

SHEET


D-2.0

PROJECT NUMBER


449-19


DRAVIL SHI

DRIVE





(U8) STANDARD THRUST BLOCKING







(U9) STANDARD ASPHALT PAVEMENT PATCH DETAIL











ISSUED FOR CONSTRUCTION DRAWING

DRAWINGS IL SHEET

ONSTRUC UTILITY

REDF(

101

D-2.1 PROJECT NUMBER 449-19

U14 FEBCO 825YA

Job Name	Contractor
Job Location	Approval
Engineer	Contractor's P.O. No.
Approval	Representative

LEAD FREE*

MasterSeries® LF880V Reduced Pressure Zone

Prevention Assemblies

Size: 21/2" - 10"

The FEBCO MasterSeries LF880V Reduced Pressure Zone Assembly is specifically designed to protect against possible backpressure and backsiphonage conditions for high hazard [i.e., toxic] application in accordance with Local Governing Water Utility Code. This Backflow Assembly is primarily used on potable drinking water systems where Local Governing Code mandates protection from non-potable quality water being pumped or siphoned back into the potable water system.

The LF880V features Lead Free* construction to comply with low lead installation requirements. The Lead Free* Reduced Pressure Zone Assemblies shall comply with state codes and standards, where applicable, requiring reduced lead content.

Features

- Inline Serviceable Assembly
- Horizontal "N-Pattern" Installations Vertical-Up "Z-Pattern" Installations
- No Special Tools Required for Servicing
- Captured Modular Spring Assembly
- Reversible & Replaceable Discs
- Field Replaceable Seats Ductile Iron Valve Body Design
- Stainless Steel Check Components
- Modular Pressure Differential Relief Valve Repairable Pressure Differential Relief Valve
- Clapper Check Assembly
- Captured O-ring Design



MODEL 880V REDUCED PRESSURE ZONE ASSEMBLY (Shown in standard orientation)

Specifications

The FEBCO MasterSeries LF880V Reduced Pressure Zone Assembly shall be installed on the potable water supply and at each point of cross-connection to protect against possible backpressure and backsiphonage conditions for high hazard [i.e., toxic] applications. The assembly shall consist of a main line valve body composed of a pressure differential relief valve located in a zone between two (2) independently acting approved clapper style check modules with replaceable seats and disc rubbers. Servicing of the pressure differential relief valve and both check modules does not require any special tools; both check modules are accessed through independently top entry covers. This assembly shall be fitted with AWWA Compliant inlet/outlet resilient seated shutoff valves; when used on a Fire-Sprinkler application, the assembly shall be fitted with approved UL/FM inlet/outlet resilient seated shutoff valves and contain four (4) properly located resilient seated test cocks as specified by AWWA Standard C511. Flow and pressure loss performance parameters shall meet the requirements of AWWA Standard C511.

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

NOTICE

Inquire with governing authorities for local installation requirements *The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

FEBCO product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact FEBCO Technical Service. FEBCO reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on FEBCO products previously or subsequently sold.



Size: 21/2" - 10"

Dimensions - Weights

ES-F-LF880V

Below are the nominal dimensions and physical weights for the Model LF880V size 21/2" through 10". Allowances must be made for normal manufacturing tolerances. Please visit our website to download a copy of this product's installation instructions, or contact your local FEBCO

Representative for more information. Model LF880V Model LF880V Standard Orientation (N-Pattern) **Vertical Orientation** (Z-Pattern) **Relief Valve Detail** Relief shipped on right side (shown) field reversible to left side.

SIZE	ZE DIMENSIONS												WEIGHT***															
	P	4	E	3	C		I)	E		F	:	(ì	H	1		l		J	K	*	Ľ	k*	NF	RS	08	SY
in.	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg.	lbs.	kg.
21/2	25½	654	12½	318	61/4	159	241/4	616	16%	422	13%	346	271/4	692	5½	140	71/4	184	3½	89	12%	321	16%	416	221	100	225	102
3	25¾	654	12½	318	61/4	159	241/4	629	16%	422	141//8	359	281/4	718	5½	140	71/4	184	3¾	95	12%	327	221/4	565	247	112	251	114
4	27%	708	14	356	7	178	26¾	680	17¾	451	15½	394	31	787	6	152	71/4	184	41/2	114	14%	365	231/4	591	344	156	356	162
6	321/4	819	16	406	8	203	321/4	819	21%	548	18%	473	371/4	946	7½	191	91/2	241	5½	140	18%	479	301//8	765	517	235	537	244
8	37½	953	18½	470	91/4	235	36%	324	247/8	632	20¾	527	41½	1054	8¾	222	101/4	260	6¾	172	23½	597	37¾	959	808	366	836	379
10	421/16	1068	21	533	107/16	264	40%	1032	27½	699	2311/16	601	475/16	1202	9%	238	11 ¹ / ₁₆	298	8	203	27½	699	45¾	1162	-	-	1344	610

* Indicates nominal dimensions with NRS Gate Valves

** Indicates nominal dimensions with OSY Gate Valves (Full Open Position) *** Indicates weight of complete Backflow Assemblies with specified Gate Valves

The gap drain is not designed to catch the maximum discharge possible from the relief valve. The installation of the FEBCO air gap with the drain line terminating above a floor drain will handle any normal discharge or nuisance spitting through the relief valve. However, floor drain size may need to be designed to prevent water damage caused by a catastrophic failure condition. Do not reduce the size of the drain line from the air gap fitting.

U15 FEBCO LF880V RPDA ASSEMBLY

DRIVE

)RD


REDFC


101


D-2.2 PROJECT NUMBER


ISSUED FOR

CONSTRUCTION










D1 CONCRETE CATCH BASIN

D2 FRAME, GRATES, AND HOOD



ISSUED FOR

CONSTRUCTION

DRAINAGE STRUCTURE STEPS

SHEET D-3.0

DRAWING

DRIVE

PLACE

REDFORD

115

 \approx


101


N DRAWINGS DETAIL SHEET

CTION NAGE [

CONSTRUC STORM DRAIN


PROJECT NUMBER 449-19







SILT FENCE OUTLET (E1 NTS

TEMPORARY SILT FENCE E2 NTS







STANDARD GRAVEL YARD INLET PROTECTION

CONSTRUCTION ENTRANCE

TEMPORARY DIVERSION DITCH NTS

ISSUED FOR

CONSTRUCTION

NTS

DRIVE DRAWINGS DETAIL SHEE **PLACE** CTION ORD CONSTRUCE EROSION CON REDF

8 101

115

DRAWING

D-4.0 PROJECT NUMBER


101

8

REVISED PER TOR COMMEN
REVISED PER TOR COMMEN
REVISED PER WAKE CO COI

DRAWING

D-4.1 PROJECT NUMBER 449-19









STANDARD CHECK DAM

- #57 WASHED STONE

FRONT VIEW

SIDE VIEW

DESIGN OF SPILLWAYS

10.0


NOTES:


1) HEIGHT & WIDTH DETERMINED BY EXISTING TOPOGRAF


2) KEY RIPRAP INTO THE DAM FOR STABILIZATION.


AND SEDIMENT STORAGE REQUIRED.

DIMENSIONS SHOWN ARE MINIMUM











ISSUED FOR CONSTRUCTION

ECS-1B™ Single Net Straw Biodegradable Rolled Erosion Control Product The ECS-1B™ is made with uniformly distributed 100% agricultural straw and one organic jute net securely sewn together with biodegradable thread. The tightly compressed blankets are wrapped and include a product label, code and installation guide. The blankets are palletized for easy transportation. The ECS-1B™ has functional longevity of approximately 12 months, but will vary depending on soil and climatic conditions, and is suitable for slopes 3:1 or less and low flow channels. The ECS-1B[™] meets Type 2.C specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) FP-03 Section 713.17. 100% Straw Top: Organic Leno Weave Jute Middle: None Bottom: None 0.5" x 1.0" Biodegradable Thread Natural 8 ft 2.4 m 4 ft 1.2 m 16 ft 4.9 m 112.5 ft 34.3 m 225 ft 68.6 m 112.5 ft 34.3 m 57 lbs 25.9 kg 57 lbs 25.9 kg 114 lbs 51.7 kg 100 yd² 83.6 m² 100 yd² 83.6 m² 200 yd² 167.2 m² #/Pallet: *Weight at time of manufacturing. Mass/Unit Area ASTM D6475 9.00 oz/yd² 305.1 g/m² 50mm (2in) / hr-30 min SLR**=6.73 ASTM D6525 0.30 in 7.62 mm 100mm (4in) / hr-30 min SLR**=7.45 ECTC Method 2 Rainfall ASTM D6818 106 lb/ft 150mm (6in) / hr-30 min SLR**=8.26 Tensile Strength-MD 1.55 kN/m **ASTM D6818** 17 % ECTC Method 3 Shear Resistance Shear at .50 in soil loss 1.40 lb/ft² **ASTM D6818** 118 lb/ft ECTC Method 4 Germination Top soil; Fescue; 21 day incubation 580 % Tensile Strength-TD ASTM D6818 26.8 % *Bench scale tests should not be used for design purposes. Light Penetration **ASTM D6567** 20 % **Soil Loss Ratio=Soil Loss Bare Soil/Soil Loss with RECP=1/C-Factor Density / Specific Gravity ASTM D792 ***The preceding test data excerpts were reproduced with the permission N/A g/cm³ of AASHTO, however, this does not constitute endorsement or approval of **ASTM D1117** Water Absorption the product, material or device by AASHTO *May differ depending upon raw material variations Property C-Factors ASTM D6459 3:1-2:1 Slope Length (L) ≤ 3:1

Manning's N (Value Represents a Range)

*Large-Scale Results obtained by 3rd Party GAI Accredited Independent

Proud Member and Participant of:

443 Bricker Road Bernville, PA 19506

1.800.582.4005 +1.610.488.8496 Fax +1.610.488.8494 INTERNA

SOME MUNICPALITIES DO NOT ALLOW GUTTER PROTECTION ON PUBLIC ROADS SILT BAGS SHOULD BE USED WITH THESE

BAGS SHOULD BE CLEANED OUT AFTER EVERY RAIN EVENT AND/OR AS NEEDED.

NTS

< 50 ft (15 m) 50 ft – 100 ft

>100 ft (30 m)

0.236

*Large-Scale Results obtained by 3rd Party GAI Accredited Independent Laboratory

1" REBAR FOR BAG

STANDARD SILT BAG - INLET SEDIMENT CONTROL DEVICE

STANDARD GRAVEL BAG INLET PROTECTION

INSTALLATION DETAIL

(1/4" NYLON ROPE,

TEMPORARY SKIMMER BASIN

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

	Re	equired Ground Stabil	ization Timeframes
Si	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zone -10 days for Falls Lake Watershed unless there is zero slope

ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below

- Temporary Stabilization • Temporary grass seed covered with straw or | • Permanent grass seed covered with straw or
- other mulches and tackifiers Hydroseeding
- Rolled erosion control products with or without temporary grass seed
- Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Appropriately applied straw or other mulch
 Shrubs or other permanent plantings covered with mulch Plastic sheeting Uniform and evenly distributed ground cover
 - Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

other mulches and tackifiers

sufficient to restrain erosion

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- . Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures. Apply flocculants at the concentrations specified in the NC DWR List of Approved *PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging
- 5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment. 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- 4. Collect all spent fluids, store in separate containers and properly dispose as
- hazardous waste (recycle when possible). Remove leaking vehicles and construction equipment from service until the problem
- has been corrected. 6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

ITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or
- provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds. 7. Empty waste containers as needed to prevent overflow. Clean up immediately if
- containers overflow. . Dispose waste off-site at an approved disposal facility.

9. On business days, clean up and dispose of waste in designated waste containers.

- PAINT AND OTHER LIQUID WASTE Do not dump paint and other liquid waste into storm drains, streams or wetlands. 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from

PORTABLE TOILETS


Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.

Provide staking or anchoring of portable toilets during periods of high winds or in high

foot traffic areas Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- 4. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in
- addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence. Install temporary concrete washouts per local requirements, where applicable. If an
- alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail. Do not use concrete washouts for dewatering or storing defective curb or sidewalk
- sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum.
- install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow. Locate washouts in an easily accessible area, on level ground and install a stone
- entrance pad in front of the washout. Additional controls may be required by the approving authority. Install at least one sign directing concrete trucks to the washout within the project
- limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary
- 0. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout

HERBICIDES, PESTICIDES AND RODENTICIDES Store and apply herbicides, pesticides and rodenticides in accordance with label

products, follow manufacturer's instructions.

- Store herbicides, pesticides and rodenticides in their original containers with the
- label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

SECTION C: REPORTING

(b) Oil spills if:

Occurrence

deposition in a

(b) Oil spills and

substances per Item

release of

hazardous

1(b)-(c) above

(c) Anticipated

bypasses [40 CFR

122.41(m)(3)]

(d) Unanticipated

bypasses [40 CFR

with the conditions

of this permit that

122.41(m)(3)]

may endanger

environment[40

CFR 122.41(I)(7)]

health or the

stream or wetland

1. Occurrences that Must be Reported

They are 25 gallons or more,

Permittees shall report the following occurrences:

(Ref: 40 CFR 302.4) or G.S. 143-215.85.

. Reporting Timeframes and Other Requirements

(a) Visible sediment • Within 24 hours, an oral or electronic notification.

case-by-case basis.

effect of the bypass

location of the spill or release.

quality and effect of the bypass.

(d) Anticipated bypasses and unanticipated bypasses.

(a) Visible sediment deposition in a stream or wetland.

They are less than 25 gallons but cannot be cleaned up within 24 hours,

(c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA

(e) Noncompliance with the conditions of this permit that may endanger health or the

After a permittee becomes aware of an occurrence that must be reported, he shall contact

the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800)

with the federal or state impaired-waters conditions.

Within 24 hours, an oral or electronic notification.

Within 24 hours, an oral or electronic notification.

Reporting Timeframes (After Discovery) and Other Requirements

. Within 7 calendar days, a report that contains a description of the

sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a

If the stream is named on the NC 303(d) list as impaired for sediment-

related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff

Within 24 hours, an oral or electronic notification. The notification

shall include information about the date, time, nature, volume and

A report at least ten days before the date of the bypass, if possible.

The report shall include an evaluation of the anticipated quality and

Within 7 calendar days, a report that includes an evaluation of the

• Within 7 calendar days, a report that contains a description of the

including exact dates and times, and if the noncompliance has not

continue; and steps taken or planned to reduce, eliminate, and

prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).

Division staff may waive the requirement for a written report on a

been corrected, the anticipated time noncompliance is expected to

noncompliance, and its causes: the period of noncompliance.

determine that additional requirements are needed to assure compliance

 They cause sheen on surface waters (regardless of volume), or They are within 100 feet of surface waters (regardless of volume).

- Create designated hazardous waste collection areas on-site.
- 2. Place hazardous waste containers under cover or in secondary containment.
- 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

SECTION A: SELF-INSPECTION Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend of holiday periods, and no individual-day rainfall information available, record the cumulative rain measurement for those ur attended days (and this will determine if a site inspection in needed). Days on which no rainfall occurred shall be recorded a "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, an 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit
(6) Ground stabilization measures	After each phase of grading	The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

SECTION B: RECORDKEEPING

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

- site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make
- this requirement not practical:
- (a) This General Permit as well as the Certificate of Coverage, after it is received. (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if

shown to provide equal access and utility as the hard-copy records.

. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART II, SECTION G, ITEM (4)

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

(a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,

Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include
- properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems, (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
 - NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

NORTH CAROLINA Environmental Quality

| EFFECTIVE: 04/01/19

PERMANENT SEEDING SCHEDULE

SEEDING MIXTURE PER NCDOT (EAST), ALTERNATE NATIVE SEED VARIETIES AND MIX RATES MAY BE CONSIDERED IF INCLUDED IN THE NC STATE UNIVERSITY/AT&T UNIVERSITY COOPERATIVE EXTENSION THAT'S APPROVED BY NCDEQ. AND TABLES IN NCDEQ EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL SECTION 6.11

MARCH 1- AUG. 31

RATE (LB/ACRE **SPECIES**

TALL FESCUE CENTIPEDE

BERMUDAGRASS (HULLED) FERTILIZER

SEPTEMBER 1 - FEBRUARY 28

RATE (LB/ACRE) TALL FESCUE CENTIPEDE BERMUDAGRASS (UNHULLED) FERTILIZER

SEEDBED PREPARATION

LIMESTONE

- . CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 2 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF
- 2. AVAILABLE. 3. RIP THE ENTIRE AREA TO 6 INCHES DEPTH.
- 4. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE LEAVING REASONABLY SMOOTH AND UNIFORM.
- 5. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL. 6. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONALBE UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP.
- 7. SEED ON A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- 8. MULCH IMMEDIATELY AFTER SEEING AND ANCHOR MULCH. 9. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND

SHOULD BE OVER 60% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.

ON CUT AND FILL SLOPES 2:2 OR STEEPER CENTIPEDE SHALL BE APPLIED AT THE RATE OF 5 LBS/ACRE AND ADD 20 LB/ACRE OF SERICEA

FERTILIZER SHALL BE 10-20-20 ANALYSIS. A DIFFERENT ANALYSIS OF FERTILIZER MAY BE USED PROVIDED THE 1-2-2 RATIO IS MAINTAINED AND THE RATE OF APPLICATION ADJUSTED TO PROVIDE THE SAME AMOUNT OF PLANT FOOD AS 10-20-20 ANALYSIS AND AS DIRECTED.

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET

REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

TEMPORARY SEEDING SCHEDULE

SEEDING MIXTURE PER NCDEQ EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL IN THE

(LATE WINTER AND EARLY SPRING): JAN. 1-MAY 1

NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

RATE (LB/ACRE)

ANNUAL LESPEDEZA (KOBE IN PIEDMONT AND COASTAL PLAIN, KOREAN IN MOUNTAINS

OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.

RATE (LB/ACRE

GERMAN MILLET

IN THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDAN GRASS MAY BE SUBSTITUTED AT A RATE OF 50 LB/ACRE.

(FALL): AUG. 15- DEC. 30

RATE (LB/ACRE) **SPECIES**

RYE (GRAIN)

SOIL AMENDMENTS: FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE:


REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE. FOR THE FALL, REPAIR AND REFERTILIZE DAMAGED AREAS IMMEDIATELY. TOP DRESS WITH 50 LB/ACRE KOBE (PIEDMONT AND COASTAL PLAIN) OR KOREAN (MOUNTAINS) LESPEDEZA IN LATE FEBRUARY OR EARLY MARCH.

> ISSUED FOR CONSTRUCTION

PI ORD SONSTRUC SION CON **REDF** 115

PROJECT NUMBER

D-4.2



GENERAL PLANTING NOTES:

ALL LANDSCAPING SHALL BE INSTALLED ACCORDING TO SOUND NURSERY PRACTICES AND SHALL MEET ALL STANDARDS AS STATED IN THE LATEST EDITION OF 'AMERICAN STANDARD FOR NURSERY STOCK'.

PLANT LIST QUANTITIES ARE PROVIDED FOR CONVENIENCE ONLY. IN THE EVENT OF QUANTITY DISCREPANCIES, THE DRAWINGS SHALL TAKE

NO SUBSTITUTIONS SHALL BE MADE WITHOUT WRITTEN AUTHORIZATION FROM THE OWNER OR LANDSCAPE DESIGNER.

CONTRACTOR SHALL HAVE UTILITY COMPANY LOCATE ALL UTILITIES PRIOR TO DIGGING. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES **INCURRED BY HIS/HER WORK.**

METHODS OF TREE STAKING INDICATED ON THE DRAWINGS ARE SUGGESTIONS ONLY. THE LANDSCAPE CONTRACTOR SHALL USE WHATEVER METHOD HE DEEMS FIT, HOWEVER HE WILL BE HELD LIABLE FOR ANY DAMAGES CAUSED TO TREES BY IMPROPER STAKING METHODS (OR ABSENCE OF STAKING) AND IS RESPONSIBLE FOR UPRIGHTING AND REPLANTING TREES WHICH ARE BLOWN

ALL AREAS NOT SHOWN AS HARD SURFACES, PLANT BED, MULCHED OR UNDISTURBED AREAS, SHALL BE SEEDED OR SODDED AS LAWN WITH "REBEL IV", CONFEDERATE PLUS OR LESCO TALL TURF TYPE FESCUE FOR IN ALL AREAS IN RIGHT OF WAY UP TO THE ROAD.

ALL LANDSCAPE BEDS CONTAIN TRIPLE SHREDDED HARDWOOD MULCH AT A

ALL LANDSCAPE BEDS SHALL HAVE POSITIVE DRAINAGE AWAY FROM ALL

9. ALL PLANT BEDS SHALL BE TREATED WITH PRE-EMERGENT WEED CONTROL

(I.E. TREFLON GRANULES). 10. ALL PLANTS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE

AMERICAN ASSOCIATION OF NURSERYMEN AND SHALL BE VIGOROUS, HEALTHY MATERIAL FREE OF PESTS AND DISEASE.

11. VERIFICATION OF TOTAL QUANTITIES AS SHOWN ON THE PLANT LIST SHALL BE THE RESPONSIBILITY OF THE PLANTING CONTRACTOR, AND THE TOTAL QUANTITIES SHALL BE REQUIRED ON THE PLANTING PLAN.

12. OWNERS SHALL MAINTAIN ALL PLANT BEDS AND PLANT MATERIAL IN GOOD HEALTH, AND ANY DEAD, UNHEALTHY OR MISSING PLANTS SHALL BE REPLACED WITH THE SAME PLANT MATERIAL ORIGINALLY SPECIFIED ON THIS

13. PLANT MATERIAL ON THIS SITE MUST BE INSTALLED IN CONFORMANCE WITH THE GENERAL PLANTING NOTES AND DETAILS ON THIS PLAN OR TO THE STANDARDS OF TOWN OF ROLESVILLE.

14. LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED PERMITS AND LICENSES TO PERFORM THE REQUIRED WORK.

LANDSCAPE CALCULATIONS:

STREETSCAPE BUFFERS

REDFORD PLACE DRIVE

30' STREETSCAPE BUFFER - THOROUGHFARE

REQUIRED: COLLECTOR STREET / 1 STREET TREE EVERY 50 LF 489 LF / 50 = 9.78 STREET TREES

PROVIDED: 10 STREET TREES

10' STREETSCAPE BUFFER - 10 D

REQUIRED: STREET FRONT TYPE D / 1 TREE EVERY 40 LF 186 LF / 40 = 4.73 DECIDUOUS CANOPY TREE (TWO UNDERSTORY ORNAMENTAL TREES IN SUBSTITUTE OF ONE DECIDUOUS CANOPY TREE WHEN OVERHEAD UTILITY LINES ARE PRESENT)

4.73 TREES = 9.46 UNDERSTORY ORNAMENTAL TREES PROVIDED: 10 UNDERSTORY ORNAMENTAL TREES

LANDSCAPE BUFFERS

25' LANDSCAPE BUFFER - 25 B

REQUIRED: SEMI-OPAQUE TYPE B SEMI-OPAQUE SCREEN FROM GROUND TO 3' MIN. HEIGHT OF 20' NO UNOBSTRUCTED OPENINGS WIDER THAN 20' BETWEEN

TREE CANOPIES MIN. 50% OF SHRUBS TO BE EVERGREEN

PROVIDED: 8 EVERGREEN TREES

8 EVERGREEN SHRUBS

D EAST BUFFER (AGAINST CEMETERY)

REQUIRED: SEMI-OPAQUE TYPE B

SEMI-OPAQUE SCREEN FROM GROUND TO 3' MIN. HEIGHT OF 20'

NO UNOBSTRUCTED OPENINGS WIDER THAN 20' BETWEEN TREE CANOPIES

MIN. 50% OF SHRUBS TO BE EVERGREEN

PROVIDED: 6 EVERGREEN TREES **8 EVERGREEN SHRUBS**

1 DECIDUOUS TREE

EAST BUFFER (AGAINST SCHOOL)

10' LANDSCAPE BUFFER - 10 C

REQUIRED: SPATIAL DEFINITION TYPE C NO UNOBSTRUCTED OPENINGS WIDER THAN 50' BETWEEN

TREE CANOPIES PROVIDED: 8 DECIDUOUS TREES

F VEHICULAR USE AREAS (VUAs)

REQUIRED: VUAs SHALL BE WITHIN 60' OF CANOPY TREES SCREEN OFF-SITE VIEWS WITH CONTINUOUS EVERGREEN

PROVIDED: 23 CANOPY TREES 232 EVERGREEN SHRUBS DRAWING SHEET

EVISED PEI EVISED PEI EVISED PER EVISED PER EVISED PER

REVENE

DRA:


ISTRUC LAND

NO O

)RD


REDF

PROJECT NUMBER



- 1. CONTRACTOR IS RESPONSIBLE FOR
- ADEQUATE DRAINAGE OF ALL PLANTING PITS. (POSITIVE DRAINAGE AWAY FROM PIT)
- 2. ADHERE TO STANDARDS IN THE CITY TREE MANUAL.
- 3. STREET TREES MUST BE 3" CALIPER AT
- INSTALLATION WITH A 5' MINIMUM FIRST
- BRANCH HEIGHT. 4. PLANTING SEASON OCTOBER - APRIL.
- 5. A TREE IMPACT PERMIT IS REQUIRED.
- 6. ELECTRICAL OUTLETS AND OTHER UTILITIES
- ARE PROHIBITED IN THE PLANTING AREA IMMEDIATELY SURROUNDING THE TREE.

TREE PLANTING FOR B&B TREES



L2 SHRUB PLANTING

ISSUED FOR CONSTRUCTION

DRIVE

ICTION DRAWINGS

APE DETAIL SHEET

ORD

REDFC

101

L-1.1 PROJECT NUMBER

S. PUBLIC RING			Description Lumens LLF QTY Wattage
**************************************	*0.0 *0.0 *0.0 *0.0 *0.0 *0.0 *0.0 *0.0		
	1.2 1.1 1.2 1.1 1.3 1.6 1.5 1.1 1.4 1.3 1.6 1.5 1.1 1.5 1.6 1.8 1.2 1.6 1.8 1.2 1.6 1.8 1.2 1.6 1.3 1.7 1.8 1.3 1.8 1.3 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8	FIXTURE "A" & "B"	
†0.5 †1.1 †1.9 †2.3 †2.2 †0.3 †0.8 †1.9 \$3.2 †3.1 †0.5 †1.5 †3.3 †4.2 †1.1 †2.3 †3.6 †1.0 †1.1 †1.8	**\frac{1.8}{1.7} \frac{1}{1.8} \frac{1}{1.8} \frac{1}{2.0} \frac{1}{2.1} \frac{1}{2.2} \frac{1}{2.1} \frac{1}{2.2} \frac{1}{2.2} \frac{1}{2.5} \frac{1}{2.0} \frac{1}{1.4} \frac{1}{1.0} \frac{1}{1.1} \frac{1}{2.3} \frac{1}{3.9} \frac{1}{3.2} \frac{1}{2.4} \frac{1}{2.3} \frac{1}{2.0} \frac{1}{1.0} \frac{1}{1.0} \frac{1}{1.1} \frac{1}{2.3} \frac{1}{3.9} \frac{1}{3.2} \frac{1}{2.3} \frac{1}{2.0} \frac{1}{1.0} \frac{1}{1.0} \frac{1}{1.1} \frac{1}{2.3} \frac{1}{3.9} \frac{1}{3.2} \frac{1}{2.3} \frac{1}{2.0} \frac{1}{2.0	.8 .1	
	†0.7 †1.5 †2.2 †2.6 †2.4 †2.0 †1.7 †1.3 †1.1 †1.2 †2.2 †3.0 †3.4 †3.0 †0.4 †1.0 †2.1 †2.9 †2.6 †2.1 †1.9 †1.5 †1.2 †1.0 †1.7 †2.7 †3.3 †2.1 †0.3 †0.6 †1.8 †3.6 †3.5 †2.6 †2.1 †1.8 †1.4 †1.3 †1.4 †2.6 †3.7 †3.7 †3.7 †3.7 †3.7 †3.7 †3.8 †4.3 †3.1 †2.3 †2.1 †1.8 †1.6 †1.6 †2.6 †4.4 †4.4 †4.6 †3.7 †3.7 †3.8 †4.3 †3.1 †2.3 †2.1 †1.8 †1.6 †1.6 †2.6 †4.4 †4.5 †4.6 †3.7 †3.7 †3.8 †4.3 †3.1 †2.3 †2.1 †1.8 †1.6 †1.6 †2.6 †4.4 †4.5 †3.7 †3.8 †3.1 †3.8 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.2 †3.1 †3.1 †3.1 †3.2 †3.1 †3.1 †3.1 †3.1 †3.1 †3.1 †3.1 †3.1	2.9 †2.4 †1.9 †1.2 2.2 †2.5 †2.1 †1.4 †0.9 2.0 †2.8 †2.2 †1.1 †1.1 2.5 †3.0 †2.3 †1.8 †1.3 3.8 †3.1 †2.5 †2.0 †1.6 †1.2	
	†0.5 †1.2 †2.0 †2.7 †2.9 †2.7 †2.4 †2.1 †1.9 †2.1 †1.0 †2.7 †3.2 †2.8 †2.5 †2.4 †2.0 †2.1 †1.0 †2.2 †4.0 †3.5 †2.8 †2.6 †2.3 †2.6 †2.6 †2.6 †2.6 †2.6 †2.6 †2.6 †2.6	2.2 †2.4 †2.2 †1.8 †3 †1.0 1.1 †2.3 †2.2 †2.0 †1.7 †1.3 †1.0 1.2 †2.2 †2.0 †1.9 †1.6 †1.2 †0.9 †0.7 1.4 †2.7 • †2.2 †1.9 †1.6 †1.2 †0.9 †0.7 1.6 †2.5 †1.7 †2.0 †1.6 †1.2 †0.9 †0.7 †0.5 1.0 †2.8 2.6 †2.2 †1.8 †1.6 †1.2 †0.9 †0.7 †0.5	
EX. FH	EX. WV †0.3 †0.4 †0.5 †0.9 †1.4 †1.9 †2.3 †2. †0.3 †0.4 †0.5 †0.9 †1.4 †1.9 †2. †0.2 †0.3 †0.4 †0.7 †1.5 †2. †0.2 †0.3 †0.5 †1.0 †1.0 †2.	2.8	
	†0.6 †1.0 †1. †0.6 †1.0 †1. †0.6 †0. †0.3 †0.	1.3	
		†0.1 †0.2 †0.3 †0.1	

 Description
 Symbol
 Avg
 Max
 Min
 Max/Min
 Avg/Min

 PARKING LOT
 +
 2.4 fc
 4.7 fc
 1.0 fc
 4.7:1
 2.4:1

 PROPERTY LINE
 +
 0.4 fc
 1.0 fc
 0.0 fc
 N/A
 N/A

1. Based on initial footcandle levels.

ANGUS CLARK
ENGINEERING PC
NCBEES #C-2726
543 KEISLER DRIVE

SUITE 101 CARY NORTH CAROLINA 27518 919 859.2674 919 859.2675 FAX

DRIVE

PLACE

CONSTRUCTION

LIGHTING

REDFORD 115 8

101

DRAWING SHEET

GRAPHIC SCALE

(IN FEET) 1 inch = 30 ft.

SLI-1.0

PROJECT NUMBER 449-19








West (Redford Place Drive) Elevation


SCALE 3/16" = 1'-0"



BUILDING CE DRIVE

TRIANGLE FAMILY DENTIS
MEDICAL OFFICE BUILDI
101 REDFORD PLACE DRIVE
ROLESVILLE, NORTH CAROLINA





ARCHITECT'S STAMP				
No	Rev./Submissons Date			
	NEIGHB	07/17/19		
	PERMIT		06/11/21	
SCALE		PROJECT NO		
AS NOTED		190701		
DESIGNED		DATE		
RSR		11 JUNE 21		
DRAWN		CHECKED		
RSR		RSR		


BUILDING
ELEVATIONS

A2.0



South (Parking) Elevation


SCALE 3/16" = 1'-0"




2 East (Elementary School) Elevation Scale 3/16" = 1'-0"



TRIANGLE FAMILY DENTISTRY MEDICAL OFFICE BUILDING 101 REDFORD PLACE DRIVE ROLESVILLE, NORTH CAROLINA





ARCHITECT'S STAMP					
No	Rev./Submissons Date				
	NEIGHB	07/17/19			
	PERMIT		06/11/21		
SCALE		PROJECT NO			
AS NOTED		190701			
DESIGNED		DATE			
RSR		11 JUNE 21			
DRAWN		CHECKED			
RSR		RSR			

BUILDING
ELEVATIONS

A2.1