

Roy Cooper Governor J. Eric Boyette
Secretary

June 5, 2023

# **Harris Creek Farm Development**

## Traffic Impact Analysis Review Report Congestion Management Section

TIA Project: SC-2023-115

Division: 5

County: Wake



Nicholas C. Lineberger, P.E. Regional Engineer Charles V. Sorrell, Project Engineer Daniel W. Collins, Project Design Engineer

Harris Creek Farm Development					
SC-2023-115	Rolesville	Wake County			

Per your request, the Congestion Management Section (CMS) of the Transportation Mobility and Safety Division has completed a review of the subject site. The comments and recommendations contained in this review are based on data for background conditions presented in the Traffic Impact Analysis (TIA) and are subject to the approval of the local District Engineer's Office and appropriate local authorities.

Date Initially Received by CMS	05/08/23	Date of Site Plan	09/30/22
Date of Complete Information	05/08/23	Date of Sealed TIA	05/08/23

## **Proposed Development**

The TIA assumes the development is completed by 2027 and consists of the following:

Land Use	Land Use Code	Size
Single-Family Detached Housing	210	68 d.u.
Single-Family Attached Housing	215	81 d.u.

Trip Generation - Unadjusted Volumes During a Typical Weekday					
	IN	OUT	TOTAL		
AM Peak Hour	22	66	88		
PM Peak Hour	70	44	114		
Daily Trips			1,276		

#### **General Reference**

For reference to various documents applicable to this review please reference the following link: <a href="https://connect.ncdot.gov/resources/safety/Pages/Congestion-Management.aspx">https://connect.ncdot.gov/resources/safety/Pages/Congestion-Management.aspx</a>

Once the driveway permit has been approved and issued, a copy of the final driveway permit requirements should be forwarded to this office. If we can provide further assistance, please contact the Congestion Management Section.

### Signalization

We defer to the District Engineer, the Division Traffic Engineer, and the Regional Traffic Engineer for final decisions regarding signalization.



