



East Young Street Sidewalk – Phase 2A

Addendum #1

The following changes and clarifications are applicable to the referenced project and are now a part of its contract documents. Where any article, division, or subparagraph of the original contract documents or other addenda is supplemented herein, the provisions of the original documents shall remain in effect. All the supplemental provisions shall be considered as added thereto. Where any such article, division, or subparagraphs are amended, voided, or superseded thereby, the provisions of such article, division, or subparagraph not so specifically amended, voided, or superseded shall remain in effect.

The attention of each contractor is called to the following clarifications, additions to, and changes in the plans sealed on May 23, 2019, and specifications and contract documents sealed on May 24, 2019, for the above project. It will be the responsibility of each contractor to call such clarifications, additions, and changes in plans and specifications to the attention of subcontractors concerned. The Town in no way assumes any responsibility for notifying any subcontractor, material dealers, or others not having received the original contract documents.

Updated Proposal Due Date

Proposals Due: Monday, June 17, 2019 at 11:00am
Submit sealed proposals
Opening to be held at:
Rolesville Town Hall, 502 Southtown Circle, Rolesville NC 27571

Updated Bid Proposal Form

See the attached Bid Proposal form. This project has been updated from a lump sum bid to a unit cost bid, based upon the estimated quantities from the designing engineer.

Updated Erosion Control Plans

The erosion control plans from the original bid set have been updated to better reflect the delineation between Phase 2A and Phase 2B.

Submitted Questions & Answers

The following questions and comments were received after the pre-bid meeting on May 31, 2019:

- (1) Sheet 2A - there is a key in detail shown. Is there any area where this detail is applicable?
AMT Response: This is a standard NCDOT detail used to show how the pavement is to tie back to existing at begin/end road limits. Because there is some widening along E. Young street, we felt the need to include this detail.

- (2) Sheet 4 - There is a note that states "if required existing columns are to be relocated in similar fashion outside area of construction " Can this be clarified? As written, this is a wide open statement for a lump sum job .
Response: For the purpose of this bid, it is not anticipated that the project will relocate the brick entrance columns.
- (3) Sheet EC-04 - should there be additional key notes indicating the erosion control items on this sheet. there is a key note showing pavement removal.
AMT Response: No additional key notes are required. Please refer to Legend on Sheet EC-2.
- (4) Sheet EC-04 - There is a concrete washout structure indicated. will this be required?
AMT Response: Yes, this was required by NCDOT.
- (5) Sheet UO-1 - On each side of US 401 there are existing traffic signal boxes indicated to be adjusted. Please clarify the intent of this note.
Response: For the purpose of this bid, it is not anticipated that the project will relocate the traffic signal boxes.
- (6) On Sheet 4 approximate station 13+85 there is an existing brick column (not shown) that has a paper box attached and a mail box inside. Are we responsible to remove and replace "AS IS" this brick column?
Response: It is anticipated that the brick mailbox column will be relocated. The Town will assist in the coordination of said relocation. This item will be paid separately.
- (7) On Sheet 4 there are several DOT directional signs (not shown) that appear to be within the new sidewalk area. Is this contractor responsible to remove and re-install these directional signs?
AMT Response: Yes, these signs are to be relocated following NCDOT Standard Drawings and Specifications. An updated bid spreadsheet has been provided to include the following pay item:
- 4116100000-N – Sign Erection, Relocate Type F
- (8) On Sheet 4 there is a key note symbol for pavement removal. Sheet UO-1 shows this pavement removal to be within the existing monolithic islands between approximate stations 15+00 to 17+00. This appears to have been done under a previous contract. Comment?
AMT Response: This note is intended for the future Phase B and should be removed from Phase A plans. The note should also be updated to say "concrete" rather than pavement.
- (9) On Sheet UO-1 approximate station 15+00 there are two existing traffic signal boxes shown to be adjusted. A field inspection shown the ere three of these traffic signal boxes in this area. Comment.
Response: For the purpose of this bid, it is not anticipated that the project will relocate the traffic signal boxes.
- (10) Sheet PMP-3 indicates pavement marking. has this pavement marking been previously installed?
AMT Response: No pavement markings are required for Phase A. This was intended to be shown in future Phase

BID PROPOSAL

Name of Contractor _____

Address _____

City / State / ZIP _____

License # _____

Contact Person _____

Telephone _____ Email _____

Acknowledgements & Representations

Bidder agrees, if this proposal is accepted, to enter into an Independent Contractor Service Agreement, as included in the request for proposal, and to perform all work as specified or indicated for the prices and within the times indicated.

Bidder has visited the site, conducted a thorough, alert visual examination of the site and adjacent areas, and become familiar with and satisfied itself as to the general, local, and site conditions that may affect cost, progress, and performance of the work.

Bidder is familiar with and has satisfied itself as to all laws and regulations that may affect cost, progress, and performance of the work.

Bidder is aware of the general nature of the work to be performed at the site, and the bidding documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance and furnishing of work.

Bidder has not directly or indirectly induced or solicited any other bidder to submit a false or sham bid, and bidder has not solicited or induced any individual or entity to refrain from bidding.

Bidder acknowledges that award will be based on the unit prices listed below. This supersedes the original RFP document referencing lump sum bids.

EAST YOUNG STREET SIDEWALK – PHASE 2A							
Line	Item	Sec	Description	Quantity	Units	Unit Cost	Amount
1	0000100000-N	800	Mobilization	1	LS		
2	0000400000-N	801	Construction Survey	1	LS		
3	0043000000-N	226	Grading	1	LS		
4	0057000000-E	226	Undercut Excavation	50	CY		
5	0156000000-E	250	Removal of Existing Asphalt Pavement	410	SY		
6	0196000000-E	270	Geotextile for Soil Stabilization	100	SY		
7	0318000000-E	300	Foundation Cond. Mat., Minor Strs	60	Tons		
8	0320000000-E	300	Foundation Cond. Geotextile	180	SY		
9	0343000000-E	310	15” Side Drain Pipe	36	LF		
10	0345000000-E	310	24” Side Drain Pipe	144	LF		

EAST YOUNG STREET SIDEWALK – PHASE 2A

Line	Item	Sec	Description	Quantity	Units	Unit Cost	Amount
11	0342000000-E	310	30" Side Drain Pipe	20	LF		
12	0448200000-E	310	15" RC Pipe Culv, Class IV	288	LF		
13	0995000000-E	340	Pipe Removal	32	LF		
14	1099500000-E	505	Shallow Undercut	25	CY		
15	1099700000-E	505	Class IV Subgrade Stabilization	50	Tons		
16	1231000000-E	560	Shoulder Borrow	24	CY		
17	1491000000-E	610	Asphalt Concrete Base Course, Type B 25.0 C	120	Tons		
18	1503000000-E	610	Asphalt Binder Course, Type I 19.0 C	30	Tons		
19	1519000000-E	610	Asphalt Concrete Surface Course, Type SF 9.5 B	50	Tons		
20	1575000000-E	620	Asphalt Binder for Plant Mix PG 64-22	15	Tons		
21	2286000000-N	840	Masonry Drainage Structures	15	Each		
22	2367000000-N	840	Frame w/ Two Grates, 840.29	2	Each		
23	2374000000-N	840	Frame w/ Grate & Hood, Std. 840.03E	2	Each		
24	2374000000-N	840	Frame w/ Grate & Hood, Std. 840.03F	3	Each		
25	2374000000-N	840	Frame w/ Grate & Hood, Std. 840.03G	3	Each		
26	2396000000-N	840	Frame w/ Cover, Std. 840.54	4	Each		
27	2549000000-E	846	2'-6" Concrete Curb and Gutter	830	LF		
28	2591000000-E	848	4" Concrete Sidewalk	490	SY		
29	2605000000-N	848	Concrete Curb Ramps	3	Each		
30	3649000000-E	876	Rip Rap, Class B	13	Tons		
31	3656000000-E	876	Geotextile for Drainage	35	SY		
32	4116100000-N	904	Sign Erection, Relocate Type F	9	Each		
33	4400000000-E	1110	Work Zone Signs (Stationary)	104	SF		
34	4405000000-E	1110	Work Zone Signs (Portable)	104	SF		
35	4415000000-N	1115	Flashing Arrow Board	2	Each		
36	4430000000-N	1130	Drums	37	Each		
37	3656000000-E	876	Geotextile for Drainage	95	SY		
38	6000000000-E	1605	Temporary Silt Fence	410	LF		

EAST YOUNG STREET SIDEWALK – PHASE 2A

Line	Item	Sec	Description	Quantity	Units	Unit Cost	Amount
39	6006000000-E	1610	Erosion Control Stone, Class A	85	Tons		
40	6009000000-E	1610	Erosion Control Stone, Class B	25	Tons		
41	6012000000-E	1610	Sediment Control Stone	145	Tons		
42	6015000000-E	1615	Temporary Mulching	1.0	Acre		
43	6018000000-E	1620	Seed for Temporary Seeding	100	LB		
44	6021000000-E	1620	Fertilizer for Temporary Seeding	0.5	Tons		
45	6024000000-E	1622	Temporary Slope Drains	200	LF		
46	6030000000-E	1630	Silt Excavation	60	CY		
47	6036000000-E	1631	Matting for Erosion Control	370	SY		
48	6042000000-E	1632	¼” Hardware Cloth	600	LF		
49	6045000000-E	SP	24” Temporary Pipe	20	LF		
50	6071010000-E	SP	Wattle	20	LF		
51	6084000000-E	1660	Seeding and Mulching	3	Acre		
52	6087000000-E	1660	Mowing	0.5	Acre		
53	6090000000-E	1661	Seed for Repair Seeding	50	LB		
54	6093000000-E	1661	Fertilizer for Repair Seeding	0.25	Tons		
55	6096000000-E	1662	Seed for Supplemental Seeding	50	LB		
56	6108000000-E	1665	Fertilizer Topdressing	0.75	Tons		
57	6114500000-N	1667	Specialized Hand Mowing	10	MHR		
58	6117000000-N	1675	Response for Erosion Control	13	Each		
59	6132000000-N	SP	Concrete Washout Structure	1	Each		
60	2830000000-N	858	Adjust Manhole	1	Each		

TOTAL

Signature

Printed name /Title

Date