



East Young Street Sidewalk – Phase 2A

Addendum #3

The following changes and clarifications are applicable to the referenced project and are now a part of its contract documents. Where any article, division, or subparagraph of the original contract documents or other addenda is supplemented herein, the provisions of the original documents shall remain in effect. All the supplemental provisions shall be considered as added thereto. Where any such article, division, or subparagraphs are amended, voided, or superseded thereby, the provisions of such article, division, or subparagraph not so specifically amended, voided, or superseded shall remain in effect.

The attention of each contractor is called to the following clarifications, additions to, and changes in the plans sealed on May 23, 2019, and specifications and contract documents sealed on May 24, 2019, for the above project. It will be the responsibility of each contractor to call such clarifications, additions, and changes in plans and specifications to the attention of subcontractors concerned. The Town in no way assumes any responsibility for notifying any subcontractor, material dealers, or others not having received the original contract documents.

Updated Proposal Due Date

Proposals Due: Tuesday, June 25, 2019 at 3:00pm
Submit sealed proposals

Updated Project Scope

Due to budgetary constraints, the project scope has been reduced. The project now generally includes 275 linear feet of concrete sidewalk from the current terminus at the Cedar Lakes subdivision to the north side of the 401 Bypass.

Updated Bid Proposal Form

See the attached Bid Proposal form. Revisions reflect estimates for the proposed scope of work and are simplified as described below:

- All construction shall occur in the southwest quadrant of US 401 and East Young Street.
- All borrow and/or excavation, with the exception of undercut shall be paid under the lump sum grading quantity.
- The project size is such that a formal erosion control permit shall not be required. However, the attached quantities reflect anticipated field recommendations and requirements to ensure sedimentation does not leave the site. The installation of said quantities will closely but not completely follow the plan locations. This is intended to facilitate, not hinder construction.
- All seeding, mulching and fertilization shall be paid under one item. The estimate quantities allow for a minimum of two complete applications.
- The concrete wash structure shall be field located within the project limits.

BID PROPOSAL

Name of Contractor _____
Address _____
City / State / ZIP _____
License # _____

Contact Person _____
Telephone _____ Email _____

Acknowledgements & Representations

Bidder agrees, if this proposal is accepted, to enter into an Independent Contractor Service Agreement, as included in the request for proposal, and to perform all work as specified or indicated for the prices and within the times indicated.

Bidder has visited the site, conducted a thorough, alert visual examination of the site and adjacent areas, and become familiar with and satisfied itself as to the general, local, and site conditions that may affect cost, progress, and performance of the work.

Bidder is familiar with and has satisfied itself as to all laws and regulations that may affect cost, progress, and performance of the work.

Bidder is aware of the general nature of the work to be performed at the site, and the bidding documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance and furnishing of work.

Bidder has not directly or indirectly induced or solicited any other bidder to submit a false or sham bid, and bidder has not solicited or induced any individual or entity to refrain from bidding.

Bidder acknowledges that award will be based on the unit prices listed below. This supersedes the original RFP document referencing lump sum bids.

EAST YOUNG STREET SIDEWALK – PHASE 2A						
Line #	Sec #	Description	Quantity	Units	Unit Cost	Amount
1	800	Mobilization	1	LS		
2	801	Construction Survey	1	LS		
3	226	Grading	1	LS		
4	226	Undercut Excavation	22	CY		
5	250	Removal of Existing Asphalt Pavement	31	SY		
6	300	Foundation Cond. Mat., Minor Strs	10	Tons		
7	310	15” RC Pipe Culv, Class IV	32	LF		
8	505	Class IV Subgrade Stabilization	6	Tons		
9	610	Asphalt Concrete Base Course, Type B 25.0 C	40	Tons		
10	610	Asphalt Binder Course, Type I 19.0 C	8	Tons		
11	610	Asphalt Concrete Surface Course, Type SF 9.5 B	16	Tons		
12	620	Asphalt Binder for Plant Mix PG 64-22	5	Tons		
13	840	Masonry Drainage Structures	5	Each		
14	840	Tie to Existing Masonry Drainage Structure	1	Each		
15	840	Frame w/ Grate & Hood, Std. 840.03F	3	Each		

EAST YOUNG STREET SIDEWALK – PHASE 2A

16	840	Frame w/ Cover, Std. 840.54	2	Each		
17	846	2'-6" Concrete Curb and Gutter	275	LF		
18	848	4" Concrete Sidewalk	190	SY		
19	848	12' Concrete driveway apron	2	Each		
20	848	Concrete Curb Ramps	1	Each		
21	904	Sign Erection, Relocate Type F	2	Each		
22	1110	Work Zone Signs (Portable)	192	SF		
23	1130	Drums	14	Each		
24	1605	Temporary Silt Fence	300	LF		
25	1610	Erosion Control Stone, Class A	5	Tons		
26	1610	Erosion Control Stone, Class B	5	Tons		
27	1610	Sediment Control Stone	12	Tons		
28	1631	Matting for Erosion Control	100	SY		
29	1632	¼" Hardware Cloth	20	LF		
30	1660	Seeding and Mulching	0.6	Acre		
31	SP	Concrete Washout Structure	1	Each		

TOTAL _____

Signature _____

Printed name /Title _____

Date _____