# ROLESVILLE CROSSING

# CONSTRUCTION DOCUMENTS - PHASE 1 & 2

ROLESVILLE PROJECT # CD 21-08 1801 ROLESVILLE RD ROLESVILLE, NORTH CAROLINA 27587

WAKE COUNTY

CIVIL ENGINEER:

**TIMMONS GROUP** TIMMONS GROUP PATRICK BARBEAU, P.E. TERRY WESTENDORF, PLS

5410 TRINITY ROAD; SUITE 102 RALEIGH, NC 27607

PH: (919) 866-4512 PH: (984) 255-2353 PATRICK.BARBEAU@TIMMONS.COM TERRY.WESTENDORF@TIMMONS.COM

C8.2

SURVEYOR:

5410 TRINITY ROAD; SUITE 102

RALEIGH, NC 27607

**BUFFER/WETLAND:** SOIL AND ENVIRONMENTAL CONSULTANTS, PA

STEVEN BALL, RF, PWS

8412 FALLS OF NEUSE ROAD, SUITE 104

PH: (919) 846-5900

(BOUNDARY ONLY)

15.4.5 - STREETS

PS-100

PS-101

PS-102

PS-103

PS-104

PS-105

PS-106

E1.2

E2.1

E3.1

E4.1

E4.2

E4.3

E4.4

**CUL-DE-SACS** 

SUBDIVISION STREET DISCLOSURE STATEMENT

ALL STREETS SHOWN ON THE FINAL PLAT SHALL BE DESIGNATED IN ACCORDANCE WITH G.S. § 136-102.6 AND DESIGNATION AS PUBLIC SHALL BE CONCLUSIVELY PRESUMED AN OFFER OF DEDICATION TO THE PUBLIC. WHERE STREETS ARE DEDICATED TO THE PUBLIC BUT NOT ACCEPTED INTO A MUNICIPAL OR THE STATE SYSTEM, BEFORE LOTS ARE SOLD, A STATEMENT EXPLAINING THE STATUS OF THE STREET SHALL BE INCLUDED WITH THE FINAL PLAT.

ROLESVILLE ROAD CROSS SECTIONS

MITCHELL MILL ROAD CROSS SECTIONS

PUMP STATION PLAN

PUMP STATION LAYOUT AND SECTIONS

PUMP STATION DATA

PUMP STATION DETAILS

PUMP STATION DETAILS

PUMP STATION DETAILS

PUMP STATION DETAILS

ELECTRICAL - SITE PLAN, NOTES & LEGEND

PUMP STATION PLAN - ELECTRICAL

ODOR CONTROL BUILDING FLOOR PLAN -

ELECTRICAL

RISER AND DETAILS

SCHEDULES

SPECIFICATIONS

**SPECIFICATIONS** 

**SPECIFICATIONS** 

SPECIFICATIONS

ODOR CONTROL BUILDING FLOOR PLAN -

ODOR CONTROL BUILDING FLOOR PLAN -

MECHANICAL

Rolesville CD 21-08 / Construction Drawings Rolesville Crossing Subdivision Date: September 20, 2023 Meredith Truber

ATTENTION CONTRACTORS The Construction Contractor responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for contacting the Public Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their construction.

reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Public  Water Distribution / Extension System  The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.  City of Raleigh Public Utilities Department Permit # W-4081  Authorization to Construct See digital signature
Public Sower Collection / Extension System

Sewer Collection / Extension System

The City of Raleigh consents to the connection and extension of the City's public sewer system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

Public Utilities Department Permit #

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this

City of Raleigh Development Approval

EROSION CONTROL, STORMWATER AND FLOODPLAIN MANAGEMENT STORMWATER MGMT. 
S- WF-069095-20

Town of Rolesville Planning Department

Failure to call for Inspection, Install a Downstream Plug, have Permitted Plans on the Jobsite, or any other Violation of City of Raleigh Standards will result in a Fine and Possible Exclusion from

, , , , , , , , , , , , , , , , , , ,
Public  Water Distribution / Extension System  The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.
City of Raleigh Public Utilities Department Permit #
Public

RALEIGH, NC 27615

SBALL@SANDEC.COM

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

09/17/2021

DRAWN BY

R. WINGATE

P. BARBEAU

CHECKED BY

P. BARBEAU

AS SHOWN

SHEET NO.



Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require

future work in the City of Raleigh.

Public  Water Distribution / Extension System  The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.
City of Raleigh Public Utilities Department Permit #W-4081  Authorization to Construct See digital signature
Public Sewer Collection / Extension System

Authorization to Construct See digital signature

CUL-DE-SACS SHALL NOT EXCEED 250 FEET IN LENGTH FROM THE NEAREST INTERSECTION. CUL-DE-SAC LENGTHS LONGER THAN 250 FEET WILL BE REVIEWED FOR APPROVAL ON A CASE-BY-CASE BASIS. AS SUCH, THE BOARD HAS APPROVED AVERY DRIVE. CARTERET DRIVE, AND DAVIE DRIVE AS THESE CUL-DE-SAC STREETS EXCEED 250' IN LENGTH.

**VICINITY MAP** 

C2.21	ROAD 6 PLAN & PROFILE
C2.22	ROAD 8 PLAN & PROFILE
C2.23	ROAD 9 PLAN & PROFILE
C2.24	ROAD 10 PLAN & PROFILE
C2.25	ROUNDABOUT CURB PLAN & PROFIL
C2.26	PAVEMENT MARKING & SIGNAGE PLA
C2.27	PAVEMENT MARKING & SIGNAGE PLA
C2.28	PAVEMENT MARKING & SIGNAGE PLA
C2.29	PAVEMENT MARKING & SIGNAGE PLA
C3.0	OVERALL GRADING AND DRAINAGE PL
C3.1	GRADING AND DRAINAGE PLAN
C3.2	GRADING AND DRAINAGE PLAN
C3.3	GRADING AND DRAINAGE PLAN
C3.4	GRADING AND DRAINAGE PLAN
C3.5	STORM SEWER TABLES
C3.6	STORM SEWER TABLES
C3.7	STORM SEWER TABLES
C3.8	STORM PROFILES
C3.9	STORM PROFILES
C4.0	EROSION CONTROL-STAGE 1 OVERA
C4.1	EROSION CONTROL STAGE 1 SPEC TAB
C4.2	SEDIMENT BASIN GRADING DETAIL
C4.3	SEDIMENT BASIN GRADING DETAIL
C4.4	SEDIMENT BASIN GRADING DETAIL
C4.5	SEDIMENT BASIN GRADING DETAIL
C4.6	STREAM CROSSING EROSION CONTRO
C4.7	STREAM CROSSING EROSION CONTRO
C4.8	EROSION CONTROL-STAGE 2 OVERA
C4.9	EROSION CONTROL STAGE 2
C4.10	EROSION CONTROL-STAGE 2
	C2.22 C2.23 C2.24 C2.25 C2.26 C2.27 C2.28 C2.29 C3.0 C3.1 C3.2 C3.3 C3.4 C3.5 C3.6 C3.7 C3.8 C3.9 C4.0 C4.1 C4.2 C4.3 C4.4 C4.5 C4.6 C4.7 C4.8 C4.9

**OWNERS:** 

HC ROLESVILLE INVESTMENTS, LLC

1616 CLEVELAND AVE

CHARLOTTE, NC 28203

PH: (704) 805-4801

FORCE MAIN PLAT: BM2023 PG 1009 & 1010

HOPPER COMMUNITIES INC. / HC

SITE DATA TABLE

WHEELER TRACT

ROLESVILLE, LLC

1767-48-3143 (46.8 AC) 1767-58-6083 (44.59 AC)

D.B. 005456 PG. 00627

D.B. 009828 PG. 00902

1801 ROLESVILLE RD

ROLESVILLE, NC 27587

SINGLE FAMILY: 177

90.65 AC AFTER R/W DEDICATION

ROLESVILLE ROAD: 1/2 OF 100' R/W

MITCHELL MILL ROAD: 1/2 OF 110' PER TOWN

INTERNAL ROADS: 50' AND 60' AND 63' R/W

SINGLE FAMILY RESIDENTIAL: 71.2 AC

TOWN HOME COMMERCIAL: 18.9 AC

TOWNHOUSE: 120

BUFFALOE CREEK

TOTAL: 90.1 AC

RESIDENTIAL

RESIDENTIAL

PROJECT NAME:

DEED REFERENCE:

PLAT REFERENCE:

PROPERTY ADDRESS

**EXISTING ZONING** 

CURRENT USE:

PROPOSED USE:

TOTAL PROJECT AREA

PROPOSED NEW PUBLIC R/W

Number

CVR

C0.0

C1.1

C1.2

C1.3

C1.4

C1.5

C2.0

C2.1

C2.2

C2.3

C2.4

C2.5

C2.6

C2.9

C2.10

C2.11

C2.12

C2.13

C2.14

C2.15

C2.16

C2.18

**UNIT COUNT:** 

DEDICATION:

WATERSHED

RIVER BASIN:

DISTURBED AREA:

APPLICANT/ PROPERTY OWNER:

C2.21	ROAD 6 PLAN & PROFILE	
22.22	ROAD 8 PLAN & PROFILE	
22.23	ROAD 9 PLAN & PROFILE	
2.24	ROAD 10 PLAN & PROFILE	
22.25	ROUNDABOUT CURB PLAN & PROFILE	
2.26	PAVEMENT MARKING & SIGNAGE PLAN	
2.27	PAVEMENT MARKING & SIGNAGE PLAN	
2.28	PAVEMENT MARKING & SIGNAGE PLAN	
2.29	PAVEMENT MARKING & SIGNAGE PLAN	
C3.0	OVERALL GRADING AND DRAINAGE PLAN	
C3.1	GRADING AND DRAINAGE PLAN	
C3.2	GRADING AND DRAINAGE PLAN	
C3.3	GRADING AND DRAINAGE PLAN	
C3.4	GRADING AND DRAINAGE PLAN	
C3.5	STORM SEWER TABLES	
C3.6	STORM SEWER TABLES	
C3.7	STORM SEWER TABLES	
C3.8	STORM PROFILES	
C3.9	STORM PROFILES	
C4.0	EROSION CONTROL-STAGE 1 OVERALL	
C4.1	EROSION CONTROL STAGE 1 SPEC TABLES	
C4.2	SEDIMENT BASIN GRADING DETAIL	
C4.3	SEDIMENT BASIN GRADING DETAIL	
C4.4	SEDIMENT BASIN GRADING DETAIL	
C4.5	SEDIMENT BASIN GRADING DETAIL	
C4.6	STREAM CROSSING EROSION CONTROL 1	
C4.7	STREAM CROSSING EROSION CONTROL 2	
C4.8	EROSION CONTROL-STAGE 2 OVERALL	
C4.9	EROSION CONTROL STAGE 2	
24.10	EROSION CONTROL-STAGE 2	

CITY OF RALEIGH PUBLIC UTILITIES NOTE

within Rolesville Crossing is relying upon

Conveyance of sewage from the proposed lots

improvements to the Harris Creek Interceptor that

titled Harris Creek Sanitary Sewer Replacement

and will be assigned permit # S-5037. Rolesville

Crossing lots will not be recorded and the onsite

water/sewer utilities will not be accepted until these

improvements under permit S-5037 are approved,

installed and accepted by Raleigh for maintenance

are being designed by American Engineering and is

DEVELOPER:

HOPPER COMMUNITIES, INC

1616 CLEVELAND AVE

**CHARLOTTE NC 28203** 

PH: (704) 805-4801

C4.11	EROSION CONTROL-STAGE 2		
C4.12	EROSION CONTROL-STAGE 2		
C4.13	EROSION CONTROL-STAGE 2 STREAM CROSSINGS		
C4.14	EROSION CONTROL-STAGE 2 FORCE MAIN		
C4.15	EROSION CONTROL STAGE 2 LIMITS OF DISTURBANCE		
C5.0	OVERALL UTILITY PLAN		
C5.1	UTILITY PLAN		
C5.2	UTILITY PLAN		
C5.3	UTILITY PLAN		
C5.4	UTILITY PLAN		
C5.5	SANITARY SEWER TABLES		
C5.6	SANITARY SEWER OUTFALL PLAN & PROFILE		
C5.7	MITCHELL MILL FORCE MAIN PLAN AND PROFILE		
C5.8	MITCHELL MILL AND ROLESVILLE FORCE MAIN PLAN AND PROFILE		
C5.9	MULBERRY TREE DRIVE FORCE MAIN PLAN AND PROFILE		
C5.10	MULBERRY TREE DRIVE FORCE MAIN PLAN AND PROFILE		
C5.11	TANSLEY CREST LOOP FORCE MAIN PLAN AND PROFILE		
C5.12	MITCHELL MILL WATER MAIN PLAN AND PROFILE		
C5.13	MITCHELL MILL WATER MAIN PLAN AND PROFILE		
C5.14	STREET LIGHTING PLAN		
C7.0	SITE DETAILS		
C7.1	SITE DETAILS		
C7.2	STORM DRAINAGE DETAILS		
C7.3	EROSION CONTROL & STORM DRAINAGE DETAILS		
C7.4	EROSION CONTROL DETAILS		
C7.5	EROSION CONTROL NOTES AND DETAILS		
C7.6	EROSION CONTROL NOTES AND DETAILS		
C7.7	NCDOT DETAILS		
C7.8	UTILITY DETAILS		
C7.9	UTILITY DETAILS		
C7.10	UTILITY DETAILS		
C7.11	SITE DETAILS		
C8.0	SCM 1 DETAILS		
C8.1	SCM 2 DETAILS		
C8.1	SCM 2 DETAILS		

CONTROL-STAGE 2
CONTROL-STAGE 2
STAGE 2 STREAM CROSSINGS
ROL-STAGE 2 FORCE MAIN
TROL STAGE 2 LIMITS OF
STURBANCE LL UTILITY PLAN
TILITY PLAN
TILITY PLAN
TILITY PLAN
TILITY PLAN
RY SEWER TABLES
R OUTFALL PLAN & PROFILE
RCE MAIN PLAN AND PROFILE
ID ROLESVILLE FORCE MAIN
RIVE FORCE MAIN PLAN AND
PROFILE
RIVE FORCE MAIN PLAN AND PROFILE
OOP FORCE MAIN PLAN AND PROFILE
TER MAIN PLAN AND PROFILE
TER MAIN PLAN AND PROFILE
T LIGHTING PLAN
TE DETAILS
TE DETAILS
PRAINAGE DETAILS
& STORM DRAINAGE DETAILS
CONTROL DETAILS
ROL NOTES AND DETAILS
ROL NOTES AND DETAILS
DOT DETAILS
LITY DETAILS
LITY DETAILS
LITY DETAILS
TE DETAILS
M 1 DETAILS
M 2 DETAILS

C8.3	SCM 4 DETAILS	
C8.4	SCM 5 DETAILS	
C8.5	SCM NOTES & DETAILS	
L1.0	OVERALL LANDSCAPE PLAN	
L1.1	LANDSCAPE PLAN	
L1.2	LANDSCAPE PLAN	
L1.3	LANDSCAPE PLAN	
L1.4	LANDSCAPE PLAN	
L1.5	LANDSCAPE PLAN	
L1.6	LANDSCAPE PLAN	
L1.7	LANDSCAPE PLAN	
L1.8	LANDSCAPE PLAN	
L1.9	LANDSCAPE PLAN	
L1.10	LANDSCAPE PLAN	
L1.11	LANDSCAPE PLAN	
L1.12	LANDSCAPE PLAN	
L2.0	LANDSCAPE NOTES & DETAILS 1	
L2.1	LANDSCAPE NOTES & DETAILS 2	
R1.00	COVER SHEET	
R2.00	GENERAL NOTES, DETAILS & CONVENTIONAL SYMBOLS	
R2.01	TYPICAL SECTIONS	
R2.02	STANDARD DETAILS	
R3.01	EXISTING CONDITIONS & PLAN & STRIPING SHEET	
R3.02	GRADING & PROFILE SHEET	
R3.03	EROSION CONTROL PLAN	
R4.01	EXISTING CONDITIONS & PLAN & STRIPING SHEET	
R4.02	GRADING & PROFILE SHEET	
R4.03	EROSION CONTROL PLAN	
R5.01	EXISTING CONDITIONS & PLAN & STRIPING SHEET	
R5.02	GRADING & PROFILE SHEET	
R5.03	EROSION CONTROL PLAN	
R7.00	TRAFFIC MANAGEMENT PLAN	
R8.01	ROLESVILLE ROAD CROSS SECTIONS	
D0 02	DOLESVILLE DOAD CROSS SECTIONS	

SCM 3 DETAILS

C8.5	SCM NOTES & DETAILS
L1.0	OVERALL LANDSCAPE PLAN
L1.1	LANDSCAPE PLAN
L1.2	LANDSCAPE PLAN
L1.3	LANDSCAPE PLAN
L1.4	LANDSCAPE PLAN
L1.5	LANDSCAPE PLAN
L1.6	LANDSCAPE PLAN
L1.7	LANDSCAPE PLAN
L1.8	LANDSCAPE PLAN
L1.9	LANDSCAPE PLAN
L1.10	LANDSCAPE PLAN
L1.11	LANDSCAPE PLAN
L1.12	LANDSCAPE PLAN
L2.0	LANDSCAPE NOTES & DETAILS 1
L2.1	LANDSCAPE NOTES & DETAILS 2
R1.00	COVER SHEET
R2.00	GENERAL NOTES, DETAILS & CONVENTION SYMBOLS
R2.01	TYPICAL SECTIONS
R2.02	STANDARD DETAILS
R3.01	EXISTING CONDITIONS & PLAN & STRIPING
R3.02	GRADING & PROFILE SHEET
R3.03	EROSION CONTROL PLAN
R4.01	EXISTING CONDITIONS & PLAN & STRIPING
R4.02	GRADING & PROFILE SHEET
R4.03	EROSION CONTROL PLAN
R5.01	EXISTING CONDITIONS & PLAN & STRIPING
R5.02	GRADING & PROFILE SHEET
R5.03	EROSION CONTROL PLAN
R7.00	TRAFFIC MANAGEMENT PLAN
R8.01	ROLESVILLE ROAD CROSS SECTION
R8.02	ROLESVILLE ROAD CROSS SECTION

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

KNOW WHAT'S BELOW.

CALL 811 BEFORE YOU DIG.

#### Conditional Zoning District Zoning Conditions

1. The total number of dwelling units on the subject property shall not exceed 297 dwelling units and not more than 120 of these dwelling units are permitted to be townhomes. No apartments (multi-family units) shall be permitted.

2. A twenty feet (20') wide Type A landscape buffer shall be installed along the subject property's frontage on Rolesville Road and along Mitchell Mill Road. The buffer shall be maintained the

Homeowners Association for the proposed subdivision.

3. Sidewalk meeting town standards shall be installed along the subject property's frontage along Mitchell Mill Road at the same time road improvement are being installed on Mitchell Mill Road pursuant to Condition 5 below. The sidewalk shall be dedicated to and maintained by the Town of

4. Recreational Amenities: The following recreational amenities shall be provided generally as shown on the attached Exhibit 1 as a part of the development of the subject property and dedicated to and maintained by the Homeowners Association for the proposed subdivision except for the public greenway which shall be dedicated as such to the Town of Rolesville:

- A swimming pool and cabana, including changing rooms and restrooms shall be constructed prior to the issuance of the 150th building permit;
- At least one fenced playground shall be constructed prior to the issuance of the 150<sup>th</sup> building
- At least one fenced dog park shall be constructed prior to the issuance of the 150<sup>th</sup> building
- Public greenway on a greenway easement at least 25' wide with paved trails at least ten feet wide (10') shall be constructed generally as shown on the attached Exhibit 1 and dedicated to the Town of Rolesville; and
- A private Multi-purpose Trail at least ten feet (10') shall be provided generally as shown on the attached Exhibit 1 and dedicated to and maintained by the Homeowners Association for the proposed subdivision.

5. Transportation Improvements: To address transportation impacts reasonably expected to be generated by the development, the following road improvements shall be installed as recommended by the Traffic Impact Analysis for the Wheeler Tract, prepared by Ramey Kemp & Associates and dated May 2019, a copy of which is on file with the Town of Rolesville, together with the comments made by the North Carolina Department of Transportation in their Traffic Impact Analysis Review Report dated July 26, 2019:

#### Rolesville Road and Site Drive 1:

- o Provide site access via full movement intersection with one ingress and one egress lane
- Provide stop control for westbound drive approach; Construct a designated southbound left-turn lane with at least 100 feet of storage and
- appropriate deceleration and taper; Provide a designated northbound right-turn lane with at least 100 feet of storage and appropriate deceleration and taper.
- Mitchel Mill and Site Drive 2:

- Provide access via full movement intersection with one ingress lane and one egress
- Provide stop control for southbound site drive approach; and Provide a designated eastbound left-turn lane with at least 100 feet of storage and
- Rolesville Road and Mitchell Mill Road: prior to the issuance of a building permit for the 150<sup>th</sup> dwelling unit, the property owner shall contribute Fifty Thousand Dollars (\$50,000.00) to the Town of Rolesville to be used by the Town of Rolesville to install a traffic light at the intersection
- <u>No Extension of Taviston Court</u>: In addition, the Board of Commissioners has determined that the extension of Taviston Court, including the dedication or preservation of right-of-way for a future extension of Taviston Court, into the subject property is undesirable, does not serve the

#### public interest and shall be prohibited. Conditions Applicable to single-family homes only:

of Mitchell Mill and Rolesville Road.

appropriate deceleration and taper.

6. All homes shall include either crawl space foundations or stem wall foundations. Any stem wall foundations shall have a brick or stone veneer on all sides facing a public street.

7. The minimum square footage for two-story homes shall be 2,200 square feet. The minimum square footage for one-story homes shall be 1,600 square feet.

8. A twenty-five foot (25') wide Type A landscape buffer shall be installed adjacent the properties to the north currently owned by Dwight and Carolyn Woodlief and more particularly described as Lot 6 on

Book Maps 2011, Page 84, Wake County Registry (Wake County PIN 1767 58 09384.) This buffer shall be located within an easement that may be a part of a residential lot. The buffer shall be maintained the

Homeowners Association for the proposed subdivision. 9. A twenty foot (20') wide Type A landscape buffer shall be installed along the common boundary line with the following properties. This buffer shall be located within an easement that may be a part of a residential lot. The buffer shall be maintained the Homeowners Association for the proposed

- 1809 Rolesville Road, Wake Forest, Wake County PIN # 1767375272, Book 12777, Page 1559; 3813 Taviston Court, Wake Forest, Wake County PIN # 1767377282, Book 12779, Page 2611;
- 3820 Taviston Court, Wake Forest, Wake County PIN # 1767470283, Book 17687, Page 672;
- 3813 Arbor Rose Lane, Wake Forest, Wake County PIN # 1767472196, Book 9496, Page 2630; 3816 Arbor Rose Lane, Wake Forest, Wake County PIN # 1767474134, Book 16324, Page 1810;
- 3812 Arbor Rose Lane, Wake Forest, Wake County PIN # 1767465953, Book 11390, Page 1138;
- 3804 Arbor Rose Lane, Wake Forest, Wake County PIN # 1767466746, Book 11327, Page 1152;
- 1725 Rolesville Road, Wake Forest, Wake County, PIN # 1767 38 7170, Book 17107, Page 582; 1727 Rolesville Road, Wake Forest, Wake County, PIN # 1767 38 8313; Book 3750, Page 591; and

 1709 Rolesville Road, Wake Forest, Wake County, PIN # 1767 38 9615; Book 4572, Page 246. Conditions Applicable to townhomes only:

No townhome building shall exceed six (6) units. 11. The minimum square footage for townhomes shall be 1,200 square feet.

#### LEOEND

<u>LE</u> 0	GEND
	PROPOSED WATER LINE PROPOSED SANITARY SEWER PROPOSED FORCE MAIN
→ PROPOSED FIRE HYDRANT  PROPOSED WATER VALVE  PROPOSED TEE  PROPOSED CROSS	PROPOSED STORM PIPE PROPOSED CATCH BASIN PROPOSED YARD INLET PROPOSED JUNCTION BOX PROPOSED END WALL PROPOSED FLARED END SECTION PROPOSED RISER STRUCTURE

→ PROPOSED TRAFFIC ARROW

#### PARKING SUMMARY REQUIRED PARKING SINGLE FAMILY UNITS 2 SPACES PER DWELLING UNIT 2 SPACES PER DWELLING UNIT PLUS 1/2 PER BEDROOM OVER TWO BEDROOMS **TOWNHOMES** PLUS 1 VISITOR SPACE FOR EACH 4 FOUR DWELLING UNITS PHASE 1 PHASE 2 105 SINGLE FAMILY UNITS 72 49 (INCL. 18 END 71 (INCL. 28 END **TOWNHOMES (3-BEDROOM)** UNITS) UNITS) VISITOR PARKING 18 13 MAIL KIOSK PARKING 5 TOTAL SPACES REQUIRED 287 411 PROVIDED PARKING PHASE 1 PHASE 2 GARAGE PARKING 121 176 72 UNITS X 1 SPACE 105 UNITS X 1 SINGLE FAMILY SPACE = 105 TOWNHOMES 49 UNITS X 1 SPACE 71 UNITS X 1 SPACE DRIVEWAY PARKING\* 72 UNITS X 1 SPACE | 105 UNITS X 1 SINGLE FAMILY SPACE = 105 (18 END UNITS X 2 (28 END UNITS X 2 SPACES) + (31 SPACES) + (43 **TOWNHOMES** UNITS X 1 SPACE) = UNITS X 1 SPACE) = PARKING LOT SPACES (PROVIDED TO 40 SERVE MAIL KIOSKS AND VISITOR SPOTS TOAL PROVIDED PARKING 300 441 \*NOTE: TOWNHOME END UNITS PROVIDE 2 DRIVEWAY SPACES

#### **OPFN SPACE CALCULATIONS**

	AOL OAL	DEATION	
AREA PHASE	ADEA	REQUIRED 10% GROSS AREA	PROVIDED
	AREA	TOTAL (ACTIVE)	TOTAL (ACTIVE)
	(AC)	(AC)	(AC)
PHASE 1	41.06	4.11 (2.06)	5.76 (2.06)
PHASE 2	50.61	5.06 (2.53)	8.97 (2.68)
TOTAL	91.67		14.73 (4.74)

#### PUBLIC IMPROVEMENT QUANTITY TABLE

PHASE	1	2
NUMBER OF LOT(S)	297	
LOT NUMBER(S) BY PHASE	1-60, 126-129, 170-185, 194-216, 280-297	61-125, 130-169, 186-193, 217-279
NUMBER OF SINGLE FAMILY UNITS	72	105
NUMBER OF TOWNHOME UNITS	49	71
LIVABLE BUILDINGS	121	176
OPEN SPACE?	YES	YES
NUMBER OF OPEN SPACE LOTS (AC)	5 (5.76)	14 (8.97)
PUBLIC WATER (LF)	5,860	6,610
PUBLIC SEWER (LF)	5,420	6,760
PUBLIC FORCEMAIN (LF)	4,600	0
PUBLIC STREET (LF) - FULL	5,670	6,930
PUBLIC STREET (LF) - PARTIAL	2,830	0
PUBLIC SIDEWALK (LF)	10,550	13,365
NUMBER OF STREET SIGNS	21	12
WATER SERVICE STUBS	123	176
SEWER SERVICE STUBS	122	176

#### MAIL KIOSK CALCULATIONS NUMBER OF MAIL BOXES (UNITS) REQUIRED PARKING SPACES 52 OR LESS 53-78 3 79-104 4 PLUS 1 PER EACH ADDITION 105 OR MORE 26 MAIL BOXES MAIL KIOSK AREA 1 (LOTS 1-177) 4 + 1 x (177-105) / 26 = 6.77 SPACES MINIMUM REQUIRED PARKING SPACES: TOTAL REQUIRED: 7 SPACES (1 AD MAIL KIOSK AREA 2 (LOTS 178-297) 4 + 1 x (120-105) / 26 = 4.58 SPACES MINIMUM REQUIRED PARKING SPACES: TOTAL REQUIRED: 5 SPACES (1 AD SPACE) STORMWATER SITE DATA IMPERVIOUS BREAKDOWN FOR LOTS **IMPERVIOUS** IMPERVIOUS | IMPE # OF LOTS ALLOWANCE (SF) (SF) 1,500 180,000 22' TOWNHOME 120 301,000 86 3,600 SHALLOW LOT DEEP LOT 318,500 3,600 91 TOTAL UNITS 297 799,500 IMPERVIOUS BREAKDOWN FOR TOTAL SITE AREA (SF) AREA (AC) ONSITE SIDEWALK 160,674 3.69 ONSITE ROAD 407,189 9.35 535,666 12.30 LOT - ROOF

131,917

131,917

1,367,363

LOT - DRIVEWAY

LOT - SIDEWALK

TOTAL IMPERVIOUS

	7.1. 2.07.1111	TIGHT ER COMMISSIONE	
	PIN(S):	1767-48-3143 1767-58-6083	
NAL	DEED REFERENCE:	D.B. 005456 PG. 00627 D.B. 009828 PG. 00902	
	PLAT REFERENCE:	BM1998-01776	
is .	PROPERTY ADDRESS:	1801 ROLESVILLE RD ROLESVILLE, NC 27587	
.DA	EXISTING ZONING:	R-30 (WAKE COUNTY)	
	PROPOSED ZONING:	R-3-CZ	
:S	CURRENT USE:	RESIDENTIAL	
DA	PROPOSED USE:	RESIDENTIAL	
	UNIT COUNT:	SINGLE FAMILY: 177 TOWNHOUSE: 120	
	TOTAL PROJECT AREA:	91.39 AC	
	TOTAL DISTURBED AREA:	90.1 AC	
	TOWNHOUSE AREA (DENSITY):	15.00 ACRES (8.0 DU/AC)	
OTAL	SINGLE FAMILY AREA (DENSITY):	76.39 ACRES (2.32 DU/AC)	
ERVIOUS (AC)		ROLESVILLE ROAD: 20' R/W (50' FROM CENTER LINE)	
4.13	PROPOSED NEW PUBLIC R/W DEDICATION	MITCHELL MILL ROAD: 25' DE (55' FROM CENTER LINE)	
6.91		INTERNAL ROADS: 50' AND 60	
7.31	PROJECT AREA AFTER R/W DEDICATION	90.65 AC	
18.35	RIVER BASIN:	NEUSE	
	SURFACE WATER CLASSIFICATION:	C; NSW	
	WATERSHED:	BUFFALOE CREEK	
	BUILDING SETBACKS (SINGLE FAMILY, DETACHED RESIDENTIAL):		
	FRONT:*	25'	
		*LOTS 72-76 HAVE 40' FRONT	
	CORNER:	15'	
	SIDE:	10'	
	SIDE STREET:	15'	
	REAR:	25'	
	LOT WIDTH:	65'	

BUILDING SETBACKS (TOWNHOUSES):

MINIMUM LOT AREA: 6,000 SF

CORNER: 10'

REAR: 15'

LOT WIDTH: 20'

0' WITH 30' MINIMUM BETWEEN

STRUCTURES


PROJECT NAME:


APPLICANT:

SITE DATA TABLE

ROLESVILLE CROSSING

HOPPER COMMUNITIES





JOB NO. SHEET NO.

C0.0

RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

25' SB 25' SB 25' SB 25' SB MINIMUM LOT SIZE: MINIMUM LOT SIZE: 10,000 SF 10,000 SF **TYPICAL SHALLOW LOT** 

3.03

3.03


31.40

TYPICAL LOT DIMENSIONS "TOWNHOMES"

**DIMENSIONS** "SINGLE FAMILY" 3,500 SF IMPERVIOUS

**TYPICAL DEEP LOT DIMENSIONS** "SINGLE FAMILY" 3,500 SF IMPERVIOUS

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF



#### **SURVEY NOTES**

- 1. ON SITE BOUNDARY INFORMATION IS TAKEN FROM A SURVEY BY TIMMONS GROUP DATED 08/19/2019. OFFSITE TOPOGRAPHY AND PLANIMETRIC INFORMATION FROM OTHER SOURCES AND HAS NOT BEEN FIELD VERIFIED BY TIMMONS GROUP. ONSITE TOPOGRAPHY RECEIVED FROM THE CE GROUP ON
- ONSITE WETLAND LOCATION AND STREAM DELINEATION BY S&EC, PA.
- 3. ALL DISTANCES SHOWN ON SURVEY ARE HORIZONTAL GROUND DISTANCES UNLESS OTHERWISE NOTED.
- THIS SURVEY DOES NOT REPRESENT A TITLE SEARCH BY THIS FIRM. BASIS OF BEARING SHOWN HEREON IS NC GRID NAD 83 (NSRS 2007).
- VERTICAL DATUM SHOWN HEREON IS NAVD88. 7. OTHER SOURCES OF INFORMATION INCLUDE CITY OF RALEIGH GIS AND
- AERIAL IMAGERY. NOT LOCATED IN FLOOD HAZARD AREA PER FEMA MAP #3720176600J
- (EFFECTIVE 05/02/2006). RECORDED PROPERTY DATA:
- 9.1. DB 005456, PG 00627
- 9.2. DB 009828, PG 00902
- 10. EXISTING IMPERVIOUS AREA = 0.0 ACRES
- 11. THE UTILITIES ON THESE PLANS ARE APPROXIMATE ONLY, AND ARE NOT ACCURATE FOR CONSTRUCTION PURPOSES. FOR FIELD MARKS CALL
- 1-800-632-4949. 12. OFFSITE TOPOGRAPHY FROM WAKE COUNTY GIS.

#### DEMOLITION KEYNOTES

NUMBER	DESCRIPTION
D01	EXISTING FEATURE TO REMAIN.
D02	REMOVE EXISTING FEATURE IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS. CONTRACTOR TO COORDINATE AS NEEDED WITH LOCAL MUNICIPALITY, INSPECTORS, AND/OR UTILITY COMPANIES.
D02	RELOCATE AND MODIFY EXISTING FEATURE TO REMAIN IN SERVICE IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL

LEGEND	
	DESCRIPTION
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	100 YEAR FLOODPLAIN
	TREE LINE
	50' RIPARIAN BUFFER
	WETLANDS

D03  REGULATIONS. CONTRACTOR TO COOL LOCAL MUNICIPALITY, INSPECTORS, A		
LEGEND		
	DESCRIPTION	
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	100 YEAR FLOODPLAIN	
. ~~~~~~~.	TREE LINE	

LIMITS OF DISTURBANCE

09/17/2021 DRAWN BY

> **DESIGNED BY** P. BARBEAU CHECKED BY . BARBEAU

R. WINGATE

09/06/2023

SCALE AS SHOWN

SHEET NO.


### DEMOLITION NOTES


- 1. ALL UTILITIES OR STRUCTURES NOT INDICATED FOR REMOVAL OR MODIFICATION ARE TO REMAIN AND BE PROTECTED FROM DAMAGE. 2. CONTRACTOR TO OBTAIN, REFERENCE, AND UTILIZE ALL AVAILABLE
- 3. ALL WASTE MATERIAL GENERATED FROM CLEARING AND DEMOLITION ACTIVITIES SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ALL

ENVIRONMENTAL REPORTS (PHASE 1 ESA, ASBESTOS, ETC.) FROM


- APPLICABLE RULES AND REGULATIONS. 4. REMOVE/ DEMOLISH/ ABANDON AFTER EROSION CONTROL MEASURES ARE IN PLACE AN APPROVAL OF THE INSPECTOR. REFER TO EROSION CONTROL
- 5. REMOVE TOPSOIL AND STOCKPILE APPROPRIATELY ON-SITE. ON-SITE TEMPORARY STOCKPILES SHALL BE LOCATED WITHIN CONSTRUCTION
- 6. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED BY THE OWNER OR OTHERS EXCEPT WHEN PERMITTED UNDER THE FOLLOWING CONDITIONS AND THEN ONLY AFTER ARRANGING TO PROVIDE ACCEPTABLE TEMPORARY UTILITY SERVICES. (1) NOTIFY OWNER NOT LESS THAN ONE WEEK IN ADVANCE OF PROPOSED UTILITY INTERRUPTIONS. (2) DO NOT PROCEED WITH UTILITY INTERRUPTIONS WITHOUT RECEIVING OWNER WRITTEN PERMISSION. (3) COORDINATE ALL UTILITY RELOCATION WITH
- APPROPRIATE UTILITY PROVIDER. 7. ALL PAVEMENT OR CONCRETE TO BE REMOVED SHALL BE SAW CUT TO PROVIDE A STRAIGHT AND UNIFORM JOINT WITH NEW CONSTRUCTION. ANY EXISTING PAVEMENT, SIDEWALK, CURB & GUTTER, ETC. THAT MUST BE REMOVED TO ALLOW NEW CONSTRUCTION SHALL BE REMOVED TO ALLOW NEW CONSTRUCTION SHALL BE REMOVED AND REPAIRED PER THE SPECIFICATIONS AND DETAILS OR TO MATCH EXISTING CONDITIONS (WHETHER OR NOT SHOWN ON THE DRAWINGS TO BE REMOVED). UTILITY INSTALLATIONS MAY UTILIZE OPEN CUT OF PAVEMENTS UNLESS INDICATED OTHERWISE. TRENCH IN EXISTING ASPHALT SHALL BE PATCHED PER
- PAVEMENT REPAIR DETAIL. PROTECT ALL ADJACENT PROPERTIES, THE GENERAL PUBLIC AND ALL OF THE OWNER'S FACILITIES. SHOULD DAMAGE OCCUR, NOTIFY ARCHITECT IMMEDIATELY.


- 9. SUBSURFACE FEATURES ARE SHOWN IN APPROXIMATE LOCATION. CONTRACTOR IS RESPONSIBLE FOR SUBSURFACE UTILITY EXPLORATION TO DETERMINE UTILITY LOCATIONS AND DEPTHS.
- 10. THE CONTRACTOR SHALL USE NC ONE CALL (811) TO LOCATE ALL
- UNDERGROUND UTILITIES. 11. CONTRACTOR TO VERIFY LOCATIONS AND SIZES OF ALL EXISTING FEATURES PRIOR TO COMMENCEMENT OF CONSTRUCTION. REPAIR AND REPLACE ANY DAMAGES TO EXISTING UTILITIES RESULTING FROM CONSTRUCTION.
- 12. CONTRACTOR IS RESPONSIBLE FOR REMOVING OR ABANDONING ALL EXISTING UTILITIES AND STRUCTURES REQUIRED TO COMPLETE SITE CONSTRUCTION, EITHER ONSITE OR IN PUBLIC ROW, IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
- 13. WATER AND SEWER ABANDONMENT SHALL BE DONE IN ACCORDANCE WITH CITY OF RALEIGH STANDARDS INCLUDING DISCONNECT FROM THE MAIN AND REMOVAL OF SERVICES FROM THE RIGHT-OF-WAY.
- 14. ANY EXISTING UNIDENTIFIED SEPTIC SYSTEMS AND WELLS FOUND ON SITE SHALL BE REMOVED OR ABANDONED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS AT NO CHARGE TO THE OWNER
- 15. VERIFY ALL ILLUSTRATED KNOWN UNDERGROUND ELEMENTS. EXERCISE REASONABLE EFFORTS TO PROTECT ANY UNKNOWN UNDERGROUND ELEMENTS. NOTIFY THE ARCHITECT IMMEDIATELY IF UNKNOWN ELEMENTS ARE DISCOVERED THAT WOULD NECESSITATE MODIFICATION TO THE PROPOSED DESIGN.
- 16. CONTRACTOR SHALL COORDINATE ALL CONNECTIONS, RELOCATION AND DEMOLITION WORK WITH THE APPROPRIATE COMPANY OR JURISDICTION HAVING AUTHORITY AND SHALL OBTAIN ANY PERMITS AS REQUIRED. 17. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE
- LOCAL, STATE, AND OSHA REGULATIONS. 18. EXISTING MANHOLES, VALVE BOXES, VAULTS, CLEANOUTS, UTILITY POLES ETC. TO REMAIN WITHIN THE GRADING LIMITS SHALL BE ADJUSTED AS NEEDED TO FUNCTION PROPERLY WITH THE PROPOSED FINISHED GRADES
- (WHETHER OR NOT INDICATED TO BE MODIFIED). 19. GENERAL CONTRACTOR TO COORDINATE ALL PEDESTRIAN ACCESS PATHS, LOCATIONS, LIGHTING ETC. WITH THE DEVELOPER
- 20. CONTRACTOR SHALL NOTIFY APPROPRIATE DEPARTMENTS PRIOR TO BEGINNING ANY WORK WITHIN PUBLIC RIGHT-OF-WAY.








ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS





























PHASE	1	2
NUMBER OF LOT(S)	29	97
LOT NUMBER(S) BY PHASE	1-60, 126-129, 170-185, 194-216, 280-297	61-125, 130-169, 186-193, 217-279
NUMBER OF SINGLE FAMILY UNITS	72	105
NUMBER OF TOWNHOME UNITS	49	71



09/06/2023

09/17/2021 DRAWN BY

> R. WINGATE DESIGNED BY P. BARBEAU CHECKED BY P. BARBEAU

SCALE AS SHOWN

43398

SHEET NO. C2.5

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



OPEN SPACE PARCE	L TABLE
Lot	Total Area (Acres)
OS - GREENWAY : 1009	0.55
OS - GREENWAY : 1028	0.84
OS ACTIVE : 1002	0.21
OS ACTIVE : 1003	0.07
OS ACTIVE : 1006	0.49
OS ACTIVE : 1015	0.29
OS ACTIVE : 1016	0.10
OS ACTIVE : 1018	0.06
OS ACTIVE : 1019	0.35
OS ACTIVE : 1024	0.33
OS ACTIVE : 1030	0.10
OS ACTIVE : 1033	0.17
OS ACTIVE : 1034	0.48
OS ACTIVE : 1035	0.44
OS ACTIVE : 1037	0.09

TOTAL ACTIVE OPEN SPACE	4.74 AC


OPE	OPEN SPACE PARCEL TABLE		
	Lot	Total Area (Acres)	
os	CONS : 1008	1.14	
os	CONS: 1013	5.57	
os	CONS : 1025	2.07	
os	CONS: 1032	1.02	
	CONSERVATION PEN SPACE	9.82 AC	

OPEN SPACE PARCEL TABLE		
Lot	Total Area (Acres)	
OS : 1000	0.16	
OS : 1001	0.37	
OS : 1004	0.87	
OS : 1005	1.67	
OS : 1007	0.52	
OS : 1010	0.52	
OS : 1011	0.21	
OS : 1012	0.86	
OS : 1014	0.07	
OS : 1017	0.04	
OS : 1021	0.32	
OS : 1022	0.36	
OS : 1026	0.30	
OS : 1027	0.66	
OS : 1029	0.69	
OS : 1031	1.22	
OS : 1036	0.70	


AREA	REQUIRED 10% GROSS AREA	PROVIDED
	TOTAL (ACTIVE)	TOTAL (ACTIVE)
(AC)	(AC)	(AC)
41.06	4.11 (2.06)	5.76 (2.06)
50.61	5.06 (2.53)	8.97 (2.68)
91.67		14.73 (4.74)
	(AC) 41.06 50.61	AREA TOTAL (ACTIVE)  (AC) (AC)  41.06 4.11 (2.06)  50.61 5.06 (2.53)

OPEN SPACE LEGEND		
HATCH	DESCRIPTION	
	ACTIVE OPEN SPACE	
	CONS. OPEN SPACE	

REFER TO DETAIL SHEETS FOR REPRESENTATIVE OPEN SPACE IMPROVEMENTS




ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




09/17/2021 DRAWN BY R. WINGATE DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN





STA 10+00 - 17+50

NOTE: ANY SEWER DEEPER THAN 12' REQUIRES

MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6'

SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER

DIAMETER MANHOLES AND DIP SEWER PIPE



PVC SDR35 MIN. 3' TO 12' NON-TRAFFIC AREA;

PVC SDR26

MIN. 5' TO 12' TRAFFIC AREA

12'-20' TRAFFIC AND NON-TRAFFIC AREAS MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING);

GREATER THAN 20' WITH DIRECTOR APPROVAL

PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A **FINE AND POSSIBLE EXCLUSION** FROM FUTURE WORK IN THE CITY OF RALEIGH.

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM

ATTENTION CONTRACTORS

### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


09/17/2021 DRAWN BY R. WINGATE


**DESIGNED BY** P. BARBEAU

CHECKED BY P. BARBEAU


AS SHOWN


JOB NO.





BRUNSWICK DR PLAN VIEW STA 17+50 - 23+49.78





BRUNSWICK DR PROFILE STA 17+50 - 23+49.78

> NOTE: ANY SEWER DEEPER THAN 12' REQUIRES SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6' DIAMETER MANHOLES AND DIP SEWER PIPE

#### SEWER MAIN MATERIAL:

PVC SDR26

PVC SDR35 MIN. 3' TO 12' NON-TRAFFIC AREA; MIN. 5' TO 12' TRAFFIC AREA

12'-20' TRAFFIC AND NON-TRAFFIC AREAS

MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING); GREATER THAN 20' WITH DIRECTOR APPROVAL

#### ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RÉSPONSIBLE FOR **CONTACTING** THE **PUBLIC WORKS DEPARTMENT** at **(919)** 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) **996-4540** AT LEAST **TWENTY FOUR HOURS** PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **FINE AND POSSIBLE EXCLUSION** FROM FUTURE WORK IN THE CITY OF RALEIGH.

# SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/17/2021 DRAWN BY R. WINGATE

**DESIGNED BY** P. BARBEAU CHECKED BY


P. BARBEAU AS SHOWN


JOB NO.

43398 SHEET NO.

C2.10


KNOW WHAT'S BELOW. CALL 811 BEFORE YOU DIG.





CARTERET DR PLAN VIEW

STA 9+50 - 20+00



CARTERET DR PROFILE STA 9+50 - 20+00

#### ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) **996-4540** AT LEAST **TWENTY FOUR HOURS** PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION FAILURE.

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A FINE AND POSSIBLE EXCLUSION FROM FUTURE WORK IN THE CITY OF RALEIGH.

### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/06/2023

DRAWN BY R. WINGATE **DESIGNED BY** 

09/17/2021


P. BARBEAU CHECKED BY P. BARBEAU


AS SHOWN

JOB NO.

SHEET NO. C2.11

KNOW WHAT'S BELOW. CALL 811 BEFORE YOU DIG.





CARTERET DR PROFILE STA 19+50 - 27+50

## ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) **996-4540** AT LEAST **TWENTY FOUR HOURS** PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION *FAILURE*.

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A FINE AND POSSIBLE EXCLUSION FROM FUTURE WORK IN THE CITY OF RALEIGH.

### SITE PERMITTING APPROVAL

### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards

and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


09/17/2021 DRAWN BY R. WINGATE


**DESIGNED BY** P. BARBEAU CHECKED BY

P. BARBEAU AS SHOWN


JOB NO.







### CARTERET DR PLAN VIEW STA 27+00 - 38+50





09/17/2021 DRAWN BY R. WINGATE **DESIGNED BY** 

P. BARBEAU CHECKED BY P. BARBEAU

AS SHOWN

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE

996-2409, And the **Public Utilities Department** at **(919)** 

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE

REINSTALLATION OF ANY WATER OR SEWER FACILITIES

NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

EXTENSION OF WATER. SEWER AND/OR REUSE. AS

APPROVED IN THESE PLANS, IS RESPONSIBLE FOR

996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO

BEGINNING ANY OF THEIR CONSTRUCTION.

CONTACTING THE PUBLIC WORKS DEPARTMENT at (919)

#### SITE PERMITTING APPROVAL

FAILURE.

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

PROFILE SCALE

City of Raleigh Review Officer


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


SHEET NO. C2.13

KNOW WHAT'S BELOW.


CALL 811 BEFORE YOU DIG.

JOB NO.






CARTERET DR PLAN VIEW STA 38+00 - 46+92.22



CARTERET DR PROFILE STA 38+00 - 46+92.22



09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU CHECKED BY P. BARBEAU

AS SHOWN

NOT INSPECTED AS A RESULT OF THIS NOTIFICATION FAILURE. FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A **FINE AND POSSIBLE EXCLUSION** FROM FUTURE WORK IN THE CITY OF RALEIGH.

ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE

EXTENSION OF WATER. SEWER AND/OR REUSE. AS

APPROVED IN THESE PLANS, IS RESPONSIBLE FOR

996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO

OF BEGINNING CONSTRUCTION, WILL RESULT IN THE

REINSTALLATION OF ANY WATER OR SEWER FACILITIES

BEGINNING ANY OF THEIR CONSTRUCTION.

ISSUANCE OF **MONETARY FINES**, AND REQUIRE

CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919)

# SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval


City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


JOB NO. SHEET NO.

C2.14





DARE DR PLAN VIEW STA 9+00 - 19+00



# ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS. IS RÉSPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES. AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's **Public Sewer System** as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit # \_\_

PROFILE SCALE

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



09/17/2021


DRAWN BY R. WINGATE DESIGNED BY

P. BARBEAU CHECKED BY P. BARBEAU


AS SHOWN

JOB NO. SHEET NO. C2.15





STA 18+00 - 29+50



AVERY DR C/L -BRUNSWICK DR C/L -MH 48 TOP 388.67 CB155 TOP 389.98 LOW POINT ELEV = 388.47 INV IN 382.81 (FR MH 47 INV IN 378 50 FR (CB156) PVI STA = 28+41.30 INV OUT 382 09 (TO MH 49) HIGH PT STA = 25+28.37 LOW POINT STA = 23+18.57 INV OUT 378.30 TO (DI154) PVI ELEV = 387.57 HIGH PT STA = 21+85.61 LOW POINT STA = 19+70.73 LOW POINT ELEV = 391.70 HIGH POINT ELEV = 392.45 HIGH POINT ELEV = 394.16 A.D. = 4.80% LOW POINT ELEV = 389.63 PVI STA = 23+49.88 INV IN 379.16 (FR MH 12 K = 31.24 PVI STA = 21+50.74 PVI STA = 25+35.53 PVI STA = 19+89.96 PVI ELEV = 391.26 INV IN 381.12 (FR MH 55) ₩ 150' VC — PVI ELEV = 394.98 PVI ELEV = 392.90 PVI ELEV = 389.28 A.D. = 2.82% INV IN 379.16 (FR MH 49) င္က ၉ MH 49 မွာ စွာ TOP 388.94 38 A.D. = -3.07% A.D. = -4.42% A.D. = 3.25% INV IN 384.18 (FR MH 33) K = 53.16 K = 48.83 K = 33.92 INV IN 381.02 (FR MH 48) K = 30.77 INV OUT 383.98 (TO MH 55) INV OUT 380.82 (TO MH 13) CB213
TOP 388.97 CB180 TOP 390.27 TOP 391.90 INV IN 384.30 FR (CB214) INV IN 386.03 (FR CB140) INV OUT 384.10 TO (FE212) INV IN 383.20 FR (CB166) INV OUT 385.93 (TO CB105) INV OUT 383.00 TO (CB157) INV IN 385.25 FR (CB216) INV|IN 384.60 FR (CB215) TOP 392.54 EXISTING -INV IN 383.41 (FR MH 34) INV IN 384.60 FR (CB217) INV IN 384.20 FR (DI167) INV OUT 385.15 TO (CB214) INV IN 376.55 FR (CB106) GROUND INV IN 383.41 (FR MH 54) INV OUT 384.50 TO (CB213) V OUT 384.00 TO (CB180) INV OUT 387.00 TO (¢B139) INV IN 385.10 FR (CB139) INV OUT 383.21 (TO MH 13 INV OUT 376.45 TO (CB104) INV OUT 387.62 TO (CB215 TOP 388.70 INV IN 385.00 FR (DI219) HYDRANT ASSEMBLY INV OUT \$84.90 TO (CB217) HYDRANT (TYP.) ASSEMBLY 15 inch RCP-8" GV (3) — 8" DIP WATERLINE + SAN. SEWER FORCEMAIN CROSSING 129.01' OF 8" PVC 15" RCP └─ 8" X 8" CROSS 113.10' OF 418.16' OF 8" Ductile Iron @ 0.50% **`**—39.99' ФF 106,63' OF 30" RCP LESS THAN 24" VERTICAL SEPARATION -8 PVC 18" MIN. 332.23' OF 8" SDR-26 @ 0.50% @ 1.00% PROVIDE CONCRETE CRADLE — WATER TOP 389.83 └24" MIN. -- INV IN 383.00 (FR CB158) 5' DIA. MANHOLE INV IN 382.00 (FR CB180) @ 0.91% INV OUT 379.40 (TO CB156) TOP 389.83 INV IN 379.00 (FR CB157) \_INV OUT 378.80 (TO CB155) \_ 18+00 18+50 20+50 21+00 21+50 22+00 22+50 23+50 24+00 25+50 26+50 27+00 27+50 28+00 28+50 DARE DR PROFILE



PROFILE SCALE

ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RÉSPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF **MONETARY FINES**, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/06/2023

09/17/2021 DRAWN BY R. WINGATE

**DESIGNED BY** P. BARBEAU CHECKED BY


P. BARBEAU

AS SHOWN


JOB NO.


SHEET NO.


C2.16



STA 28+50 - 34+50







WILKES LANE PLAN VIEW STA 9+86 - 10+79.15

LOW POINT STA = 28+41.95 LOW POINT ELEV = 388.47 PVI STA = 28+41.30 415 PVI ELEV = 387 57 A.D. = 4.80% K = 31.24 HIGH PT STA = 30+30 15 HIGH POINT ELEV = 390.81 PVI STA = 29+99.53 PVI ELEV = 391.34 A.D. = 3.38% K = 44.38 BULB C/L -LOW POINT STA = 34+22.56 LOW POINT ELEV = 387.61 INV IN 384.40 FR (CB206) PVI STA = 34+22.56 INV IN 384.20 FR (CB208) PVI ELEV = 387.11 INV OUT 383.75 TO (FE201) A.D. = 2.00% K = 100.00 INV IN 385.30 FR (CB207) 400 ∃200' VC <del>|</del> MH 35NM OUT 385.10 TO (CB202) TOP 389.19 INV IN 384.60 FR (DI209) INV OUT 382.51 (TO MH 40) INV OUT 384.40 TO (CB202) TOP 388.67 MH 47 TOP 390.03 INV IN 384.36 (FR CB205) INV IN 382.81 (FR MH 47) INV OUT 384.16 (TO DI203A) INV OUT 384.40 (TO MH 48) INV OUT 382.09 (TO MH 49) FIRE HYDRAN INV IN 381.35 (FR MH 39) 395 INV OUT 381.15 (TO MH 41) INV IN 379.83 (FR MH 41) INV OUT 379.63 (TO MH 43) - FIRE HYDRANT INV IN 384.30 FR (CB214) INV OUT 384.50 (TO CB204) TOP 388.32 GRADE ASSEMBLY INV OUT 384.10 TO (FE212) INV IN 380.64 (FR MH 40) (TYP.) INV OUT 380.44 (TO MH 42) 390 15 inch RCP 8" DIP WATERLINE -24" RCP @ 0.57% GROUND 178.89' OF └-18" MIN. 102.28' OF 8" PVC └39.99' OF 30" RCP @ 0.50% @ 0.65% 121.36' OF 8" **₽**∨C @ 0.50% 375 *386.4* 389.33 *385.1* 388.58 *385.4* 388.83

DARE DR PROFILE

32+00

33+00

34+00

PROFILE SCALE

31+50

TOP 389.57 MH 44 TDP 388.50 INV OUT 383.73 (TO MH 44) – FIRE HYDRANT ASSEMBLY (TYP.) INV IN 378.53 (FR MH 43) INV IN 380.70 (FR MH 46) INV OUT 378.33 (TO MH 45 390 GROUND . GRADE 8" X 6" TEE 8" GV (2) WATERLINE 6" GV (1) Water and Sewer Permits (If applicable) Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_ - 5' DROP MANHOLE w/EXTENDED BASE REFER TO DETAIL S-53 *386.6* 389.17 *387.5* 389.55 *388.5* 389.92 11+00 10+00 PROFILE SCALE WILKES LANE PROFILE STA 9+86 - 10+79.15

ATTENTION CONTRACTORS THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES. AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

The City of Raleigh consents to the connection and extension of the City's **Public Sewer System** as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

KNOW WHAT'S BELOW. CALL 811 BEFORE YOU DIG.

28+50

29+00


30+00

09/17/2021 DRAWN BY R. WINGATE **DESIGNED BY** 


P. BARBEAU CHECKED BY P. BARBEAU

AS SHOWN

JOB NO.



DARE DR PLAN VIEW STA 33+50 - 45+00





CALL 811 BEFORE YOU DIG.

PROFILE SCALE

ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER **VIOLATION** OF **CITY OF RALEIGH STANDARDS** WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/06/2023


09/17/2021 DRAWN BY R. WINGATE **DESIGNED BY** 

P. BARBEAU CHECKED BY


P. BARBEAU

AS SHOWN

JOB NO.



DAVIE DR PLAN VIEW STA 44+00 - 55+00



KNOW WHAT'S BELOW. CALL 811 BEFORE YOU DIG. THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE

ATTENTION CONTRACTORS

EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RÉSPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF **MONETARY FINES**, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit # \_\_

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF

09/17/2021 DRAWN BY R. WINGATE

**DESIGNED BY** P. BARBEAU CHECKED BY . BARBEAU


AS SHOWN

JOB NO.


SHEET NO. C2.19


RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


PROFILE SCALE




STA 10+00 - 14+35.34








PAMLICO LN PLAN VIEW STA 10+00 - 12+00



HYDE DR PROFILE STA 10+00 - 14+35.34

DIP



ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RÉSPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG. HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_\_\_

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/17/2021

DRAWN BY R. WINGATE **DESIGNED BY** 

P. BARBEAU CHECKED BY P. BARBEAU

AS SHOWN

JOB NO. SHEET NO. C2.20

NOTE: ANY SEWER DEEPER THAN 12' REQUIRES SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6' DIAMETER MANHOLES AND DIP SEWER PIPE.


SEWER MAIN MATERIAL:

PVC SDR35 MIN. 3' TO 12' NON-TRAFFIC AREA;


MIN. 5' TO 12' TRAFFIC AREA

PVC SDR26 12'-20' TRAFFIC AND NON-TRAFFIC AREAS

> MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING); GREATER THAN 20' WITH DIRECTOR APPROVAL



**AVERY DRIVE PLAN VIEW** STA 10+00 - 13+68.74



# AVERY DRIVE PROFILE

STA 10+00 - 13+68.74

NOTE: ANY SEWER DEEPER THAN 12' REQUIRES PVC SDR26 SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6' DIAMETER MANHOLES AND DIP SEWER PIPE

SEWER MAIN MATERIAL: PVC SDR35 MIN. 3' TO 12' NON-TRAFFIC AREA;

MIN. 5' TO 12' TRAFFIC AREA 12'-20' TRAFFIC AND NON-TRAFFIC AREAS

MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING); GREATER THAN 20' WITH DIRECTOR APPROVAL

# ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS. IS RÉSPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES. AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit # \_\_

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



09/17/2021 R. WINGATE


**DESIGNED BY** P. BARBEAU CHECKED BY


P. BARBEAU

AS SHOWN


JOB NO. SHEET NO.


C2.21





CATAWBA DR PLAN VIEW STA 10+83 - 19+50





#### CATAWBA DR PROFILE STA 10+83 - 19+50

NOTE: ANY SEWER DEEPER THAN 12' REQUIRES SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6' DIAMETER MANHOLES AND DIP SEWER PIPE

## SEWER MAIN MATERIAL

PVC SDR26

PVC SDR35 MIN. 3' TO 12' NON-TRAFFIC AREA; MIN. 5' TO 12' TRAFFIC AREA

12'-20' TRAFFIC AND NON-TRAFFIC AREAS

MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING); **GREATER THAN 20' WITH DIRECTOR APPROVAL** 

09/17/2021 DRAWN BY R. WINGATE

**DESIGNED BY** P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE

OF BEGINNING CONSTRUCTION, WILL RESULT IN THE

REINSTALLATION OF ANY WATER OR SEWER FACILITIES

NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

EXTENSION OF WATER, SEWER AND/OR REUSE, AS

APPROVED IN THESE PLANS, IS RESPONSIBLE FOR

996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO

BEGINNING ANY OF THEIR CONSTRUCTION.

ISSUANCE OF MONETARY FINES, AND REQUIRE

CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919)

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit#

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.


Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.


City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

JOB NO.





### CALDWELL DR PROFILE STA 10+00 - 17+00

SEWER MAIN MATERIAL

MIN. 3' TO 12' NON-TRAFFIC AREA; PVC SDR35 MIN. 5' TO 12' TRAFFIC AREA NOTE: ANY SEWER DEEPER THAN 12' REQUIRES PVC SDR26 12'-20' TRAFFIC AND NON-TRAFFIC AREAS SDR-26 OR DIP SEWER PIPE AND 5' DIAMETER MANHOLES. SEWER DEEPER THAN 20' REQUIRES 6' MIN. 3' TO 5' TRAFFIC AREA (CLASS 1 BEDDING); DIAMETER MANHOLES AND DIP SEWER PIPE **GREATER THAN 20' WITH DIRECTOR APPROVAL** 

### ATTENTION CONTRACTORS

THE CONSTRUCTION CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER AND/OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC WORKS DEPARTMENT at (919) 996-2409, AND THE PUBLIC UTILITIES DEPARTMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF **MONETARY FINES**, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

#### Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # \_\_

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State, and Federal Rules and Regulations.

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

City of Raleigh Review Officer

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


09/17/2021


DRAWN BY R. WINGATE DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN

JOB NO. SHEET NO. C2.23





DRAWN BY R. WINGATE **DESIGNED BY** 

09/17/2021

P. BARBEAU CHECKED BY P. BARBEAU

SCALE

AS SHOWN

FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER OR SEWER FACILITIES NOT INSPECTED AS A RESULT OF THIS NOTIFICATION

ATTENTION CONTRACTORS

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTREAM PLUG, HAVE PERMITTED PLANS ON THE JOBSITE, OR ANY OTHER VIOLATION OF CITY OF RALEIGH STANDARDS WILL RESULT IN A **Fine and possible exclusion** from future WORK IN THE CITY OF RALEIGH.

#### SITE PERMITTING APPROVAL

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

#### CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


Plans for the proposed use have been reviewed for general compliance with applicable codes. This limited review, and authorization for construction is not to be considered to represent total compliance with all legal requirements for development and construction. The property owner, design consultants, and contractors are each responsible for compliance with all applicable City, State and Federal laws. This specific authorization below is not a permit, nor shall it be construed to permit any violation of City, State or Federal Law. All Construction must be in accordance with all Local, State,


Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.


City of Raleigh Review Officer


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF


JOB NO.














ROUNDABOUT CURB PROFILE NOTES:

- 1. PROFILES ARE FOR BACK OF CURB ELEVATIONS. 2. REFER TO GRADING AND DRAINAGE PLANS FOR STORM DRAINAGE.
- 3. REFER TO UTILITY PLANS FOR UTILITIES.

SCALE 1"=50'

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/06/2023

09/17/2021 DRAWN BY


R. WINGATE DESIGNED BY


P. BARBEAU CHECKED BY


P. BARBEAU AS SHOWN


43398 SHEET NO.

C2.25











	AND STODIA	1 DRAINAGE NO
UNICIANU	HIND STURIN	I DRAINAGE NO

1. CONTRACTOR SHALL CALL "NORTH CAROLINA ONE CALL" (811) AT LEAST 3-12 BUSINESS DAYS PRIOR TO DIGGING TO HAVE EXISTING UTILITIES LOCATED. REPORT ANY DISCREPANCIES TO THE ENGINEER.

2. CONTRACTOR TO COORDINATE ACTIVITIES WITH UTILITY COMPANIES INVOLVED IN ANY RELATED RELOCATION (I.E. POWER POLES, TELEPHONE

PEDESTALS, WATER METERS, ETC.). EXISTING UTILITIES SHOWN ARE BASED ON FIELD SURVEYS AND THE BEST AVAILABLE RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY CONDITIONS PRIOR TO BEGINNING CONSTRUCTION. ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE PLANS SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.

THE CATCH BASINS AND YARD INLETS SHALL BE CONSTRUCTED IN THE LOCATIONS SHOWN UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES IN THE CATCH BASIN ELEVATIONS OR THE PROPOSED PIPE SLOPES TO THE ENGINEER. THE CONTRACTOR IS ALSO RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN ANY UTILITY, STORM DRAIN LINE, WATER LINE, SEWER LINE OR ANY OTHER PROPOSED OR EXISTING STRUCTURE TO THE

A LAND DISTURBING PERMIT WILL BE REQUIRED PRIOR TO THE COMMENCEMENT OF ANY LAND-DISTURBING ACTIVITIES.

ALL EXISTING VAULTS, MANHOLES, STORM DRAIN STRUCTURES, VALVE BOXES, CLEANOUTS, ETC. SHALL BE ADJUSTED AS NEEDED TO MATCH FINISHED GRADE.

7. ALL BACKFILL, COMPACTION, SOILS TESTING, ETC. SHALL BE PERFORMED BY THE OWNER'S INDEPENDENT TESTING LABORATORY.

ALL SPOT ELEVATIONS INDICATED ARE AT TOP OF CURB UNLESS NOTED OTHERWISE. ALL ELEVATIONS ARE BASED ON VERTICAL DATUM NAVD88. A PRE-CONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO ANY

WORK, GRADING OR INSTALLATION OF EROSION CONTROL MEASURES. 10. ALL HANDICAP PARKING SPACES AND STRIPED ACCESSIBILITY AISLES ARE TO HAVE NO MORE THAN A 1:50 (2.0%) SLOPE IN ALL DIRECTIONS. ALL SIDEWALKS ARE TO HAVE NO MORE THAN A 1:20 (5.0%) SLOPE FOR THE LENGTH OF THE SIDEWALK AND NO MORE THAN A 1:50 (2.0%) SLOPE FOR THE WIDTH OF THE SIDEWALK.

11. CONTRACTOR TO IDENTIFY ALL NECESSARY SPILL CURB SECTION LOCATIONS AND INSTALL TO ENSURE POSITIVE DRAINAGE TO STORM STRUCTURES.

12. IF CONTRACTOR NOTICES ANY DISCREPANCIES IN ANY OF THESE SLOPE REQUIREMENTS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNER PRIOR TO POURING ANY CONCRETE SO THAT A SOLUTION CAN

13. SPOT ELEVATIONS ARE GIVEN AT THE MAJORITY OF THE MAJOR BREAK POINTS BUT IT SHOULD NOT BE ASSUMED THAT ALL NECESSARY SPOT ELEVATIONS ARE SHOWN. DUE TO SPACE LIMITATIONS, THERE MAY BE OTHER CRITICAL SPOTS NOT LABELED THAT SHOULD BE TAKEN INTO CONSIDERATION. THE CONTRACTOR SHALL REVIEW THE GRADING PLAN IN DETAIL AND SHALL ENSURE THAT ALL CRITICAL GRADE POINTS ARE STAKED AND FOLLOWED TO PROVIDE POSITIVE DRAINAGE.

14. EXISTING VEGETATION WITHIN TREE PROTECTIVE AREAS SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE. ANY AND ALL LANDSCAPING AND EXISTING TREES AND SHRUBS TO REMAIN WHICH ARE DAMAGED DURING DEMOLITION OR CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR USING A LICENSED LANDSCAPE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH RAINFALL EVENT OR AS DIRECTED BY THE EROSION CONTROL INSPECTOR OR THE ENGINEER.

THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING CONSTRUCTION AND FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS.

ALL CATCH BASINS MUST BE MARKED "DUMP NO WASTE DRAINS TO STREAM" OR EQUIVALENT.

RETAINING WALLS TO BE DESIGNED BY OTHERS' STRUCTURAL ENGINEER. WALLS GREATER THAN 30" IN HEIGHT TO HAVE 42" SAFETY RAIL.

74444	09	/0	6/	20	23	<u>}</u>
10:00:0151 WWW.tillinglis:0011	IPTION	JNTY COMMENTS	JNTY COMMENTS	ENT SUBMITTAL	T COMMENTS	

09/17/2021

DRAWN BY R. WINGATE **DESIGNED BY** 

P. BARBEAU CHECKED BY

P. BARBEAU AS SHOWN

43398 SHEET NO. C3.0


SCALE 1"=50'


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


21101111111111	101 1115 111 71	10.11.11.21.12.11.11.11.11.1	201101111111111111111111111111111111111	0.51010115	
PDD-1	7 FT	1 FT	1	3:1	North American Green, S75
PDD-2	7.6 FT	1.1 FT	1	3:1	North American Green, S75
PDD-3	8.2 FT	1.2 FT	1	3:1	North American Green, S75
PDD-4	9.6 FT	1.6 FT	0	3:1	North American Green, S75
PDD-5	10 FT	1 FT	0	3:1	North American Green, S75
PDD-6	20 FT	1 FT	0	3:1	North American Green, S75
PDD-7	8 FT	1 FT	1	3:1	North American Green, S75
PDD-8	8.2 FT	1.2 FT	1	3:1	North American Green, S75
PDD-9	10.8 FT	1.4 FT	1	3:1	North American Green, S75
PDD-10	7 FT	1 FT	1	3:1	North American Green, S75
PDD-11	8.2 FT	1.2 FT	1	3:1	North American Green, S75
PDD-12	6 FT	1 FT	0	3:1	North American Green, SC150
PDD-13	7.2 FT	1.2 FT	0	3:1	North American Green, S75
PDD-14	12 FT	1 FT	0	3:1	North American Green, S75
PDD-15	5.6 FT	1.4 FT	0	3:1	North American Green, S150
PDD-16	7.8 FT	1.3 FT	0	3:1	North American Green, S75
PDD-17	9 FT	1 FT	3	3:1	North American Green, S75
PDD-18	6.6 FT	1.1 FT	0	3:1	North American Green, S75
PDD-19	10 FT	1 FT	0	3:1	North American Green, S75
PDD-20	7.2 FT	1.2 FT	0	3:1	North American Green, S75
PDD-21	6 FT	1 FT	0	3:1	North American Green, S75
PDD-22	6 FT	1 FT	0	3:1	North American Green, S75
PDD-23	8.8 FT	1.3 FT	1	3:1	North American Green, SC150
PDD-24	6 FT	1 FT	0	3:1	North American Green, S75
PDD-25	6.6 FT	1.1 FT	0	3:1	North American Green, S150
PDD-26	6 FT	1 FT	0	3:1	North American Green, S75
PDD-27	8.2 FT	1.2 FT	1	3:1	North American Green, S75
PDD-28	6 FT	1 FT	0	3:1	North American Green, S75
PDD-29	6 FT	1 FT	0	3:1	North American Green, S75


REFER TO SHEETS C3.1-C3.4 FOR LOCATIONS OF PERMANENT DITCHES.

DITCH NAME | TOP WIDTH "A" | MIN. DITCH DEPTH (FT) "B" | BOTTOM WIDTH (FT) "C" | SIDE SLOPE "D" | LINER TYPE & THICKNESS









		371.30 (42 KCF FROW CB114)		
CB103	387.22'	375.06' (36" RCP FROM CB104) 381.32' (15" RCP FROM CB181)	374.96' (36" RCP TO CB183)	NCDOT 840.02 CONCRETE CATCH BASIN
CB104	392.16'	376.20' (30" RCP FROM CB105) 385.00' (24" RCP FROM CB136)	376.10' (36" RCP TO CB103)	NCDOT 840.02 CONCRETE CATCH BASIN
00105	000.54	376.55' (30" RCP FROM CB106)	276 AEL (2011 DOD TO OD404)	NODOT 646 00 CONODETE CATOURDADIU
CB105	392.54'	385.10' (15" RCP FROM CB139)	376.45' (30" RCP TO CB104)	NCDOT 840.02 CONCRETE CATCH BASIN
CB106	394.42'	377.05' (30" RCP FROM CB107)	376.95' (30" RCP TO CB105)	NCDOT 840.02 CONCRETE CATCH BASIN
CB107	396.68'	377.81' (30" RCP FROM CB108) 383.00' (18" RCP FROM DI141)	377.71' (30" RCP TO CB106)	NCDOT 840.02 CONCRETE CATCH BASIN
CB108	397.75'	389.50' (15" RCP FROM CB144) 378.43' (24" RCP FROM CB109)	378.33' (30" RCP TO CB107)	NCDOT 840.02 CONCRETE CATCH BASIN
CB109	393.12'	380.88' (24" RCP FROM CB110) 385.91' (15" RCP FROM CB146)	380.78' (24" RCP TO CB108)	NCDOT 840.02 CONCRETE CATCH BASIN
CB110	386.73'	382.20' (18" RCP FROM DI111) 382.00' (15" RCP FROM CB147) 381.90' (18" RCP FROM CB182)	381.80' (24" RCP TO CB109)	NCDOT 840.02 CONCRETE CATCH BASIN
CB112	389.02'	377.50' (15" RCP FROM CB113)	377.30' (15" RCP TO CB101)	NCDOT 840.02 CONCRETE CATCH BASIN
CB113	388.52'		378.00' (15" RCP TO CB112)	NCDOT 840.02 CONCRETE CATCH BASIN
CB114	384.27'	372.10' (30" RCP FROM CB115) 378.00' (15" RCP FROM CB124) 377.50' (15" RCP FROM CB125)	371.98' (42" RCP TO CB102)	NCDOT 840.02 CONCRETE CATCH BASIN
CB115	384.75'	372.65' (30" RCP FROM CB116) 378.50' (15" RCP FROM CB126)	372.51' (30" RCP TO CB114)	NCDOT 840.02 CONCRETE CATCH BASIN
CB116	386.55'	374.00' (30" RCP FROM CB117) 377.32' (18" RCP FROM CB127)	373.90' (30" RCP TO CB115)	NCDOT 840.02 CONCRETE CATCH BASIN
CB117	385.70'	375.80' (30" RCP FROM CB118) 376.00' (18" RCP FROM CB132)	374.25' (30" RCP TO CB116)	NCDOT 840.02 CONCRETE CATCH BASIN
CB118	385.70'	376.25' (30" RCP FROM CB119)	376.00' (30" RCP TO CB117)	NCDOT 840.02 CONCRETE CATCH BASIN
CB119	385.64'	376.60' (30" RCP FROM CB120)	376.60' (30" RCP TO CB118)	NCDOT 840.02 CONCRETE CATCH BASIN
CB120	384.51'	377.37' (24" RCP FROM CB121) 377.70' (24" RCP FROM CB134)	377.37' (30" RCP TO CB119)	NCDOT 840.02 CONCRETE CATCH BASIN
CB121	383.79'	377.84' (18" RCP FROM CB122)	377.84' (24" RCP TO CB120)	NCDOT 840.02 CONCRETE CATCH BASIN
CB122	383.33'	378.70' (18" RCP FROM CB123) 379.41' (15" RCP FROM CB148A)	378.50' (18" RCP TO CB121)	NCDOT 840.02 CONCRETE CATCH BASIN
CB123	385.17'		380.00' (18" RCP TO CB122)	NCDOT 840.02 CONCRETE CATCH BASIN
CB124	384.12'		379.41' (15" RCP TO CB114)	NCDOT 840.02 CONCRETE CATCH BASIN
CB125	384.27'		379.38' (15" RCP TO CB114)	NCDOT 840.02 CONCRETE CATCH BASIN
CB126	384.75'		379.00' (15" RCP TO CB115)	NCDOT 840.02 CONCRETE CATCH BASIN
CB127	386.55'	377.63' (18" RCP FROM CB128)	377.53' (18" RCP TO CB116)	NCDOT 840.02 CONCRETE CATCH BASIN
CB128	386.69'	378.50' (18" RCP FROM CB129)	378.30' (18" RCP TO CB127)	NCDOT 840.02 CONCRETE CATCH BASIN
CB129	386.69'	378.90' (15" RCP FROM CB130) 379.85' (15" RCP FROM CB149)	378.80' (18" RCP TO CB128)	NCDOT 840.02 CONCRETE CATCH BASIN
CB130	387.79'	381.50' (15" RCP FROM CB131)	381.30' (15" RCP TO CB129)	NCDOT 840.02 CONCRETE CATCH BASIN
CB131	388.08'		382.12' (15" RCP TO CB130)	NCDOT 840.02 CONCRETE CATCH BASIN
CB132	382.27'	377.30' (15" RCP FROM CB133)	377.00' (18" RCP TO CB117)	NCDOT 840.02 CONCRETE CATCH BASIN
CB133	382.19'		377.70' (15" RCP TO CB132)	NCDOT 840.02 CONCRETE CATCH BASIN
CB134	383.96'	378.15' (24" RCP FROM DI135)	378.15' (24" RCP TO CB120)	NCDOT 840.02 CONCRETE CATCH BASIN
CB136	392.15'	385.31' (18" RCP FROM CB137)	385.21' (24" RCP TO CB104)	NCDOT 840.02 CONCRETE CATCH BASIN
CB137	394.19'	386.14' (15" RCP FROM CB138)	385.94' (18" RCP TO CB136)	NCDOT 840.02 CONCRETE CATCH BASIN
CB138	394.33'	386.75' (15" RCP FROM CB190)	386.55' (15" RCP TO CB137)	NCDOT 840.02 CONCRETE CATCH BASIN
CB139	391.90'	386.03' (15" RCP FROM CB140)	385.93' (15" RCP TO CB105)	NCDOT 840.02 CONCRETE CATCH BASIN
CB140	391.90'		387.00' (15" RCP TO CB139) 390.50' (15" RCP TO CB108)	NCDOT 840.02 CONCRETE CATCH BASIN
CB144	397.75'		388.00' (15" RCP TO CB109)	NCDOT 840.02 CONCRETE CATCH BASIN
CB146 CB147	392.43' 386.36'		382.65' (15" RCP TO CB110)	NCDOT 840.02 CONCRETE CATCH BASIN  NCDOT 840.02 CONCRETE CATCH BASIN
CB147	383.33'	379.80' (15" RCP FROM CB148B)	379.75' (15" RCP TO CB122)	NCDOT 840.02 CONCRETE CATCH BASIN
CB148B	383.34'		379.90' (15" RCP TO CB148A)	NCDOT 840.02 CONCRETE CATCH BASIN
CB140B	385.63'		380.31' (15" RCP TO CB129)	NCDOT 840.02 CONCRETE CATCH BASIN
CB150	382.85'	372.90' (30" RCP FROM CB151) 377.50' (15" RCP FROM CB162)	372.80' (30" RCP TO DI149)	NCDOT 840.02 CONCRETE CATCH BASIN
CB151	383.50'	373.30' (30" RCP FROM CB152)	373.20' (30" RCP TO CB150)	NCDOT 840.02 CONCRETE CATCH BASIN
CB152	385.99'	375.54' (30" RCP FROM DI153) 380.30' (15" RCP FROM CB164)	375.40' (30" RCP TO CB151)	NCDOT 840.02 CONCRETE CATCH BASIN
CB155	389.98'	378.50' (24" RCP FROM CB156)	378.30' (30" RCP TO DI154)	NCDOT 840.02 CONCRETE CATCH BASIN
CB156	389.83'	379.00' (24" RCP FROM CB157)	378.80' (24" RCP TO CB155)	NCDOT 840.02 CONCRETE CATCH BASIN
		383.00' (18" RCP FROM CB158)	,	
CB157	389.83'	382.00' (15" RCP FROM CB180)	379.40' (24" RCP TO CB156)	NCDOT 840.02 CONCRETE CATCH BASIN

STORM STRUCTURE TABLE

INV. OUT

DESCRIPTION

370.65' (48" RCP TO EW100) NCDOT 840.02 CONCRETE CATCH BASIN

371.24' (42" RCP TO CB101) NCDOT 840.02 CONCRETE CATCH BASIN

STR.# TOP

INV. IN

CB101 387.82' 370.75' (42" RCP FROM CB102) 375.00' (15" RCP FROM CB112)

CB102 386.25' 371.50' (42" RCP FROM CB183) 371.30' (42" RCP FROM CB114)

STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION	
CB158	389.61'	385.29' (18" RCP FROM CB159) 385.70' (15" RCP FROM CB168)	385.00' (18" RCP TO CB157)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB159	390.81'	386.70' (15" RCP FROM CB160) 386.90' (15" RCP FROM CB170)	386.50' (18" RCP TO CB158)	NCDOT 840.02 CONCRETE CATCH BAS	
CB160	394.36'	390.50' (15" RCP FROM CB161)	390.30' (15" RCP TO CB159)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB161	394.36'		390.76' (15" RCP TO CB160)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB162	382.26'	377.90' (15" RCP FROM DI163)	377.80' (15" RCP TO CB150)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB164	387.46'	382.70' (15" RCP FROM CB165)	380.74' (15" RCP TO CB152)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB165	388.33'		385.00' (15" RCP TO CB164)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB166	390.71'	384.20' (15" RCP FROM DI167)	384.00' (15" RCP TO CB180)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB168	389.61'	386.00' (15" RCP FROM CB169)	385.90' (15" RCP TO CB158)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB169	391.29'		386.76' (15" RCP TO CB168)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB170	390.81'		387.10' (15" RCP TO CB159)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB180	390.27'	383.20' (15" RCP FROM CB166)	383.00' (15" RCP TO CB157)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB181	387.21'		383.00' (15" RCP TO CB103)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB182	385.98'		382.20' (18" RCP TO CB110)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB183	386.74'	373.20' (36" RCP FROM CB103)	373.00' (42" RCP TO CB102)	NCDOT 840.02 CONCRETE CATCH BASIN	
CB190	395.70'	387.56' (15" RCP FROM DI192)	387.56' (15" RCP TO CB138)	NCDOT 840.02 CONCRETE CATCH BASIN	
DI111	387.17'		384.00' (18" RCP TO CB110)	36" X 36" SLAB TOP YARD INLET	
DI135	382.00'	378.94' (24" RCP FROM DI188)	378.84' (24" RCP TO CB134)	36" X 36" SLAB TOP YARD INLET	
DI141	390.91'	384.20' (18" RCP FROM DI142)	384.00' (18" RCP TO CB107)	36" X 36" SLAB TOP YARD INLET	
DI142	391.26'	385.20' (18" RCP FROM DI143) 386.00' (18" RCP FROM DI143A)	385.00' (18" RCP TO DI141)	36" X 36" SLAB TOP YARD INLET	
DI143	388.42'		385.80' (18" RCP TO DI142)	36" X 36" SLAB TOP YARD INLET	
DI143A	389.14'		386.50' (18" RCP TO DI142)	36" X 36" SLAB TOP YARD INLET	
DI149	378.86'	371.10' (30" RCP FROM CB150)	371.00' (48" RCP TO EW148)	60" X 60" SLAB TOP YARD INLET	
DI153	382.56'	376.63' (30" RCP FROM DI154)	376.50' (30" RCP TO CB152)	36" X 36" SLAB TOP YARD INLET	
DI154	383.86'	377.34' (30" RCP FROM CB155)	377.10' (30" RCP TO DI153)	36" X 36" SLAB TOP YARD INLET	
DI163	381.91'		378.60' (15" RCP TO CB162)	36" X 36" SLAB TOP YARD INLET	
DI167	388.91'		384.76' (15" RCP TO CB166)	36" X 36" SLAB TOP YARD INLET	
DI188	384.27'	380.30' (18" RCP FROM DI195)	380.10' (24" RCP TO DI135)	36" X 36" SLAB TOP YARD INLET	
DI192	392.26'	388.60' (15" RCP FROM DI193)	388.40' (15" RCP TO CB190)	36" X 36" SLAB TOP YARD INLET	
DI193	393.48'		390.75' (15" RCP TO DI192)	36" X 36" SLAB TOP YARD INLET	
DI194	385.64'		383.10' (15" RCP TO DI195)	36" X 36" SLAB TOP YARD INLET	
DI195	384.05'	381.90' (15" RCP FROM DI194)	381.80' (18" RCP TO DI188)	36" X 36" SLAB TOP YARD INLET	
EW100	374.50'	370.00' (48" RCP FROM CB101)	,	NCDOT 838.80 CONCRETE ENDWALL	
EW148	374.50'	370.00' (48" RCP FROM DI149)		NCDOT 838.80 CONCRETE ENDWALL	

		STOR	RM STRUCTURE TABLE	
STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION
CB202	389.19'	384.40' (24" RCP FROM CB206) 384.20' (24" RCP FROM CB208)	383.75' (30" RCP TO FE201)	NCDOT 840.02 CONCRETE CATCH BASIN
CB204	387.81'	384.36' (15" RCP FROM CB205)	384.16' (24" RCP TO DI203A)	NCDOT 840.02 CONCRETE CATCH BASIN
CB205	387.81'		384.50' (15" RCP TO CB204)	NCDOT 840.02 CONCRETE CATCH BASIN
CB206	390.49'	385.30' (15" RCP FROM CB207)	385.10' (24" RCP TO CB202)	NCDOT 840.02 CONCRETE CATCH BASIN
CB207	390.58'		385.60' (15" RCP TO CB206)	NCDOT 840.02 CONCRETE CATCH BASIN
CB208	389.19'	384.60' (18" RCP FROM DI209)	384.40' (24" RCP TO CB202)	NCDOT 840.02 CONCRETE CATCH BASIN
CB213	388.97'	384.30' (30" RCP FROM CB214)	384.10' (30" RCP TO FE212)	NCDOT 840.02 CONCRETE CATCH BASIN
CB214	388.79'	384.60' (18" RCP FROM CB215) 384.60' (24" RCP FROM CB217)	384.50' (30" RCP TO CB213)	NCDOT 840.02 CONCRETE CATCH BASIN
CB215	390.18'	385.25' (15" RCP FROM CB216)	385.15' (18" RCP TO CB214)	NCDOT 840.02 CONCRETE CATCH BASIN
CB216	391.32'		387.62' (15" RCP TO CB215)	NCDOT 840.02 CONCRETE CATCH BASIN
CB217	388.67'	384.85' (24" RCP FROM CB218)	384.75' (24" RCP TO CB214)	NCDOT 840.02 CONCRETE CATCH BASIN
CB218	388.70'	385.00' (24" RCP FROM DI219)	384.90' (24" RCP TO CB217)	NCDOT 840.02 CONCRETE CATCH BASIN
DI203	387.24'	383.50' (24" RCP FROM DI203A)	383.40' (24" RCP TO EW220)	36" X 36" SLAB TOP YARD INLET
01203A	388.55'	383.95' (24" RCP FROM CB204)	383.85' (24" RCP TO DI203)	36" X 36" SLAB TOP YARD INLET
DI209	388.00'		385.40' (18" RCP TO CB208)	36" X 36" SLAB TOP YARD INLET
DI219	388.46'		385.70' (24" RCP TO CB218)	36" X 36" SLAB TOP YARD INLET
W220	385.25'	383.00' (24" RCP FROM DI203)		NCDOT 838.80 CONCRETE ENDWALL
FE201	N/A	383.20' (30" RCP FROM CB202)		FLARED END SECTION
E212	N/A	383.00' (30" RCP FROM CB213)		FLARED END SECTION

STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION
CB278	368.07'	360.69' (18" RCP FROM CB327)	360.19' (18" RCP TO VI276)	NCDOT 840.02 CONCRETE CATCH BASIN
CB302	358.15'	348.90' (36" RCP FROM CB303) 350.87' (15" RCP FROM CB323) 347.92' (30" RCP FROM DI324)	347.72' (36" RCP TO JB301)	NCDOT 840.02 CONCRETE CATCH BASIN
CB303	359.79'	349.51' (36" RCP FROM CB304) 351.00' (15" RCP FROM CB326)	349.40' (36" RCP TO CB302)	NCDOT 840.02 CONCRETE CATCH BASIN
CB304	360.95'	353.00' (36" RCP FROM CB305) 351.62' (15" RCP FROM CB325)	350.22' (36" RCP TO CB303)	NCDOT 840.02 CONCRETE CATCH BASIN
CB305	361.55'	354.00' (36" RCP FROM CB306) 355.80' (15" RCP FROM CB398)	353.80' (36" RCP TO CB304)	NCDOT 840.02 CONCRETE CATCH BASIN
CB306	364.83'	356.19' (36" RCP FROM CB307)	356.09' (36" RCP TO CB305)	NCDOT 840.02 CONCRETE CATCH BASIN
CB307	367.74'	356.77' (36" RCP FROM VI276)	356.67' (36" RCP TO CB306)	NCDOT 840.02 CONCRETE CATCH BASIN
CB308	365.81'	357.89' (30" RCP FROM VI309) 361.20' (15" RCP FROM CB333) 361.00' (15" RCP FROM DI380)	357.79' (36" RCP TO VI276)	NCDOT 840.02 CONCRETE CATCH BASIN
CB310	364.51'	359.20' (30" RCP FROM CB311) 359.20' (15" RCP FROM DI361)	359.00' (30" RCP TO VI309)	NCDOT 840.02 CONCRETE CATCH BASIN
CB311	365.57'	361.20' (30" RCP FROM CB312) 361.90' (18" RCP FROM CB337)	361.00' (30" RCP TO CB310)	NCDOT 840.02 CONCRETE CATCH BASIN
CB312	367.67'	362.40' (30" RCP FROM CB314) 363.53' (15" RCP FROM CB338)	362.20' (30" RCP TO CB311)	NCDOT 840.02 CONCRETE CATCH BASIN
CB314	369.34'	363.16' (30" RCP FROM CB315) 364.70' (15" RCP FROM CB340)	362.82' (30" RCP TO CB312)	NCDOT 840.02 CONCRETE CATCH BASIN
CB315	370.31'	363.90' (24" RCP FROM CB316) 364.91' (18" RCP FROM DI341)	363.69' (30" RCP TO CB314)	NCDOT 840.02 CONCRETE CATCH BASIN
CB316	371.29'	365.20' (24" RCP FROM CB317) 367.00' (18" RCP FROM CB342)	365.00' (24" RCP TO CB315)	NCDOT 840.02 CONCRETE CATCH BASIN
CB317	372.50'	366.20' (18" RCP FROM VI318) 368.10' (24" RCP FROM CB346)	366.00' (24" RCP TO CB316)	NCDOT 840.02 CONCRETE CATCH BASIN
CB319	377.98'	372.70' (15" RCP FROM CB320) 374.10' (15" RCP FROM CB349)	372.50' (18" RCP TO VI318)	NCDOT 840.02 CONCRETE CATCH BASIN
CB320	382.05'	375.20' (15" RCP FROM CB321)	375.00' (15" RCP TO CB319)	NCDOT 840.02 CONCRETE CATCH BASIN
CB321	381.98'	376.20' (15" RCP FROM CB322)	376.00' (15" RCP TO CB320)	NCDOT 840.02 CONCRETE CATCH BASIN
CB322	381.40'		376.70' (15" RCP TO CB321)	NCDOT 840.02 CONCRETE CATCH BASIN
CB323	355.26'		351.75' (15" RCP TO CB302)	NCDOT 840.02 CONCRETE CATCH BASIN
CB325	355.50'		352.20' (15" RCP TO CB304)	NCDOT 840.02 CONCRETE CATCH BASIN
CB326	359.82'		353.00' (15" RCP TO CB303)	NCDOT 840.02 CONCRETE CATCH BASIN
CB327	370.06'	362.00' (18" RCP FROM CB350)	361.80' (18" RCP TO CB278)	NCDOT 840.02 CONCRETE CATCH BASIN
CB329	374.53'	369.20' (15" RCP FROM CB330)	369.00' (15" RCP TO VI328)	NCDOT 840.02 CONCRETE CATCH BASIN
CB330	374.53'		370.00' (15" RCP TO CB329)	NCDOT 840.02 CONCRETE CATCH BASIN
CB332	372.16'	367.00' (15" RCP FROM DI397)	367.00' (15" RCP TO VI328)	NCDOT 840.02 CONCRETE CATCH BASIN
CB333	365.69'	361.70' (15" RCP FROM CB334)	361.50' (15" RCP TO CB308)	NCDOT 840.02 CONCRETE CATCH BASIN
CB334	366.62'		362.20' (15" RCP TO CB333)	NCDOT 840.02 CONCRETE CATCH BASIN
CB335	364.75'	360.15' (15" RCP FROM DI336)	360.05' (18" RCP TO VI334A)	NCDOT 840.02 CONCRETE CATCH BASIN
CB337	366.44'		362.40' (18" RCP TO CB311)	NCDOT 840.02 CONCRETE CATCH BASIN
CB338	367.52'	364.00' (15" RCP FROM CB339)	363.80' (15" RCP TO CB312)	NCDOT 840.02 CONCRETE CATCH BASIN
CB339	367.47'		364.18' (15" RCP TO CB338)	NCDOT 840.02 CONCRETE CATCH BASIN
CB340	368.72'		365.01' (15" RCP TO CB314)	NCDOT 840.02 CONCRETE CATCH BASIN
CB342	371.37'	367.90' (15" RCP FROM CB343) 367.30' (15" RCP FROM CB345)	367.20' (18" RCP TO CB316)	NCDOT 840.02 CONCRETE CATCH BASIN
CB343	372.50'	368.50' (15" RCP FROM CB344)	368.30' (15" RCP TO CB342)	NCDOT 840.02 CONCRETE CATCH BASIN
CB344	377.43'	,	370.68' (15" RCP TO CB343)	NCDOT 840.02 CONCRETE CATCH BASIN
CB345	370.84'		367.90' (15" RCP TO CB342)	NCDOT 840.02 CONCRETE CATCH BASIN
CB346	372.68'	368.50' (18" RCP FROM DI347) 368.60' (24" RCP FROM DI381)	368.40' (24" RCP TO CB317)	NCDOT 840.02 CONCRETE CATCH BASIN
CB348	373.27'	, , , , , , , , , , , , , , , , , , ,	369.95' (15" RCP TO DI347)	NCDOT 840.02 CONCRETE CATCH BASIN
CB349	378.56'		374.70' (15" RCP TO CB319)	NCDOT 840.02 CONCRETE CATCH BASIN
CB350	370.28'	363.20' (18" RCP FROM VI328)	363.00' (18" RCP TO CB327)	NCDOT 840.02 CONCRETE CATCH BASIN
CB398	361.94'	356.07' (15" RCP FROM DI399)	355.97' (15" RCP TO CB305)	NCDOT 840.02 CONCRETE CATCH BASIN
DI324	351.96'		348.52' (30" RCP TO CB302)	36" X 36" SLAB TOP YARD INLET
DI336	362.83'	360.95' (15" RCP FROM DI362)	360.75' (15" RCP TO CB335)	36" X 36" SLAB TOP YARD INLET
DI341	369.88'	<u> </u>	365.89' (18" RCP TO CB315)	36" X 36" SLAB TOP YARD INLET
DI347	371.27'	368.80' (15" RCP FROM CB348)	368.70' (18" RCP TO CB346)	36" X 36" SLAB TOP YARD INLET
DI361	363.02'	,	359.90' (15" RCP TO CB310)	36" X 36" SLAB TOP YARD INLET
DI362	364.00'		361.90' (15" RCP TO DI336)	36" X 36" SLAB TOP YARD INLET
	363.91'		361.80' (15" RCP TO CB308)	36" X 36" SLAB TOP YARD INLET
DI380	ויאַ הטסן		,	, ,

STORM STRUCTURE TABLE

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

NOTES:
1. TOP REFERS TO:
1.1. CATCH BASIN: TOP OF CURB
1.2. YARD INLET: SILL
1.3. VALLEY GUTTER INLET: FLOW LINE

09/17/2021

R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN

43398 SHEET NO. *C3.5* 

STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION
DI382	373.19'		370.30' (18" RCP TO DI381)	36" X 36" SLAB TOP YARD INLET
DI397	372.50'		367.80' (15" RCP TO CB332)	36" X 36" SLAB TOP YARD INLET
DI399	359.00'		356.60' (15" RCP TO CB398)	36" X 36" SLAB TOP YARD INLET
EW300	348.42'	345.00' (36" RCP FROM JB301)		NCDOT 838.80 CONCRETE ENDWALL
JB301	351.42'	346.12' (36" RCP FROM CB302)	345.80' (36" RCP TO EW300)	NCDOT 840.34 TRAFFIC BEARING JUNCTION BO
VI276	367.62'	357.14' (36" RCP FROM CB308) 359.98' (18" RCP FROM CB278)	357.04' (36" RCP TO CB307)	VALLEY GUTTER INLET
VI309	363.89'	358.71' (30" RCP FROM CB310) 359.40' (18" RCP FROM VI334B)	358.61' (30" RCP TO CB308)	VALLEY GUTTER INLET
VI318	373.98'	368.20' (18" RCP FROM CB319)	368.00' (18" RCP TO CB317)	VALLEY GUTTER INLET
VI328	371.18'	366.20' (15" RCP FROM CB329) 366.20' (15" RCP FROM CB332)	366.00' (18" RCP TO CB350)	VALLEY GUTTER INLET
VI334A	364.27'	359.75' (18" RCP FROM CB335)	359.65' (18" RCP TO VI334B)	VALLEY GUTTER INLET
VI334B	363.89'	359.60' (18" RCP FROM VI334A)	359.55' (18" RCP TO VI309)	VALLEY GUTTER INLET

STORM STRUCTURE TABLE

CB402 382.60' 368.99' (48" RCP FROM CB403) 368.99' (48" RCP TO DI401) NCDOT 840.02 CONCRETE CATCH BASIN

CB403 | 381.82' | 369.33' (48" RCP FROM CB404) | 369.23' (48" RCP TO CB402) | NCDOT 840.02 CONCRETE CATCH BASIN

INV. OUT

DESCRIPTION

STR.# TOP

		,	, ,	
CB404	382.71'	369.84' (48" RCP FROM DI405)	369.74' (48" RCP TO CB403)	NCDOT 840.02 CONCRETE CATCH BASIN
CB406	381.15'	371.82' (36" RCP FROM CB407) 374.50' (18" RCP FROM CB424) 371.82' (24" RCP FROM CB423)	371.82' (48" RCP TO DI405)	NCDOT 840.02 CONCRETE CATCH BASIN
CB407	381.91'	372.40' (30" RCP FROM CB409)	372.28' (36" RCP TO CB406)	NCDOT 840.02 CONCRETE CATCH BASIN
CB409	381.21'	374.50' (30" RCP FROM CB410) 374.40' (24" RCP FROM CB430)	373.31' (30" RCP TO CB407)	NCDOT 840.02 CONCRETE CATCH BASIN
CB410	384.05'	378.32' (24" RCP FROM CB411) 375.80' (24" RCP FROM CB433)	375.60' (30" RCP TO CB409)	NCDOT 840.02 CONCRETE CATCH BASIN
CB411	385.52'	379.00' (24" RCP FROM CB412)	378.74' (24" RCP TO CB410)	NCDOT 840.02 CONCRETE CATCH BASIN
CB412	385.82'	379.50' (24" RCP FROM CB413)	379.24' (24" RCP TO CB411)	NCDOT 840.02 CONCRETE CATCH BASIN
CB413	387.76'	382.78' (18" RCP FROM CB414) 382.10' (24" RCP FROM DI438) 382.10' (15" RCP FROM CB439)	382.00' (24" RCP TO CB412)	NCDOT 840.02 CONCRETE CATCH BASIN
CB414	389.69'	385.90' (15" RCP FROM CB415)	385.70' (18" RCP TO CB413)	NCDOT 840.02 CONCRETE CATCH BASIN
CB415	389.90'		386.19' (15" RCP TO CB414)	NCDOT 840.02 CONCRETE CATCH BASIN
CB416	383.62'	379.18' (15" RCP FROM CB422) 372.70' (18" RCP FROM CB417)	372.50' (24" RCP TO CB402)	NCDOT 840.02 CONCRETE CATCH BASIN
CB417	384.50'	373.40' (18" RCP FROM CB418)	373.20' (18" RCP TO CB416)	NCDOT 840.02 CONCRETE CATCH BASIN
CB418	384.30'	374.20' (18" RCP FROM CB419)	374.00' (18" RCP TO CB417)	NCDOT 840.02 CONCRETE CATCH BASIN
CB419	384.26'	374.60' (18" RCP FROM CB420)	374.40' (18" RCP TO CB418)	NCDOT 840.02 CONCRETE CATCH BASIN
CB420	380.64'	376.20' (15" RCP FROM CB421)	376.00' (18" RCP TO CB419)	NCDOT 840.02 CONCRETE CATCH BASIN
CB421	380.65'		376.50' (15" RCP TO CB420)	NCDOT 840.02 CONCRETE CATCH BASIN
CB422	383.62'		380.18' (15" RCP TO CB416)	NCDOT 840.02 CONCRETE CATCH BASIN
CB423	380.51'		372.80' (24" RCP TO CB406)	NCDOT 840.02 CONCRETE CATCH BASIN
CB424	381.15'	374.70' (18" RCP FROM CB425)	374.70' (18" RCP TO CB406)	NCDOT 840.02 CONCRETE CATCH BASIN
CB425	380.54'	375.50' (15" RCP FROM CB441) 375.30' (15" RCP FROM DI426)	375.30' (18" RCP TO CB424)	NCDOT 840.02 CONCRETE CATCH BASIN
CB427	382.36'	377.50' (15" RCP FROM CB428)	377.30' (15" RCP TO CB430)	NCDOT 840.02 CONCRETE CATCH BASIN
CB428	383.23'	378.20' (15" RCP FROM CB429)	378.00' (15" RCP TO CB427)	NCDOT 840.02 CONCRETE CATCH BASIN
CB429	384.26'		379.00' (15" RCP TO CB428)	NCDOT 840.02 CONCRETE CATCH BASIN
CB430	381.21'	376.55' (15" RCP FROM CB427) 374.90' (24" RCP FROM CB431)	374.70' (24" RCP TO CB409)	NCDOT 840.02 CONCRETE CATCH BASIN
CB431	381.80'	376.20' (18" RCP FROM DI432)	375.60' (24" RCP TO CB430)	NCDOT 840.02 CONCRETE CATCH BASIN
CB433	384.84'	379.32' (18" RCP FROM DI440) 376.30' (24" RCP FROM CB434)	376.10' (24" RCP TO CB410)	NCDOT 840.02 CONCRETE CATCH BASIN
CB434	382.29'	377.50' (18" RCP FROM CB436) 377.50' (18" RCP FROM DI435) 377.60' (18" RCP FROM CB437)	377.40' (24" RCP TO CB433)	NCDOT 840.02 CONCRETE CATCH BASIN
CB436	381.92'		377.88' (18" RCP TO CB434)	NCDOT 840.02 CONCRETE CATCH BASIN
CB437	381.25'		378.00' (18" RCP TO CB434)	NCDOT 840.02 CONCRETE CATCH BASIN
CB439	387.76'		383.00' (15" RCP TO CB413)	NCDOT 840.02 CONCRETE CATCH BASIN
CB441	380.51'		376.00' (15" RCP TO CB425)	NCDOT 840.02 CONCRETE CATCH BASIN
DI401	378.22'	367.77' (48" RCP FROM CB402)	367.67' (48" RCP TO EW400)	60" X 60" SLAB TOP YARD INLET
DI405	379.50'	371.01' (48" RCP FROM CB406)	370.91' (48" RCP TO CB404)	60" X 60" SLAB TOP YARD INLET
DI426	378.93'		376.00' (15" RCP TO CB425)	36" X 36" SLAB TOP YARD INLET
DI432	379.00'		376.70' (18" RCP TO CB431)	36" X 36" SLAB TOP YARD INLET
DI435	381.35'		377.80' (18" RCP TO CB434)	36" X 36" SLAB TOP YARD INLET
DI438	386.12'		383.10' (24" RCP TO CB413)	36" X 36" SLAB TOP YARD INLET
DI440	384.69'		380.07' (18" RCP TO CB433)	36" X 36" SLAB TOP YARD INLET
EW400	371.50'	367.25' (48" RCP FROM DI401)		NCDOT 838.80 CONCRETE ENDWALL
		<del></del>		

STR.#	TOP	INV. IN	INV. OUT	DESCRIPTION
CB501	360.84'	355.94' (30" RCP FROM CB502)	355.84' (30" RCP TO EW500)	NCDOT 840.02 CONCRETE CATCH BAS
CB502	363.90'	356.64' (30" RCP FROM CB503)	356.54' (30" RCP TO CB501)	NCDOT 840.02 CONCRETE CATCH BAS
CB503	364.99'	357.10' (30" RCP FROM CB504)	357.00' (30" RCP TO CB502)	NCDOT 840.02 CONCRETE CATCH BAS
CB504	369.59'	361.00' (24" RCP FROM CB505) 357.95' (24" RCP FROM CB509)	357.95' (30" RCP TO CB503)	NCDOT 840.02 CONCRETE CATCH BAS
CB505	370.82'	364.20' (24" RCP FROM CB506) 365.92' (18" RCP FROM CB514)	364.00' (24" RCP TO CB504)	NCDOT 840.02 CONCRETE CATCH BAS
CB506	373.30'	366.20' (18" RCP FROM CB507) 369.00' (15" RCP FROM CB519)	366.00' (24" RCP TO CB505)	NCDOT 840.02 CONCRETE CATCH BAS
CB507	376.45'	371.20' (15" RCP FROM CB508)	371.00' (18" RCP TO CB506)	NCDOT 840.02 CONCRETE CATCH BAS
CB508	376.44'		371.50' (15" RCP TO CB507)	NCDOT 840.02 CONCRETE CATCH BAS
CB509	368.95'	358.31' (24" RCP FROM CB510)	358.21' (24" RCP TO CB504)	NCDOT 840.02 CONCRETE CATCH BAS
CB510	365.60'	361.10' (15" RCP FROM CB513) 358.87' (18" RCP FROM CB520)	358.87' (24" RCP TO CB509)	NCDOT 840.02 CONCRETE CATCH BAS
CB511	363.94'	359.70' (15" RCP FROM CB512)	359.70' (15" RCP TO CB520)	NCDOT 840.02 CONCRETE CATCH BAS
CB512	363.95'		360.09' (15" RCP TO CB511)	NCDOT 840.02 CONCRETE CATCH BAS
CB513	365.45'		361.69' (15" RCP TO CB510)	NCDOT 840.02 CONCRETE CATCH BAS
CB514	370.82'	366.18' (18" RCP FROM CB515)	366.08' (18" RCP TO CB505)	NCDOT 840.02 CONCRETE CATCH BAS
CB515	370.97'	366.44' (18" RCP FROM CB516)	366.44' (18" RCP TO CB514)	NCDOT 840.02 CONCRETE CATCH BAS
CB516	370.69'	367.03' (15" RCP FROM CB518) 367.03' (15" RCP FROM DI517)	366.93' (18" RCP TO CB515)	NCDOT 840.02 CONCRETE CATCH BAS
CB518	370.69'		367.23' (15" RCP TO CB516)	NCDOT 840.02 CONCRETE CATCH BAS
CB519	373.29'		369.61' (15" RCP TO CB506)	NCDOT 840.02 CONCRETE CATCH BAS
CB520	364.60'	359.20' (15" RCP FROM CB511)	359.20' (18" RCP TO CB510)	NCDOT 840.02 CONCRETE CATCH BAS
DI517	369.67'		367.23' (15" RCP TO CB516)	36" X 36" SLAB TOP YARD INLET
EW500	357.87'	354.00' (30" RCP FROM CB501)		NCDOT 838.80 CONCRETE ENDWALI

		STORM STR	UCTURE TABLE	
STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION
EW 601	372.62'	369.50' (30" RCP FROM SCM 1 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW 601	372.62'	369.50' (30" RCP FROM SCM 1 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW 602	383.68'	380.20' (30" RCP FROM SCM 2 RISER)		CONCRETE ENDWALL
EW601	374.00'	369.50' (30" RCP FROM SCM 1 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW602	383.62'	380.20' (30" RCP FROM SCM 2 RISER)		CONCRETE ENDWALL
EW603	345.50'	341.00' (48" RCP FROM SCM 3 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW604	369.50'	365.00' (48" RCP FROM SCM 4 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW605	351.26'	347.30' (42" RCP FROM SCM 5 RISER)		NCDOT 838.80 CONCRETE ENDWALL
EW609	359.67'	354.00' (72" RCP FROM EW610)		NCDOT 838.80 CONCRETE ENDWALL
EW610	362.67'		354.50' (72" RCP TO EW609)	NCDOT 838.80 CONCRETE ENDWALL
EW611	359.67'	355.00' (72" RCP FROM EW612)		NCDOT 838.80 CONCRETE ENDWALL
EW612	362.67'		355.50' (72" RCP TO EW611)	NCDOT 838.80 CONCRETE ENDWALL
EW613	383.00'	378.50' (48" RCP FROM EW614)		NCDOT 838.80 CONCRETE ENDWALL
EW614	383.50'		379.00' (48" RCP TO EW613)	NCDOT 838.80 CONCRETE ENDWALL
EW615	383.00'	378.50' (48" RCP FROM EW616)		NCDOT 838.80 CONCRETE ENDWALL
EW616	383.50'		379.00' (48" RCP TO EW615)	NCDOT 838.80 CONCRETE ENDWALL
FE650	N/A		343.40' (24" RCP TO FE651)	FLARED END SECTION
FE651	N/A	342.30' (24" RCP FROM FE650)		FLARED END SECTION
SCM 1 RISER	REFER TO DETAIL		369.90' (30" RCP TO EW 601)	SCM 1 RISER; REFER TO DETAIL
SCM 1 RISER	REFER TO DETAIL		369.90' (30" RCP TO EW 601)	SCM 1 RISER; REFER TO DETAIL
SCM 1 RISER	REFER TO DETAIL		369.90' (30" RCP TO EW601)	SCM 1 RISER; REFER TO DETAIL
SCM 2 RISER	REFER TO DETAIL		380.55' (30" RCP TO EW 602)	SCM 2 RISER; REFER TO DETAIL
SCM 2 RISER	REFER TO DETAIL		380.55' (30" RCP TO EW602)	48 x 48 inch Rectangular Structure
SCM 3 RISER	REFER TO DETAIL		341.59' (48" RCP TO EW603)	SCM 3 RISER; REFER TO DETAIL
SCM 4 RISER	REFER TO DETAIL		365.45' (48" RCP TO EW604)	SCM 4 RISER, REFER TO DETAIL
SCM 5 RISER	REFER TO DETAIL		347.88' (42" RCP TO EW605)	SCM 5 RISER; REFER TO DETAIL

1. TOP REFERS TO:
1.1. CATCH BASIN: TOP OF CURB
1.2. YARD INLET: SILL
1.3. VALLEY GUTTER INLET: FLOW LINE

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/17/2021 R. WINGATE DESIGNED BY P. BARBEAU CHECKED BY P. BARBEAU AS SHOWN

43398 SHEET NO. *C3.6* 

		STORM	PIPE TA	ABLE			
FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL	DESCRIPTION
CB101 - EW100	370.65'	370.00'	0.49%	132.94 LF	48"	RCP	CLASS III
CB102 - CB101	371.24'	370.75'	0.50%	97.43 LF	42"	RCP	CLASS III
CB103 - CB183	374.96'	373.20'	3.56%	49.40 LF	36"	RCP	CLASS III
CB104 - CB103	376.10'	375.06'	0.60%	172.58 LF	36"	RCP	CLASS III
CB105 - CB104	376.45'	376.20'	0.59%	42.43 LF	30"	RCP	CLASS III
CB106 - CB105	376.95'	376.55'	0.60%	66.73 LF	30"	RCP	CLASS III
CB107 - CB106	377.71'	377.05'	0.61%	108.77 LF	30"	RCP	CLASS III
CB108 - CB107	378.33'	377.81'	0.60%	86.74 LF	30"	RCP	CLASS III
CB109 - CB108	380.78'	378.43'	0.60%	392.67 LF	24"	RCP	CLASS III
CB110 - CB109	381.80'	380.88'	0.54%	169.45 LF	24"	RCP	CLASS III
CB112 - CB101	377.30'	375.00'	2.43%	94.73 LF	15"	RCP	CLASS III
CB113 - CB112	378.00'	377.50'	1.28%	39.16 LF	15"	RCP	CLASS III
CB114 - CB102	371.98'	371.30'	0.49%	137.77 LF	42"	RCP	CLASS III
CB115 - CB114	372.51'	372.10'	0.58%	70.32 LF	30"	RCP	CLASS III
CB116 - CB115	373.90'	372.65'	0.51%	245.19 LF	30"	RCP	CLASS III
CB117 - CB116	374.25'	374.00'	0.54%	46.53 LF	30"	RCP	CLASS III
CB118 - CB117	376.00'	375.80'	0.74%	27.00 LF	30"	RCP	CLASS III
CB119 - CB118	376.60'	376.25'	0.77%	45.41 LF	30"	RCP	CLASS III
CB120 - CB119	377.37'	376.60'	0.67%	115.77 LF	30"	RCP	CLASS III
CB121 - CB120	377.84'	377.37'	0.62%	75.64 LF	24"	RCP	CLASS III
CB122 - CB121	378.50'	377.84'	0.79%	83.58 LF	18"	RCP	CLASS III
CB123 - CB122	380.00'	378.70'	0.83%	155.76 LF	18"	RCP	CLASS III
CB124 - CB114	379.41'	378.00'	5.00%	28.29 LF	15"	RCP	CLASS III
CB125 - CB114	379.38'	377.50'	5.37%	35.00 LF	15"	RCP	CLASS III
CB126 - CB115	379.00'	378.50'	1.43%	35.00 LF	15"	RCP	CLASS III
CB127 - CB116	377.53'	377.32'	0.60%	35.00 LF	18"	RCP	CLASS III
CB128 - CB127	378.30'	377.63'	1.45%	46.28 LF	18"	RCP	CLASS III
CB129 - CB128	378.80'	378.50'	1.11%	27.00 LF	18"	RCP	CLASS III
CB130 - CB129	381.30'	378.90'	2.24%	107.12 LF	15"	RCP	CLASS III
					15"		
CB131 - CB130	382.12'	381.50'	1.58%	39.20 LF		RCP	CLASS III
CB132 - CB117	377.00'	376.00'	0.85%	117.54 LF	18"	RCP	CLASS III
CB133 - CB132	377.70'	377.30'	1.48%	27.05 LF	15"	RCP	CLASS III
CB134 - CB120	378.15'	377.70'	0.69%	64.98 LF	24"	RCP	CLASS III
CB136 - CB104	385.21'	385.00'	0.60%	35.00 LF	24"	RCP	CLASS III
CB137 - CB136	385.94'	385.31'	1.00%	63.35 LF	18"	RCP	CLASS III
CB138 - CB137	386.55'	386.14'	1.00%	40.57 LF	15"	RCP	CLASS III
CB139 - CB105	385.93'	385.10'	1.00%	82.75 LF	15"	RCP	CLASS III
CB140 - CB139	387.00'	386.03'	3.59%	27.03 LF	15"	RCP	CLASS III
CB144 - CB108	390.50'	389.50'	2.86%	35.00 LF	15"	RCP	CLASS III
CB146 - CB109	388.00'	385.91'	5.11%	40.91 LF	15"	RCP	CLASS III
CB147 - CB110	382.65'	382.00'	1.67%	38.92 LF	15"	RCP	CLASS III
CB148A - CB122	379.75'	379.41'	0.97%	35.00 LF	15"	RCP	CLASS V
CB148B - CB148A	379.90'	379.80'	2.22%	4.50 LF	15"	RCP	CLASS III
CB149 - CB129	380.31'	379.85'	1.00%	45.91 LF	15"	RCP	CLASS III
CB150 - DI149	372.80'	371.10'	1.03%	165.28 LF	30"	RCP	CLASS III
CB150 - D1149 CB151 - CB150	373.20'	371.10	0.72%	41.38 LF	30"	RCP	CLASS III
CB152 - CB151	375.40'	373.30'	1.69%	124.57 LF	30"	RCP	CLASS III
CB155 - DI154	378.30'	377.34'	0.70%	136.50 LF	30"	RCP	CLASS III
CB156 - CB155	378.80'	378.50'	0.91%	32.88 LF	24"	RCP	CLASS III
CB157 - CB156	379.40'	379.00'	1.48%	27.00 LF	24"	RCP	CLASS III
CB158 - CB157	385.00'	383.00'	3.39%	58.95 LF	18"	RCP	CLASS III
CB159 - CB158	386.50'	385.29'	1.52%	79.35 LF	18"	RCP	CLASS III
CB160 - CB159	390.30'	386.70'	2.18%	165.29 LF	15"	RCP	CLASS III
CB161 - CB160	390.76'	390.50'	0.96%	27.00 LF	15"	RCP	CLASS III
CB162 - CB150	377.80'	377.50'	0.76%	39.30 LF	15"	RCP	CLASS III
CB164 - CB152	380.74'	380.30'	0.61%	72.45 LF	15"	RCP	CLASS III
				50.25 LF	15"	RCP	CLASS V
CB165 - CB164	385.00'	382.70'	4.58%	00.20 Li	_	. <del>-</del> -	
					15"	RCP	
CB165 - CB164  CB166 - CB180  CB168 - CB158	385.00' 384.00' 385.90'	382.70' 383.20' 385.70'	4.58% 1.74% 0.74%	46.02 LF 27.00 LF	15" 15"	RCP RCP	CLASS III

-		UPSTREAM	DOWNSTREAM	<u>,                                    </u>				
	FROM - TO	INVERT	INVERT	" SLOPI	LENGTH	H DIA	A. MATERIA	L DESCRIPTION
	CB170 - CB159	387.10'	386.90'	0.74%	27.01 LF	15'	' RCP	CLASS V
	CB180 - CB157		382.00'	1.62%				CLASS III
	CB181 - CB103		381.32'	4.82%		-		CLASS III
	CB182 - CB110		381.90'	0.70%				CLASS III
	CB183 - CB102		371.50'	1.26%				CLASS III
	CB190 - CB138		386.75'	1.00%				CLASS III
	DI111 - CB110		382.20'	0.53%				CLASS III
	DI135 - CB134		378.15' 383.00'					CLASS III CLASS III
	DI141 - CB107	384.00	383.00	0.96%		_		CLASS III
	DI142 - DI141	385.80'	385.20'	0.96%				CLASS III
	DI143 - DI142		386.00'	0.63%				CLASS III
	DI149 - EW148		370.00'	1.44%		-		CLASS III
	DI153 - CB152		375.54'	0.70%				CLASS III
	DI153 - CB152	370.30	376.63'	0.70%			+	CLASS III
	DI163 - CB162		377.90'	0.70%				CLASS III
	DI163 - CB162		384.20'	2.35%				CLASS III
	DI188 - DI135		378.94'	0.57%		_		CLASS III
	DI188 - DI135	+	378.94	0.57%				CLASS III
	DI192 - CB190		388.60'	1.23%				CLASS III
	DI193 - DI192		381.90'	0.81%	_	-		CLASS III
	DI194 - DI193		380.30'	0.51%				CLASS III
_	D1193 - D1100	301.00	300.30	0.5970	254.52 L	1 10	INOF	OLAGO III
			STOR	RM PIPE	TABLE			
	FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL	DESCRIPTION
	CB202 - FE201	383.75'	383.20'	0.33%	167.79 LF	30"	RCP	CLASS III
С	B204 - DI203A	384.16'	383.95'	0.54%	38.73 LF	24"	RCP	CLASS V
	CB205 - CB204	384.50'	384.36'	0.52%	27.04 LF	15"	RCP	CLASS V
	CB206 - CB202	385.10'	384.40'	0.57%	122.07 LF	24"	RCP	CLASS III
	CB207 - CB206	385.60'	385.30'	1.05%	28.48 LF	15"	RCP	CLASS V
	CB208 - CB202	384.40'	384.20'	0.74%	27.00 LF	24"	RCP	CLASS III
	CB213 - FE212	384.10'	383.00'	0.66%	167.47 LF	30"	RCP	CLASS III
	CB214 - CB213	384.50'	384.30'	0.50%	39.99 LF	30"	RCP	CLASS III
	CB215 - CB214	385.15'	384.60'	0.55%	99.88 LF	18"	RCP	CLASS III
	CB216 - CB215	387.62'	385.25'	4.34%	54.55 LF	15"	RCP	CLASS III
	CB217 - CB214	384.75'	384.60'	0.56%	27.00 LF	24"	RCP	CLASS V
-	CB218 - CB217	384.90'	384.85'	0.55%	9.13 LF	24"	RCP	CLASS IV
	DI203 - EW220	383.40'	383.00'	0.47%	85.03 LF	24"	RCP	CLASS V
	DI203A - DI203	383.85'	383.50'	0.48%	72.52 LF	24"	RCP	CLASS V
_[	DI209 - CB208	385.40'	384.60'	0.57%	140.85 LF	18"	RCP	CLASS III
	DI219 - CB218	385.70'	385.00'	0.56%	125.90 LF	24"	RCP	CLASS III; O-RIN
			STO	RM PIPE	TABLE			
	FROM - TO	UPSTREAM INVERT	I DOWNSTREAM	SLOP	E LENGTI	H DIA	A. MATERIA	L DESCRIPTIO
	CB501 - EW500		354.00'	4.38%	42.01 LI	= 30	" RCP	CLASS III
	CB502 - CB50 <sup>2</sup>	1 356.54'	355.94'	0.60%	99.76 LI	= 30	" RCP	CLASS V
	CB503 - CB502	2 357.00'	356.64'	0.82%	44.10 LI	= 30	" RCP	CLASS III
	CB504 - CB503	357.95'	357.10'	0.54%	5 157.79 L	F 30	" RCP	CLASS III
	1	4 004.001	361.00' 3.45%		87.00 LI	= 24	" RCP	CLASS III
	CB505 - CB504	364.00'	001.00		102.201	F 24	" DCD	01.400.111
	CB505 - CB504		364.20'	0.93%	5   193.28 L	'   47	" RCP	CLASS III
		366.00'		0.93%				CLASS III
	CB506 - CB505	366.00' 371.00'	364.20'		210.00 L	F 18	" RCP	
	CB506 - CB505	366.00' 371.00' 7 371.50'	364.20' 366.20'	2.29%	210.00 L 27.01 LI	F 18	" RCP	CLASS III
	CB506 - CB506 CB507 - CB506 CB508 - CB507	366.00' 371.00' 7 371.50' 4 358.21'	364.20' 366.20' 371.20'	2.29%	210.00 L 27.01 Ll 42.43 Ll	F 18 = 15 = 24	" RCP " RCP	CLASS III
	CB506 - CB506 CB507 - CB506 CB508 - CB507 CB509 - CB504	366.00' 371.00' 371.50' 4 358.21' 9 358.87'	364.20' 366.20' 371.20' 357.95'	2.29% 1.11% 0.61%	210.00 L 27.01 Ll 42.43 Ll 93.40 Ll	F 18 = 15 = 24 = 24	" RCP " RCP " RCP	CLASS III CLASS III
	CB506 - CB505 CB507 - CB506 CB508 - CB507 CB509 - CB504 CB510 - CB509	366.00' 371.00' 371.50' 4 358.21' 9 358.87' 0 359.70'	364.20' 366.20' 371.20' 357.95' 358.31'	2.29% 1.11% 0.61% 0.60%	210.00 L 27.01 Ll 42.43 Ll 93.40 Ll 6 63.49 Ll	F 18 = 15 = 24 = 24 = 15	" RCP " RCP " RCP " RCP	CLASS III CLASS III CLASS III
	CB506 - CB505 CB507 - CB506 CB508 - CB507 CB509 - CB504 CB510 - CB509 CB511 - CB520	366.00' 371.00' 371.50' 358.21' 358.87' 359.70' 1 360.09'	364.20' 366.20' 371.20' 357.95' 358.31' 359.20'	2.29% 1.11% 0.61% 0.60% 0.79%	210.00 L 27.01 Ll 42.43 Ll 93.40 Ll 6 63.49 Ll 27.15 Ll	F 18 = 15 = 24 = 15 = 15	" RCP " RCP " RCP " RCP " RCP	CLASS III CLASS III CLASS III CLASS III

0.61% | 42.43 LF | 18" |

367.03'

369.00'

367.03'

0.60% | 82.10 LF | 18" |

0.74% | 27.00 LF | 15" |

2.26% 27.01 LF 15"

0.77% | 42.66 LF | 18" |

0.65% 30.15 LF 15"

RCP

RCP

CLASS III

CB515 - CB514 366.44'

CB516 - CB515 366.93'

CB518 - CB516 367.23'

CB519 - CB506 369.61'

DI517 - CB516 367.23'

CLASS   CLAS			INVERI	INVERI					
CLASS     CASS	CLASS V	CB278 - VI276	360.19'	359.98'	0.82%	25.50 LF	18"	RCP	CLASS III
CLASS	CLASS III	CB302 - JB301	347.72'	346.12'	1.53%	104.91 LF	36"	RCP	CLASS III; O-RING
CLASS III	CLASS III	CB303 - CB302	349.40'	348.90'	0.60%	82.86 LF	36"	RCP	CLASS III
CLASS	CLASS III	CB304 - CB303	350.22'	349.51'	0.60%	118.63 LF	36"	RCP	CLASS III
CLASS III	CLASS III	CB305 - CB304	353.80'	353.00'	1.98%	40.48 LF	36"	RCP	CLASS III
CLASS III	CLASS III	CB306 - CB305	356.09'	354.00'	2.03%	103.07 LF	36"	RCP	
CLASS									
CLASS									
CLASS   II									
CLASS   II									
CLASS III   CB314 - CB312   362.82"   362.40"   0.61%   88.95 L   30   NCP   CLASS III									
CLASS III   CR315 - CR314									
CLASS III									
CLASS III   CB317 - CB316   306.00"   306.20"   2.04%   30.27 LF   24"   RCP		CB315 - CB314	363.69'	363.16'	0.60%	88.47 LF	30"	RCP	CLASS III
CLASS III   CR391 - VIS18   372 - 50"   388 20"   4.15%   105 51 IE   18"   IRCP   CLASS III   CR392 - CR393   375 00"   377 20"   1.69%   4.156 IE   15"   RCP   CLASS III   CLASS III   CR392 - CR393   375 00"   375 20"   1.69%   4.256 IE   15"   RCP   CLASS III   CR392 - CR393   376 00"   375 20"   1.69%   4.256 IE   15"   RCP   CLASS III   CR392 - CR393   376 70"   376 20"   0.69%   8.82 2 IE   15"   RCP   CLASS III   CLASS III   CR392 - CR393   381 70"   350 87"   0.77%   1137 IE   15"   RCP   CLASS III   CLASS III   CR392 - CR393   383 30"   351 30"   7.37%   7.714 IE   15"   RCP   CLASS III   CR392 - CR393   383 30"   361 30"   360 87"   7.37%   7.714 IE   15"   RCP   CLASS III   CR392 - CR393   383 30"   360 20"   2.59%   47.16 IE   15"   RCP   CLASS III   CR392 - CR393   370 00"   366 20"   2.29%   47.16 IE   15"   RCP   CLASS III   CR393 - CR393   370 00"   366 20"   2.29%   47.16 IE   15"   RCP   CLASS III   CR393 - CR393   381 30"   369 20"   2.99%   47.16 IE   15"   RCP   CLASS III   CR393 - CR393   381 30"   369 20"   2.99%   3.515 IE   15"   RCP   CLASS III   CR393 - CR393   381 30"   369 20"   2.99%   3.515 IE   15"   RCP   CLASS III   CLASS III   CR393 - CR393   382 20"   381 30"   369 20"   2.99%   3.515 IE   15"   RCP   CLASS III   CLASS III   CR393 - CR393   382 20"   381 30"   389 30"   389 75"   3.556 IE   370 IE   380	CLASS III	CB316 - CB315	365.00'	363.90'	1.12%	98.46 LF	24"	RCP	CLASS III
CLASS III   CB321 - CB320   375.00   377.27   160%   14396 LF   15"   RCP   CLASS III   CLASS III   CB321 - CB320   376.00   376.20   1.28%   0.288 LF   15"   RCP   CLASS III   CLASS III   CB321 - CB320   376.00   376.20   0.28%   58.2 LF   15"   RCP   CLASS III   CLASS III   CB321 - CB320   381.73"   380.87   0.77%   11376 LF   15"   RCP   CLASS III   CLASS III   CB322 - CB304   392.20"   381.82"   0.28%   110.87 LF   15"   RCP   CLASS III   CLASS III   CB323 - CB304   392.20"   381.82"   0.73%   17.74%   11376 LF   15"   RCP   CLASS III   CLASS III   CB323 - CB320   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CB323 - CB320   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CB323 - CB323   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CB323 - CB323   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CB323 - CB323   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CB332 - CB323   391.00"   390.92"   2.36%   47.18 LF   15"   RCP   CLASS III   CLASS III   CB332 - CB323   391.20"   391.70"   2.35%   47.8 LF   15"   RCP   CLASS III   CLASS III   CLASS III   CB333 - CB323   392.20"   391.92"   2.36%   47.8 LF   15"   RCP   CLASS III   CLASS III   CB334 - CB334   392.20"   391.92"   2.36%   47.9 LF   15"   RCP   CLASS III   CLASS III   CB334 - CB334   392.20"   391.92"   0.56%   64.6 LF   15"   RCP   CLASS III   CLASS III   CLASS III   CB334 - CB334   398.30"   391.92"   0.56%   64.6 LF   15"   RCP   CLASS III   CLASS III   CB334 - CB334   398.30"   391.92"   0.56%   64.6 LF   15"   RCP   CLASS III   CLASS III   CB334 - CB334   398.30"   391.92"   0.57%   49.91 LF   15"   RCP   CLASS III   CLASS III   CB334 - CB334   398.30"   391.92"   0.57%   49.91 LF   15"   RCP   CLASS III   CLASS III   CB344 - CB343   398.30"   397.90"   0.56%   64.91 LF   15"   RCP   CLASS III   CLASS III   CB344 - CB343   398.30"   397.90"   0.56%   64.91 LF   15"   RCP   CLASS III   CLASS III   CB344 - CB343   398.30"   398.90"   398.90"   399.90"   399.90"   399.9	CLASS III	CB317 - CB316	366.00'	365.20'	2.04%	39.27 LF	24"	RCP	CLASS III
CLASS III   CR321 - CR320   S70.00   S75.20   1.26%   G2.80 LF   10	CLASS III	CB319 - VI318	372.50'	368.20'	4.15%	103.51 LF	18"	RCP	CLASS III
CLASS III   CB322 - CB321   S76.70	CLASS III	CB320 - CB319	375.00'	372.70'	1.60%	143.96 LF	15"	RCP	CLASS III
CLASS III   CB923 - CB902   S51.76   S00.87   O.77%   113.78 LF   16"   RCP   CLASS III   CB926 - CB904   S32.20"   S61.62"   O.52%   110.87 LF   19"   RCP   CLASS II   CB926 - CB903   S55.00"   S61.00"   7.37%   27.14 LF   19"   RCP   CLASS III   CB927 - CB928   S61.60"   S62.00"   S61.00"   7.37%   27.14 LF   19"   RCP   CLASS III   CB927 - CB928   S68.00"   S68.00"   368.00"   3.54%   79.14 LF   19"   RCP   CLASS III   CB928 - CB929   S71.00"   S68.00"   2.54%   79.14 LF   19"   RCP   CLASS III   CB932 - V1028   S68.00"   368.00"   2.54%   79.14 LF   19"   RCP   CLASS III   CLASS III   CB932 - V1028   S67.00"   S68.00"   2.54%   31.51 LF   19"   RCP   CLASS III   CLASS III   CB932 - V1028   S67.00"   S68.00"   2.54%   31.51 LF   19"   RCP   CLASS III   CLASS III   CB932 - V1028   S67.00"   S68.00"   S69.00"   2.54%   31.51 LF   19"   RCP   CLASS III   CLASS III   CB932 - V1034   S69.00"	CLASS III	CB321 - CB320	376.00'	375.20'	1.28%	62.68 LF	15"	RCP	CLASS III
CLASS III	CLASS III	CB322 - CB321	376.70'	376.20'	0.86%	58.22 LF	15"	RCP	CLASS III
CLASS III	CLASS III	CB323 - CB302	351.75'	350.87'	0.77%	113.78 LF	15"	RCP	CLASS III
CB327 - CB278   301,807   300,007   2,35%   47,18 LF   187   RCP   CLASS III	CLASS III	CB325 - CB304	352.20'	351.62'	0.52%	110.87 LF	15"	RCP	CLASS V
CB327 - CB278   361.807   360.807   2.35%   47.16 LF   18"   RCP   CLASS III	CLASS III	CB326 - CB303	353.00'	351.00'	7.37%	27.14 LF	15"	RCP	CLASS III
DESCRIPTION   CB330 - CB329   370 007   368 207   3.54%   79.14 LP   15"   RCP   CLASS III									
CLASS III									
CLASS III	DESCRIPTION								
CLASS V   CB334 - CB308   361.50   361.20   1.09%   27.54 LF   15"   RCP   CLASS III	OLACC III								
CLASS V   CB334 - CB333   362 20   361 70   2.35%   21 26 LF   15°   RCP   CLASS III									
CLASS III									
CLASS III   CB397 - CB311   362.40'   361.90'   0.84%   69.64 LF   18"   RCP   CLASS III   CLASS III   CB339 - CB312   363.80'   363.53'   0.57%   46.96 LF   15"   RCP   CLASS III   CLASS III   CB339 - CB338   364.18'   364.00'   0.66%   27.07 LF   15"   RCP   CLASS III   CLASS III   CB340 - CB314   365.01'   364.70'   0.78%   39.72 LF   15"   RCP   CLASS III   CLASS III   CB343 - CB314   365.01'   364.70'   0.71%   27.99 LF   15"   RCP   CLASS III   CLASS III   CB343 - CB314   365.01'   366.70'   0.71%   27.99 LF   15"   RCP   CLASS III   CLASS IV   CB344 - CB343   370.66'   366.50'   1.72%   126.46 LF   15"   RCP   CLASS III   CLASS IV   CB344 - CB343   370.66'   366.50'   1.72%   62.90 LF   15"   RCP   CLASS IV   CLASS IV   CB346 - CB317   368.40'   366.10'   1.06%   28.30 LF   24"   RCP   CLASS IV   CLASS V   CB348 - D1347   368.40'   366.10'   1.06%   28.30 LF   15"   RCP   CLASS III   CLASS III   CB349 - CB319   374.70'   374.10'   31.00'   32.30 LF   16"   RCP   CLASS III   ASS III   CB349 - CB319   374.70'   374.10'   31.00'   32.30 LF   16"   RCP   CLASS III   CLASS III   CLASS III   CLASS III   D1341 - CB315   365.89'   368.80'   3.57%   10.66 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   360.15'   0.57%   106.18 LF   15"   RCP   CLASS III   D1361 - CB310   359.90'   360.95'   0.72%   32.11 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   359.20'   1.27%   54.91 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   359.20'   1.27%   54.91 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   360.60'   0.76%   26.21 LF   18"   RCP   CLASS III   CLASS III   D1362 - D1336   361.80'   361.00'   1.25%   59.91 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   359.20'   1.27%   54.91 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   359.90'   359.20'   1.27%   54.91 LF   15"   RCP   CLASS III   CLASS III   D1361 - CB310   366.60'   366.60'   0.70%   7.15 LF   24"   RCP   CLASS III   CLASS III   D1361 - CB310   366.60'									
CLASS III	CLASS III								
CLASS III   CB339 - CB338   364.18"   364.00"   0.66%   27.07 LF   15"   RCP   CLASS III	CLASS V	CB337 - CB311	362.40'	361.90'	0.84%	59.64 LF	18"	RCP	CLASS III
CLASS III   CB340 - CB314   366.01"   364.70"   0.78%   39.72 L   15"   RCP   CLASS III   CLASS III   CB342 - CB316   367.20"   367.00"   0.71%   27.99 L   15"   RCP   CLASS V   CB344 - CB343   370.68"   368.50"   1.72%   726.46 L   15"   RCP   CLASS V   CB344 - CB343   370.68"   368.50"   1.72%   726.46 L   15"   RCP   CLASS V   CLASS V   CB344 - CB342   367.90"   367.30"   0.72%   82.90 L   15"   RCP   CLASS V   CLASS V   CB346 - CB317   366.40"   368.10"   1.06%   28.30 L   24"   RCP   CLASS V   CB346 - CB317   366.40"   368.10"   1.06%   28.30 L   24"   RCP   CLASS V   CB348 - DI347   369.59"   368.80"   3.39%   33.33 L   15"   RCP   CLASS III   CLASS III   CB349 - CB319   374.70"   374.10"   1.99%   31.70 L   15"   RCP   CLASS III   CLASS III   CB398 - CB305   355.97"   355.80"   0.54%   31.76 L   15"   RCP   CLASS III   CB398 - CB305   356.97"   356.80"   3.30%   33.30 L   18"   RCP   CLASS III	CLASS III	CB338 - CB312	363.80'	363.53'	0.57%	46.96 LF	15"	RCP	CLASS III
CLASS III   CB342 - CB316	CLASS III	CB339 - CB338	364.18'	364.00'	0.66%	27.07 LF	15"	RCP	CLASS III
CLASS III   CB343 - CB342   368.30'   367.90'   0.62%   64.90 LF   15'   RCP   CLASS V   CLASS V   CB344 - CB343   370.68'   368.50'   1.72%   126.46 LF   15'   RCP   CLASS V   CLASS V   CB345 - CB342   367.90'   367.30'   0.72%   82.90 LF   15'   RCP   CLASS V   CLASS V   CB346 - CB317   368.40'   368.10'   1.06%   28.30 LF   24"   RCP   CLASS V   CLASS V   CB348 - DI347   369.95'   368.80'   3.39%   33.93 LF   15'   RCP   CLASS III   CLASS III   CB348 - CB319   374.70'   374.10'   1.89%   31.70 LF   15'   RCP   CLASS III   CB389 - CB327   363.00'   362.00'   3.10%   32.30 LF   18"   RCP   CLASS III   CB389 - CB326   355.90'   355.80'   0.54%   31.76 LF   15'   RCP   CLASS III   CB389 - CB336   355.97'   368.015'   0.57%   106.18 LF   15'   RCP   CLASS III   CB385   III   CLASS III	CLASS III	CB340 - CB314	365.01'	364.70'	0.78%	39.72 LF	15"	RCP	CLASS III
CLASS IV CB344 - CB343 370.68' 368.50' 1.72% 126.46 LF 15' RCP CLASS III CBASS IV CB345 - CB342 367.90' 367.30' 0.72% 82.90 LF 15' RCP CLASS V CB346 - CB317 368.40' 368.10' 1.06% 28.30 LF 24" RCP CLASS V CB348 - DI347 368.95' 368.80' 3.39% 33.93 LF 15' RCP CLASS III CB349 - CB319 374.70' 374.10' 1.89% 31.70 LF 15' RCP CLASS III CB349 - CB319 374.70' 374.10' 1.89% 31.70 LF 15' RCP CLASS III CB349 - CB319 374.70' 374.10' 1.89% 31.70 LF 15' RCP CLASS III CB349 - CB327 363.00' 362.00' 3.10% 32.30 LF 18' RCP CLASS III CB398 - CB305 355.97' 355.80' 0.54% 31.76 LF 15' RCP CLASS III CB398 - CB305 355.97' 355.80' 0.54% 31.76 LF 15' RCP CLASS III CB398 - CB305 360.75' 360.15' 0.57% 106.18 LF 15' RCP CLASS III CLASS I	CLASS III	CB342 - CB316	367.20'	367.00'	0.71%	27.99 LF	18"	RCP	CLASS V
CLASS IV   CB345 - CB342   367,90'   367,30'   0.72%   82,90 LF   15"   RCP   CLASS V   CLASS V   CB346 - CB317   368,40'   368,10'   1.06%   28,30 LF   24"   RCP   CLASS V   CLASS V   CB346 - D1347   369,95'   368,80'   3.39%   33,33 LF   15"   RCP   CLASS III   CLASS III   CB349 - CB319   374,70'   374,10'   1.89%   31,70 LF   15"   RCP   CLASS III   RCP   CLASS III   CB350 - CB327   363,00'   362,00'   3.10%   32,30 LF   18"   RCP   CLASS III   RCP   CLASS III   CB398 - CB305   355,97'   355,80'   0.54%   31,76 LF   15"   RCP   CLASS III   RCP   CLASS III   CB398 - CB305   345,52'   347,92'   0.60%   100,69 LF   30"   RCP   30 inch RCP   CLASS III   CB398 - CB305   360,76'   360,15'   0.57%   106,18 LF   15"   RCP   CLASS III   CLASS I	CLASS III	CB343 - CB342	368.30'	367.90'	0.62%	64.90 LF	15"	RCP	CLASS V
CLASS V CB346 - CB317 368.40' 368.10' 1.06% 28.30 LF 24" RCP CLASS V CLASS V CB348 - D1347 369.95' 368.80' 3.39% 33.93 LF 15" RCP CLASS III CB350 - CB327 363.00' 362.00' 3.10% 32.30 LF 16" RCP CLASS III CB350 - CB327 363.00' 362.00' 3.10% 32.30 LF 16" RCP CLASS III CB398 - CB305 - CB327 363.00' 362.00' 3.10% 32.30 LF 16" RCP CLASS III CB398 - CB305 - S55.97' 355.80' 0.54% 31.76 LF 15" RCP CLASS III D1324 - CB302 348.52' 347.92' 0.60% 100.69 LF 30" RCP 30 inch RCP D1336 - CB335 360.75' 360.15' 0.57% 106.18 LF 15" RCP CLASS III D1341 - CB315 365.89' 364.91' 1.47% 66.54 LF 16" RCP CLASS III D1347 - CB346 368.70' 368.50' 0.76% 26.21 LF 16" RCP CLASS III D1347 - CB346 368.70' 368.50' 0.76% 26.21 LF 16" RCP CLASS III D1362 - D1336 361.90' 360.95' 0.72% 132.71 LF 15" RCP CLASS III D1362 - D1336 361.90' 360.95' 0.72% 132.71 LF 15" RCP CLASS III D1397 - CB332 367.80' 367.00' 1.59% 50.45 LF 15" RCP CLASS III D1399 - CB398 356.60' 356.07' 0.89% 59.86 LF 15" RCP CLASS III C	CLASS V	CB344 - CB343	370.68'	368.50'	1.72%	126.46 LF	15"	RCP	CLASS III
CLASS III CLASS	CLASS IV	CB345 - CB342	367.90'	367.30'	0.72%	82.90 LF	15"	RCP	CLASS V
CLASS III CLASS	CLASS V	CB346 - CB317	368.40'	368.10'	1.06%	28.30 LF	24"	RCP	CLASS V
CLASS III  CB349 - CB319	CLASS V	CB348 - DI347	369.95'	368.80'	3.39%	33.93 LF	15"	RCP	CLASS III
ASS III; O-RING  CB350 - CB327 363.00' 362.00' 3.10% 32.30 LF 18" RCP CLASS III  CB398 - CB305 355.97' 355.80' 0.54% 31.76 LF 15" RCP CLASS III  DI324 - CB302 348.52' 347.92' 0.60% 100.69 LF 30" RCP 30 inch RCP  DI336 - CB335 360.75' 360.15' 0.57% 106.18 LF 15" RCP CLASS III  CLASS III		CB349 - CB319	374.70'	374.10'	1.89%	31.70 LF	15"	RCP	CLASS III
CB398 - CB305   355.97   355.80   0.54%   31.76 LF   15"   RCP   CLASS III									
DI324 - CB302   348.52'   347.92'   0.60%   100.69 LF   30"   RCP   30 inch RCP									
DESCRIPTION   CLASS III   DI336 - CB335   360.75'   360.15'   0.57%   106.18 LF   15"   RCP   CLASS III   DI341 - CB315   365.89'   364.91'   1.47%   66.54 LF   18"   RCP   CLASS III   CLASS III   DI347 - CB346   368.70'   368.50'   0.76%   26.21 LF   18"   RCP   CLASS III   CLASS III   DI362 - DI336   361.90'   360.95'   0.72%   132.71 LF   15"   RCP   CLASS III   DI380 - CB308   361.80'   361.00'   1.35%   59.14 LF   15"   RCP   CLASS III   DI382 - DI381   370.30'   369.20'   0.95%   115.61 LF   18"   RCP   CLASS III   DI397 - CB332   367.80'   367.00'   1.59%   50.45 LF   15"   RCP   CLASS III   CLASS III   DI399 - CB398   356.60'   356.07'   0.89%   59.86 LF   15"   RCP   CLASS III   VI276 - CB307   357.04'   356.77'   0.59%   45.58 LF   36"   RCP   CLASS III   VI309 - CB308   358.61'   357.89'   0.63%   114.74 LF   30"   RCP   CLASS III   VI318 - CB317   368.00'   366.20'   1.79%   100.75 LF   18"   RCP   CLASS III   VI328 - CB350   366.00'   363.20'   3.39%   82.56 LF   18"   RCP   CLASS III   VI328 - CB350   366.00'   363.20'   3.39%   82.56 LF   18"   RCP   CLASS III   VI328 - CB350   366.00'   363.20'   3.39%   82.56 LF   18"   RCP   CLASS III   VI334B - VI309   359.55'   359.40'   0.62%   24.00 LF   18"   RCP   CLASS III   RCP   CLASS III   VI334B - VI309   359.55'   359.40'   0.62%   24.00 LF   18"   RCP   CLASS III   RCP   CLASS III   CLA									
Di341 - CB315   365.89   364.91   1.47%   66.54 LF   18"   RCP   CLASS III									
CLASS III	DESCRIPTION								
CLASS V         CLASS III         DI361 - CB310         359.90'         359.20'         1.27%         54.91 LF         15"         RCP         CLASS III           CLASS III         DI362 - DI336         361.90'         360.95'         0.72%         132.71 LF         15"         RCP         CLASS III           CLASS III         DI380 - CB308         361.80'         361.00'         1.35%         59.14 LF         15"         RCP         CLASS III           CLASS III         DI381 - CB346         369.10'         368.60'         0.70%         71.15 LF         24"         RCP         CLASS III           CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI328 - C	CLASS III								
CLASS III         DI362 - DI336         361.90'         360.95'         0.72%         132.71 LF         15"         RCP         CLASS III           CLASS III         DI380 - CB308         361.80'         361.00'         1.35%         59.14 LF         15"         RCP         CLASS III           CLASS III         DI381 - CB346         369.10'         368.60'         0.70%         71.15 LF         24"         RCP         CLASS III           CLASS III         DI382 - DI381         370.30'         369.20'         0.95%         115.61 LF         18"         RCP         CLASS III           CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI334B	CLASS V								
CLASS III         DI362 - DI336         361.90'         360.95'         0.72%         132.71 LF         15"         RCP         CLASS III           CLASS III         DI380 - CB308         361.80'         361.00'         1.35%         59.14 LF         15"         RCP         CLASS III           CLASS III         DI381 - CB346         369.10'         368.60'         0.70%         71.15 LF         24"         RCP         CLASS III           CLASS III         DI382 - DI381         370.30'         369.20'         0.95%         115.61 LF         18"         RCP         CLASS III           CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI384 - CB350         366.00'         363.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI334B	CLASS III								
CLASS III         DI380 - CB308         361.80'         361.00'         1.35%         59.14 LF         15"         RCP         CLASS III           CLASS III         DI381 - CB346         369.10'         368.60'         0.70%         71.15 LF         24"         RCP         CLASS III           CLASS III         DI382 - DI381         370.30'         369.20'         0.95%         115.61 LF         18"         RCP         CLASS III           CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         3		DI362 - DI336	361.90'	360.95'	0.72%	132.71 LF	15"	RCP	CLASS III
Di381 - CB346   369.10'   368.60'   0.70%   71.15 LF   24"   RCP   CLASS III		DI380 - CB308	361.80'	361.00'	1.35%	59.14 LF	15"	RCP	CLASS III
CLASS III         DI382 - DI381         370.30'         369.20'         0.95%         115.61 LF         18"         RCP         CLASS III           CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI309 - CB308         358.61'         357.89'         0.63%         114.74 LF         30"         RCP         CLASS III           CLASS III         VI328 - CB350         366.00'         363.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III		DI381 - CB346	369.10'	368.60'	0.70%	71.15 LF	24"	RCP	CLASS III
CLASS III         DI397 - CB332         367.80'         367.00'         1.59%         50.45 LF         15"         RCP         CLASS III           CLASS III         DI399 - CB398         356.60'         356.07'         0.89%         59.86 LF         15"         RCP         CLASS III           CLASS III         JB301 - EW300         345.80'         345.00'         1.50%         53.27 LF         36"         RCP         CLASS III           CLASS III         VI276 - CB307         357.04'         356.77'         0.59%         45.58 LF         36"         RCP         CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III		DI382 - DI381	370.30'	369.20'	0.95%	115.61 LF	18"	RCP	CLASS III
Disage		DI397 - CB332	367.80'	367.00'	1.59%	50.45 LF	15"	RCP	CLASS III
CLASS   III		DI399 - CB398	356.60'	356.07'	0.89%	59.86 LF	15"	RCP	CLASS III
CLASS   III		JB301 - EW300	345.80'	345.00'	1.50%	53.27 LF	36"	RCP	CLASS III; O-RING
CLASS III         VI309 - CB308         358.61'         357.89'         0.63%         114.74 LF         30"         RCP         CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI328 - CB350         366.00'         363.20'         3.39%         82.56 LF         18"         RCP         CLASS III           CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III		VI276 - CB307	357.04'	356.77'	0.59%	45.58 LF	36"	RCP	CLASS III
CLASS III           CLASS III         VI318 - CB317         368.00'         366.20'         1.79%         100.75 LF         18"         RCP         CLASS III           CLASS III         VI328 - CB350         366.00'         363.20'         3.39%         82.56 LF         18"         RCP         CLASS III           VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III									
CLASS III         VI328 - CB350         366.00'         363.20'         3.39%         82.56 LF         18"         RCP         CLASS III           CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III	CLASS III								
CLASS III         VI334A - VI334B         359.65'         359.60'         1.25%         4.00 LF         18"         RCP         CLASS III           CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III           CLASS III	CLASS III								
CLASS III         VI334B - VI309         359.55'         359.40'         0.62%         24.00 LF         18"         RCP         CLASS III           CLASS III	CLASS III								
CLASS III  CLASS V  CLASS III	CLASS III								
CLASS III	CLASS III	VI334B - VI309	359.55'	359.40'	0.62%	24.00 LF	18"	RCP	CLASS III
	CLASS V								
	CLASS III								
	CL A C C III								

STORM PIPE TABLE


UPSTREAM DOWNSTREAM SLOPE LENGTH DIA. MATERIAL

FROM - TO

DESCRIPTION	F	ROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL	DESCRIPTION
CLASS III	СВ	3402 - DI401	368.99'	367.77'	0.60%	203.66 LF	48"	RCP	CLASS III; O-RING
ASS III; O-RING	CB	403 - CB402	369.23'	368.99'	0.60%	40.15 LF	48"	RCP	CLASS III; O-RING
CLASS III	CB	404 - CB403	369.74'	369.33'	0.60%	68.03 LF	48"	RCP	CLASS III; O-RING
CLASS III	СВ	406 - DI405	371.82'	371.01'	0.59%	136.50 LF	48"	RCP	CLASS III
CLASS III		407 - CB406	372.28'	371.82'	0.61%	75.44 LF	36"	RCP	CLASS III
CLASS III		409 - CB407	373.31'	372.40'	1.00%	91.16 LF	30"	RCP	CLASS III
CLASS III		410 - CB409	375.60'	374.50'	0.61%	179.40 LF	30"	RCP	CLASS III
CLASS III		411 - CB410	378.74'	378.32'	0.99%	42.43 LF	24"	RCP	CLASS III
CLASS III		412 - CB411	379.24'	379.00'	0.70%	34.60 LF	24"	RCP	CLASS III
CLASS III		413 - CB412	382.00'	379.50'	1.77%	141.43 LF	24"	RCP	CLASS III
CLASS III		414 - CB413					18"	RCP	
CLASS III			385.70'	382.78'	2.09%	140.00 LF			CLASS III
CLASS III		415 - CB414	386.19'	385.90'	0.94%	30.89 LF	15"	RCP	CLASS III
CLASS III		416 - CB402	372.50'	372.00'	1.14%	43.91 LF	24"	RCP	24 inch RCP
CLASS III		417 - CB416	373.20'	372.70'	0.63%	78.95 LF	18"	RCP	CLASS III
CLASS III		418 - CB417	374.00'	373.40'	1.06%	56.61 LF	18"	RCP	CLASS III
CLASS III		419 - CB418	374.40'	374.20'	0.74%	27.07 LF	18"	RCP	CLASS III
CLASS III		420 - CB419	376.00'	374.60'	0.77%	181.07 LF	18"	RCP	CLASS III
CLASS III	CB	421 - CB420	376.50'	376.20'	1.11%	27.01 LF	15"	RCP	CLASS III
CLASS III	CB	422 - CB416	380.18'	379.18'	3.70%	27.00 LF	15"	RCP	CLASS III
CLASS V	CB	423 - CB406	372.80'	371.82'	1.12%	87.48 LF	24"	RCP	CLASS III
CLASS III	CB	424 - CB406	374.70'	374.50'	0.74%	27.00 LF	18"	RCP	CLASS III
CLASS III	CB	425 - CB424	375.30'	374.70'	0.81%	73.98 LF	18"	RCP	CLASS III
CLASS III	CB	427 - CB430	377.30'	376.55'	1.00%	75.25 LF	15"	RCP	CLASS III
CLASS III	CB	428 - CB427	378.00'	377.50'	0.55%	91.35 LF	15"	RCP	CLASS III
CLASS III	CB	429 - CB428	379.00'	378.20'	0.74%	108.10 LF	15"	RCP	CLASS III
CLASS III	CB	430 - CB409	374.70'	374.40'	1.11%	27.00 LF	24"	RCP	CLASS III
CLASS III	CB	431 - CB430	375.60'	374.90'	1.08%	65.00 LF	24"	RCP	CLASS III
CLASS III	CB	433 - CB410	376.10'	375.80'	0.50%	60.34 LF	24"	RCP	CLASS III
	CB	434 - CB433	377.40'	376.30'	0.53%	206.09 LF	24"	RCP	24 inch RCP
CLASS III	CB	436 - CB434	377.88'	377.50'	1.29%	29.28 LF	18"	RCP	CLASS V
CLASS III	CB	437 - CB434	378.00'	377.60'	0.83%	48.18 LF	18"	RCP	CLASS V
CLASS III	CB	439 - CB413	383.00'	382.10'	3.33%	27.00 LF	15"	RCP	CLASS III
CLASS III	CB4	441 - CB425	376.00'	375.50'	3.70%	13.51 LF	15"	RCP	CLASS III
CLASS V	DI4	01 - EW400	367.67'	367.25'	1.27%	33.20 LF	48"	RCP	CLASS III; O-RING
CLASS V		105 - CB404	370.91'	369.84'	0.60%	177.10 LF	48"	RCP	CLASS III; O-RING
CLASS III		126 - CB425	376.00'	375.30'	0.51%	136.50 LF	15"	RCP	CLASS III
CLASS V		132 - CB431	376.70'	376.20'	0.95%	52.63 LF	18"	RCP	CLASS III
CLASS V									
CLASS III		135 - CB434	377.80'	377.50'	0.51%	58.49 LF	18"	RCP	CLASS V; O-RING
CLASS III		138 - CB413	383.10'	382.10'	0.56%	178.54 LF	24"	RCP	24 inch RCP
CLASS III	DI4	140 - CB433	380.07'	379.32'	0.62%	121.54 LF	18"	RCP	18 inch RCP

STORM PIPE TABLE

STORM PIPE TABLE								
FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL	DESCRIPTION	
EW610 - EW609	354.50'	354.00'	0.86%	58.32 LF	72"	RCP	CLASS III	
EW612 - EW611	355.50'	355.00'	0.85%	58.96 LF	72"	RCP	CLASS III	
EW614 - EW613	379.00'	378.50'	0.68%	73.83 LF	48"	RCP	CLASS III	
EW616 - EW615	379.00'	378.50'	0.67%	74.32 LF	48"	RCP	CLASS III	
FE650 - FE651	343.40'	342.30'	1.11%	99.34 LF	24"	RCP	CLASS V	
SCM 1 RISER - EW 601	369.90'	369.50'	0.97%	41.43 LF	30"	RCP	CLASS III	
SCM 1 RISER - EW 601	369.90'	369.50'	0.99%	40.32 LF	30"	RCP	CLASS III	
SCM 1 RISER - EW601	369.90'	369.50'	0.94%	42.48 LF	30"	RCP	CLASS III	
SCM 2 RISER - EW 602	380.55'	380.20'	1.02%	34.19 LF	30"	RCP	CLASS III	
SCM 2 RISER - EW602	380.55'	380.20'	1.04%	33.79 LF	30"	RCP	CLASS III	
SCM 3 RISER - EW603	341.59'	341.00'	0.43%	139.37 LF	48"	RCP	CLASS III	
SCM 4 RISER - EW604	365.45'	365.00'	0.67%	67.61 LF	48"	RCP	CLASS III	
SCM 5 RISER - EW605	347.88'	347.30'	0.66%	88.55 LF	42"	RCP	CLASS III	




09/17/2021 DRAWN BY R. WINGATE DESIGNED BY P. BARBEAU SCALE


CHECKED BY P. BARBEAU AS SHOWN

SHEET NO. *C3.7* 


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




SCM 1 INLET 1 -0+25 - 2+50




-0+25 - 2+00



SCM 1 INLET 2 -0+25 - 2+50



SCM 2 INLET 1 -0+25 - 2+00



09/17/2021

R. WINGATE P. BARBEAU

P. BARBEAU


AS SHOWN

43398


SHEET NO. *C3.8* 

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF


PROFILE SCALE



**SCM3 INLET** -0+25 - 2+00



SCM 4 INLET -0+25 - 7+00



09/17/2021 R. WINGATE

P. BARBEAU

P. BARBEAU


AS SHOWN


43398 SHEET NO.

C3.9

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

PROFILE SCALE





#### STAGE I WAKE COUNTY EROSION CONTROL SEQUENCE

- 1. SCHEDULE A PRECONSTRUCTION CONFERENCE WITH THE ENVIRONMENTAL CONSULTANT
- KARYN PAGEAU, 919-796-8769. OBTAIN A LAND DISTURBING PERMIT. CONTRACTOR SHALL OBTAIN AND READ ALL PERMITS NECESSARY TO COMPLETE THE
- PROJECT, INCLUDING BUT NOT LIMITED TO LAND DISTURBANCE PERMIT
- INSTALL GRAVEL CONSTRUCTION PAD, SILT FENCE, ETC. AS SHOWN ON THESE PLANS. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS, BERMS AND BASINS IMMEDIATELY AFTER CONSTRUCTION.
- INSTALL SEDIMENT SKIMMER BASINS. IN BASINS 1, 2, 4, AND 5 INSTALL PERMANENT RISER AND OUTFALL WITH TEMPORARY SKIMMER BASIN. PROMPTLY SEED/STABILIZE ALL SLOPES. SEE DETAILS. INSTALL RISER AND CONNECT SKIMMER TO RISER. EMBANKMENTS TO BE CONSTRUCTED AND TESTED AS PERMANENT STRUCTURES PER THE STORMWATER DETAILS
- PROMPTLY STABILIZE ALL 3:1 SLOPES OR GREATER AROUND BASINS AND DOWN-SLOPE OF DISTURBANCE ACTIVITY. SEED/USE EROSION CONTROL BLANKETS SUCH AS NORTH
- AMERICAN GREEN S150, OR SIMILAR PRODUCT RATED FOR STEEP SLOPES. INSTALL TEMPORARY DIVERSION BERM/DITCHES WITH SEED & LINER. INSTALL ALL REMAINING EROSION CONTROL MEASURES PER THIS PLAN.
- CALL 919.796.8769 FOR AN ONSITE INSPECTION BY THE WAKE COUNTY WATERSHED MANAGER & OBTAIN CERTIFICATE OF COMPLIANCE.
- . BEGIN CLEARING AND GRUBBING AND ROUGH SITE GRADING. MAINTAIN DEVICES AS NEEDED. 9. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL EROSION CONTROL MEASURES THROUGHOUT CONSTRUCTION. ALL EROSION CONTROL DEVICES SHOULD BE INSPECTED AFTER EACH RAINFALL EVENT, AND ON A WEEKLY BASIS, AND REFURBISHED IMMEDIATELY. DO NOT REMOVE SKIMMER BASINS NOR OTHER MEASURES UNTIL INSTRUCTED TO DO SO. SKIMMER BASINS TO REMAIN THROUGHOUT CONSTRUCTION.
- 10. PROCEED TO STAGE 2 EROSION CONTROL PLANS / SEQUENCE FOR CONTINUATION.

#### **GENERAL NOTES**

- 1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE.
- 2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH
- RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE ARCHITECT. 3. THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND
- FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM ALL ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE OWNER RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.
- 5. CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)
- 6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING PERMIT AND INSTALLATION OF EROSION CONTROL. 7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.
- 8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE CONSTRUCTION OF THE PROJECT.
- 9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT STABILIZATION REQUIREMENTS FOUND ON THIS SHEET. 10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING
- PEDESTRIAN TRAFFIC AREAS. 11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM UNLESS OTHERWISE NOTED. 12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR
- THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE. 13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.

#### TEMPORARY STOCKPILE NOTES

- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC.
- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING
- AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE. 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

#### **ATTENTION CONTRACTORS** The **Construction Contractor** responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public*

Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, Install a Downstream **Plug**, have **Permitted Plans** on the **Jobsite**, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the City of Raleigh.

# **EROSION CONTROL LEGEND**

TREE PROTECTION FENCE LIMITS OF DISTURBANCE ---- STOCKPILE AREA -SF ----SF --- SILT FENCE SILT/TREE PROTECTION **COMBINATION FENCE** POROUS BAFFLE — TEMPORARY DIVERSION DITCH SILT BAG AND PAD

SILT FENCE STONE OUTLET SILT FENCE STONE OUTLET W/J HOOKS EMERGENCY SPILLWAY / RIP RAP CHECK DAM WITH A WEIR

CHECK DAM CONSTRUCTION ENTRANCE

TEMPORARY INLET PROTECTION TEMPORARY DOUBLE INLET PROTECTION **CONCRETE WASHOUT** 

 $\longrightarrow$ 

WATTLE

HORSESHOE INLET PROTECTION SKIMMER

TEMPORARY SLOPE DRAIN (TSD)

TEMPORARY TIMBER MAT

TEMPORARY DIVERSION BERM

ROLLED EROSION CONTROL FABRIC

EC104 TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.) TREE FENCE. REFER TO DETAIL (TYP.) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1 EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN UMMARY ON SHEET C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2 EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN SUMMARY ON SHEET C4.1) EMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHEE EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN SUMMARY ON SHEET C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5 EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN SUMMARY ON SHEET C4.1) TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHEET TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHEET EMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHEET EMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHEET SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.1 (TYP.) TEMP. DIVERSION DITCH #1A (REFER TO C4.1) EC118 TEMP. DIVERSION DITCH #1B (REFER TO C4.1) TEMP. DIVERSION DITCH #2A (REFER TO C4.1) TEMP. DIVERSION DITCH #2B (REFER TO C4.1) TEMP. DIVERSION DITCH #3A (REFER TO C4.1) TEMP. DIVERSION DITCH #3B (REFER TO C4.1) TEMP. DIVERSION DITCH #4A (REFER TO C4.1) TEMP. DIVERSION DITCH #4B (REFER TO C4.1) TEMP. DIVERSION DITCH #5A (REFER TO C4.1) TEMP. DIVERSION DITCH #5B (REFER TO C4.1) TEMP. DIVERSION DITCH #6A (REFER TO C4.1) TEMP. DIVERSION DITCH #6B (REFER TO C4.1) TEMP. DIVERSION DITCH #7A (REFER TO C4.1) TEMP. DIVERSION DITCH #7B (REFER TO C4.1 TEMP. DIVERSION DITCH #8A (REFER TO C4.1) TEMP. DIVERSION DITCH #8B (REFER TO C4.1) TEMP. DIVERSION DITCH #9A (REFER TO C4.1) TEMP. DIVERSION DITCH #9B (REFER TO C4.1) ROCK CHECK DAM REFER TO DETAIL (TYP.) POROUS BAFFLES (TYP.) SILT BAG AND SILT BAG PAD IMPERMEABLE MEMBRANE APRON EC139 3:1 SIDE SLOPE EC140 STOCKPILE AREA CONCRETE WASHOUT EC142 TEMPORARY CLASS III 18" RCP PIPE FOR DITCH CROSSING TEMPORARY HORSESHOE INLET PROTECTION EC143 PIPE OUTFALL PROTECTION. (REFER TO C4.1) DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.1 AND STORM PLAN FOR DETAILS) EC146 TEMPORARY PIPE FOR OUTFALL CROSSING ROCK CHECK DAM WITH WEIR (REFER TO STREAM CROSSING PLAN) FC148 SILT FENCE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)

**EROSION CONTROL PLAN-STAGE 1 KEYNOTES** 

**NUMBER** 

EC101 LIMITS OF DISTURBANCE

EC102 SILT FENCE; REFER TO DETAIL (TYP).

FC103 SILT FENCE OUTLET: REFERT TO DETAIL (TYP).

DESCRIPTION


### Required Wake County Basin Removal Sequence

- 1. Schedule a site meeting with the Environmental Consultant to determine if a basin can be removed. Install silt fencing or other temporary erosion control measures as needed prior to removal of the basin.
- 2. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be extended, perform this operation at this time. Fine grade area in preparation for seeding.
- 3. Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas
- 4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan.
- 5. When site is fully stabilized, call Environmental Consultant for approval of removing remaining temporary erosion control measures and advice on when site can be issued a Certificate of Completion. Note: A meeting should also be scheduled with the Environmental Consultant to determine when a basin may be converted for stormwater

#### MAINTENANCE PLAN:

use. Some municipalities may also require this.

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS
- DESIGNED. 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A
- 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS,
- DENSE VEGETATIVE GROWTH.
- 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE REQUIREMENTS.



ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



09/17/2021 DRAWN BY A. BROWN

**DESIGNED BY** P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN

JOB NO. 43398 SHEET NO.

C4.0

### BASIN SUMMARY SCHEDULE

<b>BASIN NAME</b>	BASIN 1	BASIN NAME	BASIN 2	BASIN NAME	BASIN 3	BASIN NAME	BASIN 4	BASIN NAME
BASIN TYPE	RISER	BASIN TYPE	RISER	BASIN TYPE	RISER	BASIN TYPE	RISER	BASIN TYPE
TOTAL DRAINAGE AREA	21.62 ac res	TOTAL DRAINAGE AREA	8.07 ac res	TOTAL DRAINAGE AREA	1.12 ac res	TOTAL DRAINAGE AREA	7.49 acres	TOTAL DRAINAGE AREA
Tc (TIME OF CONCENTRATION)	5 min	Tc (TIME OF CONCENTRATION)	5 min	Tc (TIME OF CONCENTRATION)	5 min	Tc (TIME OF CONCENTRATION)	10 min	Tc (TIME OF CONCENTRATION)
C VALUE	0.50	C VALUE	0.50	C VALUE	0.50	C VALUE	0.50	C VALUE
I (10 YEAR STORM)	7.20 in/hr	I (10 YEAR STORM)	7.20 in/hr	I (10 YEAR STORM)	7.20 in/hr	I (10 YEAR STORM)	5.76 in/hr	I (10 YEAR STORM)
SURFACE AREA CALCULATION:		SURFACE AREA CALCULATION:		SURFACE AREA CALCULATION:		SURFACE AREA CALCULATION:		SURFACE AREA CALCULATION:
Q10 = CIA	78 cfs	Q10 = CIA	29 cfs	Q10 = CIA	4 cfs	Q10 = CIA	22 cfs	Q10 = CIA
SURFACE AREA (AC) = 435 SF * Q10 (CFS)		SURFACE AREA (AC) = 435 SF * Q10 (CFS)		SURFACE AREA (AC) = 435 SF * Q10 (CFS)		SURFACE AREA (AC) = 435 SF * Q10 (CFS)	22 013	SURFACE AREA (AC) = 435 SF * Q10 (CFS)
SURFACE AREA REQUIRED	33,857 ft <sup>2</sup>	SURFACE AREA REQUIRED	12,638 ft <sup>2</sup>	SURFACE AREA REQUIRED	1,754 ft <sup>2</sup>		9,383 ft <sup>2</sup>	
RECTANGLE BASIN PROVIDED	99.5' X 349.4'	RECTANGLE BASIN PROVIDED	50' X 279'	RECTANGLE BASIN PROVIDED	70' X 140'	SURFACE AREA REQUIRED RECTANGLE BASIN PROVIDED	9,363 π 99.5' X 349.4'	SURFACE AREA REQUIRED RECTANGLE BASIN PROVIDED
SURFACE AREA PROVIDED	40,474 ft <sup>2</sup>	SURFACE AREA PROVIDED	22,949 ft <sup>2</sup>	SURFACE AREA PROVIDED	10,740 ft <sup>2</sup>	SURFACE AREA PROVIDED	17,593 ft <sup>2</sup>	利用的な一般では、1980年の特別では、1990年の19
BASIN VOLUME CALCULATION:	172 CAUT 15	BASIN VOLUME CALCULATION:		BASIN VOLUME CALCULATION:	10,110 10	TIME FIRST AND ADDRESS OF THE PARTY OF THE P	17,595 π	SURFACE AREA PROVIDED
BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre		BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre				BASIN VOLUME CALCULATION:		BASIN VOLUME CALCULATION:
THE STATE OF PARTY MANAGEMENT AND STATE OF PARTY AND STATE OF THE STAT	3			BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre	-	BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre	100	BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre
BASIN VOLUME REQUIRED	38,916 ft <sup>3</sup>	BASIN VOLUME REQUIRED	14,526 ft <sup>3</sup>	BASIN VOLUME REQUIRED	2,016 ft <sup>3</sup>	BASIN VOLUME REQUIRED	13,482 ft <sup>3</sup>	BASIN VOLUME REQUIRED
BASIN VOLUME PROVIDED	O ft <sup>3</sup>	BASIN VOLUME PROVIDED	41,376 ft <sup>3</sup>	BASIN VOLUME PROVIDED	42,446 ft <sup>3</sup>	BASIN VOLUME PROVIDED	68,733 ft <sup>3</sup>	BASIN VOLUME PROVIDED
TOP OF EMBANKMENT ELEVATION	376	TOP OF EMBANKMENT ELEVATION	386	TOP OF EMBANKMENT ELEVATION	351	TOP OF EMBANKMENT ELEVATION	374	TOP OF EMBANKMENT ELEVATION
EMBANKMENT WIDTH	10 ft	EMBANKMENT WIDTH	10 ft	EMBANKMENT WIDTH	10 ft	EMBANKMENT WIDTH	10 ft	EMBANKMENT WIDTH
BOTTOM ELEVATION	370.00	BOTTOM ELEVATION	383.00	BOTTOM ELEVATION	345.00	BOTTOM ELEVATION	368.00	BOTTOM ELEVATION
EMERGENCY SPILLWAY ELEVATION	375.00	EMERGENCY SPILLWAY ELEVATION	385.00	EMERGENCY SPILLWAY ELEVATION	350.00	EMERGENCY SPILLWAY ELEVATION	373.00	EMERGENCY SPILLWAY ELEVATION
BASIN DEPTH	5 ft	BASIN DEPTH	2 ft	BASIN DEPTH	5 ft	BASIN DEPTH	5 ft	BASIN DEPTH
EMERGENCY SPILLWAY WIDTH	48.5 ft	EMERGENCY SPILLWAY WIDTH	30 ft	EMERGENCY SPILLWAY WIDTH	10 ft	EMERGENCY SPILLWAY WIDTH	45 ft	EMERGENCY SPILLWAY WIDTH
SEDIMENT STORAGE VOLUME	28,332 ft <sup>3</sup>	SEDIMENT STORAGE VOLUME	12,024 ft <sup>3</sup>	SEDIMENT STORAGE VOLUME	6,950 ft <sup>3</sup>	SEDIMENT STORAGE VOLUME	28,332 ft <sup>3</sup>	SEDIMENT STORAGE VOLUME
	@ 376'		@ 386'		@ 351'	The second secon	@ 374'	and the second that the second second the second se
TOP OF RISER ELEVATION	373.00	TOP OF RISER ELEVATION	384.00 ft	TOP OF RISER ELEVATION	348.50	TOP OF RISER ELEVATION	371.00	TOP OF RISER ELEVATION
PROVIDE 3 BAFFLES		PROVIDE 3 BAFFLES		PROVIDE 3 BAFFLES		PROVIDE 3 BAFFLES		PROVIDE 3 BAFFLES
SKIMMER SIZE	5 inch	SKIMMER SIZE	3 inch	SKIMMER SIZE	2.5 inch	SKIMMER SIZE	3 inch	SKIMMER SIZE
ORIFICE DIAMETER	3 inch	ORIFICE DIAMETER	2 inch	ORIFICE DIAMETER	0.75 inch	ORIFICE DIAMETER	1.75 inch	ORIFICE DIAMETER
DEWATERING TIME	3.24 days	DEWATERING TIME	3.14 days	DEWATERING TIME	3.40 days	DEWATERING TIME	3.81 days	DEWATERING TIME
BASIN NAME	BASIN 8	BASIN NAME	BASIN 9					
BASIN TYPE	SKIMMER	BASIN TYPE	SKIMMER					
TOTAL DRAINAGE AREA	8.13 acres	TOTAL DRAINAGE AREA	3.61 acres					
Tc (TIME OF CONCENTRATION)	5 min	Tc (TIME OF CONCENTRATION)	5 min					
C VALUE	0.50	C VALUE	0.50					
I (10 YEAR STORM)	7.20 in/hr	I (10 YEAR STORM)	7.20 in/hr					
SURFACE AREA CALCULATION:		SURFACE AREA CALCULATION:						
Q10 = CIA	29 cfs	Q10 = CIA	13 cfs					
SURFACE AREA (AC) = 435 SF * Q10 (CFS)		SURFACE AREA (AC) = 435 SF * Q10 (CFS)						
SURFACE AREA REQUIRED	12,732 ft <sup>2</sup>	SURFACE AREA REQUIRED	5,653 ft <sup>2</sup>					
RECTANGLE BASIN PROVIDED	80' X 165'	RECTANGLE BASIN PROVIDED	56' X 112'					
SURFACE AREA PROVIDED	14,561 ft <sup>2</sup>	SURFACE AREA PROVIDED	7,261 ft <sup>2</sup>					
BASIN VOLUME CALCULATION:	11,001	BASIN VOLUME CALCULATION:	1 Set 1 455 1 10 1855					
BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /acre		BASIN VOLUME DESIGN = 1,800 ft <sup>3</sup> /ac re						
BASIN VOLUME REQUIRED	14,634 ft <sup>3</sup>	BASIN VOLUME REQUIRED	6,498 ft <sup>3</sup>					
		BASIN VOLUME PROVIDED	17,377 ft <sup>3</sup>					
BASIN VOLUME PROVIDED	37,314 ft <sup>3</sup>	TOP OF EMBANKMENT ELEVATION	390					
TOP OF EMBANKMENT ELEVATION	357	EMBANKMENT WIDTH	10 ft					
EMBANKMENT WIDTH	10 ft	BOTTOM ELEVATION	386.00	-				
BOTTOM ELEVATION	353.00	EMEDGENCY SPILLWAY ELEVATION	380.00					

DIVERSION DITCH SUMMARY SC	HEDULE
----------------------------	--------

BASIN DEPTH

SKIMMER SIZE

PROVIDE 3 BAFFLES

ORIFICE DIAMETER
DEWATERING TIME

EMERGENCY SPILLWAY ELEVATION

EMERGENCY SPILLWAY WIDTH

SEDIMENT STORAGE VOLUME

389.00

3 ft

20 ft

4,868 ft<sup>3</sup>

@ 389'

3 inch

1.25 inch

3.60 days

356.00

30 ft

@ 356

4 inch

1.75 inch

11,103 ft<sup>3</sup>

EMERGENCY SPILLWAY ELEVATION

EMERGENCY SPILLWAY WIDTH

SEDIMENT STORAGE VOLUME

PROVIDE 3 BAFFLES

ORIFICE DIAMETER

DEWATERING TIME

SKIMMER SIZE

BASIN DEPTH

DITCH NAME	TOP WIDTH "A"	MIN. DITCH DEPTH (FT) "B"	BOTTOM WIDTH (FT) "C"	SIDE SLOPE "D"	LINER TYPE & THICKNESS
TDD 1A	15 FT	2 FT	3	3:1	North American Green, S75
TDD 1B	10 FT	1.5 FT	1	3:1	North American Green, S75
TDD 2A	8.8 FT	1.3 FT	1	3:1	North American Green, S75
TDD 2B	8.2 FT	1.2 FT	1	3:1	North American Green, S75
TDD 3A	7 FT	1 FT	1	3:1	North American Green, S75
TDD 3B	7 FT	1 FT	1	3:1	North American Green, S75
TDD 4A	10.5 FT	1.5 FT	1.5	3:1	North American Green, S75
TDD 4B	7 FT	1 FT	1	3:1	North American Green, S75
TDD 5A	7.6 FT	1.1 FT	1	3:1	North American Green, S75
TDD 5B	8.2 FT	1.2 FT	1	3:1	North American Green, S75
TDD 6A	8.2 FT	1.2 FT	1	3:1	North American Green, S75
TDD 6B	7 FT	1 FT	1	3:1	North American Green, S75
TDD 7A	12 FT	1.75 FT	1.5	3:1	North American Green, S75
TDD 7B	6 FT	1 FT	0	3:1	North American Green, S75
TDD 8A	11 FT	1.5 FT	2	3:1	North American Green, S75
TDD 8B	5.5 FT	0.75 FT	1	3:1	North American Green, S75
TDD 9A	8.2 FT	1.2 FT	1	3:1	North American Green, S75
TDD 9B	7 FT	1 FT	1	3:1	North American Green, S75

	DITCH OL	JTLET PROTECTI	ON (NYDOT METHOD)	
DITCH NAME	APRON WIDTH (ft)	RIP RAP CLASS	APRON THICKNESS (in)	APRON LENGTH (ft)
TDD1A	15.0	В	18.0	24.0
TDD1B	10.0	Α	12.0	10.0
TDD2A	8.8	Α	12.0	8.0
TDD2B	8.2	Α	12.0	8.0
TDD3A	7.0	Α	12.0	6.0
TDD3B	7.0	Α	12.0	6.0
TDD4A	10.5	Α	12.0	10.0
TDD4B	7.0	Α	12.0	6.0
TDD5A	8.2	Α	12.0	6.0
TDD5B	8.2	Α	12.0	6.0
TDD6A	8.2	Α	12.0	8.0
TDD6B	7.0	Α	12.0	6.0
TDD7A	12.0	В	18.0	18.0
TDD7B	6.0	Α	12.0	6.0
TDD8A	11.0	В	18.0	18.0
TDD8B	5.5	Α	12.0	4.0
TDD9A	8.2	Α	12.0	8.0
TDD9B	7.0	Α	12.0	6.0
			A. RIP RAP APRON SHOUL	D CONTINUE TO THE
TOE OF THE SI	LOPE FROM POINT (	OF OUTFALL		

	PIP	E OUTLET PROTE	CTION (NYDOT METHOD	)	PIPE OUTLET PROTECTION (NYDOT METHOD)								
STRUCTURE NAME	PIPE DIAMETER (in)	RIP RAP CLASS	APRON THICKNESS (in)	APRON LENGTH (ft)	APRON WIDTH (ft)								
CULVERT 1	72 (2 PIPES)	1	36	40	22.5								
CULVERT 2	44 (2 PIPES)	1	24	20	15.0								
EW100	48	В	18	24	12.0								
EW148	48	1	24	32	12.0								
FE201	30	В	18	15	7.5								
FE212	30	В	18	15	7.5								
EW220	24	Α	12	8	6.0								
EW300	36	1	24	24	9.0								
EW400	48	1	24	32	12.0								
EW500	30	1	24	20	7.5								
EW601	30 (3 PIPES)	В	18	15	22.5								
EW602	30 (2 PIPES)	В	18	15	14.0								
EW603	48	В	18	24	12.0								
EW604	48	В	18	24	12.0								
EW605	42	В	18	21	10.5								
FE651	24	В	18	12	6.0								

**BASIN NAME** 

SURFACE AREA (AC) = 435 SF \* Q10 (CFS)

Tc (TIME OF CONCENTRATION)

SURFACE AREA CALCULATION:

SURFACE AREA REQUIRED

SURFACE AREA PROVIDED

BASIN VOLUME REQUIRED

BASIN VOLUME PROVIDED

EMBANKMENT WIDTH BOTTOM ELEVATION

PROVIDE 3 BAFFLES

ORIFICE DIAMETER

DEWATERING TIME

BASIN DEPTH

SKIMMER SIZE

TOP OF EMBANKMENT ELEVATION

EMERGENCY SPILLWAY WIDTH

SEDIMENT STORAGE VOLUME

MERGENCY SPILLWAY ELEVATION

RECTANGLE BASIN PROVIDED

BASIN VOLUME CALCULATION:

BASIN VOLUME DESIGN = 1,800 ft3/acre

BASIN TYPE

3.44 acres TOTAL DRAINAGE AREA

C VALUE

I (10 YEAR STORM)

BASIN 5

RISER

10 min

5.76 in/hr

10 cfs

4,310 ft<sup>2</sup>

8,258 ft<sup>2</sup>

6,192 ft3

32,943 ft3

357

350.00

356.00

10 ft

20 ft

4,392 ft<sup>3</sup>

353.00

@ 357'

3 inch 1.25 inch

3.43 days

60' X 120'

0.50

BASIN 6

SKIMMER

5 min

7.20 in/hr

13 cfs

5,794 ft<sup>2</sup>

5,881 ft<sup>2</sup>

6,660 ft3

13,723 ft<sup>3</sup>

360

356.00

359.00

10 ft

15 ft

@ 359'

3 inch

1.25 inch

3.69 days

5,688 ft3

60' X 120'

0.50

**BASIN TYPE** 

3.70 acres TOTAL DRAINAGE AREA

VALUE

Q10 = CIA

(10 YEAR STORM)

**BASIN NAME** 

SURFACE AREA (AC) = 435 SF \* Q10 (CFS)

BASIN VOLUME DESIGN = 1,800 ft<sup>3</sup>/acre

TOP OF EMBANKMENT ELEVATION

EMERGENCY SPILLWAY ELEVATION

EMERGENCY SPILLWAY WIDTH

SEDIMENT STORAGE VOLUME

Tc (TIME OF CONCENTRATION)

SURFACE AREA CALCULATION:

SURFACE AREA REQUIRED

SURFACE AREA PROVIDED

BASIN VOLUME CALCULATION:

BASIN VOLUME REQUIRED

BASIN VOLUME PROVIDED

EMBANKMENT WIDTH

BOTTOM ELEVATION

PROVIDE 3 BAFFLES

ORIFICE DIAMETER

DEWATERING TIME

BASIN DEPTH

SKIMMER SIZE

RECTANGLE BASIN PROVIDED

BASIN 7

SKIMMER

13.63 acres

10 min

7.20 in/hr

49 cfs

0.50

21,345 ft<sup>2</sup>

23,812 ft<sup>2</sup>

24,534 ft<sup>3</sup>

63,172 ft<sup>3</sup>

371

367.00

370.00

10 ft

3 ft

48 ft

@ 370'


4 inch

2.25 inch

3.64 days

19,312 ft<sup>3</sup>

104' X 212'



	09		6/	20	123
z   Kaleigii, NC 27807 3.8124 www.timmons.com	NC	COMMENTS	COMMENTS	SUBMITTAL	MMENTS

DATE

09/17/2021 DRAWN BY A. BROWN

DESIGNED BY P. BARBEAU CHECKED BY

P. BARBEAU


SCALE AS SHOWN

43398

SHEET NO. C4.1

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF

SCALE 1"=150'




09/17/2021 DRAWN BY

A. BROWN **DESIGNED BY** P. BARBEAU

CHECKED BY . BARBEAU

SCALE AS SHOWN



	SION CONTROL PLAN-STAGE TRETNOTES
NUMBER	DESCRIPTION
EC101	LIMITS OF DISTURBANCE
	SILT FENCE; REFER TO DETAIL (TYP).
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
	TREE FENCE. REFER TO DETAIL (TYP.)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN
	SUMMARY ON SHEET C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
	TEMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHEET
	C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #4
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
1 (1440)	PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN SUMMARY ON SHEET C4.1)
	TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHEET
EC112	C4.1)
	TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHEET
	C4.1)
L('11/1	TEMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHEET C4.1)
	C4.1) TEMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHEET
L('115	C4.1)
	SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.1 (TYP.)
EC117	TEMP. DIVERSION DITCH #1A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #1B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #2A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #2B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #3A (REFER TO C4.1)
EC122	TEMP. DIVERSION DITCH #3B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #4A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #4B (REFER TO C4.1)
EC125	TEMP. DIVERSION DITCH #5A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #5B (REFER TO C4.1)
EC127	TEMP. DIVERSION DITCH #6A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #6B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #7A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #7B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #8A (REFER TO C4.1)
EC132	TEMP. DIVERSION DITCH #8B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #9A (REFER TO C4.1)
	TEMP. DIVERSION DITCH #9B (REFER TO C4.1)
	ROCK CHECK DAM REFER TO DETAIL (TYP.)
	POROUS BAFFLES (TYP.)
	SILT BAG AND SILT BAG PAD
	IMPERMEABLE MEMBRANE APRON
	3:1 SIDE SLOPE
	STOCKPILE AREA
	CONCRETE WASHOUT
	TEMPORARY CLASS III 18" RCP PIPE FOR DITCH CROSSING
	TEMPORARY HORSESHOE INLET PROTECTION
	PIPE OUTFALL PROTECTION. (REFER TO C4.1)
L('1/16	DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.1 AND STORM
	PLAN FOR DETAILS)
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING
EC147	ROCK CHECK DAM WITH WEIR (REFER TO STREAM CROSSING PLAN) SILT FENCE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)

#### Required Wake County Basin Removal Sequence

- I. Schedule a site meeting with the Environmental Consultant to determine if a basin can be removed. Install silt fencing or other temporary erosion control measures as needed prior to removal of the basin.
- 2. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be extended, perform this operation at this time. Fine grade area in preparation for seeding.
- 3. Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas
- 4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan.
- 5. When site is fully stabilized, call Environmental Consultant for approval of removing remaining temporary erosion control measures and advice on when site can be issued a Certificate of Completion. Note: A meeting should also be scheduled with the Environmental Consultant to determine when a basin may be converted for stormwater use. Some municipalities may also require this.

### ATTENTION CONTRACTORS

extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public* Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this

Failure to call for Inspection, Install a Downstream **Plug**, have **Permitted Plans** on the **Jobsite**, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the City of Raleigh.

SCALE 1"=50'

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




09/17/2021 DRAWN BY A. BROWN **DESIGNED BY** 

P. BARBEAU CHECKED BY

P. BARBEAU

AS SHOWN

JOB NO. 43398



NUMBER	DESCRIPTION
	LIMITS OF DISTURBANCE
EC102	SILT FENCE; REFER TO DETAIL (TYP).
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
EC106	TREE FENCE. REFER TO DETAIL (TYP.)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
20107	PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN
	SUMMARY ON SHEET C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
EC109	TEMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHEE C4.1)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #4
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN
	SUMMARY ON SHEET C4.1) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
EC112	TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHEE
	C4.1) TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHEET
EC113	C4.1)
	TEMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHEET
EC114	C4.1)
EC115	TEMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHEET
	C4.1) SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.1 (TYP.)
EC116 EC117	TEMP. DIVERSION DITCH #1A (REFER TO C4.1)
EC118	TEMP. DIVERSION DITCH #18 (REFER TO C4.1)
EC119	TEMP. DIVERSION DITCH #2A (REFER TO C4.1)
EC120	TEMP. DIVERSION DITCH #2B (REFER TO C4.1)
EC121	TEMP. DIVERSION DITCH #3A (REFER TO C4.1)
EC122	TEMP. DIVERSION DITCH #3B (REFER TO C4.1)
EC123	TEMP. DIVERSION DITCH #4A (REFER TO C4.1)
EC124	TEMP. DIVERSION DITCH #4B (REFER TO C4.1)
EC125	TEMP. DIVERSION DITCH #5A (REFER TO C4.1)
EC126	TEMP. DIVERSION DITCH #5B (REFER TO C4.1)
EC127	TEMP. DIVERSION DITCH #6A (REFER TO C4.1)
EC128	TEMP. DIVERSION DITCH #6B (REFER TO C4.1)
EC129	TEMP. DIVERSION DITCH #7A (REFER TO C4.1)
EC130	TEMP. DIVERSION DITCH #7B (REFER TO C4.1)
EC131	TEMP. DIVERSION DITCH #8A (REFER TO C4.1)
EC132	TEMP. DIVERSION DITCH #8B (REFER TO C4.1)
EC133	TEMP. DIVERSION DITCH #9A (REFER TO C4.1)
EC134	TEMP. DIVERSION DITCH #9B (REFER TO C4.1)
EC135	ROCK CHECK DAM REFER TO DETAIL (TYP.)
EC136	POROUS BAFFLES (TYP.)
EC137	SILT BAG AND SILT BAG PAD
EC138	IMPERMEABLE MEMBRANE APRON
EC139	3:1 SIDE SLOPE
EC140	STOCKPILE AREA
EC141	CONCRETE WASHOUT
EC142	TEMPORARY CLASS III 18" RCP PIPE FOR DITCH CROSSING
EC143	TEMPORARY HORSESHOE INLET PROTECTION
EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.1)
	DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.1 AND STORM
	PLAN FOR DETAILS)
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING
EC147	ROCK CHECK DAM WITH WEIR (REFER TO STREAM CROSSING PLAN)
	SILT FENCE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)

**EROSION CONTROL PLAN-STAGE 1 KEYNOTES** 

## STAGE I WAKE COUNTY EROSION CONTROL SEQUENCE

1. SCHEDULE A PRECONSTRUCTION CONFERENCE WITH THE ENVIRONMENTAL CONSULTANT

- KARYN PAGEAU, 919-796-8769. OBTAIN A LAND DISTURBING PERMIT. 2. CONTRACTOR SHALL OBTAIN AND READ ALL PERMITS NECESSARY TO COMPLETE THE
- PROJECT, INCLUDING BUT NOT LIMITED TO LAND DISTURBANCE PERMIT.
- ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS, BERMS AND BASINS IMMEDIATELY AFTER CONSTRUCTION. 4. INSTALL SEDIMENT SKIMMER BASINS. IN BASINS 1, 2, 4, AND 5 INSTALL PERMANENT RISER AND
- OUTFALL WITH TEMPORARY SKIMMER BASIN. PROMPTLY SEED/STABILIZE ALL SLOPES. SEE DETAILS. INSTALL RISER AND CONNECT SKIMMER TO RISER. EMBANKMENTS TO BE CONSTRUCTED AND TESTED AS PERMANENT STRUCTURES PER THE STORMWATER DETAILS
- 5. PROMPTLY STABILIZE ALL 3:1 SLOPES OR GREATER AROUND BASINS AND DOWN-SLOPE OF DISTURBANCE ACTIVITY. SEED/USE EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILAR PRODUCT RATED FOR STEEP SLOPES.
- 6. INSTALL TEMPORARY DIVERSION BERM/DITCHES WITH SEED & LINER. INSTALL ALL REMAINING EROSION CONTROL MEASURES PER THIS PLAN.
- 7. CALL 919.796.8769 FOR AN ONSITE INSPECTION BY THE WAKE COUNTY WATERSHED MANAGER
- & OBTAIN CERTIFICATE OF COMPLIANCE.
- 8. BEGIN CLEARING AND GRUBBING AND ROUGH SITE GRADING. MAINTAIN DEVICES AS NEEDED.
- 9. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL EROSION CONTROL MEASURES THROUGHOUT CONSTRUCTION. ALL EROSION CONTROL DEVICES SHOULD BE INSPECTED AFTER EACH RAINFALL EVENT, AND ON A WEEKLY BASIS, AND REFURBISHED IMMEDIATELY, DO NOT REMOVE SKIMMER BASINS NOR OTHER MEASURES UNTIL INSTRUCTED TO DO SO. SKIMMER BASINS TO REMAIN THROUGHOUT CONSTRUCTION.

### TEMPORARY STOCKPILE NOTES

- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC.
- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING
- AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.

5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

SCALE 1"=50'

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

SHEET NO.

C4.4

09/17/2021

DRAWN BY


A. BROWN

DESIGNED BY

P. BARBEAU

CHECKED BY . BARBEAL

AS SHOWN



9. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL EROSION CONTROL MEASURES

10. PROCEED TO STAGE 2 EROSION CONTROL PLANS / SEQUENCE FOR CONTINUATION.

SKIMMER BASINS TO REMAIN THROUGHOUT CONSTRUCTION.

SKIMMER

TEMPORARY SLOPE DRAIN (TSD)

TEMPORARY DIVERSION BERM

ROLLED EROSION CONTROL FABRIC

TEMPORARY TIMBER MAT

beginning construction, will result in the issuance of

or sewer facilities not inspected as a result of this

monetary fines, and require reinstallation of any water

Failure to call for Inspection, Install a Downstream

other Violation of City of Raleigh Standards will result

in a *Fine and Possible Exclusion* from future work in

the City of Raleigh.

*Plug*, have *Permitted Plans* on the *Jobsite*, or any

THROUGHOUT CONSTRUCTION. ALL EROSION CONTROL DEVICES SHOULD BE INSPECTED

AFTER EACH RAINFALL EVENT, AND ON A WEEKLY BASIS, AND REFURBISHED IMMEDIATELY,

DO NOT REMOVE SKIMMER BASINS NOR OTHER MEASURES UNTIL INSTRUCTED TO DO SO.

STABILIZATION REQUIREMENTS FOUND ON THIS SHEET.

11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM.

CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE.

PEDESTRIAN TRAFFIC AREAS.

13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.

10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING

12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR

THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF

NUMBER	DESCRIPTION
EC101	LIMITS OF DISTURBANCE
EC102	SILT FENCE; REFER TO DETAIL (TYP).
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
EC106	TREE FENCE. REFER TO DETAIL (TYP.)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1
EC107	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2
EC108	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
EC 106	PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN
	SUMMARY ON SHEET C4.1) TEMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHE
EC109	C4.1)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #4
EC110	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
ECTTO	PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5
EC111	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN
	SUMMARY ON SHEET C4.1)
	TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHE
EC112	C4.1)
EC113	TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHE
	C4.1)
EC114	TEMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHE C4.1)
	TEMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHE
EC115	C4.1)
EC116	SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.1 (TYP.)
EC117	TEMP. DIVERSION DITCH #1A (REFER TO C4.1)
EC118	TEMP. DIVERSION DITCH #1B (REFER TO C4.1)
EC119	TEMP. DIVERSION DITCH #2A (REFER TO C4.1)
EC120	TEMP. DIVERSION DITCH #2B (REFER TO C4.1)
EC121	TEMP. DIVERSION DITCH #3A (REFER TO C4.1)
EC122	TEMP. DIVERSION DITCH #3B (REFER TO C4.1)
EC122	TEMP. DIVERSION DITCH #4A (REFER TO C4.1)
EC123	TEMP. DIVERSION DITCH #4B (REFER TO C4.1)
EC124 EC125	TEMP. DIVERSION DITCH #5A (REFER TO C4.1)
EC125 EC126	TEMP. DIVERSION DITCH #5B (REFER TO C4.1)
	TEMP. DIVERSION DITCH #6A (REFER TO C4.1)
EC127	,
EC128	TEMP. DIVERSION DITCH #6B (REFER TO C4.1)
EC129	TEMP. DIVERSION DITCH #7A (REFER TO C4.1)
EC130	TEMP. DIVERSION DITCH #7B (REFER TO C4.1)
EC131	TEMP. DIVERSION DITCH #8A (REFER TO C4.1)
EC132	TEMP. DIVERSION DITCH #8B (REFER TO C4.1)
EC133	TEMP. DIVERSION DITCH #9A (REFER TO C4.1)
EC134	TEMP. DIVERSION DITCH #9B (REFER TO C4.1)
EC135	ROCK CHECK DAM REFER TO DETAIL (TYP.)
EC136	POROUS BAFFLES (TYP.)
EC137	SILT BAG AND SILT BAG PAD
EC138	IMPERMEABLE MEMBRANE APRON
EC139	3:1 SIDE SLOPE
EC140	STOCKPILE AREA
EC141	CONCRETE WASHOUT
EC142	TEMPORARY CLASS III 18" RCP PIPE FOR DITCH CROSSING
EC143	TEMPORARY HORSESHOE INLET PROTECTION
EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.1)
EC145	DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.1 AND STORM
	PLAN FOR DETAILS)
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING
EC147	ROCK CHECK DAM WITH WEIR (REFER TO STREAM CROSSING PLAN)
	SILT FENCE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)

- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH
- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.
- 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

#### MAINTENANCE PLAN:

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS
- 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A
- 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE GROWTH.
- 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE
- REQUIREMENTS.

SCALE 1"=50'


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

09/17/2021 A. BROWN

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN



**Required Wake County Basin Removal Sequence** 

to removal of the basin.

construction.

notification failure.

the City of Raleigh.

. Schedule a site meeting with the Environmental Consultant to determine if a basin can be

removed. Install silt fencing or other temporary erosion control measures as needed prior

. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be

. Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas

. When site is fully stabilized, call Environmental Consultant for approval of removing remaining temporary erosion control measures and advice on when site can be issued a

Certificate of Completion. Note: A meeting should also be scheduled with the

use. Some municipalities may also require this.

**ATTENTION CONTRACTORS** 

extension of water, sewer, and/or reuse, as approved in

these plans, is responsible for  $\emph{contacting}$  the  $\emph{Public}$ 

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water

or sewer facilities not inspected as a result of this

Failure to call for Inspection, Install a Downstream

other Violation of City of Raleigh Standards will result

in a *Fine and Possible Exclusion* from future work in

**Plug**, have **Permitted Plans** on the **Jobsite**, or any

Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their

he Construction Contractor responsible for the

4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan.

Environmental Consultant to determine when a basin may be converted for stormwater

extended, perform this operation at this time. Fine grade area in preparation for seeding.

Check Dam with a Weir: STAGE I STREAM CROSSING 1 EROSION CONTROL SEQUENCE 1. ONCE PROPER 401/404 BUFFER AUTHORIZATIONS AND ALL OTHER NECESSARY PERMITS ARE OBTAINED BEGIN STREAM CROSSING PROCESS. 2. OPERATION AND CONSTRUCTION FOR STREAM CROSSINGS SHOULD BE PERFORMED IN A DRY WEATHER PATTERN OF AT LEAST 3-5 DAYS AND SHOULD NOT BEGIN UNTIL ALL NECESSARY Q10 CONSTRUCTION MATERIALS ARE LOCATED ON THE SITE. Storage Required 3. SILT FENCE MUST BE INSTALLED ALONG STREAM BANKS AT THE END OF THE WORK DAY TO MINIMIZE IMPACTS. Weir Length 4. INSTALL CHECK DAM WITH WEIR AT EXISTING GRADES. Check Dam with a Weir: 5. INSTALL THE IMPERVIOUS DIKES (SAND BAGS, SHEET PILING, OR NO. 57 STONE WITH POLYPROPYLENE FOR WIDTH AND DEPTH OF CHANNEL. SET UP AND BEGIN BYPASS PUMPING OF EXISTING FLOW PER THE DETAIL. 6. IF A TEMPORARY CROSSING IS REQUIRED, UTILIZE TIMBER MAT. 6.1. STONE APPROACHES WILL BE REQUIRED ON BOTH SIDES AND THE BOARDS WILL HAVE

NO GAPS. GEOTEXTILE SHALL BE UNDERLAIN OR OVERLAIN AND SIDE BOARDS WILL BE

SPECIFICATIONS WITHIN THIS PLAN SET. INFORM THE ENGINEER IF FIELD CONDITIONS DIFFER

BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILAR PRODUCT RATED FOR STEEP

7. INSTALL CULVERT PIPES AND HEADWALLS PER THE STORMWATER AND GRADING SHEETS AND

10. BRING PERMANENT CROSSING TO GRADE AND PROMPTLY STABILIZE ALL 3:1 SLOPES OR

GREATER DOWN-SLOPE OF DISTURBANCE ACTIVITY. SEED/USE EROSION CONTROL

11. ADJUST TEMPORARY DIVERSION DITCHES IN PROXIMITY AS NECESSARY TO MAINTAIN

12. PROCEED TO STREAM CROSSING 2 OR OTHER SITE IMPROVEMENTS PER THE PLANS.

INSTALLED ALONG THE PERIMETER OF THE MAT.

POSITIVE DRAINAGE TO SEDIMENT BASINS.

DB 9828, PG 902

BM 1998. PG 1776

PIN'1767-58-6083

FROM THE PLANS TO AN EXTENT REQUIRING ANY MODIFICATIONS.

0.3 7.2 in/hr A 0.037 AC 0.08 CFS Q=C\*I\*A 133.2 CF Volume = A\*3600 0.09 FT (Q cfs / 0.88) # 2 0.3 7.2 in/hr 0.060 AC Q10 0.13 CFS Q=C\*I\*A Volume = A\*3600 216 CF Storage Required 0.15 FT (Q cfs / 0.88)

1. CHECK DAMS WITH A WEIR TO SERVE AS SEDIMENT STORAGE FOR STREAM CROSSINGS AS NEEDED. CHECK AND REMOVE SEDIMENT AS REQUIRED.

**GENERAL NOTES** 1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE.

2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE ARCHITECT. 3. THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND

FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM ALL ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE OWNER RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.

5. CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT NO. NCG010000. 6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING PERMIT AND

INSTALLATION OF EROSION CONTROL. 7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.

8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE CONSTRUCTION OF THE PROJECT. 9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT

10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING

PEDESTRIAN TRAFFIC AREAS.

STABILIZATION REQUIREMENTS FOUND ON THIS SHEET.

11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM. 12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE.

13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.

NUMBER	DESCRIPTION
EC101	LIMITS OF DISTURBANCE
EC102	SILT FENCE; REFER TO DETAIL (TYP).
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
EC106	TREE FENCE. REFER TO DETAIL (TYP.)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1
EC107	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
EC 107	PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN
	SUMMARY ON SHEET C4.01)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2 EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
EC108	PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN
	SUMMARY ON SHEET C4.01)
E0400	TEMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHEE
EC109	C4.01)
	PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #4
EC110	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
_0	PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN
	SUMMARY ON SHEET C4.01) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5
	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
EC111	PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN
	SUMMARY ON SHEET C4.01)
EC112	TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHEE
EC112	C4.01)
EC113	TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHEE
	C4.01) TEMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHEE
EC114	C4.01)
	TEMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHEE
EC115	C4.01)
EC116	SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.01 (TYP.)
EC117	TEMP. DIVERSION DITCH #1A (REFER TO C4.01)
EC118	TEMP. DIVERSION DITCH #1B (REFER TO C4.01)
EC119	TEMP. DIVERSION DITCH #2A (REFER TO C4.01)
EC120	TEMP. DIVERSION DITCH #2B (REFER TO C4.01)
EC121	TEMP. DIVERSION DITCH #3A (REFER TO C4.01)
EC122	TEMP. DIVERSION DITCH #3B (REFER TO C4.01)
EC123	TEMP. DIVERSION DITCH #4A (REFER TO C4.01)
EC124	TEMP. DIVERSION DITCH #4B (REFER TO C4.01)
EC125	TEMP. DIVERSION DITCH #5A (REFER TO C4.01)
	TEMP. DIVERSION DITCH #5B (REFER TO C4.01)
EC126	,
EC127	TEMP. DIVERSION DITCH #6A (REFER TO C4.01)
EC128	TEMP. DIVERSION DITCH #6B (REFER TO C4.01)
EC129	TEMP. DIVERSION DITCH #7A (REFER TO C4.01)
EC130	TEMP. DIVERSION DITCH #7B (REFER TO C4.01)
EC131	TEMP. DIVERSION DITCH #8A (REFER TO C4.01)
EC132	TEMP. DIVERSION DITCH #8B (REFER TO C4.01)
EC133	TEMP. DIVERSION DITCH #9A (REFER TO C4.01)
EC134	TEMP. DIVERSION DITCH #9B (REFER TO C4.01)
EC135	ROCK CHECK DAM REFER TO DETAIL (TYP.)
EC136	POROUS BAFFLES (TYP.)
EC137	SILT BAG AND SILT BAG PAD
EC138	IMPERMEABLE MEMBRANE APRON
EC139	3:1 SIDE SLOPE
EC140	STOCKPILE AREA
EC141	CONCRETE WASHOUT
EC142	TEMPORARY CLASS 3 18" RCP PIPE FOR DITCH CROSSING
EC143	TEMPORARY HORSESHOE INLET PROTECTION
EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.01)
F0445	DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.01 AND STORM
EC145	PLAN FOR DETAILS)
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING
EC147	ROCK CHECK DAM WITH WEIR (REFER TO DETAIL)
EC148	TIMBER MAT
=0110	OUT TENOS OUT ET MITH THOOKS (TVD AT OTDEAM ODOSSINOS)

**EROSION CONTROL PLAN-STAGE 1 KEYNOTES** 

#### TEMPORARY STOCKPILE NOTES


- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC.

SILT FENCE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)


- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT STOCKPILE.
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.
- 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

#### MAINTENANCE PLAN:

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS
- 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A BARRIER.
- 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE GROWTH.
- 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS
- NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE REQUIREMENTS.



ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




50' RIPARIAN BUF (MEASURED 50' FF NEW DIVERSION DITCH TOP OF BANK, EA **LOCATION AFTER** / SIDE) ROUGH GRADING NEW DIVERSION DITCH LOCATION AFTER ROUGH GRADING TEMPORARY WATER DIVERSION FOR PERMANENT CULVERT AND DRIVEWAY CONSTRUCTION. REFER TO BYPASS PUMPING GINY A. WHEELER ANDIHUSBAND STEPHEN E. WHÈELER

09/17/2021 DRAWN BY R. WINGATE

**DESIGNED BY** P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN



STA	GE I STREAM CROSSING 2 EROSION CONTROL SEQUENCE	Check Dam with a Weir:	# 1	
1.	ONCE PROPER 401/404 BUFFER AUTHORIZATIONS AND ALL OTHER NECESSARY PERMITS ARE OBTAINED BEGIN STREAM CROSSING PROCESS.	C	0.3 7.2 in/hr	
2.	OPERATION AND CONSTRUCTION FOR STREAM CROSSINGS SHOULD BE PERFORMED IN A DRY WEATHER PATTERN OF AT LEAST 3-5 DAYS AND SHOULD NOT BEGIN UNTIL ALL NECESSARY CONSTRUCTION MATERIALS ARE LOCATED ON THE SITE.	A Q10	0.200 AC 0.43 CFS	Q=C*I*A
3.	SILT FENCE MUST BE INSTALLED ALONG STREAM BANKS AT THE END OF THE WORK DAY TO MINIMIZE IMPACTS.	Storage Required Weir Length	720 CF 0.49 FT	Volume = A*3 (Q cfs / 0.88)
4.	INSTALL CHECK DAM WITH WEIR AT EXISTING GRADES.	Check Dam with a Weir:	# 2	
5.	INSTALL THE IMPERVIOUS DIKES (SAND BAGS, SHEET PILING, OR NO. 57 STONE WITH POLYPROPYLENE FOR WIDTH AND DEPTH OF CHANNEL. SET UP AND BEGIN BYPASS PUMPING OF EXISTING FLOW PER THE DETAIL.	C	0.3 7.2 in/hr	
6.	IF A TEMPORARY CROSSING IS REQUIRED, UTILIZE TIMBER MAT.	А	0.220 AC	
6.	1. STONE APPROACHES WILL BE REQUIRED ON BOTH SIDES AND THE BOARDS WILL HAVE NO GAPS. GEOTEXTILE SHALL BE UNDERLAIN OR OVERLAIN AND SIDE BOARDS WILL BE INSTALLED ALONG THE PERIMETER OF THE MAT.	Q10 Storage Required	0.48 CFS 792 CF	Q=C*I*A Volume = A*3
7.	INSTALL CULVERT PIPES AND HEADWALLS PER THE STORMWATER AND GRADING SHEETS AND SPECIFICATIONS WITHIN THIS PLAN SET. INFORM THE ENGINEER IF FIELD CONDITIONS DIFFER FROM THE PLANS TO AN EXTENT REQUIRING ANY MODIFICATIONS.	Weir Length Check Dam with a Weir:	0.54 FT # 3	(Q cfs / 0.88)
10.	BRING PERMANENT CROSSING TO GRADE AND PROMPTLY STABILIZE ALL 3:1 SLOPES OR GREATER DOWN-SLOPE OF DISTURBANCE ACTIVITY. SEED/USE EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILAR PRODUCT RATED FOR STEEP SLOPES.	C   A	0.3 7.2 in/hr 0.060 AC	
11.	ADJUST TEMPORARY DIVERSION DITCHES IN PROXIMITY AS NECESSARY TO MAINTAIN POSITIVE DRAINAGE TO SEDIMENT BASINS.	Q10 Storage Required	0.13 CFS 216 CF	Q=C*I*A Volume = A*3
12.	PROCEED WITH OTHER SITE IMPROVEMENTS PER THE PLANS AND PROCEED TO PHASE 2	Weir Length	0.15 FT	(Q cfs / 0.88)
	EROSION CONTROL WHEN POSSIBLE.	Check Dam with a Weir:	# 4	
		С	0.3	
		1	7.2 in/hr	
		A	0.090 AC	
		010	0.19 CFS	Q=C*I*A

- OPEN

TEMPORARY WATER | EC149

DIVERSION FOR

AND DRIVEWAY

PERMANENT CULVERT 2

CONSTRUCTION. REFER TO

STREAM BYPASS DETAILS

EXISTING

WETLAND\$ -

WATER

/EC144

NOTE:

1. CHECK DAMS WITH **CROSSINGS AS NEI** 

NEW DIVERSION DITCH

LOCÁTION AFTER /

ROUGH GRADING

CROSSING/

Check Dam with a Weir:	# 1	
С	0.3	
1	7.2 in/hr	
А	0.200 AC	
Q10	0.43 CFS	Q=C*I*A
Storage Required	720 CF	Volume = A*3600
Weir Length	0.49 FT	(Q cfs / 0.88)
Check Dam with a Weir:	# 2	
С	0.3	
	7.2 in/hr	
А	0.220 AC	
Q10	0.48 CFS	Q=C*I*A
Storage Required	792 CF	Volume = A*3600
Weir Length	0.54 FT	(Q cfs / 0.88)
Check Dam with a Weir:	# 3	
С	0.3	
1	7.2 in/hr	
А	0.060 AC	
Q10	0.13 CFS	Q=C*I*A
Storage Required	216 CF	Volume = A*3600
Weir Length	0.15 FT	(Q cfs / 0.88)
Check Dam with a Weir:	# 4	
С	0.3	
1	7.2 in/hr	
Α	0.090 AC	
Q10	0.19 CFS	Q=C*I*A
Storage Required	324 CF	Volume = A*3600

**GENERAL NOTES** 

Α	0.200 AC		RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE ARCHITECT.	EC101	LIMITS OF DISTURBANCE
10	0.43 CFS	Q=C*I*A	<ol><li>THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND</li></ol>	EC102	SILT FENCE; REFER TO DETAIL (TYP).
ed	720 CF	Volume = A*3600	FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS.	EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
gth	0.49 FT	(Q cfs / 0.88)	THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM ALL	EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
eir:	# 2		ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE OWNER	EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
С	0.3		RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL	EC106	TREE FENCE. REFER TO DETAIL (TYP.)
ī	7.2 in/hr		COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.		PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #1
A	0.220 AC		<ol><li>CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)</li></ol>	EC107	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
	0.220 AC 0.48 CFS	Q=C*I*A	PERMIT NO. NCG010000.	EC 107	PERMANENT PER SCM DETAILS ON SHEET C8.0 (REFER TO BASIN
10	792 CF	Volume = A*3600	6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING PERMIT AND		SUMMARY ON SHEET C4.01) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #2
ed			INSTALLATION OF EROSION CONTROL.		EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
th	0.54 FT	(Q cfs / 0.88)	7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.	EC108	PERMANENT PER SCM DETAILS ON SHEET C8.1 (REFER TO BASIN
eir:	# 3		8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE CONSTRUCTION OF		SUMMARY ON SHEET C4.01)
С	0.3		THE PROJECT.	EC109	TEMPORARY SKIMMER BASIN #3 (REFER TO BASIN SUMMARY ON SHEET
I	7.2 in/hr		<ol><li>9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT STABILIZATION REQUIREMENTS FOUND ON THIS SHEET.</li></ol>	20100	C4.01) PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #4
Α	0.060 AC		10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING		EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
10	0.13 CFS	Q=C*I*A	PEDESTRIAN TRAFFIC AREAS.	EC110	PERMANENT PER SCM DETAILS ON SHEET C8.3 (REFER TO BASIN
ed	216 CF	Volume = A*3600	11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM.		SUMMARY ON SHEET C4.01)
gth	0.15 FT	(Q cfs / 0.88)	12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR		PERMANENT RISER WITH TEMPORARY SKIMMER BASIN #5
eir:	# 4		THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF	EC111	EMBANKMENT, RISER AND OUTFALL TO BE CONSTRUCTED AS
С	0.3		CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE.		PERMANENT PER SCM DETAILS ON SHEET C8.4 (REFER TO BASIN SUMMARY ON SHEET C4.01)
ı	7.2 in/hr		13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.		TEMPORARY SKIMMER BASIN #6 (REFER TO BASIN SUMMARY ON SHEET
A	0.090 AC			EC112	C4.01)
	0.050 AC 0.19 CFS	Q=C*I*A		EC113	TEMPORARY SKIMMER BASIN #7 (REFER TO BASIN SUMMARY ON SHEET
(10		*		EC113	C4.01)
ed	324 CF	Volume = A*3600		EC114	TEMPORARY SKIMMER BASIN #8 (REFER TO BASIN SUMMARY ON SHEET C4.01)
gth	0.22 FT	(Q cfs / 0.88)			TEMPORARY SKIMMER BASIN #9 (REFER TO BASIN SUMMARY ON SHEET
				EC115	C4.01)
				EC116	SPILLWAY-REFER TO BASIN SUMMARY ON SHEET C4.01 (TYP.)
		AS SEDIMENT STORA		EC117	TEMP. DIVERSION DITCH #1A (REFER TO C4.01)
NEED	ED. CHECK AND	REMOVE SEDIMENT A	S REQUIRED.	EC118	TEMP. DIVERSION DITCH #1B (REFER TO C4.01)
				EC119	TEMP. DIVERSION DITCH #2A (REFER TO C4.01)
				EC120	TEMP. DIVERSION DITCH #2B (REFER TO C4.01)
				EC121	TEMP. DIVERSION DITCH #3A (REFER TO C4.01)
				EC122	TEMP. DIVERSION DITCH #3B (REFER TO C4.01)
				EC123	TEMP. DIVERSION DITCH #4A (REFER TO C4.01)
				EC124	TEMP. DIVERSION DITCH #4B (REFER TO C4.01)
				EC125	TEMP. DIVERSION DITCH #5A (REFER TO C4.01)
				EC126	TEMP. DIVERSION DITCH #5B (REFER TO C4.01)
				EC127	TEMP. DIVERSION DITCH #6A (REFER TO C4.01)
	11 ////	, x	· » 4·	EC128	TEMP. DIVERSION DITCH #6B (REFER TO C4.01)
		- 4 /	136°/	EC129	TEMP. DIVERSION DITCH #7A (REFER TO C4.01)
370	-11 HUC			EC130	TEMP. DIVERSION DITCH #7B (REFER TO C4.01)
	(			EC131	TEMP. DIVERSION DITCH #8A (REFER TO C4.01)
-371-				EC132	TEMP. DIVERSION DITCH #8B (REFER TO C4.01)
				EC133	TEMP. DIVERSION DITCH #9A (REFER TO C4.01)
372-				EC134	TEMP. DIVERSION DITCH #9B (REFER TO C4.01)
/ / / /		1HH		EC135	ROCK CHECK DAM REFER TO DETAIL (TYP.)
				EC136	POROUS BAFFLES (TYP.)
373			EC145	EC137	SILT BAG AND SILT BAG PAD
•				EC138	IMPERMEABLE MEMBRANE APRON
		` /		EC139	3:1 SIDE SLOPE
<i>−374</i>	!				STOCKPILE AREA
			` <u>.</u>	EC140	
9				EC141	CONCRETE WASHOUT
07				EC142	TEMPORARY CLASS 3 18" RCP PIPE FOR DITCH CROSSING
-3/	J			EC143	TEMPORARY HORSESHOE INLET PROTECTION
		<		EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.01)
				EC145	DIVERSION DITCH OUTLET PROTECTION (REFER TO C4.01 AND STORM
\	76-			LC 143	PLAN FOR DETAILS)

1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING

2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH

RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE ARCHITECT.


EROSION CONTROL MEASURES BOTH ON AND OFF-SITE.

- ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH
- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.
- 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

#### MAINTENANCE PLAN:

- FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS DESIGNED.
- INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A
- DENSE VEGETATIVE GROWTH.
- 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS
- NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- REQUIREMENTS.

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS




**EROSION CONTROL PLAN-STAGE 1 KEYNOTES** 

**DESCRIPTION** 

NUMBER

- THE PLASTIC.
- STOCKPILE.

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED
- 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6
- 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS,
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE



1. Schedule a site meeting with the Environmental Consultant to determine if a basin can be removed. Install silt fencing or other temporary erosion control measures as needed prior 2. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be extended, perform this operation at this time. Fine grade area in preparation for seeding. 3. Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas 4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan. 5. When site is fully stabilized, call Environmental Consultant for approval of removing remaining temporary erosion control measures and advice on when site can be issued a Certificate of Completion. Note: A meeting should also be scheduled with the Environmental Consultant to determine when a basin may be converted for stormwater

ATTENTION CONTRACTORS

use. Some municipalities may also require this.

to removal of the basin.

The **Construction Contractor** responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public* Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their construction.

Required Wake County Basin Removal Sequence

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, Install a Downstream *Plug*, have *Permitted Plans* on the *Jobsite*, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the City of Raleigh.

09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN

JOB NO.



## ATTENTION CONTRACTORS

The **Construction Contractor** responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public* Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their

construction.

—C4.1

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, Install a Downstream *Plug*, have *Permitted Plans* on the *Jobsite*, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the *City of Raleigh*.

#### NPDES GROUND STABILIZATION

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE:

- 1. ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES AND SLOPES STEEPER THAN 3:1 SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT WITHIN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.
- 2. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.

#### Required Wake County Basin Removal Sequence

1. Schedule a site meeting with the Environmental Consultant to determine if a basin can be removed. Install silt fencing or other temporary erosion control measures as needed prior to removal of the basin.

- 2. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be extended, perform this operation at this time. Fine grade area in preparation for seeding.


- . When site is fully stabilized, call Environmental Consultant for approval of removing Certificate of Completion. Note: A meeting should also be scheduled with the

- 3. Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas
- 4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan.
- remaining temporary erosion control measures and advice on when site can be issued a Environmental Consultant to determine when a basin may be converted for stormwater use. Some municipalities may also require this.



NUMBER	DESCRIPTION
EC101	LIMITS OF DISTURBANCE
EC102	SILT FENCE; REFER TO DETAIL (TYP).
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)
EC106	TREE FENCE. REFER TO DETAIL (TYP.)
EC136	POROUS BAFFLES (TYP.)
EC137	SILT BAG AND SILT BAG PAD
EC138	IMPERMEABLE MEMBRANE APRON
EC139	3:1 SIDE SLOPE
EC140	STOCKPILE AREA
EC141	CONCRETE WASHOUT
EC142	TEMPORARY CLASS 3 18" RCP PIPE FOR DITCH CROSSING
EC143	TEMPORARY HORSESHOE INLET PROTECTION
EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.1)
EC145	DIVERSION DITCH OUTLET PROTECTION (C3.0 FOR DITCH CHARTS)
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING
EC147	TEMPORARY STORM INLET PROTECTION; REFER TO DETAIL (TYP.)
EC148	GREENWAY BOARDWALK BRIDGE.
EC149	TEMPORARY STREAM BYPASS AND TIMBER MATTING FOR SEWER CROSSING; REFER TO DETAIL (TYP.)
EC150	2:1 SIDE SLOPE (SOD/STABILIZÈ WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILARLY RATED PRODUCT FOR STEEP SLOPES).
EC151	2.5:1 SIDE SLOPE (SOD/STABILÍZE WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN \$150, OR SIMILARLY RATED PRODUCT FOR STEEP SLOPES).
EC152	TEMPORARY INLET PROTECTION; REFER TO DETAIL (TYP.)
EC153	ROCK CHECK DAM WITH WEIR (REFER TO DETAIL)
EC154	TIMBER MAT
FC155	SILT FENCE STONE OUTLET WITH J HOOKS (TYP. AT STREAM

## **EROSION CONTROL LEGEND**



SUBMIT AS-BUILT SURVEY TO OWNER/ENGINEER, AND SEEK COUNTY APPROVAL OF SCMS.

10. INSTALL RIPRAP APRONS OVER FILTER FABRIC. INSTALL PERMANENT SPILLWAY LINER AND SOD.

919.796.8769 FOR AN ONSITE INSPECTION WITH THE WAKE COUNTY WATERSHED MANAGER.

14. IF SITE IS APPROVED, THEN REMOVE TEMPORARY EROSION CONTROL MEASURES INCLUDING

5. WHEN VEGETATION HAS BECOME ESTABLISHED, CALL FOR A FINAL SITE INSPECTION BY THE

WAKE COUNTY ENVIRONMENTAL CONSULTANT KARYN PAGEAU, 919-796-8769. OBTAIN A

STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT

IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE

2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT

1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR

THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A BARRIER.

3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND

MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS, DENSE

4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS NECESSARY TO

5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE SCALE 1"=150"

TEMPORARY DIVERSIONS, SILT FENCE, SKIMMER BASINS, ETC. AND SEED OUT OR STABILIZE ANY

RESULTING BARE AREAS. ALL REMAINING PERMANENT EROSION CONTROL DEVICES, SUCH AS

12. CONTACT ENGINEER TO REQUEST FINAL POND INSPECTION & PE CERTIFICATION OF POND.

13. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CALL

11. REMOVE TEMPORARY SKIMMER. CLOSE RISER DRAIN. UNPLUG ALL RISER ORIFICES.

RIPRAP APRONS OVER FILTER FABRIC SHOULD NOW BE INSTALLED.

IMMEDIATELY TO MAINTAIN ALL MEASURES AS DESIGNED.

SOD BERM & ALL BASIN SLOPES PER DETAILS.

CERTIFICATE OF COMPLETION.

VEGETATIVE GROWTH.

REQUIREMENTS.

MAINTAIN PROPER FUNCTIONING.

MAINTENANCE PLAN:

1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE.

- 2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE 3. THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF
- ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM
- ALL ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE OWNER RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.
- CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT NO. NCG010000.
- 6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING
- PERMIT AND INSTALLATION OF EROSION CONTROL.
- 7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.
- 8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE
- CONSTRUCTION OF THE PROJECT.
- 9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT STABILIZATION REQUIREMENTS FOUND ON THIS SHEET.
- 10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING PEDESTRIAN TRAFFIC AREAS. 11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM UNLESS OTHERWISE NOTED.
- 12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE.
- 13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.

{ 14.FOR UTILITY STREAM CROSSING, DISTURB ONLY THE AREA REQUIRED FOR INSTALLATION. CONSTRUCTION FOR CROSSING TO ONLY BEGIN ONCE ALL NECESSARY MATERIALS ARE ON SITE AND CONDITIONS ARE IN A DRY WEATHER PATTERN OF 3-5 DAYS.

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


09/17/2021 DRAWN BY A. BROWN


**DESIGNED BY** P. BARBEAU CHECKED BY


P. BARBEAU

AS SHOWN

JOB NO.








09/17/2021 A. BROWN DESIGNED BY P. BARBEAU CHECKED BY P. BARBEAU AS SHOWN

JOB NO.



09/06/2023

DRAWN BY A. BROWN DESIGNED BY


P. BARBEAU CHECKED BY P. BARBEAU

SCALE

AS SHOWN

JOB NO. SHEET NO.

C4.12




<b>EROSION CONTROL PLAN-STAGE 2 KEYNOTES</b>								
NUMBER	DESCRIPTION							
EC101	LIMITS OF DISTURBANCE							
EC102	SILT FENCE; REFER TO DETAIL (TYP).							
EC103	SILT FENCE OUTLET; REFERT TO DETAIL (TYP).							
EC104	TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL							
EC105	SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)							
EC106	TREE FENCE. REFER TO DETAIL (TYP.)							
EC136	POROUS BAFFLES (TYP.)							
EC137	SILT BAG AND SILT BAG PAD							
EC138	IMPERMEABLE MEMBRANE APRON							
EC139	3:1 SIDE SLOPE							
EC140	STOCKPILE AREA							
EC141	CONCRETE WASHOUT							
EC142	TEMPORARY CLASS 3 18" RCP PIPE FOR DITCH CROSSING							
EC143	TEMPORARY HORSESHOE INLET PROTECTION							
EC144	PIPE OUTFALL PROTECTION. (REFER TO C4.1)							
EC145	DIVERSION DITCH OUTLET PROTECTION (C3.0 FOR DITCH CHARTS)							
EC146	TEMPORARY PIPE FOR OUTFALL CROSSING							
EC147	TEMPORARY STORM INLET PROTECTION; REFER TO DETAIL (TYP.)							
EC148	GREENWAY BOARDWALK BRIDGE.							
EC149	TEMPORARY STREAM BYPASS AND TIMBER MATTING FOR SEWER CROSSING; REFER TO DETAIL (TYP.)							
EC150	2:1 SIDE SLOPE (SOD/STABILIZÈ WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILARLY RATED PRODUCT FOR STEEP SLOPES).							
EC151	2.5:1 SIDE SLOPE (SOD/STABILÍZE WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILARLY RATED PRODUCT FOR STEEP SLOPES).							
EC152	TEMPORARY INLET PROTECTION; REFER TO DETAIL (TYP.)							
EC153	ROCK CHECK DAM WITH WEIR (REFER TO DETAIL)							
EC154	TIMBER MAT							
EC155	SILT FENCE STONE OUTLET WITH J HOOKS (TYP. AT STREAM CROSSINGS)							

## **GENERAL NOTES**

- 1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. 2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE
- 3. THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES
- AND/OR WASTE AREAS. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM ALL ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE OWNER RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.
- 5. CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT NO. NCG010000.
- 6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING PERMIT AND INSTALLATION OF EROSION CONTROL.
- 7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.
- 8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE
- CONSTRUCTION OF THE PROJECT. 9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT
- 10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING PEDESTRIAN TRAFFIC AREAS.
- 11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM.

STABILIZATION REQUIREMENTS FOUND ON THIS SHEET.

- 12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING
- 13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.



SEWE	R CROSSIN	<u>IG</u>	GREENWAY CROSSING						
heck Dam with a Weir:	# 1		Check Dam with a Weir:	# 1					
С	0.3		С	0.3					
1	7.2 in/hr		I	7.2 in/hr					
Α	0.030 AC		А	0.147 AC					
Q10	0.06 CFS	Q=C*I*A	Q10	0.32 CFS	Q=C*I*A				
Storage Required	108 CF	Volume = A*3600	Storage Required	529.2 CF	Volume = A*3600				
Weir Length	0.07 FT	(Q cfs / 0.88)	Weir Length	0.36 FT	(Q cfs / 0.88)				
heck Dam with a Weir:	# 2		Check Dam with a Weir:	# 2					
С	0.3		С	0.3					
1	7.2 in/hr		I	7.2 in/hr					
Α	0.284 AC		А	0.097 AC					
Q10	0.61 CFS	Q=C*I*A	Q10	0.21 CFS	Q=C*I*A				
Storage Required	1022.4 CF	Volume = A*3600	Storage Required	349.2 CF	Volume = A*3600				
Weir Length	0.70 FT	(Q cfs / 0.88)	Weir Length	0.24 FT	(Q cfs / 0.88)				
heck Dam with a Weir:	# 3		Check Dam with a Weir:	# 3					
С	0.3		С	0.3					
1	7.2 in/hr		1	7.2 in/hr					
А	0.030 AC		А	0.050 AC					
Q10	0.06 CFS	Q=C*I*A	Q10	0.11 CFS	Q=C*I*A				
Storage Required	108 CF	Volume = A*3600	Storage Required	180 CF	Volume = A*3600				
Weir Length	0.07 FT	(Q cfs / 0.88)	Weir Length	0.12 FT	(Q cfs / 0.88)				
heck Dam with a Weir:	# 4								

1. CHECK DAMS WITH A WEIR TO SERVE AS SEDIMENT STORAGE FOR STREAM CROSSINGS AS NEEDED. CHECK AND REMOVE SEDIMENT AS REQUIRED.

#### NPDES GROUND STABILIZATION

0.11 FT

0.3

A 0.046 AC

Storage Required 165.6 CF

Weir Length

7.2 in/hr

0.10 CFS Q=C\*I\*A

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE:

Volume = A\*3600

(Q cfs / 0.88)

- 1. ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES AND SLOPES STEEPER THAN 3:1 SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT WITHIN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.
- 2. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.

### TEMPORARY STOCKPILE NOTES

STOCKPILE.

- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH
- THE PLASTIC. 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.
- 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

#### STAGE 2 STREAM CROSSING EROSION CONTROL SEQUENCE ONCE PROPER 401/404 BUFFER AUTHORIZATIONS AND ALL OTHER NECESSARY PERMITS OBTAINED BEGIN STREAM CROSSING PROCESS AS NECESSARY FOR FORCE MAIN

- CONSTRUCTION. 2. OPERATION AND CONSTRUCTION FOR STREAM CROSSINGS SHOULD BE PERFORMED IN A DRY WEATHER PATTERN OF AT LEAST 3-5 DAYS AND SHOULD NOT BEGIN UNTIL ALL NECESSARY CONSTRUCTION MATERIALS ARE LOCATED ON AT THE SITE.
- 3. SILT FENCE MUST BE INSTALLED ALONG STREAM BANKS AT THE END OF THE WORK DAY TO
- INSTALL CHECK DAM WITH WEIR AT EXISTING GRADES PER SIZING ON THIS SHEET FOR
- SEDIMENT STORAGE. 5. INSTALL THE IMPERVIOUS DIKES (SAND BAGS, SHEET PILING, OR NO. 57 STONE WITH POLYPROPYLENE FOR WIDTH AND DEPTH OF CHANNEL. SET UP AND BEGIN BYPASS PUMPING OF EXISTING FLOW PER THE DETAIL.
- 6. IF A TEMPORARY CROSSING IS REQUIRED, UTILIZE TIMBER MAT.
- 6.1. STONE APPROACHES WILL BE REQUIRED ON BOTH SIDES AND THE BOARDS WILL HAVE NO GAPS. GEOTEXTILE SHALL BE UNDERLAIN OR OVERLAIN AND SIDE BOARDS WILL BE INSTALLED ALONG THE PERIMETER OF THE MAT.
- 7. INSTALL SEWER MAIN PIPES PER THE UTILITY DESIGN AND SPECIFICATIONS WITHIN THIS PLAN SET. INFORM THE ENGINEER IF FIELD CONDITIONS DIFFER FROM THE PLANS TO AN EXTENT REQUIRING MODIFICATIONS. OR CONSTRUCT GREENWAY BOARDWALK PER PLANS.
- 10. BACKFILL TRENCHING OR BRING CROSSING TO GRADE, RETURN IMPACTED AREAS TO PRE-EXISTING GRADES AND PROMPTLY STABILIZE AREAS. MAINTENANCE PLAN:
- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS DESIGNED.
- 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A BARRIER.
- 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE GROWTH.
- 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE REQUIREMENTS.

#### ATTENTION CONTRACTORS

The **Construction Contractor** responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public* Utilities Department at (919) 996-4540 at least twenty four hours prior to beginning any of their

Failure to notify both City Departments in advance of beginning construction, will result in the issuance of *monetary fines*, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, Install a Downstream *Plug*, have *Permitted Plans* on the *Jobsite*, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the *City of Raleigh*.

SCALE 1"=50'

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS



09/17/2021 DRAWN BY R. WINGATE **DESIGNED BY** 


P. BARBEAU CHECKED BY

P. BARBEAU

AS SHOWN

43398 SHEET NO.

C4.13



			·			<u></u>			<del></del>		
Check Dam with a Weir:	# 1		Check Dam with a Weir:	# 2		Check Dam with a Weir:	# 3		Check Dam with a Weir:	# 4	
С	0.3		С	0.3		С	0.3		С	0.3	
I	7.2 in/hr			7.2 in/hr		I	7.2 in/hr		l	7.2 in/hr	
A	0.100 AC		А	0.130 AC		А	0.140 AC		A	0.024 AC	
Q10	0.22 CFS	Q=C*I*A	Q10	0.28 CFS	Q=C*I*A	Q10	0.30 CFS	Q=C*I*A	Q10	0.05 CFS	Q=C*I*A
Storage Required	360 CF	Volume = A*3600	Storage Required	468 CF	Volume = A*3600	Storage Required	504 CF	Volume = A*3600	Storage Required	86.4 CF	Volume = A*3600
Weir Length	0.25 FT	(Q cfs / 0.88)	Weir Length	0.32 FT	(Q cfs / 0.88)	Weir Length	0.34 FT	(Q cfs / 0.88)	Weir Length	0.06 FT	(Q cfs / 0.88)
Check Dam with a Weir:	# 5		Check Dam with a Weir:	# 6		Check Dam with a Weir:	# 7		Check Dam with a Weir:	# 8	
С	0.3		С	0.3		С	0.3		С	0.3	
I	7.2 in/hr			7.2 in/hr		1	7.2 in/hr		1	7.2 in/hr	
A	0.070 AC		А	0.029 AC		А	0.093 AC		А	0.028 AC	
Q10	0.15 CFS	Q=C*I*A	Q10	0.06 CFS	Q=C*I*A	Q10	0.20 CFS	Q=C*I*A	Q10	0.06 CFS	Q=C*I*A
Storage Required	252 CF	Volume = A*3600	Storage Required	104.4 CF	Volume = A*3600	Storage Required	334.8 CF	Volume = A*3600	Storage Required	100.8 CF	Volume = A*3600
Weir Length	0.17 FT	(Q cfs / 0.88)	Weir Length	0.07 FT	(Q cfs / 0.88)	Weir Length	0.23 FT	(Q cfs / 0.88)	Weir Length	0.07 FT	(Q cfs / 0.88)

1. CHECK DAMS WITH A WEIR TO SERVE AS SEDIMENT STORAGE FOR STREAM CROSSINGS AS NEEDED. CHECK AND REMOVE SEDIMENT AS REQUIRED.

#### GENERAL NOTES

- 1. THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. 2. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AFTER EACH RAINFALL EVENT OR AS DIRECTED BY LOCAL AUTHORITIES OR THE
- 3. THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEARING AND GRADING WASTE MATERIALS GENERATED DURING THIS PHASE OF WORK AND FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY TRACKED SOIL FROM ALL ADJACENT ROADWAYS THAT ARE IMPACTED BY CONSTRUCTION TRAFFIC. THE
- OWNER RESERVES THE RIGHT TO REQUIRE THAT A WASH STATION BE INSTALLED AT NO ADDITIONAL COST IF PAVEMENT AREAS ARE NOT KEPT CLEAN.
- 5. CONTRACTOR SHALL ABIDE BY ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT NO. NCG010000.
- 6. A PRECONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO WORK, GRADING PERMIT AND INSTALLATION OF EROSION CONTROL.
- 7. UTILITY LOCATIONS ARE TO BE FOUND BY CALLING NC ONE CALL.
- 8. ALL TEMPORARY MEASURES SHALL BE REMOVED AT THE END OF THE CONSTRUCTION OF THE PROJECT.
- 9. CUT AND FILL SLOPES SHALL BE STABILIZED AS REQUIRED BY THE GENERAL PERMIT
- STABILIZATION REQUIREMENTS FOUND ON THIS SHEET. 10. SILT FENCING SHALL BE INSTALLED AROUND THE PERIMETER SEPARATING EXISTING
- PEDESTRIAN TRAFFIC AREAS.
- 11. ALL CUT AND FILL SLOPES ARE TO BE AT A 3:1 MAXIMUM.
- 12. THERE SHALL BE NO SOIL DISTURBANCE OR RECOMPACTION WITHIN AREAS DESIGNATED FOR THE TREE PRESERVATION AND PROTECTION FENCING. INCLUDING NO STOCKPILING OF CONSTRUCTION OR OTHER MATERIAL, TRAFFIC, OR BORING SAMPLE.
- 13. STOCKPILE HEIGHT SHALL NOT EXCEED 35'.

#### MAINTENANCE PLAN: 1. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED FOR

- STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL MEASURES AS DESIGNED.
- 2. REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN DEPTH REACHES 6 INCHES AT THE FENCE. REPAIR SILT FENCE AS NECESSARY TO MAINTAIN A BARRIER. 3. ALL SEEDED AREAS SHALL BE FERTILIZED, RE--SEEDED AS NECESSARY, AND MULCHED ACCORDING TO PROJECT SPECS TO MAINTAIN A VIGOROUS, DENSE
- VEGETATIVE GROWTH. 4. TOP DRESS CONSTRUCTION ENTRANCES WITH CLEAN STONE AS NECESSARY TO MAINTAIN PROPER FUNCTIONING.
- 5. REFER TO SPECIFIC DEVICE DETAILS FOR ADDITIONAL MAINTENANCE REQUIREMENTS.

#### STAGE II WAKE COUNTY EROSION CONTROL SEQUENCE- FORCE MAIN ALL STAGE 1 EROSION CONTROL MEASURES MUST BE IN PLACE BEFORE BEGINNING STAGE 2.

- REFER TO STAGE 1 EROSION CONTROL PLAN SHEETS. REFURBISH ALL STAGE 1 EROSION CONTROL MEASURES AS NEEDED BEFORE PROCEEDING WITH STAGE 2.
- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL EROSION CONTROL MEASURES THROUGHOUT CONSTRUCTION. ALL EROSION CONTROL DEVICES SHOULD BE INSPECTED AFTER EACH RAINFALL EVENT, AND ON A WEEKLY BASIS, AND REFURBISHED IMMEDIATELY. DO NOT REMOVE SKIMMER BASINS NOR OTHER MEASURES UNTIL INSTRUCTED TO DO SO. SKIMMER BASINS TO REMAIN THROUGHOUT CONSTRUCTION.
- CLEAR & GRUB THE SITE. MAINTAIN DEVICES AS NEEDED. ROUGH GRADE THE SITE. AT THE END
- OF EACH WORKDAY OF GRADING, ALL TEMPORARY DIVERSION DITCHES/BERMS SHALL BE REFURBISHED AS NEEDED TO MAINTAIN DRAINAGE PATTERNS TO BASINS. STABILIZE THE SITE AS AREAS ARE BROUGHT UP TO FINISHED GRADE WITH VEGETATION,
- PAVING, DITCH LININGS, ETC. SEED AND MULCH DENUDED AREAS PER GROUND STABILIZATION EARTH EXCAVATED FOR SEWER TRENCHING SHOULD BE WITHIN THE LIMITS OF SILT FENCE. ANY
- WATER PUMPED FROM EXCAVATED TRENCH SHOULD BE FILTERED THROUGH A SILT BAG PRIOR TO DISCHARGING. PROPERLY DISPOSE OF ANY ACCUMULATED SEDIMENT AS NECESSARY.
- REFER TO STAGE 2 STREAM CROSSING EROSION CONTROL SEQUENCE. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CALL
- 919.796.8769 FOR AN ONSITE INSPECTION WITH THE WAKE COUNTY WATERSHED MANAGER. 8. IF SITE IS APPROVED, THEN REMOVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY DIVERSIONS, SILT FENCE, SKIMMER BASINS, ETC. AND SEED OUT OR STABILIZE ANY
- RESULTING BARE AREAS. ALL REMAINING PERMANENT EROSION CONTROL DEVICES, SUCH AS RIPRAP APRONS OVER FILTER FABRIC SHOULD NOW BE INSTALLED. WHEN VEGETATION HAS BECOME ESTABLISHED, CALL FOR A FINAL SITE INSPECTION BY THE WAKE COUNTY ENVIRONMENTAL CONSULTANT KARYN PAGEAU, 919.796.8769. OBTAIN A

# CERTIFICATE OF COMPLETION.

#### ATTENTION CONTRACTORS

The **Construction Contractor** responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for *contacting* the *Public* **Utilities Department** at **(919) 996-4540** at least twenty four hours prior to beginning any of their

**Failure** to notify both **City Departments** in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, Install a Downstream *Plug*, have *Permitted Plans* on the *Jobsite*, or any other Violation of City of Raleigh Standards will result in a *Fine and Possible Exclusion* from future work in the City of Raleigh.

- STAGE 2 STREAM CROSSING EROSION CONTROL SEQUENCE 1. ONCE PROPER 401/404 BUFFER AUTHORIZATIONS AND ALL OTHER NECESSARY PERMITS OBTAINED BEGIN STREAM CROSSING PROCESS AS NECESSARY FOR FORCE MAIN
- CONSTRUCTION. 2. OPERATION AND CONSTRUCTION FOR STREAM CROSSINGS SHOULD BE PERFORMED IN A DRY WEATHER PATTERN OF AT LEAST 3-5 DAYS AND SHOULD NOT BEGIN UNTIL ALL NECESSARY
- CONSTRUCTION MATERIALS ARE LOCATED ON AT THE SITE. 3. SILT FENCE MUST BE INSTALLED ALONG STREAM BANKS AT THE END OF THE WORK DAY TO MINIMIZE IMPACTS.
- 4. INSTALL CHECK DAM WITH WEIR AT EXISTING GRADES PER SIZING ON THIS SHEET FOR SEDIMENT STORAGE.
- 5. INSTALL THE IMPERVIOUS DIKES (SAND BAGS, SHEET PILING, OR NO. 57 STONE WITH POLYPROPYLENE FOR WIDTH AND DEPTH OF CHANNEL. SET UP AND BEGIN BYPASS PUMPING OF EXISTING FLOW PER THE DETAIL.
- 6. IF A TEMPORARY CROSSING IS REQUIRED, UTILIZE TIMBER MAT.
- 6.1. STONE APPROACHES WILL BE REQUIRED ON BOTH SIDES AND THE BOARDS WILL HAVE NO GAPS. GEOTEXTILE SHALL BE UNDERLAIN OR OVERLAIN AND SIDE BOARDS WILL BE INSTALLED ALONG THE PERIMETER OF THE MAT.
- 7. INSTALL FORCE MAIN PIPES PER THE UTILITY DESIGN AND SPECIFICATIONS WITHIN THIS PLAN SET. INFORM THE ENGINEER IF FIELD CONDITIONS DIFFER FROM THE PLANS TO AN EXTENT REQUIRING MODIFICATIONS.
- 10. BACKFILL TRENCHING, RETURN IMPACTED AREAS TO PRE-EXISTING GRADES AND PROMPTLY STABILIZE AREAS.


#### TEMPORARY STOCKPILE NOTES

- 1. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT PROPERTY LINES, WITH A MAXIMUM HEIGHT OF 35 FT WITH 2:1 OR FLATTER SLOPES.
- 2. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC.
- 3. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT STOCKPILE.
- 4. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.
- 5. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

# NPDES GROUND STABILIZATION

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE:

- 1. ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES AND SLOPES STEEPER THAN 3:1 SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT WITHIN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.
- 2. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE, BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.



SIDE SLOPE (SOD/STABILIZE WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN S150, OR SIMILARLY RATED .5:1 SIDE SLOPE (SOD/STABILIZE WITH EROSION CONTROL BLANKETS SUCH AS NORTH AMERICAN GREEN \$150, OR SIMILARLY RATED TEMPORARY INLET PROTECTION; REFER TO DETAIL (TYP.)

09/17/2021 A. BROWN

**DESIGNED BY** P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN

**CONSTRUCTION ENTRANCE** 

TEMPORARY DOUBLE INLET PROTECTION

**COMBINATION FENCE** 

SILT BAG AND PAD

TEMPORARY DIVERSION DITCH

SILT FENCE STONE OUTLET

CHECK DAM WITH A WEIR

SILT FENCE STONE OUTLET W/J HOOKS

**EMERGENCY SPILLWAY / RIP RAP** 

TEMPORARY INLET PROTECTION

CONCRETE WASHOUT

WATTLE HORSESHOE INLET PROTECTION

APRON

CHECK DAM

**EROSION CONTROL PLAN-STAGE 2 KEYNOTES** 

SILT-TREE COMBINATION FENCE. REFER TO DETAIL (TYP.)

TEMPORARY CLASS 3 18" RCP PIPE FOR DITCH CROSSING

DIVERSION DITCH OUTLET PROTECTION (C3.0 FOR DITCH CHARTS)

EMPORARY STORM INLET PROTECTION; REFER TO DETAIL (TYP.)

MPORARY STREAM BYPASS AND TIMBER MATTING FOR SEWER

TEMPORARY HORSESHOE INLET PROTECTION PIPE OUTFALL PROTECTION. (REFER TO C4.1)

TEMPORARY PIPE FOR OUTFALL CROSSING

ROCK CHECK DAM WITH WEIR (REFER TO DETAIL)

SILT FENCE STONE OUTLET WITH J HOOKS (TYP. AT STREAM

**EROSION CONTROL LEGEND** 

CROSSING: REFER TO DETAIL (TYP.)

PRODUCT FOR STEEP SLOPES).

PRODUCT FOR STEEP SLOPES).

SILT FENCE OUTLET; REFERT TO DETAIL (TYP).

TREE FENCE. REFER TO DETAIL (TYP.)

**DESCRIPTION** 

TEMPORARY 25' x 100' CONSTRUCTION ENTRANCE; REFER TO DETAIL

NUMBER

EC136

EC154

EC101 |LIMITS OF DISTURBANCE

EC102 SILT FENCE; REFER TO DETAIL (TYP).

POROUS BAFFLES (TYP.)

:1 SIDE SLOPE STOCKPILE AREA

CONCRETE WASHOUT

SILT BAG AND SILT BAG PAD

IMPERMEABLE MEMBRANE APRON

SKIMMER


TEMPORARY SLOPE DRAIN (TSD) 


TEMPORARY DIVERSION BERM TEMPORARY TIMBER MAT

ROLLED EROSION CONTROL FABRIC


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

JOB NO. SHEET NO. C4.14





- 1. ALL MATERIALS & CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH CITY OF RALEIGH DESIGN STANDARDS, DETAILS & SPECIFICATIONS (REFERENCE:
- 2. CONTRACTOR SHALL LOCATE AND PROTECT ALL EXISTING PUBLIC AND PRIVATE UTILITIES AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES OR CONFLICTS
- 3.1. A DISTANCE OF 100' SHALL BE MAINTAINED BETWEEN SANITARY SEWER & ANY PRIVATE OR PUBLIC WATER SUPPLY SOURCE SUCH AS AN IMPOUNDED RESERVOIR USED AS A SOURCE OF DRINKING WATER. IF ADEQUATE LATERAL SEPARATION CANNOT BE ACHIEVED, FERROUS SANITARY SEWER PIPE SHALL BE SPECIFIED & INSTALLED TO WATERLINE SPECIFICATIONS. HOWEVER, THE MINIMUM SEPARATION SHALL NOT BE LESS THAN 25' FROM A PRIVATE WELL
- 3.2. WHEN INSTALLING WATER AND/OR SEWER MAINS, THE HORIZONTAL SEPARATION BETWEEN UTILITIES SHALL BE 10'. IF THIS SEPARATION CANNOT BE MAINTAINED DUE TO EXISTING CONDITIONS, THE VARIATION ALLOWED IS THE WATER MAIN IN A SEPARATE TRENCH WITH THE ELEVATION OF THE WATER MAIN AT LEAST 18" ABOVE THE TOP OF THE SEWER & MUST BE APPROVED BY THE PUBLIC UTILITIES DIRECTOR. ALL DISTANCES ARE MEASURED FROM OUTSIDE DIAMETER TO OUTSIDE DIAMETER.
- 3.3. WHERE IT IS IMPOSSIBLE TO OBTAIN PROPER SEPARATION, OR ANYTIME A SANITARY SEWER PASSES OVER A WATER MAIN, DIP MATERIALS OR STEEL ENCASEMENT EXTENDED 10' ON EACH SIDE OF CROSSING MUST BE SPECIFIED
- 3.4. 5.0' MINIMUM HORIZONTAL SEPARATION IS REQUIRED BETWEEN ALL SANITARY SEWER & STORM SEWER FACILITIES, UNLESS DIP MATERIAL IS SPECIFIED FOR
- 3.5. MAINTAIN 18" MIN. VERTICAL SEPARATION AT ALL WATER MAIN & RCP STORM DRAIN CROSSINGS; MAINTAIN 24" MIN. VERTICAL SEPARATION AT ALL SANITARY SEWER & RCP STORM DRAIN CROSSINGS. WHERE ADEQUATE SEPARATIONS CANNOT BE ACHIEVED, SPECIFY DIP MATERIALS & A CONCRETE CRADLE HAVING 6" MIN. CLEARANCE (PER CORPUD DETAILS W-41 & S-49).
- 3.6. ALL OTHER UNDERGROUND UTILITIES SHALL CROSS WATER & SEWER FACILITIES WITH 18" MIN. VERTICAL SEPARATION REQUIRED.
- 4. ANY NECESSARY FIELD REVISIONS ARE SUBJECT TO REVIEW & APPROVAL OF AN AMENDED PLAN &/OR PROFILE BY THE CITY OF RALEIGH PUBLIC UTILITIES
- CONTRACTOR SHALL MAINTAIN CONTINUOUS WATER & SEWER SERVICE TO EXISTING RESIDENCES & BUSINESSES THROUGHOUT CONSTRUCTION OF PROJECT. ANY NECESSARY SERVICE INTERRUPTIONS SHALL BE PRECEDED BY A 24-HOUR ADVANCE NOTICE TO THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT
- CONTRACTOR SHALL COORDINATE THE LOCATION OR RELOCATION OF ALL OVERHEAD AND UNDERGROUND COMMUNICATION LINES, ELECTRIC AND GAS SERVICE WITH THE APPROPRIATE UTILITY COMPANY AND/OR THE CITY PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL PROVIDE CONDUITS AS REQUIRED FOR THESE UTILITIES UNDER PAVED AREAS. CONTRACTOR SHALL ENSURE THAT ALL OVERHEAD UTILITY LINES ARE ADJUSTED BY APPROPRIATE UTILITY COMPANY TO MAINTAIN ACCEPTABLE CLEARANCES FOR FIRE APPARATUS, CONSTRUCTION EQUIPMENT, AND VEHICULAR ACCESS.
- 3.0' MINIMUM COVER IS REQUIRED ON ALL WATER MAINS & SEWER FORCE MAINS.
- IT IS THE DEVELOPER'S RESPONSIBILITY TO ABANDON OR REMOVE EXISTING WATER & SEWER SERVICES NOT BEING USED IN REDEVELOPMENT OF A SITE UNLESS OTHERWISE DIRECTED BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT. THIS INCLUDES ABANDONING TAP AT MAIN & REMOVAL OF SERVICE FROM ROW OR EASEMENT PER CORPUD HANDBOOK PROCEDURE
- INSTALL 2" TYPE "K" COPPER WATER SERVICE WITH METER LOCATED AT ROW OR WITHIN A 2'X2' WATERLINE EASEMENT IMMEDIATELY ADJACENT.
- 10. INSTALL 6" SCHEDULE 40 PVC SEWER SERVICES @ 1.0% MINIMUM GRADE WITH CLEANOUTS LOCATED AT ROW OR EASEMENT LINE & SPACED EVERY 75 LINEAR
- 11. PRESSURE REDUCING VALVES ARE REQUIRED ON ALL WATER SERVICES EXCEEDING 80 PSI; BACKWATER VALVES ARE REQUIRED ON ALL SANITARY SEWER SERVICES HAVING BUILDING DRAINS LOWER THAN 1.0' ABOVE THE NEXT UPSTREAM
- 12. ALL ENVIRONMENTAL PERMITS APPLICABLE TO THE PROJECT MUST BE OBTAINED FROM NCDWQ, USACE AND/OR FEMA FOR ANY RIPARIAN BUFFER, WETLAND &/OR FLOODPLAIN IMPACTS (RESPECTIVELY) PRIOR TO CONSTRUCTION.
- 13. NCDOT ENCROACHMENT AGREEMENTS ARE REQUIRED FOR ANY UTILITY WORK (INCLUDING MAIN EXTENSIONS & SERVICE TAPS) WITHIN STATE ROW PRIOR TO
- 14. CROSS-CONNECTION CONTROL PROTECTION DEVICES ARE REQUIRED BASED ON DEGREE OF HEALTH HAZARD INVOLVED AS LISTED IN APPENDIX-B OF THE RULES GOVERNING PUBLIC WATER SYSTEMS IN NORTH CAROLINA. THESE GUIDELINES ARE THE MINIMUM REQUIREMENTS. THE DEVICES SHALL MEET AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE) STANDARDS OR BE ON THE UNIVERSITY OF SOUTHERN CALIFORNIA APPROVAL LIST. THE DEVICES SHALL BE INSTALLED AND TESTED (BOTH INITIAL AND PERIODIC TESTING THEREAFTER) IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS OR THE LOCAL CROSS-CONNECTION CONTROL PROGRAM, WHICHEVER IS MORE STRINGENT. CONTACT JOANIE HARTLEY AT (919) 996-5923 OR
- BREACH) AROUND OR IN THE VICINITY OF EXISTING WATER LINES 12 INCHES IN DIAMETER OR LARGER SHALL BE REQUIRED TO PHYSICALLY SPOT THE EXISTING LINE TO BE VERIFIED BY P.U.D. DISTRIBUTION STAFF OR INSPECTION STAFF. IF OTHER EXISTING LINES SIZES ARE IN QUESTION OF CONFLICT THE CONTRACTOR SHALL BE DIRECTED BY P.U.D. STAFF OF THE LEVEL OF SUBSURFACE INVESTIGATION NEEDED TO LOCATE THE EXISTING LINE.
- SEWER LINE TO SANITARY SEWER MANHOLE 207 TO BE LINED PER CITY OF RALEIGH DETAILS FOR RECEIVE FLOW FROM SANITARY SEWER FORCE MAIN.
- 17. THIS DEVELOPMENT RELIES UPON KALAS FALLS FOR ACCESS TO PUBLIC WATER AND PUBLIC SANITARY SEWER. IF KALAS FALLS DOES NOT INSTALL NECESSARY INFRASTRUCTURE, THIS DEVELOPMENT MAY BE RESPONSIBLE FOR NECESSARY



ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS





09/17/2021 R. WINGATE **DESIGNED BY** 


P. BARBEAU CHECKED BY . BARBEAU


AS SHOWN

JOB NO.









	SANITARY SEWER STRUCTURE TABLE										
STR.#	ТОР	INV. IN	INV. OUT	DESCRIPTION							
MH 9	389.23'		383.68' (8" Ductile Iron TO MH 10)	48" Manhole							
MH 10	391.86'	383.34' (8" Ductile Iron FROM MH 9)	383.14' (8" SDR-26 TO MH 87)	60" Manhole							
MH 11	396.93'	380.48' (8" SDR-26 FROM MH 87)	380.28' (8" SDR-26 TO MH 12)	60" Manhole							
MH 12	395.18'	379.81' (8" SDR-26 FROM MH 11)	379.61' (8" SDR-26 TO MH 13)	60" Manhole							
MH 13	393.39'	379.16' (8" SDR-26 FROM MH 12) 381.12' (8" Ductile Iron FROM MH 55) 379.16' (8" SDR-26 FROM MH 49)	378.96' (8" SDR-26 TO MH 14)	60" Manhole							
MH 14	385.10'	377.16' (8" SDR-26 FROM MH 13) 378.90' (8" PVC FROM MH 60)	376.96' (8" PVC TO MH 15)	48" Manhole							
MH 15	384.13'	376.45' (8" PVC FROM MH 14)	376.07' (8" Ductile Iron TO MH 15A)	48" Manhole							
MH 15A	384.82'	375.53' (8" Ductile Iron FROM MH 15)	375.33' (8" SDR 26 TO MH 16)	48" Manhole							
MH 16	385.95'	373.93' (8" SDR 26 FROM MH 15A) 373.77' (8" PVC FROM MH 38) 374.90' (8" PVC FROM MH 45)	373.09' (8" SDR-26 TO MH 17)	60" Manhole							
MH 17	382.86'	372.38' (8" SDR-26 FROM MH 16)	372.08' (8" PVC TO MH 97)	48" Manhole							
MH 18	375.35'	369.29' (8" PVC FROM MH 97)	368.89' (8" PVC TO MH 98)	48" Manhole							
MH 20	368.47'	361.50' (8" PVC FROM MH 88)	359.94' (8" PVC TO MH 21)	48" Manhole							
MH 21	365.71'	359.18' (8" PVC FROM MH 20)	358.98' (8" PVC TO MH 22)	48" Manhole							
MH 22	364.11'	358.40' (8" PVC FROM MH 21)	357.07' (8" Ductile Iron TO MH 23)	48" Manhole							
MH 23	365.65'	356.37' (8" Ductile Iron FROM MH 22)	356.07' (8" SDR 26 TO MH 24)	48" Manhole							
MH 24	369.02'	355.33' (8" SDR 26 FROM MH 23) 356.00' (8" SDR 26 FROM MH 76)	355.10' (8" SDR 26 TO MH 25)	72" Drop Manhole							
MH 25	368.13'	354.94' (8" SDR 26 FROM MH 24)	354.74' (8" SDR-26 TO MH 25B)	60" Manhole							
MH 25B	364.54'	354.28' (8" SDR-26 FROM MH 25)	354.08' (8" SDR-26 TO MH 26)	48" Manhole							
MH 26	361.70'	353.68' (8" SDR-26 FROM MH 25B)	353.48' (8" Ductile Iron TO MH 70)	48" Manhole							
MH 27	360.59'	343.04' (12" SDR-26 FROM MH 70)	342.84' (12" SDR-26 TO MH 28)	60" Manhole							
MH 28	359.04'	342.06' (12" SDR-26 FROM MH 27)	341.86' (12" SDR-26 TO MH 29)	60" Manhole							
MH 29	348.04'	341.24' (12" SDR-26 FROM MH 28)	341.04' (12" Ductile Iron TO MH 114)	48" Manhole							
MH 30A	349.00'	329.00' (12" SDR-26 FROM MH 30B)		72" Manhole							
MH 30B	348.00'	331.70' (12" SDR-26 FROM MH 114)	329.20' (12" SDR-26 TO MH 30A)	60" Manhole							
MH 31	381.82'		376.08' (8" PVC TO MH 102)	48" Manhole							
MH 32	397.52'		383.80' (8" PVC TO MH 107)	60" Manhole							
MH 33	391.06'	204 401 (011 DV C ED ON MILL 22)	385.38' (8" PVC TO MH 34)	48" Manhole							
MH 34	389.88'	384.18' (8" PVC FROM MH 33)	383.98' (8" PVC TO MH 55)	48" Manhole							
MH 35	386.01'	277 20' (9" DVC EDOM MH 25)	378.50' (8" PVC TO MH 36)	48" Manhole							
MH 36	383.28'	377.30' (8" PVC FROM MH 35) 375.40' (8" PVC FROM MH 36)	377.00' (8" PVC TO MH 37) 375.20' (8" PVC TO MH 38)	48" Manhole							
MH 37 MH 38	383.47' 384.57'	374.69' (8" PVC FROM MH 37)	374.45' (8" PVC TO MH 16)	48" Manhole 48" Manhole							
MH 39	391.37'	374.03 (0 1 VOTTCOM WIIT 97)	382.51' (8" PVC TO MH 40)	48" Manhole							
MH 40	389.29'	381.35' (8" PVC FROM MH 39)	381.15' (8" PVC TO MH 41)	48" Manhole							
MH 41	388.32'	380.64' (8" PVC FROM MH 40)	380.44' (8" PVC TO MH 42)	48" Manhole							
MH 42	387.47'	379.83' (8" PVC FROM MH 41)	379.63' (8" PVC TO MH 43)	48" Manhole							
MH 43	387.89'	379.14' (8" PVC FROM MH 42)	378.94' (8" PVC TO MH 44)	60" Manhole							
MH 44	388.50'	378.53' (8" PVC FROM MH 43) 380.70' (8" PVC FROM MH 46)	378.33' (8" PVC TO MH 45)	72" DROP Manhole							
MH 45	387.32'	377.70' (8" PVC FROM MH 44)	377.50' (8" PVC TO MH 16)	60" Manhole							
MH 46	389.57'		383.73' (8" PVC TO MH 44)	48" Manhole							
MH 47	390.03'		384.40' (8" PVC TO MH 48)	48" Manhole							
MH 48	388.67'	382.81' (8" PVC FROM MH 47)	382.09' (8" PVC TO MH 49)	48" Manhole							
MH 49	388.94'	381.02' (8" PVC FROM MH 48)	380.82' (8" SDR-26 TO MH 13)	48" Manhole							
MH 51	394.83'		388.70' (8" PVC TO MH 52)	48" Manhole							
MH 52	391.16'	384.90' (8" PVC FROM MH 51)	384.70' (8" Ductile Iron TO MH 54)	48" Manhole							
MH 54	389.34'	384.10' (8" Ductile Iron FROM MH 52)	383.79' (8" Ductile Iron TO MH 55)	48" Manhole							
MH 55	390.08'	383.41' (8" PVC FROM MH 34) 383.41' (8" Ductile Iron FROM MH 54)	383.21' (8" Ductile Iron TO MH 13)	48" Manhole							
MH 60	386.68'	380.50' (8" PVC FROM MH 61)	380.30' (8" PVC TO MH 14)	48" Manhole							
MH 61	389.04'	271 06! (9" Ductile Inc. EDOM MILEON	382.36' (8" PVC TO MH 60)	48" Manhole							
MH 62	381.71'	371.06' (8" Ductile Iron FROM MH 85) 369.20' (8" PVC FROM MH 93)	369.00' (8" SDR-26 TO MH 63)	60" Manhole							

				1
STR.#	TOP	INV. IN	INV. OUT	DESCRIPTION
MH 63	383.00'	368.37' (8" SDR-26 FROM MH 62)	368.17' (8" SDR-26 TO MH 64)	60" Manhole
MH 64	384.48'	367.53' (8" SDR-26 FROM MH 63)	367.33' (8" SDR-26 TO MH 65)	60" Manhole
MH 65	384.85'	366.69' (8" SDR-26 FROM MH 64) 375.87' (8" DIP FROM MH 81)	366.49' (8" SDR-26 TO MH 86)	72" Drop Manhole
MH 66	374.81'	363.65' (8" SDR-26 FROM MH 86)	363.45' (8" PVC TO MH 67)	48" Manhole
MH 67	369.89'	360.74' (8" PVC FROM MH 66) 358.23' (8" PVC FROM MH 80)	358.03' (8" PVC TO MH 68)	72" DROP Manhole
MH 68	361.32'	352.05' (8" PVC FROM MH 67)	351.00' (12" SDR-26 TO MH 94)	48" Manhole
MH 69	356.03'	344.23' (12" Ductile Iron FROM MH 94)	344.03' (12" SDR-26 TO MH 70)	48" Manhole
MH 70	360.83'	353.08' (8" Ductile Iron FROM MH 26) 343.43' (12" SDR-26 FROM MH 69)	343.23' (12" SDR-26 TO MH 27)	72" DROP Manhole
MH 72	373.94'	368.12' (8" Ductile Iron FROM MH 73)	367.92' (8" Ductile Iron TO MH 88)	48" Manhole
MH 73	380.95'	375.35' (8" PVC FROM MH 74)	373.80' (8" Ductile Iron TO MH 72)	48" Manhole
MH 74	381.68'		375.88' (8" PVC TO MH 73)	48" Manhole
MH 75	381.04'	373.87' (8" PVC FROM MH 77)	373.63' (8" SDR 26 TO MH 76)	48" Manhole
MH 76	369.68'	359.21' (8" SDR 26 FROM MH 75)	358.00' (8" SDR 26 TO MH 24)	48" Manhole
MH 77	381.78'		376.10' (8" PVC TO MH 75)	48" Manhole
MH 79	364.91'		359.15' (8" Ductile Iron TO MH 80)	48" Manhole
MH 80	366.39'	358.93' (8" Ductile Iron FROM MH 79)	358.73' (8" PVC TO MH 67)	48" Manhole
MH 81	382.86'		377.76' (8" DIP TO MH 65)	48" Manhole
MH 85	384.69'	372.82' (8" PVC FROM MH 102) 375.00' (8" PVC FROM MH 100)	372.62' (8" Ductile Iron TO MH 62)	60" Manhole
MH 86	379.95'	365.17' (8" SDR-26 FROM MH 65)	364.97' (8" SDR-26 TO MH 66)	60" Manhole
MH 87	396.61'	382.21' (8" SDR-26 FROM MH 10)	382.01' (8" SDR-26 TO MH 11)	60" Manhole
MH 88	371.95'	366.20' (8" PVC FROM MH 98) 365.36' (8" Ductile Iron FROM MH 72)	365.16' (8" PVC TO MH 20)	48" Manhole
MH 89	388.83'		382.08' (8" Ductile Iron TO MH 90)	48" Manhole
MH 90	386.32'	380.48' (8" Ductile Iron FROM MH 89)	380.28' (8" PVC TO MH 91)	48" Manhole
MH 91	383.74'	378.09' (8" PVC FROM MH 90)	377.89' (8" Ductile Iron TO MH 92)	48" Manhole
MH 92	382.60'	377.62' (8" Ductile Iron FROM MH 91)	375.30' (8" Ductile Iron TO MH 93)	48" Manhole
MH 93	381.17'	374.63' (8" Ductile Iron FROM MH 92)	374.43' (8" PVC TO MH 62)	48" Manhole
MH 94	353.05'	347.19' (12" SDR-26 FROM MH 68)	345.10' (12" Ductile Iron TO MH 69)	48" Manhole
MH 97	379.13'	371.65' (8" PVC FROM MH 17)	371.45' (8" PVC TO MH 18)	48" Manhole
MH 98	372.46'	366.50' (8" PVC FROM MH 18)	366.30' (8" PVC TO MH 88)	48" Manhole
MH 100	390.31'	382.00' (8" PVC FROM MH 107)	381.60' (8" PVC TO MH 85)	48" Manhole
MH 101	387.77'		377.00' (8" Ductile Iron TO MH 102)	48" Manhole
MH 102	382.55'	375.20' (8" PVC FROM MH 31) 375.20' (8" Ductile Iron FROM MH 101)	375.00' (8" PVC TO MH 85)	48" Manhole
MH 107	390.03'	383.20' (8" PVC FROM MH 32)	383.00' (8" PVC TO MH 100)	48" Manhole
MH 114	348.00'	340.55' (12" Ductile Iron FROM MH 29)	339.89' (12" SDR-26 TO MH 30B)	48" Manhole
MH 2081	346.57'	335.99' (8" PVC FROM MH 2082)	335.79' (8" Ductile Iron TO )	48" Manhole
MH 2082	347.52'		338.04' (8" PVC TO MH 2081)	48" Manhole

	SAN	TARY SEWER	BLE										
FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL	FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH	DIA.	MATERIAL
MH 9 - MH 10	383.68'	383.34'	0.50%	68.92 LF	8"	Ductile Iron	MH 64 - MH 65	367.33'	366.69'	0.53%	119.36 LF	8"	SDR-26
MH 10 - MH 87	383.14'	382.21'	0.50%	185.38 LF	8"	SDR-26	MH 65 - MH 86	366.49'	365.17'	0.50%	264.72 LF	8"	SDR-26
MH 11 - MH 12	380.28'	379.81'	0.50%	95.17 LF	8"	SDR-26	MH 66 - MH 67	363.45'	360.74'	0.73%	373.47 LF	8"	PVC
MH 12 - MH 13	379.61'	379.16'	0.50%	90.04 LF	8"	SDR-26	MH 67 - MH 68	358.03'	352.05'	1.97%	303.63 LF	8"	PVC
MH 13 - MH 14	378.96'	377.16'	0.50%	362.44 LF	8"	SDR-26	MH 68 - MH 94	351.00'	347.19'	3.89%	97.89 LF	12"	SDR-26
MH 14 - MH 15	376.96'	376.45'	0.50%	101.40 LF	8"	PVC	MH 69 - MH 70	344.03'	343.43'	0.51%	118.62 LF	12"	SDR-26
MH 15 - MH 15A	376.07'	375.53'	0.50%	108.17 LF	8"	Ductile Iron	MH 70 - MH 27	343.23'	343.04'	0.66%	28.17 LF	12"	SDR-26
MH 15A - MH 16	375.33'	373.93'	0.50%	279.70 LF	8"	SDR 26	MH 72 - MH 88	367.92'	365.36'	1.92%	133.67 LF	8"	Ductile Iron
MH 16 - MH 17	373.09'	372.38'	0.50%	143.75 LF	8"	SDR-26	MH 73 - MH 72	373.80'	368.12'	2.76%	205.45 LF	8"	Ductile Iron
MH 17 - MH 97	372.08'	371.65'	0.50%	86.61 LF	8"	PVC	MH 74 - MH 73	375.88'	375.35'	0.50%	105.25 LF	8"	PVC
MH 18 - MH 98	368.89'	366.50'	3.17%	75.57 LF	8"	PVC	MH 75 - MH 76	373.63'	359.21'	3.91%	369.16 LF	8"	SDR 26
MH 20 - MH 21	359.94'	359.18'	0.50%	151.59 LF	8"	PVC	MH 76 - MH 24	358.00'	356.00'	4.10%	48.82 LF	8"	SDR 26
MH 21 - MH 22	358.98'	358.40'	0.50%	115.99 LF	8"	PVC	MH 77 - MH 75	376.10'	373.87'	2.38%	93.47 LF	8"	PVC
MH 22 - MH 23	357.07'	356.37'	0.50%	139.17 LF	8"	Ductile Iron	MH 79 - MH 80	359.15'	358.93'	0.50%	44.15 LF	8"	Ductile Iron
MH 23 - MH 24	356.07'	355.33'	0.50%	148.81 LF	8"	SDR 26	MH 80 - MH 67	358.73'	358.23'	0.49%	102.17 LF	8"	PVC
MH 24 - MH 25	355.10'	354.94'	0.50%	31.70 LF	8"	SDR 26	MH 81 - MH 65	377.76'	375.87'	0.99%	190.90 LF	8"	DIP
MH 25 - MH 25B	354.74'	354.28'	0.51%	91.07 LF	8"	SDR-26	MH 85 - MH 62	372.62'	371.06'	0.50%	311.47 LF	8"	Ductile Iron
MH 25B - MH 26	354.08'	353.68'	0.51%	78.22 LF	8"	SDR-26	MH 86 - MH 66	364.97'	363.65'	0.50%	264.72 LF	8"	SDR-26
MH 26 - MH 70	353.48'	353.08'	0.96%	41.39 LF	8"	Ductile Iron	MH 87 - MH 11	382.01'	380.48'	0.50%	305.65 LF	8"	SDR-26
MH 27 - MH 28	342.84'	342.06'	0.50%	156.90 LF	12"	SDR-26	MH 88 - MH 20	365.16'	361.50'	1.36%	269.48 LF	8"	PVC
MH 28 - MH 29	341.86'	341.24'	0.50%	125.28 LF	12"	SDR-26	MH 89 - MH 90	382.08'	380.48'	1.26%	126.31 LF	8"	Ductile Iron
MH 29 - MH 114	341.04'	340.55'	0.50%	96.22 LF	12"	Ductile Iron	MH 90 - MH 91	380.28'	378.09'	1.79%	121.88 LF	8"	PVC
MH 30B - MH 30A	329.20'	329.00'	0.75%	26.50 LF	12"	SDR-26	MH 91 - MH 92	377.89'	377.62'	0.50%	55.91 LF	8"	Ductile Iron
MH 31 - MH 102	376.08'	375.20'	1.55%	56.92 LF	8"	PVC	MH 92 - MH 93	375.30'	374.63'	1.00%	66.91 LF	8"	Ductile Iron
MH 32 - MH 107	383.80'	383.20'	1.05%	57.07 LF	8"	PVC	MH 93 - MH 62	374.43'	369.20'	1.96%	267.33 LF	8"	PVC
MH 33 - MH 34	385.38'	384.18'	0.93%	129.01 LF	8"	PVC	MH 94 - MH 69	345.10'	344.23'	0.50%	173.63 LF	12"	Ductile Iron
MH 34 - MH 55	383.98'	383.41'	0.50%	113.10 LF	8"	PVC	MH 97 - MH 18	371.45'	369.29'	2.54%	84.91 LF	8"	PVC
MH 35 - MH 36	378.50'	377.30'	0.74%	161.68 LF	8"	PVC	MH 98 - MH 88	366.30'	366.20'	0.50%	20.95 LF	8"	PVC
MH 36 - MH 37	377.00'	375.40'	1.56%	102.70 LF	8"	PVC	MH 100 - MH 85	381.60'	375.00'	1.61%	409.31 LF	8"	PVC
MH 37 - MH 38	375.20'	374.69'	0.50%	102.70 LF	8"	PVC	MH 101 - MH 102	377.00'	375.20'	1.21%	149.00 LF	8"	Ductile Iron
MH 38 - MH 16	374.45'	373.77'	0.50%	135.48 LF	8"	PVC	MH 102 - MH 85	375.00'	372.82'	1.41%	155.15 LF	8"	PVC
MH 39 - MH 40	382.51'	381.35'	0.65%	178.89 LF	8"	PVC	MH 107 - MH 100	383.00'	382.00'	0.64%	155.19 LF	8"	PVC
MH 40 - MH 41	381.15'	380.64'	0.50%	102.28 LF	8"	PVC	MH 114 - MH 30B	339.89'	331.70'	9.50%	86.20 LF	12"	SDR-26
MH 41 - MH 42	380.44'	379.83'	0.50%	121.36 LF	8"	PVC	MH 2081 -	335.79'	334.53'	0.60%	208.71 LF	8"	Ductile Iron
MH 42 - MH 43	379.63'	379.14'	0.50%	97.03 LF	8"	PVC	MH 2082 - MH 2081	338.04'	335.99'	2.24%	91.39 LF	8"	PVC
MH 43 - MH 44	378.94'	378.53'	0.50%	83.37 LF	8"	PVC							
MH 44 - MH 45	378.33'	377.70'	0.50%	126.18 LF	8"	PVC							
MH 45 - MH 16	377.50'	374.90'	1.88%	138.21 LF	8"	PVC							
MH 46 - MH 44	383.73'	380.70'	4.13%	73.40 LF	8"	PVC							
MH 47 - MH 48	384.40'	382.81'	2.31%	68.63 LF	8"	PVC							
MH 48 - MH 49	382.09'	381.02'	1.00%	106.63 LF	8"	PVC							
MH 49 - MH 13	380.82'	379.16'	0.50%	332.23 LF	8"	SDR-26							
			ļ										

PIPE MATERIAL DEPTH		
DEPTH		
MIN. 3'-5' w/IN TRAFFIC AREA		
>5' w/IN TRAFFIC AREA		
36" - 54"		
12' - 20' NON-TRAFFIC AREA		
>20' w/DIRECTOR APPROVAL		

1.94% 195.71 LF 8" PVC

0.63% 95.33 LF 8" Ductile Iron

0.50% | 76.17 LF | 8" | Ductile Iron

0.50% | 418.16 LF | 8" | Ductile Iron

SDR-26

2.02% | 69.24 LF | 8"

1.61% | 115.71 LF | 8" |

0.50% | 126.81 LF | 8"

0.47% | 136.67 LF | 8"

MH 51 - MH 52

MH 52 - MH 54

MH 54 - MH 55

MH 55 - MH 13

MH 60 - MH 14

MH 62 - MH 63

MH 63 - MH 64

388.70'

384.70'

383.79'

383.21'

380.30'

382.36'

369.00'

368.17'

384.90'

383.41'

381.12'

378.90'

380.50'

368.37'

367.53'

DIP AND APPROPRIATE PVC PIPE CAN BE INTERCHANGEABLE AS LONG AS CRITERIA LISTED ABOVE ARE MET.

MANHOLE SIZE REQUIREMENTS		
MANHOLE DIAMETER	SEWER MAIN SIZE	DEPTH OF INSTALLATION
4'	8"- 12"	0' - 12'
5'	15"- 30"	12' - 20'
6'	36" - 54"	>20'

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF

09/17/2021

DRAWN BY R. WINGATE


DESIGNED BY P. BARBEAU


CHECKED BY P. BARBEAU


AS SHOWN


SHEET NO. C5.5

RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS









AS SHOWN 0

09/06/2023

09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY


P. BARBEAU


SCALE

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

43398 SHEET NO. C5.6

JOB NO.





PROFILE SCALE

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


09/17/2021 DRAWN BY

R. WINGATE DESIGNED BY

P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN



09/17/2021 DRAWN BY

R. WINGATE

DESIGNED BY P. BARBEAU


CHECKED BY P. BARBEAU

SCALE AS SHOWN

JOB NO.

43398 SHEET NO.

C5.8




09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU AS SHOWN

43398

SHEET NO. **C5.9** 



09/06/2023

09/17/2021

DRAWN BY

R. WINGATE

DESIGNED BY

P. BARBEAU

CHECKED BY


P. BARBEAU


SCALE AS SHOWN

-08

JOB NO.

43398 SHEET NO. **C5.10** 





09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU


SCALE AS SHOWN


80


JOB NO. 43398 SHEET NO. *C5.11* 


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF

RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS









MITCHELL MILL PUBLIC WATER MAIN PROFILE VIEW STA 10+00 - 18+00


09/17/2021 DRAWN BY R. WINGATE DESIGNED BY JOB NO.


P. BARBEAU CHECKED BY P. BARBEAU AS SHOWN -08

43398


SHEET NO. C5.12

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS





MITCHELL MILL PUBLIC WATER MAIN PLAN VIEW
STA 18+00 - 26+40



MITCHELL MILL PUBLIC WATER MAIN PROFILE VIEW STA 18+00 - 26+40

09/17/2021 DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU


CHECKED BY


P. BARBEAU


AS SHOWN

80

SHEET NO. C5.13









ON STHICH SENSE NO. C-1652		•	· ·	OUR VISIC	YOUR VISION ACHIEVED THROUGH OURS.	оидн ours.	5410 T TEL 919.86
	F	F	R	C	DATE		REVI
		DES P. <i>E</i>		9/	04/08/2022	~	REVISIONS PE
	SCA	BAF		DA	06/24/2022	2	REVISIONS PE
WAKE COUNTY - NORTH CAROLINA	R <i>BE</i>	RBE	/N E		07/22/2022		CONSTRUCT
	AL	EAL	3Y <b>4</b> <i>TL</i>	021	04/06/2023		REVISION
JIIE DEI AILS			=	!	8606/90/60	ДО	BEVISIONS DEF


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS


C7.0


JOB NO.


















THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGES TO SUBGRADE, INSTALLED BASE


4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING PAVEMENT DURING ALL PHASES OF WORK. THE


ASPHALT PAVEMENT SECTION N.T.S.

FINAL SURFACE OF PAVEMENT SHALL BE FREE OF ALL DEFECTS OR DAMAGE.

COURSE AND/OR INTERMEDIATE PAVING PRIOR TO PLACING SUBSEQUENT PAVEMENT LIFTS AT NO ADDITIONAL








09/17/2021

R. WINGATE DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

SCALE AS SHOWN

JOB NO. SHEET NO.



SLAB TOP YARD INLET

43398 SHEET NO.

JOB NO.

C7.2

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

**DESIGNED BY** P. BARBEAU CHECKED BY P. BARBEAU SCALE AS SHOWN 0


09/06/2023


DATE


09/17/2021


DRAWN BY


R. WINGATE



















DATE 09/17/2021 DRAWN BY A. BROWN DESIGNED BY P. BARBEAU


CHECKED BY P. BARBEAU


SCALE AS SHOWN


08

RO

JOB NO. SHEET NO.








### Slope Installation

The following slope guide outlines general recommendations for installing RollMax™ System temporary and/or permanent RECPs on sloping applications. Consult the staple pattern guide (Figure 1) for fastener spacing recommendations based on the slope severity.



## SLOPE INSTALLATION STEPS

 Prepare soil before installing RECPs, including any necessary application of lime, fertilizer and seed.

2. Begin at the top of the slope by anchoring the RECPs in a 6 in. (15 cm) deep x 6 in. (15 cm) wide trench with approximately 12 in. (30 cm) of RECPs extended beyond the upslope


4. The edges of parallel RECPs must be stapled with an portion of the trench. Anchor the RECPs with a row of staples/stakes approximately 12 in. (30 cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Apply seed to the compacted soil and fold the remaining 12 in. (30 cm) portion of RECPs back over the seed and compacted soil. Secure RECPs over compacted soil with a row of staples/stakes spaced approximately 12 in. (30 cm) apart across the width of the RECPs.

3. Roll the RECPs (3A) down or (3B) horizontally across the slope. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.


approximately 2 in.-5 in. (5-12.5 cm) overlap depending on Consecutive RECPs spliced down the slope must be end-


over-end (shingle style) with an approximate 3 in. (7.5 cm) overlap. Staple through overlapped area, approximately 12 in. (30 cm) apart across entire RECPs width.\*


may be necessary to properly secure the RECPs.



PATTERN OF AT LEAST 3-5 DAYS.







PUMP AND DIKE IS A SHORT DURATION PROCESS (MAX. 5 DAYS) IMPERVIOUS DIKE OPTIONS ARE SAND BAGS, SHEET PILING, OR NO. 57 STONE WITH POLYPROPYLENE FOR WIDTH AND DEPTH OF CHANNEL. OPERATION AND CONSTRUCTION FOR STREAM CROSSING SHOULD BE PERFORMED IN A DRY WEATHER

TIMBER MAT NOTES: 1. STONE APPROACHES WILL BE PROVIDED ON BOTH SIDES. BOARDS WIL HAVE NO GAPS, GEOTEXTILE SHALL BE UNDERLAIN OR OVERLAIN, AND SIDE BOARDS WILL BE INSTALLED ALON THE PERIMTER OF THE MAT. N.T.S. TIMBER MAT


09/17/2021 DRAWN BY A. BROWN


**DESIGNED BY** P. BARBEAU CHECKED BY

P. BARBEAU SCALE

AS SHOWN

JOB NO. 43398 SHEET NO. *C7.4* 





Practice Standards and Specifications

## CHECK DAM WITH A WEIR

Purpose To reduce erosion in a drainage channel by restricting the velocity of flow. This structure also has some ability to provide sediment control.

Definition A small stone dam structure with a weir outlet with a sediment storage area on

Conditions Where This temporary practice may be used in the following locations:

Practice Applies • At outlets of temporary diversions, graded channels, and temporary slope

 In small natural drainage turnouts; and • In locations where the dams can be easily cleaned and maintained on a

Do not use a check dam with a weir in intermittent or perennial streams.

Rev. 6/06

Planning Check dams are an expedient way to reduce gullying in the bottom of channels that will be filled or stabilized at a later date. The dams should only be used Considerations that will be lined of stabilization measures are being put into place.

> Check dams installed in grass-lined channels may kill the vegetative lining if submergence after it rains is too long and/or sedimentation is excessive. All stone and riprap must be removed if mowing is planned as part of vegetative maintenance.

Design Criteria The following criteria should be used when designing a check dam with a

• Keep the weir at least 9 inches lower than the outer edges at natural ground elevation. The weir length is variable to the size of the drainage area and peak runoff. The weir length may be sized as:

• Keep the side slope of the stone at 2:1 or flatter.

• The apron length (lower side of dam) should be approximately three times the height of the dam with a minimum length of 4 feet. Stabilize outflow areas along the channel to resist erosion.

• The maximum spacing between dams places the toe of the upstream dam

at the same elevation as the top of the downstream dam (Figure 6.84a). • Use NC DOT Class B stone and line the upstream side of the dam with

NC DOT #5 or #57 stone. • Key the stone into the ditch banks and extend it beyond the abutments a

minimum of 1.5 feet to avoid washouts from overflow around the dams.

• Sediment storage area should be sized for the anticipated volume of sedimentation.

Construction 1. Place structural stone (Class B) to the lines and dimensions shown on Specifications the plan on a filter fabric foundation. The crest width of the dam should be a minimum of 2 feet.

2. Keep the center stone section at least 9 inches below the end where the dam abuts the channel banks.

3. Place sediment control stone (#5 or #57) on the upstream side of the dam that is a minimum of 1 foot thick.

4. Provide an apron that is 3 times the height of the dam. The apron width is at least 4 feet long. Undercut the apron so that the top of the apron is flush with the surrounding grade.

5. Extend the stone at least 1.5 feet beyond the ditch bank to keep water from cutting around the ends of the check dam.

**6.** Excavate sediment storage area to the dimensions shown on the plan

Maintenance Inspect check dams and channels at least weekly and after each significant (1/2

inch or greater) rainfall event and repair immediately. Clean out sediment, straw, limbs, or other debris that could clog the channel when needed.


Anticipate submergence and deposition above the check dam and erosion from high flows around the edges of the dam. Correct all damage immediately. If significant erosion occurs between dams, additional measures can be taken such as, installing a protective riprap liner in that portion of the channel (Practice 6.31, Riprap-line and Paved Channels).

Remove sediment accumulated behind the dams as needed to prevent damage to channel vegetation, allow the channel to drain through the stone check dam, and prevent large flows from carrying sediment over the dam. Add stones to dams as needed to maintain design height and cross section.


References Runoff Conveyance Measures 6.31, Riprap-lined and Paved Channels

North Carolina Department of Transportation Standard Specifications for Roads and Structures

6.87.2 Rev. 6/06



SUPER SILT FENCE



09/17/2021

DRAWN BY R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN

08

ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

## SECTION E. GROUND STABILIZATION

	Re	equired Ground Stabil	ization Timeframes
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zone -10 days for Falls Lake Watershed unless there is zero slope

practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

### GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

1		
	Temporary Stabilization	Permanent Stabilization
	Temporary grass seed covered with straw or	Permanent grass seed covered with straw or

- other mulches and tackifiers Hydroseeding Rolled erosion control products with or
- without temporary grass seed Appropriately applied straw or other mulch
- Hydroseeding Plastic sheeting
- Shrubs or other permanent plantings covered with mulch
  - Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or

reinforcement matting

retaining walls Rolled erosion control products with grass seed

other mulches and tackifiers

Geotextile fabrics such as permanent soil

### POLYACRYLAMIDES (PAMS) AND FLOCCULANT Select flocculants that are appropriate for the soils being exposed during

- construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures. . Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging Store flocculants in leak-proof containers that are kept under storm-resistant cover
- or surrounded by secondary containment structures.

### EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment. . Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- 4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem
- has been corrected. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

## LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or

Locate waste containers at least 50 feet away from storm drain inlets and surface

- provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if

### Dispose waste off-site at an approved disposal facility. 9. On business days, clean up and dispose of waste in designated waste containers.


- PAINT AND OTHER LIQUID WASTE Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site. 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

## EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- . Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





BELOW GRADE WASHOUT STRUCTURE

- 1. Do not discharge concrete or cement slurry from the site.
- 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in
- addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum. install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.

Install at least one sign directing concrete trucks to the washout within the project

- limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary
- products, follow manufacturer's instructions. 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

## HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- 4. Do not stockpile these materials onsite.

## HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

SELF-INSPECTION, RECORDKEEPING AND REPORTING

They are less than 25 gallons but cannot be cleaned up within 24 hours,

Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA

(e) Noncompliance with the conditions of this permit that may endanger health or the

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800)

Within 24 hours, an oral or electronic notification

Reporting Timeframes (After Discovery) and Other Requirements

Within 7 calendar days, a report that contains a description of the

with the federal or state impaired-waters conditions.

Within 24 hours, an oral or electronic notification.

location of the spill or release.

quality and effect of the bypass. (e) Noncompliance • Within 24 hours, an oral or electronic notification

effect of the bypass.

case-by-case basis.

sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a If the stream is named on the NC 303(d) list as impaired for sediment-

related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff

Within 24 hours, an oral or electronic notification. The notification

shall include information about the date, time, nature, volume and

A report at least ten days before the date of the bypass, if possible.

The report shall include an evaluation of the anticipated quality and

Within 7 calendar days, a report that includes an evaluation of the

Within 7 calendar days, a report that contains a description of the

including exact dates and times, and if the noncompliance has not

continue; and steps taken or planned to reduce, eliminate, and

been corrected, the anticipated time noncompliance is expected to

prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).

Division staff may waive the requirement for a written report on a

noncompliance, and its causes; the period of noncompliance,

determine that additional requirements are needed to assure compliance

 They cause sheen on surface waters (regardless of volume), or They are within 100 feet of surface waters (regardless of volume).

Place hazardous waste containers under cover or in secondary containment.

**SECTION C: REPORTING** 

(b) Oil spills if:

(a) Visible sediment

stream or wetland

deposition in a

(b) Oil spills and

substances per Iten

1(b)-(c) above

(c) Anticipated

122.41(m)(3)]

bypasses [40 CFR

(d) Unanticipated

with the conditions

of this permit that

may endanger

environment[40

CFR 122.41(I)(7)]

health or the

bypasses [40 CFR

122.41(m)(3)]

release of

hazardous

1. Occurrences that Must be Reported

They are 25 gallons or more,

Permittees shall report the following occurrences:

(Ref: 40 CFR 302.4) or G.S. 143-215.85.

. Reporting Timeframes and Other Requirements

(d) Anticipated bypasses and unanticipated bypasses.

(a) Visible sediment deposition in a stream or wetland.

# NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

| EFFECTIVE: 04/01/19

# SELF-INSPECTION, RECORDKEEPING AND REPORTING

## **SECTION A: SELF-INSPECTION**

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts.  If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection in needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	Identification of the measures inspected,     Date and time of the inspection,     Name of the person performing the inspection,     Indication of whether the measures were operating properly,     Description of maintenance needs for the measure,     Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDCs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made:  1. Actions taken to clean up or stabilize the sediment that has left the site limits,  2. Description, evidence, and date of corrective actions taken, and  3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made:  1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of gracing (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover).  2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

## SELF-INSPECTION, RECORDKEEPING AND REPORTING

## SECTION B: RECORDKEEPING

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the

corrective action. 2. Additional Documentation to be Kept on Site In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make

- (a) This General Permit as well as the Certificate of Coverage, after it is received.
- Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

### PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems, (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,

(f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

(e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

**EFFECTIVE: 04/01/19** 

NORTH CAROLINA

🔰 Environmental Quality

## SEEDING SCHEDULE (REVISED: 1-1-86)

PLANTING RATE

120 LBS/ACRE

25 LBS/ACRE

SHOULDERS, SIDE DITCHES, SLOPES (MAX 3:1)

AUG 15 - NOV 1 NOV 1 - MAR 1	TALL FESCUE TALL FESCUE & ABRUZZI RYE	300 LBS/ACRE 300 LBS/ACRE 25 LBS/ACRE
MAR 1 - APR 15	TALL FESCUE	300 LBS/ACRE
APR 15 - JUN 30	HULLED COMMON BERMUDAGRASS	25 LBS/ACRE
JUL 1 — AUG 15	TALL FESCUE AND ***BROWNTOP MILLET ***OR SORGHUM—SUDAN HYBRIDS	120 LBS/ACRE 35 LBS/ACRE 30 LBS/ACRE
	SLOPES (3:1 TO 2:1)	
MAR 1 - JUN 1	SERICEA LESPEDEZA (SCARIFIED) &	50 LBS/ACRE
(MAR 1 - APR 15)	ADD TALL FESCUE	120 LBS/ACRE
(MAR 1 — JUN 30) (MAR 1 — JUN 30) JUN 1 — SEP 1	OR ADD HULLED COMMON BERMUDAGRASS	10 LBS/ACRE 25 LBS/ACRE 120 LBS/ACRE 35 LBS/ACRE 30 LBS/ACRE
SEP 1 - MAR 1	SERICEA LESPEDEZA (UNHULLED-UNSCARIFIED)	70 LBS/ACRE

CONSULT CONSERVATION ENGINEER OR SOIL CONSERVATION SERVICE FOR ADDITIONAL INFORMATION CONCERNING OTHER ALTERNATIVES FOR VEGETATION OF DENLIDED AREAS. THE ABOVE VEGETATION RATES ARE THOSE WHICH DO WELL UNDER LOCAL CONDITIONS; OTHER SEEDING RATE COMBINATIONS ARE POSSIBLE.

AND TALL FESCUE

ADD ABRUZZI RYE

\*\*TEMPORARY - RESEED ACCORDING TO OPTIMUM SEASON FOR DESIRED PERMANENT VEGETATION. DO NOT ALLOW TEMPORARY COVER TO GROW OVER 12" IN HEIGHT BEFORE MOWING, OTHERWISE FESCUE MAY BE SHADED

## SEEDBED PREPARATION

1.) CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.

2.) RIP THE ENTIRE AREA TO 6 INCHES DEPTH.

3.) REMOVE ALL LOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM. SUPERPHOSPHATE

4.) APPLY AGRICULTURAL LIME, FERTILIZER, AND UNIFORMLY AND MIX WITH SOIL (SEE BELOW\*).

5.) CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM INCHES DEEP. REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6

6.) SEED ON A FRESHLY PREPARED SEEDBED AND COVER AFTER SEEDING. SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK 7.) MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.

8.) INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.

9.) CONSULT CONVERSATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED. \* APPLY: AGRICULTURAL LIMESTONE - 2 TONS/ ACRES (3 TONS/ACRE IN CLAY SOILS)

FERTILIZER - 1,000 lbs. / ACRE -10-10-10, SUPERPHOSPHATE- 500 lbs> / ACRE -20% ANALYSIS, MULCH -2 TONS / ACRE - SMALL GRAIN STRAW, ANOTHER - ASPHALT EMULSION @ 300 GALS./ ACRE

09/17/2021 DRAWN BY R. WINGATE


**DESIGNED BY** P. BARBEAU


CHECKED BY P. BARBEAU

AS SHOWN

43398

SHEET NO. *C7.6* 





09/17/2021


R. WINGATE DESIGNED BY P. BARBEAU CHECKED BY P. BARBEAU SCALE


AS SHOWN


0


JOB NO. 43398 SHEET NO. C7.7


ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL TOWN OF ROLESVILLE, CITY OF RALEIGH, NCDEQ AND NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS

































THRUST BLOCKING

DESIGN QUANTITY TABLE











A NO	NE CO		- 023	3	
C 27607 mmons.com				5	

REVISIONS PER WAKE COUNTY COMMENTS	REVISIONS PER WAKE COUNTY COMMENTS	CONSTRIICTION DOCHMENT SHRMITTAL
	REVISIONS PER WAKE COUNTY COMMENTS	REVISIONS PER WAKE COUNTY COMMENTS REVISIONS PER WAKE COUNTY COMMENTS

0	
>	DRAWN BY
	R. WINGAT
	DESIGNED B
	P. BARBEA
	CHECKED B
	P. BARBEA
	SCALE
	AS SHOW


DATE


09/17/2021


0


JOB NO. 43398 SHEET NO.


C7.8













































CHECKED BY


P. BARBEAU


SCALE AS SHOWN


0


JOB NO. 43398 SHEET NO. *C7.9* 











































0

09/06/2023

DATE

09/17/2021 DRAWN BY

R. WINGATE

DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

SCALE

AS SHOWN

JOB NO. 43398 SHEET NO. C7.10


## ROADWAY STANDARD DRAWINGS:


THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION -RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD.NO.	TITLE
654.01	PAVEMENT REPAIRS
848.05	CURB RAMP - PROPOSED CURB AND GUTTER
904.50	MOUNTING OF TYPE 'D', 'E', AND 'F' SIGNS ON 'U' CHANNEL POSTS
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.07	PAVEMENT MARKINGS - PEDESTRIAN CROSSWALKS
1250.01	PAVEMENT MARKER SPACING
1743.02	PEDESTALS - NORMAL DUTY TYPE II

# NOTES

- REFER TO "ROAD STANDARD DRAWINGS NCDOT" DATED JANUARY 2018, "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2018.
- RRFB SHALL BE MOUNTED TO POWDER COATED BLACK AND THE CONTROLLER BOX SHALL BE LOCATED BEHIND THE SIGNS AND MOUNTED ON A TYPE II PEDESTAL (4.5" OD ALUMINUM POLES WITH TRANSFORMER BASES). REFER TO THE NCDOT ROADWAY STANDARD DRAWING 1743.02.





09/17/2021

R. WINGATE DESIGNED BY P. BARBEAU

CHECKED BY P. BARBEAU

AS SHOWN

43398 C7.11