

Addendum No.: 3

Date of this Addendum: **October 20, 2022**

Re: **Town of Rolesville Public Works Facility**
805 E. Young Street
Rolesville, NC 27571
IBI Group # 135941

To: Prospective Bidders,

Bid Opening Date: **October 25, 2022**
Bid Opening Time: **3:00 pm**
Bid Receipt Location: **Rolesville Town Hall,
502 Southtown Circle, Rolesville, NC 27571**

This Addendum shall and does hereby become a part of the construction documents for the above Project. Contractors submitting a bid shall be responsible for ensuring that they are properly apprised of the contents of this Addendum. The clarifications or modifications in this Addendum shall be incorporated into the Work of the referenced Project and all associated costs shall be accounted for in the General Contractor's lump sum bid. All information contained in this Addendum shall supersede and take precedence over any conflicting information in the original bid documents. All other requirements of the Work, except as modified herein, shall remain unchanged.

Receipt of this addendum shall be acknowledged in the Contractor's Bid. Failure to do so may constitute grounds for rejection of the bid.

GENERAL CLARIFICATIONS:

1. Please see attached RFI responses.

ALTERNATIVE PRODUCTS AND SUBSTITUTES

The following products and/or manufacturers are acceptable for submitting bids, subject to meeting all performance criteria and design characteristics of the contract documents. Within 30 days of Construction Contract execution, all such products shall be formally submitted with all documentation necessary for the designer to evaluate full compliance with the contract documents.

1. Trident Building Systems, Section 13 34 19 Metal Building Systems
2. Chief Buildings, MSC roof panel, , Section 13 34 19 Metal Building Systems

ATTACHED DOCUMENTS:

1. RFIs 60-64

End of Addendum

Addendum #3	All bidders		
Contract / Issue:	Rolesville Public Works Facility	IBI Group Project #	135941
Date Issued:	October 20, 2022	Questions received by 10/19/2022	
Item No.	Bidder Question (Incl: Dwg No, Specification, Section)	Response	
60	We do not meet the AISC requirements for Division 5, but we've had them waived in the past and instead included costs in our bid to hire a licensed structural engineer or third-party inspector (Terracon) to perform shop inspections and oversee quality control procedures during our fabrication. Please confirm if the EOR would accept these inspections in lieu of the AISC certification.	AISC is required for the project.	
61	With no Fire Alarm plan our electrical subcontractors are asking where the Fire Alarm panel to be located?	Fire alarm panel can be located on the Mezzanine level near the MDP	
62	There should be a 120v circuit for the fire alarm, what do you want to designate that as?	Run 120V circuit to MDP to feed the Fire Alarm Panel	
63	What does the "CDT" abbreviation mean on the electrical plans?	Conduit	
64	Is the electrician to supply any metering equipment?	There is no metering equipment other than the Utility meter equipment required by Duke installed by EC.	