

Memo

То:	Mayor Currin and Town Board of Commissioners			
From:	Meredith Gruber, Planning Director			
Date:	August 15, 2023			
Re:	Pearce Farm (formerly known as Tom's Creek)			
Rezoning Map Amendment - MA 21-10				
	Voluntary Annexation Petition - ANX 22-07			

Background

Meetings to Date

The meeting history for the Pearce Farm application is as follows:

- October 24, 2022 Planning Board (recommendation of denial)
- December 6, 2022 Town Board (removed from agenda)
- **December 19, 2022 Planning Board** (tabled application to January 23, 2023; continued to March 27, 2023)
- March 27, 2023 Planning Board (recommended approval 4 1)
- April 26, 2023 Parks and Recreation Advisory Board (recommended consistency with the Bike and Greenway Plans)
- May 2, 2023 Town Board (continued to June 6, 2023)
- June 6, 2023 Town Board (continued to August 1, 2023)
- August 1, 2023 Town Board (continued to August 15, 2023)

Application Updates

The applicant previously requested a continuance from June 6, 2023 to July 18, 2023, and the Town Board continued the rezoning and annexation cases to August 1, then August 15, 2023. The continuance request was made to allow time to conduct further review of their application and provide additional zoning conditions.

The Town Board of Commissioners opened a legislative hearing for MA 21-10 and ANX 22-07, Pearce Farm, on May 2, 2023 and continued it to June 6, 2023 to allow the applicant team time to update and clarify some of their proposed zoning conditions. Town Board members requested (1) clarification on amenity center timing, (2) collector road timing, and (3) greenway locations illustrated in the Concept Site Plan. Greenway location updates were previously requested by the Planning Board and the Parks and Recreation Advisory Board, and the Town Board of Commissioners asked for these recommendations to be addressed in the Concept Site Plan.


- (1) New condition: Prior to issuance of the 175th building permit, a building permit shall be submitted for the Main Amenity facility. The Main Amenity facility shall be substantially complete prior to issuance of the 325th building permit.
- (2) New condition: Prior to issuance of the 175th building permit, the East-West collector street shall be substantially complete and open for public vehicular service from Access A (Forestville Rd) to Access C (Burlington Mills Rd).
- (3) The updated Concept Site Plan shows a greenway connection to Burlington Mills Road and shows the additional soft trails. The Concept Site Plan is on page 3 of this Memo and is included as an attachment.

In addition to the new conditions noted above, the applicant volunteered additional conditions on July 18, 2023.

- New condition: Construction Documents for the Property to include on-lot grading including (i) proposed finished floor elevations, (ii) 4-corner finished-pad spot elevations, (iii) 1-foot contours of the proposed grades, (iv) proposed high point(s), (v) proposed swale directions, spot elevations, and slopes at not less than 2%,, and (vi) other information as necessary to demonstrate future feasibility of compliance with section R401.3 of the NC Residential Code.
- (2) New condition: After home construction, each lot shall have not less than: (i) 3 large shrubs and 6 small shrubs between the R.O.W. and the front façade of the home, and (ii) 1 large shrub and two small shrubs in the rear yard of the home. Large shrubs shall be those whose mature size is 5'-8' in height and shall be planted at not less than 30" in height. Small shrubs shall be those whose mature size is 2'-4' in height and shall be planted at not less than 20" in height.
- (3) New condition: Prior to the issuance of the 325th building permit, a single family detached lot shall be developed and donated as part of Wounded Warrior Homes, Operation Coming Home, Operation Finally Home, or similar organization providing homes to veterans. Developer and builder shall be entitled to a waiver of all Town of Rolesville permit fees for this home.

Map Amendment (MA 21-10)

The Town of Rolesville Planning Department received a Map Amendment (Rezoning) application in December 2021 for 222.94 acres located at unaddressed properties on Forestville Road, Burlington Mills Road, and Alstonberg Avenue with Wake County PINs 1748891680, 1758081893, and 1748884104. The property owner and Applicant, POGE LLC and ESNE LLC., is requesting to change the zoning from Wake County's Residential-30 (WC R-30) District and Rolesville's Residential Low (RL) District to Residential Medium Density Conditional Zoning District (RM-CZ). The application includes a Vision & Intent Statement, proposed Conditions of Approval, a Concept Site Plan, and illustrations of the intended development. On May 2, 2023, the Town Board of Commissioners opened a legislatve hearing and continued the hearing to June 6, 2023.



Final Concept Site Plan

Annexation Petition (ANX 22-07)

In August 2022, a petition for a contiguous Voluntary Annexation (ANX 22-07) of the same subject properties as the Map Amendment was received and is being reviewed/processed simultaneously with the rezoning request. As provided by G.S. 160A-31, the petition was investigated by the Town Clerk as to its sufficiency of meeting G. S. 160A-31 after the October 4, 2022 Town Board Meeting. On April 4, 2023, the Town Board of Commissioners scheduled a legislative hearing for the Pearce Farm annexation petition (to be held May 2, 2023). On May 2, 2023, the Town Board of Commissioners opened a legislative hearing and continued the hearing to June 6, 2023.

Applicant Justification

The applicant provided a "Vision & Intent" justification statement as part of the most recent Submittal materials – see pages 3 and 4 of Attachment 5.

Neighborhood Meeting

The applicant has held two neighborhood meetings during the review of this application to date:

- 1. An on-line meeting on June 2, 2022 see Attachment 6 for materials.
- 2. An on-line meeting on December 1, 2022 the applicant provided no materials for this.

Comprehensive Plan

Land Use

The Future Land Use Map designates the subject parcels as Medium Density Residential, which is described as predominately single family residential uses with portions of duplex, townhouse, and/or multifamily residential. These are lots or tracts at a density range of three to five dwelling units per gross acre including preserved open space areas.

Community Transportation Plan

The Town of Rolesville's Community Transportation Plan (CTP, adopted 2021) includes recommendations for Thoroughfares, Collectors, and intersections.

Thoroughfare Recommendations

- Forestville Road is planned to be a 4-lane median-divided section with curb & gutter and sidepaths.
- Burlington Mills Road is planned to be a 4-lane median-divided section with curb & gutter, bike lanes, and sidewalks.

Collector Recommendations

- A Collector connection between Forestville Road and Burlington Mills Road is shown as part of the Proposed Network.
- A Collector connection to the future Stone Fly Drive extension is also shown.

Intersection Recommendations

• No intersection recommendations are included on the Proposed Network Map.

Greenway Plan

As per the 2022 Greenway Plan, proposed Greenways are shown in the following locations:

• Traversing north – south between Burlington Mills Road and Tom's Creek.

Traffic

Traffic Impact Analysis

The consulting firm, Stantec, performed the Traffic Impact Analysis (TIA) for this project on behalf of the Town; the study analyzed a development of 606 Single Family Detached housing units, which is analogous to the proposed density of 2.7 dwelling units per acre over the gross 224 acre site. The Final Report dated July 28, 2022 is included as Attachment 7 to this memo; the NC DOT Congestion Management section Report on the TIA is Attachment 8. Both Trip

Generation and Intersection Improvements were looked at in three phases: Initial Phase, Intermediate Phase, and Full Build.

TIA Summary - Trip Generation	Entering	Exiting	Total
2026 Initial Phase Recommendations			·
AM Peak (7-9 am)	35	98	133
PM Peak (4-6 pm)	118	69	187
Weekday Daily Trips	917	917	1,834
2028 Intermediate Phase Recommendations			
AM Peak (7-9 am)	35	101	136
PM Peak (4-6 pm)	121	71	192
Weekday Daily Trips	939	939	1,878
Cumulative Trips	1,856	1,856	3,712
2029 Full Build Recommendations			
AM Peak (7-9 am)	30	85	115
PM Peak (4-6 pm)	101	60	161
Weekday Daily Trips	791	791	1,582
Cumulative Trips	2,647	2,647	5,294

Five intersections were studied for capacity analysis and level of service (LOS) impact of this development.

TIA Summary – Intersection Improvements		
2026 Initial Phase Recomme	ndations	
#1 - Burlington Mills Road at Centaur Road / Access C	 Construct Access C as a full-movement access point Construct Access C with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet 	
#2 - Forestville Road at Access A	 Construct Access A as a full-movement access point Construct Access A with one ingress and two egress lanes (one left-turn lane and one right-turn lane) with a driveway stem length of a minimum of 170 feet Construct a northbound Forestville Road right-turn lane with 100 feet of full-width storage and appropriate taper Construct a southbound Forestville Road left-turn lane with 100 feet of full-width storage and appropriate taper 	
2028 Intermediate Phase Recommendations		
#3 - Burlington Mills Road at Forestville Road	 Extend the existing eastbound Burlington Mills Road left- turn lane to 575 feet of full-width storage and appropriate taper 	

	 Extend the existing westbound Burlington Mills Road left- turn lane to 225 feet of full-width storage and appropriate taper Construct a westbound Burlington Mills Road right-turn lane with 150 feet of full-width storage and appropriate taper Extend the existing northbound Forestville Road left-turn lane to 225 feet of full-width storage and appropriate taper Extend the existing southbound Forestville Road left-turn lane to 300 feet of full-width storage and appropriate taper Construct a southbound Forestville Road right-turn lane with 200 feet of full-width storage and appropriate taper The above recommendations will require the traffic signal at the intersection to be modified 	
#4 - Burlington Mills Road at Access B	 Construct Access B as a right-in/right-out access point Construct Access B with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet 	
#2 - Forestville Road at Access A	Monitor Access A for potential signalization	
2029 Full Build Recommend	ndations	
#5 - Burlington Mills Road at Huntingcreek Drive /Access D	 Construct Access D as a full-movement access point Construct Access D with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet 	
#2 - Forestville Road at Access A	Monitor Access A for potential signalization	


Development Review

The Technical Review Committee (TRC) reviewed three versions of the Rezoning Map Amendment application, with all comments being resolved, prior to the initial presentation of the application to the Planning Board on October 24, 2022. Town Planning staff and necessary members of the TRC reviewed the fourth submittal prior to the planned December 6, 2022 Town Board of Commissioners meeting (applicant withdrew from consideration), and the Planning Board meeting on December 19, 2022. Town Planning Staff received the fifth submittal on March 22, 2023; this was presented to the Planning Board of March 27, 2023 and to the Town Board of Commissioners at their May 2, 2023 meeting. This seventh submittal is presented with this Memo as the applicants' final submittal for consideration by the Town Board.

Planning Board / Parks & Recreation Advisory Board / Town Board of Commissioners Meetings to Date

October 24, 2022 Planning Board Meeting

At this meeting, Planning Board members heard presentations from Planning Department staff and the applicant team on Map Amendment/Rezoning MA 21-10 Tom's Creek. Board members voted 4-1 on a motion to recommend denial to the Town Board of Commissioners. This recommendation was based on a lack of detail on lot sizes, dwelling types, and open space; board members were not comfortable with the amount of information provided on the bubble diagram style concept plan.



Concept Site Plan Presented at the October 2022 Planning Board Meeting

December 6, 2022 Town Board of Commissioners Meeting

The applicant chose to withdraw the case from the agenda that evening to further revise/refine the application. The Mayor and Commissioners accepted the applicant's request to send the updated case materials back to the Planning Board for consideration at their December 19, 2022 meeting.

December 19, 2022 Planning Board Meeting

The Board heard presentations from Planning Department staff and the applicant team; discussion on many aspects of the proposed development occurred. The applicant asked to table the discussion by the Planning Board to research and come back to the Planning Board to address a list of items (see minutes). The Planning Board voted 5-1 on a motion to continue the discussion to January 23, 2023. (The case was further continued to the March 27, 2023 Planning Board meeting.)

March 27, 2023 Planning Board Meeting

The Planning Board heard presentations from Planning Department staff and the updated applicant team (Ammons Development and Alliance Group NC). The applicant team discussed the many changes made to the application and the discussions and relationships forged with surrounding property owners. Planning Board discussion focused on greenway locations, the number of dwelling units proposed, transportation improvements, stormwater, speed limits, and an outdoor museum. On a motion to recommend approval to the Town Board of Commissioners, the Planning Board voted 4-1.

April 26, 2023 Parks and Recreation Advisory Board (PARAB) Meeting

The Parks and Recreation Advisory Board heard presentations from Planning staff and the applicant team (Ammons Development and Alliance Group NC). After discussion amongst all parties, the Board unanimously approved the following motion to the Town Board of Commissioners: I [PARAB] make a recommendation to revise the Concept Site Plan to include the bike lanes on Burlington Mills Road and the side path on Forestville Road and the new collector road and an additional section of greenway that connects to Burlington Mills Road so that the Concept Site Plan is consistent with both the adopted Bike and Greenway Plans.

May 2, 2023 Town Board of Commissioners Meeting

Planning staff and the applicant both made presentations to the Town Board of Commissioners on May 2, 2023. The Town Board opened a legislative hearing and continued it to June 6, 2023 to allow the applicant time to update and clarify some of the zoning conditions. Desired condition updates included amenity center timing, collector road timing, and greenway layout.

June 6, 2023 Town Board of Commissioners Meeting

The legislative hearing was continued to August 1, 2023.

August 1, 2023 Town Board of Commissioners Meeting

The legislative hearing was continued to August 15, 2023.

LDO Appendix A / 2.3.G. Review Standards with Staff Responses

The Land Development Ordinance (LDO) Handbook, Appendix A, includes the following review standards when considering a rezoning request.

 Is the application consistent with the Comprehensive Plan and other applicable adopted Town plans; <u>Staff Response</u>: The application is consistent with the Comprehensive Plan. The proposed residential use is consistent with the Medium Density Residential land use

proposed residential use is consistent with the Medium Density Residential land use designation. The transportation network as illustrated in the Concept Site Plan is consistent with the Community Transportation Plan, Bike Plan, and Greenway Plan.

- Is the application in conflict with any provision of the LDO or the Town Code of Ordinances;
 <u>Staff Response</u>: The application is consistent with the LDO. Subsequent future development submittals are required to meet the LDO as well.
- 3. Does the application correct any errors in the existing zoning present at the time it was adopted;

<u>Staff Response</u>: There are no zoning errors to correct.

- 4. Does the application allow uses that are compatible with existing and allowed uses on surrounding land; <u>Staff Response</u>: The application is for single family detached housing at a density of 2.5 units per acre. The proposed residential use, along with the landscape buffers and open space provided around the perimeter of the site, create an appropriate transition to other residential uses and/or vacant land that is residentially zoned.
- 5. Would the application ensure efficient development within the Town, including the capacity and safety of the street network, public facilities, and other similar considerations;

<u>Staff Response</u>: The application can enhance the Town's capacity and safety of the street network through compliance with the Community Transportation Plan and building of required roadway improvements.

- 6. Would the application result in a logical and orderly development pattern; and <u>Staff Response</u>: The Concept Site Plan, included as a condition of this rezoning request, illustrates a logical and orderly development pattern through the layout of the residential lots within the vehicular and pedestrian circulation network. Open space design/placement highlights the center of the neighborhood.
- 7. Would the application result in adverse impacts on water, air, noise, storm water management, wildlife, vegetation, wetlands, and the natural functioning of the environment. <u>Staff Response</u>: The subsequent future development submittals that may follow this rezoning application are required to meet LDO standards and other state and/or federal

*regulations.*8. If a conditional rezoning, the Board of Commissioners may also consider if the conditional rezoning addresses the impacts reasonably expected to be generated by the development or use of the site, can reasonably be implemented and enforced for the subject property, and if it will mitigate specific issues that would likely result if the subject

property were zoned to accommodate all the uses and the minimum standards of the corresponding general zoning district. <u>Staff Response</u>: The applicant has proposed conditions covering architectural requirements, transportation network improvements, open space, on-lot grading during

requirements, transportation network improvements, open space, on-lot grading during construction document submittal, on-lot landscaping, and others to enhance the design of the neighborhood above what would be required for a straight Residential Medium *(RM)* zoning district.

Staff Recommendation

MA 21-10 - Map Amendment Rezoning Application

Staff finds the proposed rezoning request MA 21-10 is consistent with the Comprehensive Plan and recommends approval of it.

ANX 22-07 – Voluntary Annexation Petition

Staff finds the petition for Voluntary Annexation (see Attachment 9) to be complete. The Town Clerk has provided a Certificate of Sufficiency dated October 26, 2022 (see Attachment 10).

Consistency and Reasonableness

As noted above under the Comprehensive Plan section of this report, the rezoning request for the subject parcels is consistent with the Future Land Use designation of *Medium Density Residential*. The Concept Site Plan and proposed Conditions of Approval express general consistency with the Community Transportation Plan, Bicycle Plan, and Greenway Plan. Map Amendment MA 21-10 is thus consistent with the Comprehensive Plan and other applicable Plans and is therefore reasonable.

Proposed Motions

- 1. Motion to (approve or deny) rezoning Map Amendment request MA 21-10 Pearce Farm.
- 2. (Following Approval) Motion to adopt a Plan Consistency Statement and Statement of Reasonableness for MA 21-10.
- 3. Motion to (approve or deny) the Voluntary Annexation Petition received under G.S. 160A-31 for ANX 22-07 Pearce Farm.

Attachments


1	Vicinity Map	
2	Future Land Use Map	
3	Zoning Map	
4	Map Amendment Application – Updated March 23, 2023	
5	Submittal Package – July 18, 2023	
6	Neighborhood Meeting Package – June 2, 2022	
7	Traffic Impact Analysis (TIA) dated July 28, 2022	
8	NCDOT Congestion Management Section Report	
9	Voluntary Annexation Petition	
10	Annexation Certificate of Sufficiency – signed October 26, 2022	

ATTACHMENT 1 - VICINITY MAP



S

Case: MA 21-10 Tom's Creek Pearce Farm Address: 0 Forestville Rd, 0 Burlington Mills Rd, 0 Alstonburg Ave PIN 1748891680, 1758081893, 1748884104 Date: 04.14.2022






Case: MA 21-10 Tom's Creek Address: 0 Forestville Rd, 0 Burlington Mills Rd, 0 Alstonburg Ave PIN 1748891680, 1758081893, 1748884104

ATTACHMENT 2 - Future Land Use Map

Date: 04.14.2022




Date Saved: 4/14/2022 10:14 AM

C:\Users\SRaby\Desktop\GIS\2022 Projects\MA 21-10 Tom's Creek\MA 21-10 Tom's C


ATTACHMENT 3 - Zoning Map



Case: MA 21-10 Tom's Creek Pearce Farm Address: 0 Forestville Rd, 0 Burlington Mills Rd, 0 Alstonburg Ave PIN 1748891680, 1758081893, 1748884104 Date: 04.14.2022







Map Amendment Application

Contact Information

Property Owner POGE, LLC & ESNE, LLC		
Address PO Box 97487	City/State/Zip Raleigh, NC 27624	
Phone <u>919-845-6415</u>	Emailandy@ammonsdg.com	
Developer Ammons Development Group		

Contact Name Drew Ammons & Jacob Anderson	
Address PO Box 97487	City/State/Zip Raleigh, NC 27624
Phone 919-845-6415	Email_drew@ammonsdg.com

Property Information

Address O Forestville Rd, 0 Burlington Mills Rd, and 0 Alstonberg Ave Wake Forest, NC 27587

Wake County PIN(s) 1748891680, 1758081893, 1748884104

Current Zoning District <u>RL</u>	_ Requested Zoning District	RM-CZ
-----------------------------------	-----------------------------	-------

Total Acreage 222.94

Owner Signature

I hereby certify that the information contained herein is true and completed. I understand	d that if any item is
found to be otherwise after evidentiary hearing before the Town Board of Commissioner	s, that the action of the
Board may be invalidated.	
Signature MANT HUM MANHOR	Date 3/23/23

STATE OF NORTH CAROLINA

COUNTY OF WAKE

I, a Notary Public, do hereby certify that ANDREW L. AMMONS

personally app	eared before me th	is day and a	cknowledged the	due execution of the	foregoing instrun	ient. This
the 23rd			day of _	MARCH	2023	·
My commission	rexpires <u>03/28/27</u>			MABETH A. X	A	
Signature	AM		Seal	COMMISSION EXP	RES	
/	PO Box 250 / Role		ı of Rolesville Pla Carolina 27571 / I		1. 19:554.6517	

PEARCE FARM

Rolesville NC

PEARCE FARM | Rolesville, NC

TABLE OF CONTENTS

- 1. VISION & INTENT
- 2. DISTRICT DATA TABLE
- 3. GENERAL DISTRICT CONDITIONS
- 4. ARCHITECTURAL STANDARDS
- **5. TRANSPORTATION IMPROVEMENTS**
- 6. CONTEXT MAP
- 7. CONCEPT PLAN
- 8. Example Architecture
- 9. Active and Passive Open Spaces

1) VISION AND INTENT

INTRODUCTION

The proposed Pearce Farm project is located on approximately 224 acres within the western extents of the Town of Rolesville Planning Jurisdiction with a de minimis far western portion of property located within the Wake County Planning Jurisdiction. The property within the Rolesville Jurisdiction is currently zoned *Residential Low Density* with the Wake County Zoning designated at *R*-30. The site has roadway access along both Forestville Road and Burlington Mills Road and is located to the north of the Tom's Creek Riparian corridor. When the Town of Rolesville adopted the new LDO in 2021, the goal was to promote smart development in a growing region. A meaningful feature of the ordinance was its arrangement to ensure future neighborhoods would promote the preservation of natural resources and open space while also providing a variety of housing options within each Residential District. This rezoning application, as demonstrated within its Concept Plan, will achieve these goals, provide exceptional quality of life for new and existing residents, and will certainly become a valuable part of the fabric of Rolesville.

COMPREHENSIVE PLAN CONFORMITY

The proposal for this project is to rezone the parcels to Residential Medium Density – Conditional District. This Zoning District is defined by the Rolesville Land Development Ordinance (LDO) as having overall density generally between three (3) and five (5) dwelling units per acre (du/ac). The Zoning Application for Pearce Farm proposes to limit the overall density to 2.7 du/ac. As depicted in the included Concept Plan, Pearce Farm is proposed under LDO 3.1.B. As a supplement to the Zoning, the Concept Plan is presented with the application to provide more detail on a potential lot layout that would conform to the conditions proposed in this application.

RESPECT FOR NEIGHBORS

To ameliorate the impacts of its transportation improvements as called for by NCDOT and Town of Rolesville (discussed later), Pearce Farm will provide access and safety enhancements well surpassing the required and conventional standards for individual homeowners adjacent to roadway improvements along Forestville and Burlington Mills roads. Such improvements will variously include upgrades to individual driveways and aprons allow for better ingress and egress, curb and gutter, stormwater improvements, and enhanced landscaping to provide additional placemaking for the surrounding community.

Pearce Farm will provide appropriate screening and/or fencing along existing property owners which about the future individual residential units. Notations for such screening locations are labeled on the Concept plan.

Further, this project will also include significant Architectural Standards for new homes. The specifics of these guidelines are included in this package and include commitments for raised foundations, front porches, high quality façade materials, and promotion of diversity in the home styles by creating restrictions on repeating certain building elements for lots adjacent to each other. To illustrate the design vision of the Architectural Standards, example elevations of compliant designs are attached as Section 9, hereof.

ENVIRONMENTAL STEWARDSHIP

Per the criteria of LDO 3.1.B, the project will have a minimum of 40% open space. Within this, there is an Active Open Space requirement as highlighted in the Site Data Table below. The overall open space will consist of a public greenway trail, soft surface walking trails, a community amenity, land dedicated to the

Town for a public park and concentrated activity areas spaced throughout the community. In addition to the open space commitments, a series of Zoning Conditions are included as a part of this application.

Pearce Farm will comply with all Rolesville and North Carolina requirements for the treatment and detention of stormwater to ensure that it preserves the existing quality and quantity of the flow in the waterbodies of the Tom's Creek riparian corridor. Further, by virtue of its design, as seen on the Concept Plan, Pearce Farm will have substantially less new impervious surface than would otherwise be permitted on the site under Residential Medium Density, alone.

COMMUNITY BENEFITS

As shown on the enclosed Concept Plan, Pearce Farm proposes a residential collector street which will provide an east-west connection from Burlington Mills Rd. to Forestville Rd. allowing for the residents within the residential development to easily access either State Road. This road connection will also allow surrounding existing residents to avoid the intersection of Burlington Mill and Forestville for more of their travel. This will permit that intersection to perform better than shown in the TIA. The residential collector street also will provide adequate pedestrian and vehicular (on-street parking) access to trails and greenspace provided in the updated Parks shown in the Concept Plan.

As shown on the Concept Plan, Pearce Farm will provide a chain of active and passive open spaces accessed both by a greenway and a public parkway for robust access and engagement by all residents and citizens. These spaces, along with the community's active private amenities, will provide a superlative lifestyle experience for new and existing residents.

The Concept Plan depicts the public park dedication, including dedicated trailheads with parking for future Town use, needed to enhance the public greenway system.

Traffic is a meaningful concern for residents of this area of Rolesville. Pearce Farm will be a part of the solution. Pearce Farm, if approved, will complete upgrades to Forestville Rd, Burlington Mills Rd, and the intersection of Burlington Mills Rd. & Forestville Rd. The upgrades will help to manage existing through traffic on Forestville Rd. & Burlington Mills Rd. and alleviate some of the congestion at their intersection which would otherwise remain indefinitely unmitigated. The Town of Rolesville selected Stantec to perform a Traffic Impact Analysis (TIA) to evaluate the traffic network and selected roadway intersections near the project site. The full report has been submitted to the Town and NCDOT for review. The study identified a series of improvements that will be required, including improvements at the intersection of Forestville and Burlington Mill Roads, and at each of the four (4) proposed driveway connections for this project. A detailed list of the improvements is included with this package. This list also identifies the timing of when the infrastructure improvements will be completed.

2) RM-CZ DISTRICT DATA

Land Use Category	Required	Proposed
Open Space	89.86 ac	91.00 ac
Active Open Space	13.48 ac	22.0 ac
Public Park Land Dedication	Included in above	5.00 ac + 4.00 ac
		trailhead(s)
Community Amenity		4.5 ac
Public Greenway Trail	N/A	4,500 lf
Private, Soft-surface Trails	N/A	4,500 lf
Lot Development Standards		
Front Setback	20'	20'
Side Setback	5'	5'
Corner Setback	10'	10'
Rear Setback	20'	20'
Lot Area	5,000 sf (min)	5,000 sf – 7,500 sf

3) GENERAL DISTRICT CONDITIONS

- The following uses otherwise permitted in the district are prohibited: (i) Major Utility, excluding City of Raleigh Public Utilities or other Public or Private Utilities required by the Town of Rolesville for Public Benefit (i.e. Water Tower), and (ii) Telecommunication Tower.
- 2. The subject property shall be developed generally in accordance with the <u>Concept Plan</u> attached hereto and incorporated herein as if fully set out.
- 3. The subject property shall be developed in accordance with the <u>Architectural Requirements</u> attached hereto and incorporated herein as if fully set out.
- 4. The subject property shall be developed in accordance with the Transportation Improvements attached hereto and incorporated herein as if fully set out.
- 5. Total residential density shall not exceed 2.7 units per acre.
- 6. A Homeowners Association (HOA) shall be established in accordance with the Rolesville Land Development Ordinance. HOA documents must be recorded with the first final plat.
- A main central amenity will be constructed with development of these properties and shall include a

 (i) Clubhouse, (ii) Pool, (iii) Pickleball Courts, (iv) Grilling Station(s) and/or Fire Pit(s). and (v) other
 recreational outdoor activities for residents of the development (collectively, the "<u>Amenity Facility</u>").
- 8. In addition to the approximately 4,500-feet of greenway, as depicted on the master plan, development shall provide at least the same length of private trails (>4,500-feet) to connect programmed open spaces within the properties.
- 9. Open Space throughout the Development shall include:
 - Garbage and Pet Waste Receptacles to be maintained by the HOA.
 - Reestablishment of ground cover, shrubbery, and tree plantings using only native species, and to specifically include low-to-no maintenance plantings on slopes greater than 4:1, especially perennial flowering and fruit-bearing groundcover and tree species which provide food and habitat for pollinators.
- 10. At the time of the recording of the first plat adjoining any portion of 2017 Forestville Road (Wake PIN: 174-869-4159), approximately 4 acres of this parcel shall be dedicated to the Town as shown on the Concept Plan. In addition, at the time of the recording of the first plat adjoining any portion of 4124 Burlington Mills Road (Wake PIN: 1749-80-8878), approximately 5 acres of this parcel shall be dedicated to the Town as shown on the Concept Plan. These areas shall be dedicated as public park space subject to various grading, landscape, slope, roadway, pedestrian access, and utility easements, etc. as may be mutually beneficial to the Development and/or the Town for completion of the Development and/or the park space.

- 11. At the time of the recording of the first plat dedicating Access "B" upon the adjoining parcel known as 4124 Burlington Mills Road (Wake PIN: 1749-80-8878) as shown on the Concept Plat, Access "B" shall be constructed across said adjoining parcel through the public access easement.
- 12. Prior to issuance of the 175th building permit for a home, a building permit shall be submitted for the Main Amenity facility. The Main Amenity facility shall be substantially complete prior to issuance of the 325th building permit.
- 13. Prior to issuance of the 175th building permit, the East-West collector street shall be substantially complete and open for public vehicular service from Access A (Forestville Rd) to Access C (Burlington Mills Rd).
- 14. Construction Documents for the Property to include on-lot grading including (i) proposed finished floor elevations, (ii) 4-corner finished-pad spot elevations, (iii) 1-foot contours of the proposed grades, (iv) proposed high point(s), (v) proposed swale directions, spot elevations, and slopes at not less than 2%,, and (vi) other information as necessary to demonstrate future feasibility of compliance with section R401.3 of the NC Residential Code.
- 15. After home construction, each lot shall have not less than: (i) 3 large shrubs and 6 small shrubs between the R.O.W. and the front façade of the home, and (ii) 1 large shrub and two small shrubs in the rear yard of the home. Large shrubs shall be those whose mature size is 5'-8' in height, and shall be planted at not less than 30" in height. Small shrubs shall be those whose mature size is 2'-4' in height, and shall be planted at not less than 20" in height.
- 16. Prior to the issuance of the 325th building permit, a single family detached lot shall be developed and donated as part of Wounded Warrior Homes, Operation Coming Home, Operation Finally Home, or similar organization providing homes to veterans. Developer and builder shall be entitled to a waiver of all Town of Rolesville permit fees for this home.

4) ARCHITECTURAL STANDARDS

- Foundations will be crawl space or raised slab which vary in height based on topography and drainage requirements. Foundations will be constructed at a minimum height of 18" in not less than one location on any home.
- Foundations will be brick or stone veneered on the front elevation of all homes and on the side elevation on corner lots.
- All single-family detached homes will be constructed with a front porch with a minimum porch depth of 6'.
- Exterior wall materials may include wood, synthetic wood, cementitious materials (horizontal siding, shakes, board and batten), brick and/or stone. Front facades and the side elevations on corner lots will include a minimum of two of these materials.
- Any primary roof pitch facing a street will be greater than or equal to 5:12 and will be clad in architectural roof shingles. Secondary or accent roof pitches will be greater than or equal to 3:12 and may be clad in architectural shingles or metal roofing materials.
- There will be no uninterrupted building planes greater than 30' which face a street, including the side elevations on corner lots.
- The depth of eaves will be a minimum of 6" except for bay window or similar façade projections which may have eaves of not less than 2".
- Garage doors will include glass inserts for all front-entry garage homes. Glass design will vary, per plan.
- All windows, soffits, eaves, shutters, facia, and other exterior trims will be constructed of weather-resistant materials including cementitious, vinyl, synthetic, or metal products.
- To ensure architectural diversity and a varied streetscape in the community, no floor plan and elevation will be repeated on adjoining lots or homes directly across the street from one another. The front elevations offered will differ with respect to the following: (1) wall materials and siding configurations, (2) porch architecture and width, (3) masonry types or selections, (4) rooflines and roofing selections, (5) window size, placement, and grille styles, and (6) exterior color palettes.

Note: To illustrate the design vision of the Architectural Standards, example elevations of compliant designs are attached as "Exhibit C".

5) TRANSPORTATION IMPROVEMENTS

Prior to the issuance of the 100th Certificate of Occupancy (C.O.) for the Project Burlington Mills Road at Forestville Road:

- Construct an exclusive westbound right-turn lane with 150' of storage.
- Construct an exclusive southbound right-turn lane with 200' of storage.
- Extend the existing southbound left-turn lane to provide 300' of storage.
- Extend the existing westbound left-turn lane to provide 225' of storage.
- Extend the existing northbound left-turn lane to provide 225' of storage.
- Extend the existing eastbound left-turn lane to provide 575' of storage.

Prior to the issuance of any C.O. for the phase of development which includes Access A:

Forestville Road at Access A:

- Construct an exclusive northbound right-turn lane with 100' of storage.
- Construct an exclusive southbound left-turn lane with 100' of storage.
- Monitor intersection for signal warrants and install if/when warranted.

Forestville Road Frontage

Construction of ½ of the planned ultimate roadway section along the site frontage on Forestville Road.
 The ultimate section for Forestville Road consists of a 4-lane median divided roadway with sidepaths.

Prior to the issuance of any C.O. for the phase of development which includes Access B, C, or D: Burlington Mills Road:

Construction of ½ of the planned ultimate roadway section along the site frontage on Burlington Mill Road.
 The ultimate section for Burlington Milles Road consists of a 4-lane median divided roadway with bike lanes and sidewalks.

Prior to the issuance of any C.O. for the phase of development which includes Access B: Burlington Mills Road at Access B:

• Construct and exclusive eastbound right turn lane with 50' of storage.

Prior to the issuance of any C.O. for the phase of development which includes Access C: Burlington Mills Road at Access C/Centaur Road:


- Construct an exclusive eastbound right-turn lane with 50' of storage.
- Construct an exclusive westbound left-turn lane with 50' of storage.

Prior to the issuance of any C.O. for the phase of development which includes Access D: Burlington Mills Road at Access D/Huntingcreek Drive:

- Construct an exclusive eastbound right-turn lane with 50' of storage.
- Construct an exclusive westbound left-turn lane with 50' of storage.

CONTEXT MAP

PEARCE FARM | Rolesville, NC










THORNDIKE DR

STONEGATE AT ST **ANDREWS**

GREENVILLE LOOP RD



EAGLEROOST CT






XHIBI Ш \triangleleft Σ \times AN ROL **ARM** RTH CA \triangleleft NORTH C L H L PEAR



AGN-23001 03. 22. 2023

CONCEPT PLAN



-				
	Total Site Area	+/-224.64 acres	LOT SUMMARY	
I	Proposed Zoning	Medium Density Residential	60'x125' lot size (7,500 sf) +/-135 lots (24%)	
	Development Type	Cluster	50'x125' lot size (6,250 sf) +/-116 lots (21%)	
	Open Space Required (40%)	+/-89.86 acres	40'x130' lot size (5,200 sf) +/-155 lots (28%)	
[.	Open Space Provided	+/-91.00 acres	45'x130' lot size (5,850 sf) +/-154 lots (27%)	
4	Active Open Space Required (1/2 of 12% Base District Required)	+/-13.48 acres	Total Dwelling Units+/-560 DU	
	Active Open Space Provided	+/-22.70 acres	*Note: any product type may vary up to 10%.	



PREPARED FOR: DEVELOPMENT GROUP AGN-23001

PEARCE FARM SKETCH PLAN ROLESVILLE, NORTH CAROLINA





EXAMPLE ARCHITECTURE

PEARCE FARM RESIDENTIAL ELEVATIONS - ALLEY LOADED HOMES



















PEARCE FARM RESIDENTIAL ELEVATIONS - FRONT LOADED HOMES















PREPARED FOR:

AMMONS DEVELOPMENT GROUP

AGN-23001

MCADAMS



PEARCE FARM RESIDENTIAL ELEVATIONS - RANCH STYLE HOMES













PEARCE FARM PRECEDENT IMAGES ROLESVILLE, NORTH CAROLINA

ACTIVE AND PASSIVE OPEN SPACES

PEARCE FARM | Rolesville, NC

PEARCE FARM ACTIVE OPEN SPACE



GATHERING AREAS WITH FIRE PITS AND SEATING
















PEARCE FARM PASSIVE OPEN SPACE - GREENWAYS + SOFT TRAILS



GREENWAY TRAILS WITH FENCING AND LANDSCAPE FEATURES



GREENWAY WITH BENCHES



















PEARCE FARM PASSIVE OPEN SPACE - PONDS + NATIVE PLANTS









RANDOLPH

What makes a pollinator garden valuable?

- Variety of plants that provide both nectar and pollen sources.
 Located in sunny areas with sufficient density to provide shelter
 Establish continuous bloom—providing food throughout the g
- Planted with host plants to support reproduction.

How can I help?

- Plant your own pollinator garden at home! Any size is beneficial.
- · Support pollinator friendly businesses-especially local nurseries and ga
- that offer pollinator-friendly plants and seeds that are suited to your local Spread the word!

What kinds of native plants are in this pollinator

- Swamp Milkweed Asclepias incarnata
 Great Blue Lobelia Lobelia siphilitica
- Bee Balm or Wild Bergamot Monarda
 Dense Blazing Star Liatris spicata
- New Jersey Tea Ceanothus americanus
 Whorled Milkweed Asclepias verticilla
- Golden Ragwort Packera aurea
- Cardinal Flower Lobelia cardinal



NEIGHBORHOOD MEETING NOTICE

May 19, 2022

NEIGHBORHOOD MEETING NOTICE

Dear Property Owner:

As a representative of the proposed developer, Toll Brothers, we are sending this letter to invite you to a community engagement meeting regarding the Tom's Creek rezoning in Rolesville, North Carolina. If you are receiving this letter, it is our understanding that you own property or belong to a neighborhood association within 200 feet of the subject property.

The site of the proposed rezoning is located between Burlington Mills and Forestville Rd with the PINs 1748891680, 1758081893, and 1748884104. During the meeting, the applicant will present its plans to rezone this land from MH (Manufactured Home) and R-30 to Residential Medium Density. The total site area is approximately 224.64 acres.

We will be hosting a virtual neighborhood meeting via Zoom (see instruction sheet for details). The meeting will be held on June 2nd, 2022 from 6:00pm to 7:00pm Eastern Time. We welcome any questions or comments on the proposed project prior to the meeting.

If you have questions or cannot attend the meeting but would like further information, please feel free to contact Laura Holloman by phone: 919.610.7377 or email: <u>holloman@mcadamsco.com</u>.

Sincerely, MCADAMS

Xaurofich

Laura Holloman, AICP Sr. Planner, Planning + Design Group 919.610.7377 holloman@mcadamsco.com



NEIGHBORHOOD MEETING NOTICE

May 19, 2022

RE: Tom's Creek Rezoning Virtual Neighborhood Meeting – Zoom Instructions

Dear Property Owner,

We will be hosting a virtual neighborhood meeting via Zoom Webinar. The meeting will be held on June 2nd and begin at 6:00 PM Eastern Time.

- To attend the meeting via computer, type in the following link in your internet browser: https://mcadamsco.zoom.us/j/89755975513
- > To attend the meeting via phone, you may dial in by your location:

US: +1 646 876 9923 or +1 301 715 8592 or +1 312 626 6799 or +1 669 900 6833 or +1 253 215 8782 or +1 346 248 7799 or +1 408 638 0968 or 888 788 0099 (Toll Free) or 877 853 5247 (Toll Free)

Webinar ID: **897 5597 5513** International numbers available: <u>https://mcadamsco.zoom.us/u/kl5oaKPSv</u>

Sincerely,

MCADAMS



May 24, 2022

NEIGHBORHOOD MEETING NOTICE - CORRECTION

Dear Property Owner:

As a representative of the proposed developer, Toll Brothers, we are sending this letter as a correction to the previous neighborhood meeting notice dated May 19th. If you are receiving this letter, it is our understanding that you own property or belong to a neighborhood association within 200 feet of the subject property.

The site of the proposed rezoning was incorrectly listed to be currently zoned MH (Manufactured Home) & R-30. The correct current zoning of the project site is RL (Residential Low-Density) & R-30. The project site is located between Burlington Mills and Forestville Rd with the PINs 1748891680, 1758081893, and 1748884104. During the meeting, the applicant will present its plans to rezone this land from RL (Residential Low-Density) and R-30 to RM-CZ (Residential Medium Density, conditional district). The total site area is approximately 224.64 acres.

We will be hosting a virtual neighborhood meeting via Zoom (see instruction sheet for details). The meeting will be held on June 2nd, 2022 from 6:00pm to 7:00pm Eastern Time. We welcome any questions or comments on the proposed project prior to the meeting.

If you have questions or cannot attend the meeting but would like further information, please feel free to contact Laura Holloman by phone: 919.610.7377 or email: <u>holloman@mcadamsco.com</u>.

Sincerely, MCADAMS

XauroHclk

Laura Holloman, AICP Sr. Planner, Planning + Design Group 919.610.7377 holloman@mcadamsco.com



May 24, 2022

RE: Tom's Creek Rezoning Virtual Neighborhood Meeting – Zoom Instructions

Dear Property Owner,


We will be hosting a virtual neighborhood meeting via Zoom Webinar. The meeting will be held on June 2nd and begin at 6:00 PM Eastern Time.

- To attend the meeting via computer, type in the following link in your internet browser: https://mcadamsco.zoom.us/j/89755975513
- > To attend the meeting via phone, you may dial in by your location:

US: +1 646 876 9923 or +1 301 715 8592 or +1 312 626 6799 or +1 669 900 6833 or +1 253 215 8782 or +1 346 248 7799 or +1 408 638 0968 or 888 788 0099 (Toll Free) or 877 853 5247 (Toll Free)

Webinar ID: **897 5597 5513** International numbers available: <u>https://mcadamsco.zoom.us/u/kl5oaKPSv</u>

Sincerely, MCADAMS



Tom's Creek Neighborhood Meeting Minutes June 2, 2022 6PM

Presenters:

Nil Ghosh, Morningstar Law Group,

Laura Holloman McAdams,

Melanie Rausch McAdams,

Mike Sanchez, McAdams

Brittany Chase Exult Engineering

Attendees: Approximately 25

contacts received requesting updates:

najla.osr@gmail.com

<u>steve@newleafassociatesnc.com</u> – requested examples of Toll cluster developments

Meeting:

- Start time: 6:00 pm, this meeting was held virtually.
- Nil Ghosh overviewed the project area, current zoning, proposed zoning and proposed density. Mr. Ghosh clarified mailing snafu to relieve any confusion.
- Mr. Ghosh displayed the concept bubble plan, paying particular attention to proposed entrances to the development, and internal circulation.
- Mr. Ghosh moved on to current traffic conditions, including TIA process and the correspondence with the Town that is a required part of the process.
- Mr. Ghosh explained the cluster development model and how it will affect open space opportunities.
- Neighbor question: What square footage is proposed for the lots? -Ms. Holloman replied it is a little early in the process for lot dimensions.
- Neighbor question: Any rock that will require blasting? -Mr. Ghosh stated we do not know that yet, however Rolesville does have significant rock deposits so quite possibly.
- Neighbor asked about amenities: Mr. Ghosh overview the pool clubhouse, public greenway, and 6-acre public park dedication that will benefit the Town as a whole.
- Neighbor question: What is the public sewer and water connection? -Mr. Sanchez stated we are in discussion with city of Raleigh on where to connect to both sewer and water. Water will likely connect to Forestville Rd, and Burlington Mills Road, Sewer likely Forestville Road.
- Neighbor asked about traffic analysis: Ms. Chase stated the connection points and surrounding intersections that will be included in the TIA analysis.
- Neighbor asked what low density allows for? -Ms. Holloman stated 1-2 homes/acre in Rolesville, this is being developed as medium density which comes out to 2-5 homes/acre.
- Neighbor inquired about removal of utilities access points. Mr. Ghosh stated that would be hard to achieve.

- Neighbor asked Mr. Ghosh to explain cluster development concept. Mr. Ghosh explained that it allows for smaller lots per house, and greater open space.
- Neighbor asked what is the price range for the homes? Mr. Ghosh stated the difficulty in knowing, however the average sale price would likely be above \$500,000.
- Neighbor asked if this proposal includes townhomes. Mr. Ghosh stated no.
- Neighbor asked if environmental impact analysis was required. Mr. Ghosh stated that it is not required for residential, however the existing environmental conditions of the site is why the cluster option is being explored.
- Neighbor asked about timeline. Mr. Ghosh outlined the timeline/process for approval before construction can begin. Mr. Ghosh estimated dirt likely would not move until summer 2023, and residents may begin to move in around 2025. Full buildout would likely be around 2029.
- Resident asked about existing water and sewer hookups. Mr. Ghosh stated sewer would come from Forestville Rd slightly south of where the property abuts Forestville Rd, and water is available along both Burlington Mills Rd and Forestville Rd.
- Neighbor asked if annexation will be required? Mr. Ghosh stated yes.
- Neighbor asked when the greenway will become available. Mr. Ghosh stated that timing and construction will be under the Town's purview.
- Neighbor asked will the sewer have to cross Tom's Creek? Mr. Sanchez stated yes.
- Neighbor asked if water line will extend out to Burlington Mills? -Mr. Sanchez stated CORPUD will likely require the project to extend sewer to Burlington Mills.
- Neighbor stated Grapeland Rd is mislabeled on the map.
- Neighbor asked if a signal may be added as a result of this project to the intersection of Huntington Creek and Burlington Mills. Ms. Chase stated it is difficult to determine at this time, however the TIA will identify that.
- Neighbor asked if this project would trigger Forestville Rd to be widened to have double lanes. Mr. Ghosh stated we do not know at this point, however the TIA will identify this.
- Neighbor asked how much open space is passive versus active. Mr. Ghosh stated that is undetermined at this time.
- Neighbor asked if a traffic light will be added at intersection of Centaur Road and Burlington Mills. Mr. Ghosh again reviewed the TIA process and assured it would identify if a light would be necessary.
- Neighbor asked does Toll Brothers have a concept we can see? Mr. Ghosh stated he will get back to them with something.
- Neighbor asked if Stonewater can be targeted lot size for this development? -Mr. Ghosh stated the limitations, and market advantages for various lot sizes, and how this site coincides with the Town's Comprehensive Plan.
- Neighbor asked what school district would this be in? -Mr. Ghosh stated we do not know yet
- Neighbor stated a previous developer proposed providing water and sewer to Deer Chase is this still on the table? -Mr. Sanchez stated the goal is not to run lines within other private properties.
- Neighbor asked about architectural commitments. -Mr. Ghosh stated none have been committed to yet however Toll Brothers is generally committed to quality and they will likely be added later.

- Neighbor asked if Tuckahoe homes will be annexed into Rolesville. Mr. Ghosh explained how annexation generally has to be voluntary, so no.
- Neighbor expressed discontent with lot size, and would prefer larger lots.
- Neighbor asked where will the greenway connect offsite? Ms. Holloman stated that we met with Rolesville Parks and based the estimate off the creek alignment. However exact location is still up for discussion with the town.
- Neighbor asked if there will be a follow up meeting? Mr. Ghosh again explained the process.
- Neighbor asked if 300 houses can be approved instead of 600. Mr. Ghosh stated it is possible the town could ask for that, but 300 homes is not what is being proposed with this project.
- Neighbor asked about stormwater and expressed concern over ponds flooding and sediment contamination. Mr. Ghosh overviewed the inspection process that occurs both during and after construction. Stormwater devices are required to be inspected and approved through the Town.
- Neighbor asked why not build on larger lots, at a higher price point? -Mr. Ghosh stated this is what is being proposed and is identified by market indicators to be appropriate for the area.
- Neighbor asked if any natural boarders or fencing will be located along border of Tuckahoe? -Mrs. Holloman stated currently there is no fencing proposed, however there will be a landscape buffer. A fence can certainly be discussed with Toll Brothers.
- Neighbor asked what the distance was from their driveway to nearest entrance Road. -Mr. Sanchez stated roughly 500 feet.
- Neighbor asked if an EIS will be considered? -Mr. Sanchez stated that wetland and stream delineation are required, and endangered species have to be identified as part of the process, as well as coordination with SHPO for archaeological resources.
- Neighbor asked if Tuckahoe water supply will be affected? -Mr. Sanchez explained that the water will come from City of Raleigh Municipal Water therefor will not change status of well water.
- Neighbor expressed concern that blasting will negatively impact their well. -Mr. Sanchez stated the shallow rock is generally located away from existing wells/property boundaries meaning most of the blasting should have minimal impact to wells.
- Call in numbers were unmuted by the host and invited to ask any questions.
- Neighbor asked about traffic, and possibility of proposing fewer homes. Mr. Ghosh explained the TIA process, including potential road improvements, and the projects consistency with current Rolesville comprehensive plan.
- Neighbor requested that McAdams engineering incorporate well damage into report that may occur and requested that the project take this into consideration.
- Neighbor asked where the amenities and pool will be located within the site? -Mr. Ghosh stated we are not sure yet, however likely next to the dedicated park.
- Neighbor asked would toll brothers be willing to commit to architectural guidelines Hardy board and stone facades would be desirable. Mr. Ghosh stated that we can take the requested guidelines back to Toll Brothers and make that suggestion.
- Meeting concluded at 8:01 pm.



Tom's Creek Development Traffic Impact Analysis

July 28, 2022

Prepared for:

Town of Rolesville, North Carolina 502 Southtown Circle Rolesville, NC 27571

Applicant:

Toll Brothers Inc. 900 Perimeter Park Drive, Suite B3 Morrisville, NC 27560

Prepared by:

Stantec Consulting Services Inc. 801 Jones Franklin Road, Suite 300 Raleigh, NC 27606

Sign-off Sheet

This document entitled Tom's Creek Development Traffic Impact Analysis was prepared by Stantec Consulting Services Inc. ("Stantec") for the account of the Town of Rolesville (the "Client"). Any reliance on this document by any third party is strictly prohibited. The material in it reflects Stantec's professional judgment in light of the scope, schedule, and other limitations stated in the document and the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. In preparing the document, Stantec did not verify the information supplied to it by others. Any use which a third party makes of this document is the responsibility of such third party. Such a third party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third party as a result of decisions made or actions taken based on this document.

Pierre Ton Prepared by

Pierre Tong, PE

Reviewed by _

(signature)

(signature)

Matt Peach, PE, PTOE Approved by

(signature)

Jeff Weller, PE



Table of Contents

EXEC	JTIVE SUMMARY	I
1.0	INTRODUCTION	. 1
2.0 2.1 2.2 2.3 2.4	INVENTORY OF TRAFFIC CONDITIONS	. 5 . 5 . 6
3.0 3.1 3.2 3.3	TRIP GENERATION INITIAL PHASE TRIP GENERATION INTERMEDIATE PHASE TRIP GENERATION FULL BUILD TRIP GENERATION	10 10
4.0 4.1	TRAFFIC DISTRIBUTION	
5.0 5.1 5.2 5.3 5.4 5.5 5.6 5.7	TRAFFIC VOLUMES TRAFFIC COUNTS FUTURE TRAFFIC GROWTH	19 19 19 20 20 20
 6.0 6.1 6.2 6.3 6.4 6.5 6.6 6.7 6.8 6.9 	TRAFFIC ANALYSIS	29 31 33 35 37 39 41 43
7.0 7.1 7.2 7.3	RECOMMENDATIONS INITIAL PHASE RECOMMENDATIONS INTERMEDIATE PHASE RECOMMENDATIONS FULL BUILD RECOMMENDATIONS	47 48

8.0	CONCLUSIONS	51
9.0	REFERENCES	51
APPE	ENDIX	52

LIST OF TABLES

Table ES-1: Level of Service & Delay Summary	V
Table 1: Existing Conditions	6
Table 2: Initial Phase Trip Generation	10
Table 3: Intermediate Phase Trip Generation	11
Table 4: Full Build Trip Generation	11
Table 5: Level of Service Criteria	28
Table 6: Capacity Analysis Results for 2022 Existing Conditions	30
Table 7: Capacity Analysis Results for 2026 No Build Conditions	32
Table 8: Capacity Analysis Results for 2026 Initial Phase Conditions	34
Table 9: Capacity Analysis Results for 2026 Initial Phase with Improvements	36
Table 10: Capacity Analysis Results for 2028 No Build Conditions	38
Table 11: Capacity Analysis Results for 2028 Intermediate Build Conditions	40
Table 12: Capacity Analysis Results for 2028 Intermediate Build with Improvements	42
Table 13: Capacity Analysis Results for 2029 No Build Conditions	44
Table 14: Capacity Analysis Results for 2029 Full Build Conditions	46

LIST OF FIGURES

Figure ES-1: Site Plan	
Figure ES-2: Recommended Improvements	vi
Figure 1: Site Location and Study Area Map	
Figure 2: Proposed Site Plan	3
Figure 3: Proposed Phases	4
Figure 4: 2022 Existing Lane Configurations and Traffic Control	8
Figure 5: 2026 No Build Lane Configurations and Traffic Control	9
Figure 6: Initial Phase Trip Distribution	13
Figure 7: Initial Phase Trip Assignment	14
Figure 8: Intermediate Phase Trip Distribution	15
Figure 9: Intermediate Phase Trip Assignment	16
Figure 10: Full Build Trip Distribution	17
Figure 11: Full Build Trip Assignment	18
Figure 12: 2022 Existing Traffic Volumes	21
Figure 13: 2026 No Build Traffic Volumes	22
Figure 14: 2026 Initial Build Traffic Volumes	23
Figure 15: 2028 No Build Traffic Volumes	24
Figure 16: 2028 Intermediate Build Traffic Volumes	25
Figure 17: 2029 No Build Traffic Volumes	
Figure 18: 2029 Full Build Traffic Volumes	27
Figure 19: Recommended Lane Configurations	50

Executive Summary

The proposed Tom's Creek Development is located between SR 2049 (Forestville Road) and SR 2051 (Burlington Mills Road) in Rolesville, NC. In general, the 224.64-acre site is located in the southeast corner of the intersection of Forestville Road and Burlington Mills Road. The site is envisioned to consist of 606 single-family detached housing units. The development is anticipated to be completed in 2029.

At full build-out, the development is anticipated to generate 5,294 new trips per average weekday. In the AM and PM peak hours, the development is expected to generate approximately 384 trips (100 entering and 284 exiting) and 540 (340 entering and 200 exiting), respectively.

Four (4) access points are proposed for the development. Access A will connect to Forestville Road whereas Accesses B, C, and D will connect to Burlington Mills Road. The site plan is shown in Figure ES-1.

This study evaluates the ability of the adjacent roadways to accommodate the additional traffic and recommends transportation improvements needed to mitigate congestion that may result from the site traffic. This report presents trip generation, trip distribution, traffic analyses, and recommendations for improvements needed to meet anticipated traffic demands. The following scenarios are examined for the AM and PM peak hours:

- 2022 Existing
- 2026 No Build
- 2026 Initial Build
- 2026 Initial Build with Improvements
- 2028 No Build
- 2028 Intermediate Build
- 2028 Intermediate Build with Improvements
- 2029 No Build
- 2029 Full Build

Capacity analyses for the AM and PM peak hours in each scenario were performed for the following intersections:

- Burlington Mills Road at Ligon Mill Road
- Burlington Mills Road at Forestville Road
- Burlington Mills Road at Access B
- Burlington Mills Road at Centaur Road / Access C
- Burlington Mills Road at Huntingcreek Drive / Access D
- Burlington Mills Road at US 401 Business (S. Main Street)
- Forestville Road at Access A
- Forestville Road at US 401

Table ES-1 shows a summary of the delays and levels of service for the study area intersections.

The results presented herein indicate that the proposed development will have an impact on the surrounding roadway network. These impacts are most pronounced at the intersection of Burlington Mills Road and Forestville Road. As a result, several improvements are recommended at the intersection. These improvements not only mitigate the development's impact on the intersection but also improve LOS by a letter grade.

Other study area intersections have improvements committed by other developments or public-funded projects. The results of this analysis show that these intersections experience minor increases in delay due to the proposed development. Accordingly, improvements are not recommended at these intersections.

The primary access point (Access A) on Forestville Road is anticipated to operate with high delays if it is left as a stop-controlled intersection; even with the addition of turn-lanes on all approaches. The installation of a traffic signal will greatly improve operations but is contingent upon the intersection meeting the warrants for installation of a traffic signal outlined in the Manual on Uniform Traffic Control Devices (MUTCD) and approved by NCDOT. Accordingly, it is recommended that the location be monitored for the installation of a traffic signal and that the design and construction of the signal be the responsibility of the applicant.

All proposed driveways along Burlington Mills Road (Accesses B, C, and D) are expected to operate at an acceptable level of service in all scenarios and are not expected to have a significant impact on operations along Burlington Mills Road.

Based on the findings of this study, specific improvements have been identified and are recommended to be completed as part of the proposed development. These improvements are listed below and recommended improvements are shown in Figure ES-2.

2026 Initial Phase Recommendations

Burlington Mills Road at Centaur Road / Access C

- Construct Access C as a full-movement access point
- Construct Access C with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Forestville Road at Access A

- Construct Access A as a full-movement access point
- Construct Access A with one ingress and two egress lanes (one left-turn lane and one right-turn lane) with a
 driveway stem length of a minimum of 170 feet
- Construct a northbound Forestville Road right-turn lane with 100 feet of full-width storage and appropriate taper
- Construct a southbound Forestville Road left-turn lane with 100 feet of full-width storage and appropriate taper

2028 Intermediate Phase Recommendations

Burlington Mills Road at Forestville Road

- Extend the existing eastbound Burlington Mills Road left-turn lane to 575 feet of full-width storage and appropriate taper
- Extend the existing westbound Burlington Mills Road left-turn lane to 225 feet of full-width storage and appropriate taper
- Construct a westbound Burlington Mills Road right-turn lane with 150 feet of full-width storage and appropriate taper
- Extend the existing northbound Forestville Road left-turn lane to 225 feet of full-width storage and appropriate taper
- Extend the existing southbound Forestville Road left-turn lane to 300 feet of full-width storage and appropriate taper

- Construct a southbound Forestville Road right-turn lane with 200 feet of full-width storage and appropriate taper
- The above recommendations will require the traffic signal at the intersection to be modified

Burlington Mills Road at Access B

- Construct Access B as a right-in/right-out access point
- Construct Access B with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Forestville Road at Access A

• Monitor Access A for potential signalization

2029 Full Build Recommendations


Burlington Mills Road at Huntingcreek Drive / Access D

- Construct Access D as a full-movement access point
- Construct Access D with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Forestville Road at Access A

• Monitor Access A for potential signalization

Figure ES-1: Site Plan





MA 21-10 V2 Rcvd 03-31-22




iv

Level of Service (Delay, sec/veh)	2022 E	existing	2026 N	lo Build	2026 Ini	tial Build	2026 Initial Build with Improvements 2028 No Build 2028 Intermedia Build		2028 Intermediate		2028 Intermediate Build with Improvements		2029 No Build		ull Build			
	AM	PM	AM	PM	AM	РМ	AM	РМ	AM	РМ	AM	РМ	AM	РМ	AM	РМ	AM	РМ
Burlington Mills Road at Ligon Mill Road	D (43.4)	C (33.4)	D (53.7)	C (26.4)	D (47.1)	C (29.0)	D (47.1)	C (29.0)	E (57.8)	C (28.3)	E (59.2)	C (30.1)	E (64.7)	C (31.7)	E (70.3)	C (32.7)	E (73.5)	C (33.7)
Burlington Mills Road at Forestville Road	C (33.5)	C (32.0)	F (84.9)	F (85.7)	F (90.7)	F (80.2)	F (90.7)	F (80.2)	F (99.3)	F (89.5)	F (109.3)	F (94.1)	E (60.0)	E (60.3)	E (62.5)	E (62.2)	E (66.2)	E (64.3)
Burlington Mills Road at Access B	-	-	-	-	-	-	-	-	-	-	B (11.6)	B (11.2)	B (11.6)	B (11.2)	B (11.7)	B (11.3)	B (11.8)	B (11.6)
Burlington Mills Road at Centaur Road / Access C	B (12.4)	B (10.5)	C (16.3)	B (13.0)	C (20.7)	C (16.1)	C (20.7)	C (16.1)	C (21.4)	C (16.3)	D (29.6)	C (20.2)	D (29.6)	C (20.2)	D (30.3)	C (20.4)	D (29.4)	C (20.8)
Burlington Mills Road at Huntingcreek Drive / Access D	B (11.7)	B (10.1)	C (15.5)	C (12.2)	C (15.8)	B (12.4)	C (15.8)	B (12.4)	C (16.1)	B (12.6)	C (16.3)	B (12.8)	C (16.3)	C (12.8)	C (16.5)	B (12.9)	D (28.1)	C (20.1)
Burlington Mills Road at US 401 Business	C (27.8)	B (16.6)	E (61.0)	D (42.3)	E (62.0)	D (46.5)	E (62.0)	D (46.5)	E (65.3)	D (43.4)	E (62.9)	D (43.5)	E (70.8)	D (44.3)	E (67.8)	D (42.6)	E (69.3)	D (43.0)
Forestville Road at Access A	-	-	-	-	F (398.3)	F (1262.7)	F (297.2)	F (821.2)	F (445.5)	F (1306.6)	F (1133.7)	F (3272.1)	B (8.6)	A (7.4)	A (9.1)	A (7.5)	B (11.8)	A (9.2)
Forestville Road at US 401	D (37.2)	D (40.4)				The	e Perry Farm	s developm	ent will con	vert this inte	rsection to a	Reduced C	Conflict Inter	section by 2	026			
Forestville Road at US 401 Westbound	-	-	D (47.4)	B (17.5)	D (52.7)	C (20.8)	D (52.7)	C (20.8)	E (61.5)	B (19.1)	E (69.5)	B (19.8)	E (69.9)	B (19.8)	E (73.3)	B (19.8)	E (78.4)	B (19.1)
Forestville Road at US 401 Eastbound	-	-	B (17.9)	C (20.4)	B (18.6)	B (21.6)	B (18.6)	C (21.6)	B (19.6)	C (21.9)	C (20.3)	C (22.0)	B (16.7)	C (22.0)	B (17.5)	C (23.2)	B (17.5)	C (23.2)
US 401 Westbound U-Turn	-	-	C (31.8)	B (15.7)	C (26.9)	B (16.2)	C (26.9)	B (16.2)	C (31.3)	B (15.9)	C (30.0)	B (15.9)	C (32.5)	B (15.9)	D (35.0)	B (16.0)	D (35.1)	B (16.1)

Table ES-1: Level of Service & Delay Summary

Figure ES-2: Recommended Improvements



Introduction July 28, 2022

1.0 INTRODUCTION

The purpose of this report is to evaluate the traffic impacts of the proposed Tom's Creek Development located in Rolesville, NC. This development is located between SR 2049 (Forestville Road) and SR 2051 (Burlington Mills Road) in Rolesville, NC. In general, the 224.64-acre site is located in the southeast corner of the intersection of Forestville Road and Burlington Mills Road. The development's location and study area are shown in Figure 1.

The site currently consists of undeveloped farmland and is zoned Residential Low Density (RL). The applicant is pursuing a rezoning to Residential Medium Density – Conditional District (RM-CZ). Construction of the site is anticipated to be completed in 2029 and will consist of up to 606 units of single-family detached housing. The Rolesville Comprehensive Plan designates this property as "Medium Density Residential" with a suggested density range of 3-5 units per acre, however, the applicant has chosen to limit the proposed density to 2.7 units per acre. Figure 2 shows the conceptual site plan prepared by McAdams. Figure 3 shows each of the six (6) phases of development.

The Tom's Creek Development is expected to be constructed in six (6) phases as shown in Figure 3; however, the applicant has requested that three (3) phases be included in this study. The Initial phase studied includes what is shown as phases 1 and 2 in Figure 3 and is assumed to be fully built out and occupied by 2026. The Intermediate phase includes what is shown as phases 3 and 4 in Figure 3 and is assumed to be fully built out and occupied by 2028. The final phase includes what is shown as phases 5 and 6 in Figure 3 and is assumed to be fully built out and occupied by 2028.

The purpose of this report is to evaluate the development in terms of projected vehicular traffic conditions, evaluate the ability of the adjacent roadways to accommodate the additional traffic, and recommend transportation improvements needed to mitigate congestion that may result from additional site traffic. This report presents trip generation, trip distribution, traffic analyses, and recommendations for improvements needed to meet anticipated traffic demands. The analysis examines the AM and PM peak hours for:

- 2022 Existing
- 2026 No Build
- 2026 Initial Build
- 2026 Initial Build with Improvements
- 2028 No Build
- 2028 Intermediate Build
- 2028 Intermediate Build with Improvements
- 2029 No Build
- 2029 Full Build

Introduction July 28, 2022




Figure 1: Site Location and Study Area Map

Introduction July 28, 2022

GRAPELAND DR TOM'S CREEK CONCEPT PLAN H 0 BURLINGTON MILLS RD REEK 555 HUNTINGC FORESTVILLE RD EXISTING POND Acces Access A EXISTING CEMETERY (NOT SUBJECT TO REZONING) SITE DATA TABLE Total Site Area +/-22464 acre leudental Med PLAN SUMMARY Proposed Zoning Density [BM] Open Space Required (12%) +/- 25.95 acres Development Area Dpen Space Open Spece Provided +/- 91 астия Community Park (+/- 4-6 ac) ENVIRONMENTAL FEATURES Local Residential Roads (50" ROM) Residential Collector Street (60' ROw) NOTES Floodway 🔲 100 - Year Floodplain Contraction by 15' Type 2 Perimeter Buffer 500 - Year Floodplain 30 Thoroughfare Streetucape Buffer Final Plat process. Streams Site Boundary Stream Duffers 1800 11211 AT AT A 1.1.1

Figure 2: Proposed Site Plan





MA 21-10 V2 Rcvd 03-31-22



Introduction July 28, 2022




Figure 3: Proposed Phases



PHASE	UNITS	GUARTER
		Oct-24
		Jan-25
	110	Apr-25
		301-25
		Oct-25
2	100	Jon-28
		Apr-26
		Jul-26
3	100	Oct-26
		Jon-27
		Apr-27
4	115	Jul-27
		Oct-27
		Jon-28
5	75	Apt~28
		3.6-28
		Oct-28
14	100	Jon-29
1	500	Apr-29
		AU-29 Z
1	600	SOL
	The state	TOM'S CREEK (ROLESVILLE, NORTH CA
n and aignme aignments w he Major Subd	il be	

Inventory of Traffic Conditions July 28, 2022

2.0 INVENTORY OF TRAFFIC CONDITIONS

2.1 STUDY AREA

Stantec coordinated with the Town of Rolesville and the North Carolina Department of Transportation (NCDOT) Division 5, District 1 to determine the appropriate study area and assumptions for this study. The final scoping document is included in the appendix. The following intersections were agreed upon to be analyzed to determine the associated impacts of the proposed development.

•	Burlington Mills Road at Ligon Mill Road	(signalized)
•	Burlington Mills Road at Forestville Road	(signalized)
•	Burlington Mills Road at Centaur Road	(stop-controlled)
•	Burlington Mills Road at Huntingcreek Drive	(stop-controlled)
•	Burlington Mills Road at US 401 Business (S. Main Street)	(signalized)
•	Forestville Road at US 401	(signalized)

Figure 4 shows a diagram of the existing lane configurations, geometry, and traffic control features in the study area.

2.2 PROPOSED ACCESS

2.2.1 Initial Phase Access

Access to the Initial phase (i.e., phases 1 and 2 as shown in Figure 3) is envisioned to be provided by two access points:

- Forestville Road at Access A
- Burlington Mills Road at Centaur Road / Access C

Access A is proposed to be a full-movement driveway located along Forestville Road. This will create a new threelegged intersection. Intersection control will be provided by a stop sign on Access A. Access C is proposed to be a full-movement driveway on Burlington Mills Road at Centaur Road. Intersection control will be provided by stop signs on the minor approaches.

2.2.2 Intermediate Phase Access

The Intermediate phase (i.e., phases 3 and 4 as shown in Figure 3) will construct a new access point on Burlington Mills Road:

Burlington Mills Road at Access B

Access B is proposed to be a right-in/right-out driveway located along Burlington Mills Road. This will create a new three-legged intersection. Intersection control will be provided by a stop sign on Access B. The construction of Access B will bring the total number of access points to three during the Intermediate phase.

Inventory of Traffic Conditions July 28, 2022

2.2.3 Full Build Access

The final phase (i.e., phases 5 and 6 as shown in Figure 3 and referred to as the full build) will construct a new access point on Burlington Mills Road:

• Burlington Mills Road at Huntingcreek Drive / Access D

Access D is proposed to be a full-movement driveway on Burlington Mills Road at Huntingcreek Drive. Intersection control will be provided by stop signs on both Huntingcreek Drive and Access D. The construction of Access D will bring the total number of access points to four when the development is fully built out.

2.3 EXISTING ROADWAY CONDITIONS

Table 1 provides a detailed description of the existing study area roadway network. All functional classification and average annual daily traffic (AADT) information, where available, was obtained from NCDOT via the NCDOT.gov website. The existing roadway laneage is illustrated in Figure 4.

Road Name	Road Number	Primary Cross- Section	Functional Classification ¹	2020 AADT ² (vpd)	Speed Limit (mph)	Maintenance Agency
Burlington Mills Road	SR 2045/2051	2-Lane Undivided	Minor Collector	3,500- 8,000	45	NCDOT
Centaur Road	SR 2073	2-Lane Undivided	Local	Unknown	55	NCDOT
Forestville Road	SR 2049	2-Lane Undivided	Minor Arterial	10,500- 13,000	45	NCDOT
Huntingcreek Drive	SR 3657	2-Lane Undivided	Local	Unknown	55	NCDOT
Ligon Mill Road	SR 2044	2-Lane Undivided	Minor Collector	1,800- 7,600	45	NCDOT
Louisburg Road	US 401	4-Lane Divided	Principal Arterial	21,500	55	NCDOT
S. Main Street	US 401 Business	2-Lane/3-Lane Undivided	Principal Arterial	9,000- 12,000	35	NCDOT

Table 1: Existing Conditions

2.4 FUTURE NO BUILD ROADWAY CONDITIONS

Nearby developments have committed to specific improvements to the study intersections. While the schedule of each development is unknown, the improvements are assumed to be completed in 2026 before the Tom's Creek Development is constructed. These improvements are described in the following subsections. The future no build roadway conditions are shown in Figure 5.

Inventory of Traffic Conditions July 28, 2022

Burlington Mills Road at Ligon Mill Road

The Kitchin Farms development has committed to constructing two improvements at this intersection:

- Construct a southbound left-turn lane along Ligon Mill Road with 200 feet of storage and appropriate deceleration and taper length
- Construct a northbound left-turn lane along Ligon Mill Road with 200 feet of storage and appropriate Forestville Road at US 401

These improvements are documented in the Marshall Village Traffic Impact Analysis (Ramey Kemp & Associates, August 2021). A copy of this TIA is included in the appendix. Additional information on the Kitchin Farms development can be found in Section 5.3.

Forestville Road at US 401

The Perry Farms development has committed to converting this location to a reduced conflict intersection (RCI) where left and through movements are redirected from the Forestville Road approaches and U-turns are made at the US 401 & Leland Drive intersection and a nearby bulb-intersection east of the US 401 & Forestville Road intersection. This includes the construction of the following improvements at this intersection:

- Convert intersection to an RCI with left and through movements being eliminated from the Forestville Road approaches
- Restripe Forestville Road approaches to dual right-turn lanes
- Construct a second eastbound left-turn lane with 300 feet of storage and appropriate deceleration and taper length
- Provide an eastbound U-turn location approximately 1,300 feet east of the intersection with an eastbound U-turn lane with 500 feet of storage and appropriate deceleration and taper length

These improvements are documented in the Perry Farms Development Traffic Impact Analysis Review Report (NCDOT Congestion Management, July 2021). A copy of this memo and other associated documentation is included in the appendix. Additional information on the Perry Farms development can be found in Section 5.3


Burlington Mills Road at US 401 Business

As part of the NCDOT U-6241 project (construction year 2022) and Wallbrook development, Burlington Mills Road will be realigned and a new signalized intersection with US 401 Business will be constructed to the south of the existing intersection.

These improvements are documented in the Revised Wallbrook Development Traffic Impact Analysis (Stantec, August 2020). A copy of this memo is included in the appendix. Additional information on the Wallbrook development can be found in Section 5.3


Inventory of Traffic Conditions July 28, 2022


Figure 4: 2022 Existing Lane Configurations and Traffic Control



Inventory of Traffic Conditions July 28, 2022

Figure 5: 2026 No Build Lane Configurations and Traffic Control







T

<u>Key</u> Lanes Lanes
 Signalized Intersection
 Stop-Controlled Intersection
 Improvement by Others
 XX' Storage Length
 Figure is Not to Scale Trip Generation July 28, 2022

3.0 TRIP GENERATION

Trip generation was performed for the proposed development in three phases. Trips were estimated using the 11th Edition of the Institute of Transportation Engineers (ITE) Trip Generation Manual³. The manual provides means for calculating trips across four setting types: city center core, dense multi-use urban, general urban/suburban, and rural. This trip generation, submitted to the Town and NCDOT for review, and including internal capture and trip generation methodology, is located in the appendix.

3.1 INITIAL PHASE TRIP GENERATION

The Initial phase of the Tom's Creek Development will comprise 210 single-family detached housing units. Table 2 shows the number of anticipated trips that will be generated by the Initial phase (Daily, AM Peak, and PM Peak entering and exiting).

					Daily		A	M Peak		F	PM Peak	
Land Use	ITE LUC	Size		Total	Enter	Exit	Total	Enter	Exit	Total	Enter	Exit
Single Family Homes	210	210	Units	1834	917	917	133	35	98	187	118	69
Trips Generated for this phase					917	917	133	35	98	187	118	69

Table 2: Initial Phase Trip Generation

3.2 INTERMEDIATE PHASE TRIP GENERATION

The Intermediate phase of the Tom's Creek Development will add 215 new single-family detached housing units to those constructed as a part of the Initial phase. This results in a total of 425 single-family detached housing units. To provide a conservative estimate of the traffic to and from the development during the Intermediate phase, trips were calculated for 215 units. Trips from the Initial phase (shown in Table 2) were then added to trips from the Intermediate phase to produce the cumulative trips generated during the Intermediate phase. These cumulative values were assigned to the roadway network using the trip distribution discussed in Section 4.0. Table 3 shows the number of anticipated trips that will be generated by the Intermediate Build (Daily, AM Peak, and PM Peak entering and exiting).

Trip Generation July 28, 2022

		Size			Daily		A	M Peak		PM Peak		
Land Use	ITE LUC			Total	Enter	Exit	Total	Enter	Exit	Total	Enter	Exit
Single Family Homes	210	215	Units	1878	939	939	136	35	101	192	121	71
Trips	Trips Generated for this phase					939	136	35	101	192	121	71
Cumulative Trips Generated					1856	1856	269	70	199	379	239	140

Table 3: Intermediate Phase Trip Generation

3.3 FULL BUILD TRIP GENERATION

The Full Build, and final phase, for this site is a combined 606 units of single-family detached housing. Table 4 shows the number of anticipated trips that will be generated when the site is completed.

Table 4: Full Build	Trip Generation
---------------------	-----------------

		Size			Daily		A	M Peak		PM Peak		
Land Use	ITE LUC			Total	Enter	Exit	Total	Enter	Exit	Total	Enter	Exit
Single Family Homes	210	606	Units	5294	2647	2647	384	100	284	540	340	200
Trips Generated for this phase					791	791	115	30	85	161	101	60
Cumulative Trips Generated					2647	2647	384	100	284	540	340	200

Traffic Distribution July 28, 2022

4.0 TRAFFIC DISTRIBUTION


4.1 SITE TRIP DISTRIBUTION

To accurately determine the effect of the proposed development on the surrounding roadway network, an estimate of the expected distribution of traffic entering and exiting the site is needed. The following percentages were used in the AM and PM peak hours for the proposed site:

- 45% to/from the south via US 401 (Louisburg Road)
- 20% to/from the north via Forestville Road
- 10% to/from the west via Burlington Mills Road
- 10% to/from the south via US 401 Business (S. Main Street)
- 5% to/from the south via Ligon Mill Road
- 5% to/from the north via US 401 Business (S. Main Street)
- 5% to/from the east via US 401 (Louisburg Road)

These percentages were developed using a combination of existing traffic volume counts, historic AADTs provided by NCDOT, and engineering judgment. This trip distribution was submitted to the Town and NCDOT for review as part of NCDOT's TIA Scoping Checklist contained in the appendix. Trip distribution and assignment for the Initial phase are shown in Figure 6 and Figure 7, trip distribution and assignment for the Intermediate phase are shown in Figure 9, and trip distribution for the Full Build is shown in Figure 10 and Figure 11.

Figure 6: Initial Phase Trip Distribution









KeyPermitted MovementXXEntering[XX]Exiting

Figure 7: Initial Phase Trip Assignment







★ Key Permitted Movement XX AM Volumes [XX] PM Volumes





Figure 8: Intermediate Phase Trip Distribution






 Key


 Permitted Movement

 XX
 Entering

 [XX]
 Exiting

Figure 9: Intermediate Phase Trip Assignment







← Permitted Movement XX AM Volumes [XX] PM Volumes




Figure 10: Full Build Trip Distribution






 Key


 Permitted Movement

 XX
 Entering

 [XX]
 Exiting

Figure 11: Full Build Trip Assignment







← Permitted Movement XX AM Volumes [XX] PM Volumes

Traffic Volumes July 28, 2022

5.0 TRAFFIC VOLUMES

All traffic volume calculations can be found in the appendix.

5.1 TRAFFIC COUNTS

Morning (7:00 - 9:00 am) and evening (4:00 - 6:00 pm) turning movement counts were taken at the study intersections on May 17, 2022, while schools were in session. Due to the distance between study intersections and the number of driveways between them, the traffic counts were not balanced. All traffic count data can be found in the appendix. The 2022 existing volumes are shown in Figure 12.

5.2 FUTURE TRAFFIC GROWTH

Future traffic growth is the increase in traffic volumes due to usage increases and non-specific growth throughout the area. The 2022 existing volumes were grown by a 2% annual rate to estimate 2026, 2028, and 2029 base volumes.

5.3 APPROVED DEVELOPMENT TRAFFIC

There are three (3) approved developments within the study area. Information on each is listed below with additional information being included in the appendix

- 1. Wallbrook is a proposed mixed-use development project located along both sides of US 401 Business (S. Main Street) between Burlington Mills Road and Hampton Lake Drive/Jonesville Road. The development is expected to be complete before the completion of the Initial Build of the Tom's Creek development.
- Perry Farms is a mixed-use development located in the northeast quadrant of the US 401 (Louisburg Road) and Forestville Road intersection. The development is expected to be complete before the completion of the Initial Build of the Tom's Creek development.
- Marshall Village is a residential development located in the northwest quadrant of the Forestville Road and Burlington Mills Road intersection and is estimated to be built in 2024, before the completion of the Initial Build of the Tom's Creek development.

It should be noted that the Kitchin Farms development has committed to improvements to the intersection of Burlington Mills Road at Ligon Mill Road discussed in Section 2.4. Kitchin Farms is a residential development located west of Ligon Mill Road in Wake Forest. The residential development of 263 units is partially constructed and occupied. As a result, traffic from the constructed and occupied portion of the development is included in the traffic counts. Much of the traffic generated by the development would be traveling to/from US 1 which is not included in the study area. Therefore, traffic from this development is not included in the analysis. The minor amount of traffic to/from Kitchin Farms that would travel through the study area is assumed to be captured by the future traffic growth rate of 2% per year discussed in Section 5.2.

Traffic Volumes July 28, 2022

5.4 NO BUILD TRAFFIC VOLUMES

The future traffic growth and approved development traffic volumes were added to the existing volumes to determine the no build traffic volumes. 2026 no build traffic volumes are shown in Figure 13. 2028 no build traffic volumes are shown in Figure 15. The 2029 no build traffic volumes are shown in Figure 17.

5.5 INITIAL PHASE TRAFFIC VOLUMES

To obtain the total 2026 Initial phase traffic volumes, the distributed site traffic shown in Figure 7 was added to the respective no build traffic volumes shown in Figure 13. The total AM and PM peak hour turning movement volumes for the study intersections were then calculated and analyzed for the 2026 Initial phase. The 2026 Initial phase traffic volumes are shown in Figure 14.

5.6 INTERMEDIATE PHASE TRAFFIC VOLUMES

To obtain the total 2028 Intermediate phase traffic volumes, the distributed site traffic shown in Figure 9 was added to the respective no build traffic volumes shown in Figure 15. The total AM and PM peak hour turning movement volumes for the study intersections were then calculated and analyzed for the 2028 Intermediate phase. The 2028 Intermediate phase traffic volumes are shown in Figure 16.

5.7 FULL BUILD TRAFFIC VOLUMES

To obtain the total 2029 Full Build traffic volumes, the distributed site traffic shown in Figure 11 was added to the respective no build traffic volumes shown in Figure 17. The total AM and PM peak hour turning movement volumes for the study intersections were then calculated and analyzed for the 2029 Full Build traffic scenario. The 2029 Full Build traffic volumes are shown in Figure 18.

Traffic Volumes July 28, 2022

Figure 12: 2022 Existing Traffic Volumes







Figure 13: 2026 No Build Traffic Volumes



← 340 [206] ← 762 [578] ← 62 [62] US 401 Business	€ 29 [29] ← 39 [39] € 31 [31]	
257 [261] ↓ 48 [48] ↓ 251 [79] ↓ NO1 Business	399 [203] J 556 [661] J 22 [22] J	




KeyPermitted MovementXXAM Volumes[XX]PM Volumes

Figure is Not to Scale



Figure 14: 2026 Initial Build Traffic Volumes



← 342 [212] ← 762 [578] ← 62 [62] US 401 Busines <u>s</u>	€ 29 [29] ← 39 [39] € 31 [31]	
262 [264] 1 48 [48] 261 (283 Legen 168 102 401 Business	402 [215] J 556 [661] J 22 [22] J	




KeyPermitted MovementXXAM Volumes[XX]PM Volumes

Figure is Not to Scale



Figure 15: 2028 No Build Traffic Volumes




the set of the s	€ 29 [29] ← 39 [39] € 31 [31]	
271 [273] 1 48 [48] 48 270 [88] 1	413 [218] J 576 [685] J 22 [22] J	

	Key
\leftrightarrow	Permitted Movement
XX	AM Volumes
[XX]	PM Volumes

Figure is Not to Scale



Figure 16: 2028 Intermediate Build Traffic Volumes



the set of the s	€ 29 [29] ← 39 [39] € 31 [31]	
276 [277] J 48 [48] 280 [95] G 10 401 Business	417 [230] J 576 [685] J 22 [22] J	




KeyPermitted MovementXXAM Volumes[XX]PM Volumes

Figure is Not to Scale



Figure 17: 2029 No Build Traffic Volumes




← 364 [230] ← 802 [606] ← 62 [62] US 401 Business	€ 29 [29] ← 39 [39] € 31 [31]	
281 [281] 1 48 [48] 285 285 [97] 7 NO 401 Business	423 [232] L 586 [697] J 22 [22] J	

	Key
\leftrightarrow	Permitted Movement
XX	AM Volumes
[XX]	PM Volumes

Figure is Not to Scale



Figure 18: 2029 Full Build Traffic Volumes



the set [235] the set [235] the set [606] the set [62] US 401 Business	€ 29 [29] ← 39 [39] € 31 [31]	
285 [284] 1 48 [48] 293 [103] 1 1 1 1 1 1 1 1 1 1	426 [242] ↓ 586 [697] ↓ 22 [22] ↓	



 Key

 Permitted Movement

 XX
 AM Volumes

 [XX]
 PM Volumes

Figure is Not to Scale

6.0 TRAFFIC ANALYSIS

Capacity analyses were performed for the roadway network in the project study area. The traffic analysis program Synchro Version 10 was used to analyze all signalized and stop-controlled intersections according to methods put forth by the Transportation Research Board's Highway Capacity Manual (HCM)⁴. The Highway Capacity Manual defines capacity as "the maximum rate of flow at which persons or vehicles can be reasonably expected to traverse a point or uniform section of a lane or roadway during a specified period under the prevailing roadway, traffic, and control conditions, usually expressed as vehicles per lane per hour."

Level of service (LOS) is a term used to describe different traffic conditions and is defined as a "qualitative measure describing operational conditions within a traffic stream, and their perception by motorists/ or passengers." LOS varies from Level A, representing free flow, to Level F where traffic breakdown conditions are evident. At an unsignalized intersection, the primary traffic on the main roadway is virtually uninterrupted. Therefore, the overall delay for the intersection is usually less than what is calculated for the minor street movements. The overall intersection delay and the delay for the intersection's minor movement(s) are reported in the summary tables of this report. LOS D is acceptable for signalized intersections in suburban areas during peak periods.

Capacity analyses were completed following *NCDOT Capacity Analysis Guidelines⁵* as well as the Draft NCDOT Capacity Analysis Guidelines Best Practices⁶. Table 5 presents the criteria of each LOS as indicated in the *HCM*.

Level of Service (LOS)	Signalized Intersection Control Delay (seconds / vehicle)	Unsignalized Intersection Control Delay (seconds / vehicle)
А	≤ 10	≤ 10
В	>10 and ≤ 20	>10 and ≤ 15
С	>20 and ≤ 35	>15 and ≤ 25
D	>35 and ≤ 55	>25 and ≤ 35
E	>55 and ≤ 80	>35 and ≤ 50
F	>80	>50

Table 5: Level of Service Criteria

The Town of Rolesville's Land Development Ordinance⁷, section 8.E, establishes the following Level of Service Standards:

1. The traffic impact analysis must demonstrate that the proposed development would not cause buildout-year, peak-hour levels of service on any arterial or collector road or intersection within the study area to fall below Level of Service (LOS) "D," as defined by the latest edition of the Highway Capacity Manual, or, where the existing level of service is already LOS "E" that the proposed development would not cause the LOS to fall to the next lower letter grade.

2. If the road segment or intersection is already LOS "F," the traffic impact analysis must demonstrate that the proposed development, with any proposed improvements, would not cause build-out year peak-hour operation to degrade more than five (5) percent of the total delay on any intersection approach.

Traffic Analysis July 28, 2022

Capacity analyses were performed for the following conditions:

- 2022 Existing
- 2026 No Build
- 2026 Initial Phase
- 2026 Initial Phase with Improvements
- 2028 No Build
- 2028 Intermediate Phase
- 2028 Intermediate Phase with Improvements
- 2029 No Build
- 2029 Full Build

The following intersections were included in the capacity analysis for the above scenarios, where applicable:

- Burlington Mills Road at Ligon Mill Road
- Burlington Mills Road at Forestville Road
- Burlington Mills Road at Access B
- Burlington Mills Road at Centaur Road / Access C
- Burlington Mills Road at Huntingcreek Drive / Access D
- Burlington Mills Road at US 401 Business (S. Main Street)
- Forestville Road at Access A
- Forestville Road at US 401

SimTraffic runs were completed for all scenarios to observe the predicted traffic operations throughout the study area during each of the peak hours. Per the *Draft NCDOT Capacity Analysis Guidelines: Best Practices*⁶, ten (10) SimTraffic analysis runs were performed for each scenario. Detailed SimTraffic queuing and blocking reports can be found in the appendix.

All Synchro files and detailed printouts can be found in the appendix. A summary of the results of the analyses is provided in the following sub-sections.

6.1 2022 EXISTING ANALYSIS

In the 2022 existing scenario, all study intersections operate at an overall LOS D or better in both peak hours. The following movements operate at LOS F:

- Burlington Mills Road at Forestville Road: Eastbound Left (AM)
- Forestville Road at US 401: Northbound Left (PM), Southbound Left (AM/PM), Southbound Through (PM)

From the traffic simulation, long queues were observed on the southbound approach of Ligon Mill Road at Burlington Mills Road. This is attributed to the lack of exclusive left and right turn lanes at this intersection.

Capacity analysis results for the existing traffic conditions are listed in Table 6.

	Intersection	Approach	Lane Group	De (sec./	lay / veh.)		el of vice DS)		Queue et)	Max. Que (fe	eue
				AM	PM	AM	РМ	AM	РМ	AM	PM
		Overa	all	43.4	33.4	D	С				
		EB	LTR	16.3	28.6	В	С	185	494	245	691
淵	Burlington Mills Road at Ligon Mill Road	WB	LTR	26.3	14.5	С	В	778	178	728	436
₩	at Eight Mill Road	NB	LTR	52.3	28.7	D	С	436	272	844	458
		SB	LTR	79.8	56.4	Е	Е	582	466	1228*	841
		Over	all	33.5	32	С	С				
			L	95.9	59.9	F	Е	279	299	224	225
		EB	Т	28.8	22.4	С	С	145	90	488	603
			R	26.2	20	С	В	32	27	150	250
38;	Burlington Mills Road	WB	L	28.4	22.9	С	С	49	52	187	80
iUr	at Forestville Road	110	TR	37	22.9	D	С	307	96	308	140
		NB	L	8.3	8.6	Α	А	14	11	191	175
		ND	TR	11.3	14	В	В	387	357	524	404
		SB	L	19.3	16.5	В	В	51	44	275	244
		30	TR	40.6	44.9	D	D	917	693	744	544
	Burlington Mills Road	EB	LT	8.1	7.6	Α	А	0	0	22	17
STOP	at Centaur Road	SB	LR	12.4	10.5	В	В	3	0	29	26
_	Burlington Mills Road at Huntingcreek Drive	EB	LT	8	7.6	А	А	0	0	9	39
STOP		SB	LR	11.7	10.1	В	В	5	3	30	22
		Overall		27.8	16.6	С	В				
		ГР	L	66.4	41.8	Е	D	247	48	225	114
		EB	Т	7.1	8.7	А	А	151	261	229	268
畿	Burlington Mills Road at US 401 Business	WB	Т	22.2	15.2	С	В	396	287	680	262
	at 03 401 business		R	4.6	2.7	А	Α	77	41	250	205
		0.0	L	69.2	42.8	E	D	185	177	385	317
		SB	R	34.3	15.9	С	В	158	38	265	80
		Over	all	37.2	40.4	D	D				
			L	59.3	32.3	Е	С	382	497	314	578
		EB	Т	16.1	31.1	В	С	284	909	250	754
			R	5.6	8.7	А	А	6	9	26	24
			L	11.8	42.3	В	D	95	175	565	243
		WB	Т	42.6	39.8	D	D	915	485	813	470
箫	Forestville Road at US 401		R	17.1	36.5	В	D	49	75	525	99
_	03401		L	59	85.8	Е	F	12	25	36	54
		NB	Т	61.7	75.4	E	E	259	364	263	309
			R	35	46.1	D	D	150	233	187	266
			L	89.1	100	F	F	104	86	212	147
		SB	Т	54.4	80.5	D	F	173	336	210	324
			R	30.7	25.7	С	С	218	125	177	203
	* Q	ueue Exten	ds Off Sir	mTraffic	Network	or Into	Next Inte	ersection			

Table 6: Capacity Analysis Results for 2022 Existing Conditions

Traffic Analysis July 28, 2022

6.2 2026 NO BUILD ANALYSIS

In the 2026 No Build conditions, increases in traffic volumes due to future traffic growth and approved developments cause delays at study area intersections to increase when compared to the 2022 existing analysis. This analysis assumes the improvements committed to by the approved developments are constructed. These improvements were discussed in Section 2.4 and illustrated in Figure 5. The following observations are notable:

At the intersection of Burlington Mills Road at Forestville Road, LOS F is expected during both peak hours with several movements operating with high delays and long queues; specifically, left turns on the eastbound, northbound, and southbound approaches. The southbound shared through / right-turn lane also operates at LOS F. Long queues were observed on the shared through / right-turn lanes on the westbound, northbound, and southbound approaches.

At the intersection of Burlington Mills Road and US 401 Business, LOS E is expected in the AM peak hour with a few movements operating at LOS F. This is typical of locations that are implementing urban design concepts such as those from U-6241 and the Wallbrook development.

2026 No Build capacity analysis results are listed in Table 7.

	Intersection	Approach	Lane Group	De (sec.	lay / veh.)	Ser	el of vice DS)		Queue et)	Qu	Obs. eue et)
				AM	PM	AM	PM	AM	РМ	AM	PM
		Overa	all	53.7	26.4	D	С				
		EB	LTR	12.9	20.8	В	С	217	478	387	752
箫	Dualia ata a Milla Da a d	WB	LTR	32.2	9.2	С	А	500	178	964	627
	Burlington Mills Road at Ligon Mill Road	NB	L	122	42.8	F	D	151	74	294	114
	at Eigen wiin reduc		TR	74.3	31.8	Е	С	553	245	620	259
		SB	L	178.9	50.8	F	D	242	136	300	259
		00	TR	80.1	41.3	F	D	622	341	767	467
		Over	all	84.9	85.7	F	F				
			L	151.3	133	F	F	398	587	224	225
		EB	Т	34.7	34.4	С	С	270	254	821	1321
			R	20.3	20.5	С	С	38	53	217	250
影	Burlington Mills Road	WB	L	36.7	147.8	D	F	112	246	275	275
iUr	at Forestville Road	110	TR	118.4	75.5	F	E	698	389	2388	1130
		NB	L	106.8	88.7	F	F	155	129	200	193
			TR	51.3	61	D	Е	1148	1064	1228	1783
		SB	L	130.5	110.2	F	F	187	176	275	275
		00	TR	99.7	102.6	F	F	1435	1270	2091*	2098*
_	Burlington Mills Road	EB	LT	8.7	8.1	А	А	0	0	33	36
STCP	at Centaur Road	SB	LR	16.3	13	С	В	3	3	26	26
	Burlington Mills Road	EB	LT	8.6	8.1	А	А	0	3	37	67
STOP	at Huntingcreek Drive	SB	LR	15.5	12.2	С	В	8	3	36	24
		Over	all	61	42.3	E	D				
		EB WB	L	137.1	73.1	F	Е	504	411	404	375
			Т	61.8	36.5	Е	D	78	63	268	106
			R	46	22.3	D	С	305	44	243	129
			L	94.1	84.3	F	F	79	72	98	83
_			Т	92.3	79.6	F	E	93	83	117	91
畿	Burlington Mills Road at US 401 Business		R	60.6	36.9	Е	D	64	44	76	74
_	at 03 401 business		L	138.8	73	F	E	403	195	449	426
		NB	Т	25.8	32.6	С	С	614	734	734	700
			R	11.2	8	В	А	23	16	133	274
			L	97.5	100.5	F	F	132	160	199	199
		SB	Т	44.8	35.5	D	D	1142	628	1054	627
			R	7.2	5.7	А	А	131	52	689	145
		Over	all	47.4	17.5	D	В				
_	Freedaill D. J. S.	WB	Т	48.5	14.8	D	В	1311	113	1039	206
畿	Forestville Road at US 401 Westbound	VVD	R	20.6	18	С	В	242	117	438	263
-		NB	L	37.5	16.5	D	В	264	176	433	300
		SB	R	60.1	20.7	Е	С	693	256	606	248
		Over	all	17.9	20.4	В	С				
_	Formatelli D. J. S.	ED	Т	10.8	16.4	В	В	234	414	260	425
箫	Forestville Road at US 401 Eastbound	EB	R	9.7	9.2	Α	А	126	127	178	337
_	00401 Lastound	NB	R	32.1	36.9	С	D	178	239	278	293
		SB	L	26.8	25.1	С	С	166	143	245	383
_		Over	all	31.8	15.7	С	В				
影	US 401 Westbound U	WB	Т	23.9	13	С	В	1120	257	1265*	245
	Turn	NB	L	83.1	23.3	F	С	505	190	331	297
	* 0	ueue Exten									

Table 7: Capacity Analysis Results for 2026 No Build Conditions

Traffic Analysis July 28, 2022

6.3 2026 INITIAL PHASE ANALYSIS

In 2026 with the Initial phase of the development in place, the network experiences an incremental change in delays due to the addition of traffic generated by the proposed development. In large, operations are similar to that when compared with the 2026 No Build capacity analysis results as the overall level of service at the study intersections did not change with the addition of site trips.

The stop-controlled approach of Access A at Forestville Road operates at LOS F in both peak hours. This is attributed to high volumes of through traffic on Forestville Road.

The stop-controlled approach of Access C at Burlington Mills Road across from Centaur Road operates at LOS C in both peak hours.

The Initial phase capacity analysis results are listed in Table 8.

	Intersection	Approach	Lane Group	De (sec.,	lay (veh.)	Ser	el of vice DS)	95th % (fe	Queue et)	Qu	Obs. eue et)
				AM	РМ	AM	РМ	AM	РМ	AM	РМ
		Overa	all	47.1	29	D	С				
		EB	LTR	9	20.8	Α	С	134	465	316	934
_	Dudinates Mills David	WB	LTR	43.8	8.6	D	Α	643	168	984	865
箫	Burlington Mills Road at Ligon Mill Road	NB	L	72.8	54	E	D	95	87	290	123
	at Eigen Min Road	ND	TR	53.4	36.2	D	D	380	280	393	265
		SB	L	122.7	67.4	F	Е	150	159	300	288
		50	TR	60.4	45.6	Е	D	407	378	763	450
		Overa	all	90.7	80.2	F	F				
			L	171.7	120	F	F	424	635	224	224
		EB	Т	36	41.8	D	D	247	307	1213	1562
			R	25.7	28.2	С	С	49	74	250	250
箫	Burlington Mills Road	WB	L	36.8	71	D	E	103	205	275	275
٩Ø٢	at Forestville Road		TR	110.6	118.7	F	F	764	519	1923	1073
		NB	L	143.1	120.4	F	F	199	182	199	199
			TR	57.4	57.8	E	E	1246	1146	1812	1563
		SB	L	152.2	115.7	F	F	210	233	275	275
			TR	107.4	84	F	F	1526	1376	2100*	2058*
	Burlington Mills Road	EB	LTR	8.7	8.1	A	A	0	0	21	32
STOP	at Centaur Road /	WB	LTR	8.4	8.2	A	A	0	3	40	60
-	Access C	NB	LTR	20.6	15.9	С	С	13	5	38	31
		SB	LTR	20.7	16.1	С	С	5	3	29	32
_	Burlington Mills Road	EB	LT	8.6	8.2	A	A	0	3	42	114
STOP	at Huntingcreek Drive	SB	LR	15.8	12.4	С	В	8	3	34	22
		Overa		62	46.5	E	D				
		EB		138.5	83.2	F	F	532	439	410	394
			T	67.4	36.4	E	D	90	62	306	140
			R	51	26.8	D	С	308	98	266	155
			L	100.8	93.9	F	F	82	79	88	86
1 Q 1	Burlington Mills Road	WB	Т	98.6	92.3	F	F	96	93	136	113
읣	at US 401 Business		R	65.1	40.6	E	D	67	48	85	75
		ND	L - T	133.1	87	F C	F	418	181	435	436
		NB	Т	26.3	34.8	B	C	636	808	687	751
			R L	11.6 103.9	9 98.4	F	A F	24 137	17 163	228 199	228 200
		CD	 Т	46.7	96.4 36.7	г D	г D	1195	757	1037	627
		SB	R	7.4	7.9	A	A	139	130	790	195
		0.00				D		139	130	790	195
		Overa	all T	52.7 53.5	20.8 15.4	D	C B	1396	136	1092	221
읣	Forestville Road at	WB	R	23.2	15.4	C	B	299	136	438	221
יםי	US 401 Westbound	NB	L	38.4	18.6	D	B	284	215	406	295
		SB	R	68.3	28.1	E	C	818	360	615	281
		Overa		18.6	20.1	B	C	010	300	010	201
		Uver.	T	10.8	17.1	B	B	243	470	294	431
畿	Forestville Road at	EB	R	9.7	9.9	A	A	129	143	186	321
ישי	US 401 Eastbound	NB	R	34.2	38.4	c	D	123	236	293	311
		SB	L	28.1	32.2	c	C	105	143	253	323
		Overa		26.9	16.2	c	В	100	140	2.54	525
畿	US 401 Westbound U	WB	T	20.9	10.2	c	B	788	276	1234*	298
ינטי	Turn	NB	L	54.6	25.1	D	C	350	184	279	337
	Foroshills Dead -:	SB	LT	9.9	10.2	A	B	0	3	61	211
STOP	Forestville Road at Access A					F	F				
-	700033 A	WB	LR	398.3	1263 Network			173	180	83	91

Table 8: Capacity Analysis Results for 2026 Initial Phase Conditions

Traffic Analysis July 28, 2022

6.4 2026 INITIAL PHASE WITH IMPROVEMENTS ANALYSIS

Based on the findings of this study, specific improvements have been identified and should be completed as part of the Initial phase of this development. The recommendations are illustrated in Figure 19. The specific improvements are listed below and detailed in Section 7.1.

Forestville Road at Access A

- Provide Access A with two egress lanes (one left-turn lane and one right-turn lane) with a driveway stem length of a minimum of 170 feet
- Construct a northbound right-turn lane with 100 feet of full-width storage and appropriate taper
- Construct a southbound left-turn lane with 100 feet of full-width storage and appropriate taper

The Initial phase with Improvements capacity analysis results is listed in Table 9.

With the recommended improvements in place, the westbound approach of the Forestville Road at Access A intersection continues to operate with long delays compared to the 2026 Initial phase. The intersection is not anticipated to meet the criteria for the installation of a traffic signal at the Initial phase of development. This will be addressed as part of subsequent phases of development.

	Intersection	Approach	Lane Group		elay / veh.)	Lev Ser (LC	vice	95th % (fe	Queue et)	Qu	Obs. eue et)
				AM	РМ	AM	РМ	AM	РМ	AM	РМ
		Overa	all	47.1	29	D	С				
		EB	LTR	9	20.8	А	С	134	465	310	961*
_		WB	LTR	43.8	8.6	D	Α	643	168	992	1030
8	Burlington Mills Road at Ligon Mill Road	ND	L	72.8	54	E	D	95	87	265	151
	at Ligon will Road	NB	TR	53.4	36.2	D	D	380	280	418	293
		0.0	L	122.7	67.4	F	E	150	159	300	299
		SB	TR	60.4	45.6	E	D	407	378	867	622
		Over	all	90.7	80.2	F	F				
			L	171.7	120	F	F	424	635	225	224
		EB	Т	36	41.8	D	D	247	307	887	1497
			R	25.7	28.2	С	С	49	74	232	250
	Burlington Mills Road		L	36.8	71	D	E	103	205	275	275
8	at Forestville Road	WB	TR	110.6	118.7	F	F	764	519	2223	1078
			L	143.1	120.4	F	F	199	182	199	200
		NB	TR	57.4	57.8	Е	Е	1246	1146	1765	1652
			L	152.2	115.7	F	F	210	233	275	275
		SB	TR	107.4	84	F	F	1526	1376	2082*	2096
		EB	LTR	8.7	8.1	А	А	0	0	36	22
STOP	Burlington Mills Road	WB	LTR	8.4	8.2	А	А	0	3	25	69
	at Centaur Road /	NB	LTR	20.6	15.9	С	С	13	5	41	29
	Access C	SB	LTR	20.7	16.1	C	C	5	3	30	32
	Burlington Mills Road	EB	LT	8.6	8.2	A	A	0	3	28	74
STOP	at Huntingcreek Drive	SB	LR	15.8	12.4	C	В	8	3	36	24
-	al Hanangoroon Brito	Over		62	46.5	E	D	0	5	50	27
		Over	L	138.5	83.2	F	F	532	439	456	394
		EB	 T	67.4	36.4	E	D	90	62	375	143
		ED	R	51	26.8	D	C	308	98	274	143
			L	100.8	93.9	F	F	82	79	93	82
		WB	 T	98.6	93.9	F	F	96	93	123	108
	Burlington Mills Road		R	98.0 65.1	40.6	E	D	90 67	48	79	73
iUr	at US 401 Business		L	133.1	40.0 87	F	F	418	181	446	449
		NB	 T	26.3	34.8	C	C	636	808	624	811
		IND	R	11.6	9 9	В	A	24	17	224	276
			L	103.9	98.4	F	F	137	163	199	270
		CD	 T	46.7	36.7	D	Г D	1195	757	1096	552
		SB									
		<u></u>	R	7.4	7.9	A	A	139	130	964	167
		Over		52.7	20.8	D	C	1206	100	1240	220
8	Forestville Road at	WB	T	53.5	15.4	D	B	1396	136	1218	230
ittir	US 401 Westbound		R	23.2	18.8	C	B	299	141	438	287
		NB	L	38.4	18.6	D	B	284	215	613	314
		SB	R	68.3	28.1	E	C	818	360	645	304
		Over		18.6	21.6	В	С		455		
Dr	Forestville Road at	EB		10.8	17.1	B	B	243	470	321	463
	US 401 Eastbound		R	9.7	9.9	A	A	129	143	235	356
		NB	R	34.2	38.4	C	D	190	236	296	338
		SB	L	28.1	32.2	С	С	105	143	266	378
Dr	US 401 Westbound U	Over		26.9	16.2	С	В				
8	Turn	WB	Т	22.6	13	С	В	788	276	1217*	256
		NB	L	54.6	25.1	D	С	350	184	291	345
_	Forestville Road at	SB	L	9.9	10.2	Α	В	0	3	28	39
STOP	Access A	WB	L	414.2	1242.4	F	F	135	138	79	77
			R	16.4	16.2	С	С	5	3	27	24

Table 9: Capacity Analysis Results for 2026 Initial Phase with Improvements

Traffic Analysis July 28, 2022

6.5 2028 NO BUILD ANALYSIS

In the 2028 No Build scenario, increases in traffic volumes due to the addition of future traffic growth increase delay across the network. The following observations are notable:

The Burlington Mills Road & Ligon Mill Road intersection operates at LOS E in the AM peak hour with significant queues on several approaches.

At the intersection of Burlington Mills Road at Forestville Road, LOS F is expected during both peak hours with several movements operating with high delays and long queues. Specifically, left turns on the eastbound, northbound, and southbound approaches. The shared through / right-turn lanes on the westbound and southbound approaches also operate at LOS F.

At the intersection of Burlington Mills Road and US 401 Business, LOS E is expected in the AM peak hour with a few movements operating at LOS F. This is typical of locations that are implementing urban design concepts such as those from U-6241 and the Wallbrook development.

The Forestville Road & US 401 westbound reduced conflict intersection operates at LOS E in the AM peak hour. Similar to the 2026 scenarios, there are extensive queues for the westbound US 401 approaches in the AM peak hour.

The Forestville Road & Access A intersection still experiences excessive delays for the westbound left due to heavy traffic on Forestville Road with average delays of over 600 seconds in the AM peak hour and 1800 seconds in the PM peak hour.

2028 No Build capacity analysis results are listed in Table 10.

	Intersection	Approach	Lane Group		lay / veh.)	Ser	el of vice DS)		Queue et)	Qu	Obs. eue et)
				AM	РМ	AM	РМ	AM	РМ	AM	РМ
		Over	all	57.8	28.3	Е	С				
		EB	LTR	9.2	24.1	Α	С	145	521	288	1072*
_	Dudia star Milla Daad	WB	LTR	51.5	6.2	D	Α	496	136	947	1118
⑧	Burlington Mills Road at Ligon Mill Road	NB	L	85.4	51.3	F	D	105	83	299	112
	at Eigon Min Road	IND	TR	61.8	33.3	Е	С	423	262	541	256
		SB	L	211.4	63.2	F	Е	173	150	300	285
		30	TR	71.6	43.3	Е	D	451	362	1255*	930*
		Over	all	99.3	89.5	F	F				
			L	182.1	130.8	F	F	437	571	224	225
		EB	Т	44	36.9	D	D	285	242	1390	1687
			R	32.6	24.1	С	С	50	63	249	250
1 Q 2	Burlington Mills Road		L	41.9	71.7	D	E	184	216	275	275
畿	at Forestville Road	WB	TR	130.2	137.4	F	F	983	519	2344	1337*
		ND	L	150.5	97.3	F	F	223	153	200	200
		NB	TR	60.8	59.4	E	E	1360	1111	2031	1843
			L	177.3	137.2	F	F	230	217	274	275
		SB	TR	113.8	104.6	F	F	1668	1336	2098*	2101*
		EB	LTR	8.7	8.1	А	А	0	0	37	36
_	Burlington Mills Road	WB	LTR	8.4	8.3	А	А	0	3	35	62
STOP	at Centaur Road /	NB	LTR	21.4	16.3	С	С	13	5	36	40
	Access C	SB	LTR	21.4	16	С	С	5	3	35	30
	Burlington Mills Road	EB	LT	8.7	8.2	A	A	0	3	45	76
STOP	at Huntingcreek Drive	SB	LR	16.1	12.6	С	В	8	3	35	23
-	attraitingereen Ente	Over		65.3	43.4	E	D	0	5	- 55	23
		Over	L	61.8	77.6	E	E	451	433	408	354
		EB	T	40.5	36.1	D	D	67	76	374	110
		ED	R	38	18.7	D	B	403	52	271	123
			L	107.5	84.5	F	F	403 86	72	78	79
		WB	T			F	E			127	-
₩	Burlington Mills Road	VVD	R	104.8 43.7	79.6 37.9	г D	D	101 47	83 43	70	106 72
۱۲ ۴	at US 401 Business		L	43.7 94.7	74.2	F	E	47	43 206	474	474
		ND									
		NB	Т	37.2	32.9	D	C	791	781	920	866
			R	16.9 113.4	7.9	B F	A F	29 144	16	276	274
			L	-	114.8				164	199	200
		SB	T	102.7	36.5	F	D	1492	673	1158*	680
			R	9.1	5.7	A	A	153	57	1151*	147
		Over		61.5	19.1	E	В		46.5		
畿	Forestville Road at	WB	T	64.9	16	E	B	1545	124	1325	224
itti	US 401 Westbound		R	24	20.2	С	С	314	154	438	299
		NB	L	40.7	16.4	D	В	304	200	597	303
		SB	R	78.5	23.6	E	С	889	209	677	253
		Over		19.6	21.9	В	С				
יסי	Forestville Road at	EB	Т	11.3	18.1	В	В	265	451	330	440
畿	US 401 Eastbound		R	10	9.2	В	A	138	132	223	338
		NB	R	36.4	39.7	D	D	206	252	289	336
		SB	L	29.8	25.5	С	С	114	148	273	589
101	US 401 Westbound U	Over	all	31.3	15.9	С	В				
影	Turn	WB	Т	27	13.4	С	В	875	266	1272*	252
		NB	L	59.4	22.9	E	С	380	188	294	287
		SB	L	10	10.4	В	В	0	3	31	40
STOP	Forestville Road at		L	624.1	1823	F	F	153	148	127	68
STOP	Access A	WB	-	02							

Table 10: Capacity Analysis Results for 2028 No Build Conditions

Traffic Analysis July 28, 2022

6.6 2028 INTERMEDIATE PHASE ANALYSIS

In 2028 with the Intermediate phase of the development in place, the network experiences an incremental change in delays due to the addition of traffic generated by this phase of the proposed development. In large, operations are similar to that compared to the 2028 No Build capacity analysis results as only two locations experience a degradation in the Level of Service. Specifically, Access C in the AM peak hour increases from LOS C to LOS D. Also, the intersection of US 401 Eastbound at Forestville Road increases from LOS B to LOS C in the AM peak hour. Operations at both intersections are considered acceptable.

The Intermediate phase adds Access B, a right-in / right-out driveway, onto Burlington Mills Road. Capacity analysis results show this intersection operates at LOS B during both peak hours.

The Intermediate Build capacity analysis results are listed in Table 11.

	Intersection	Approach	Lane Group	De (sec.	lay / veh.)	Ser	el of vice DS)		Queue et)	Qu	Obs. eue et)
				AM	РМ	AM	РМ	AM	РМ	AM	РМ
		Overa	all	59.2	30.1	Е	С				
		EB	LTR	10.4	23.9	В	С	161	526	291	943'
_		WB	LTR	70.9	6.2	Е	А	574	136	1167	962
B	Burlington Mills Road at Ligon Mill Road	NB	L	78.4	55.3	Е	E	105	86	284	138
	at Ligon will Road	IND	TR	53.9	36.1	D	D	421	301	434	314
		CD	L	135.7	79.1	F	E	169	158	300	300
		SB	TR	59.6	46.4	Е	D	449	374	1071*	869
		Over	all	109.3	94.1	F	F				
			L	188.4	146	F	F	481	565	224	225
		EB	Т	48.8	36.6	D	D	323	242	1534	185
			R	34.5	24.4	С	С	60	70	249	250
	Burlington Mills Road		L	46.9	68	D	E	187	200	275	275
8;	at Forestville Road	WB	TR	139	144.3	F	F	1084	554	2606*	1828
		NB	L	205.1	106.4	F	F	277	175	200	199
		IND	TR	72.5	62.7	Е	Е	1438	1125	2423*	2166
		00	L	186.7	161.6	F	F	261	272	275	275
		SB	TR	120.4	104.6	F	F	1757	1336	2104*	2101
		EB	LTR	8.7	8.1	Α	Α	0	0	36	23
STOP	Burlington Mills Road	WB	LTR	8.5	8.4	Α	Α	0	3	153	62
	at Centaur Road / Access C	NB	LTR	29.6	20.2	D	С	35	15	119	54
	ALLESS C	SB	LTR	22.3	17	С	С	5	3	38	31
	Burlington Mills Road	EB	LT	8.7	8.3	Α	А	0	3	48	84
STOP	at Huntingcreek Drive	SB	LR	16.3	12.8	С	В	8	3	34	24
-	-	Over		62.9	43.5	E	D	-	-	-	
			L	126.8	74.3	F	E	591	429	442	363
		EB	T	54.2	36.1	D	D	90	72	417	120
			R	49.3	18.3	D	В	434	55	275	137
			L	114.3	84.5	F	F	91	72	104	90
		WB	T	111.3	79.6	F	E	105	83	123	113
E:	Burlington Mills Road	ington Mills Road	R	74.2	37.9	E	D	73	44	97	87
D	at US 401 Business			85.2	76.9	F	E	366	217	454	474
		NB	T	27.7	33.5	C	C	709	775	725	845
		ND	R	12.4	7.8	В	A	25	16	173	273
			L	117.2	111.5	F	F	150	164	199	200
		SB	T	73.6	36.8	Ē	D	1533	673	1147*	664
		30	R	15.6	5.7	B	A	319	60	1030*	139
		0						319	00	1030	139
		Over		69.5	19.8	E	B	1651	124	1304	245
8	Forestville Road at	WB	T	73.6	16.5						
d,	US 401 Westbound	NB	R	26.9 41.6	21.4 16.7	C D	C B	352 323	168 217	438 698	293 311
				-	-	-					-
		SB	R	89.5	24.6	F	C	1002	233	718	254
		Over		20.3	22	С	C	071	45.1	000	
pr	Forestville Road at	EB	T	11.4	18.1	В	B	274	454	332	437
8	US 401 Eastbound		R	10	9.2	В	A	141	132	221	344
		NB	R	38.6	39.7	D	D	218	252	312	323
		SB	L	30.9	25.9	С	С	127	148	308	496
Dr.	US 401 Westbound U	Over		30	15.9	С	В				
8	Turn	WB	Т	24.5	13.5	С	В	897	269	1275*	263
		NB	L	66.5	22.6	Е	С	407	187	283	306
_	Frankill, D. J. J.	SB	L	10.1	10.9	В	В	3	5	36	58
STOP	Forestville Road at	W/D	L	1472	4249	F	F	328	280	349	160
	Access A	WB	R	17.3	17	С	С	8	5	219	32
STOP	Burlington Mills Road	NB	R	11.6	11.2	В	в	3	0	27	24

Table 11: Capacity Analysis Results for 2028 Intermediate Build Conditions

Traffic Analysis July 28, 2022

6.7 2028 INTERMEDIATE BUILD WITH IMPROVEMENTS ANALYSIS

Based on the findings of this study, specific improvements have been identified and should be completed as part of the Intermediate phase of this development. The recommendations are illustrated in Figure 19. The specific improvements are listed below and detailed in Section 7.2.

Burlington Mills Road at Forestville Road

- Extend the existing eastbound left-turn lane to 575 feet of full-width storage and appropriate taper
- Extend the existing westbound left-turn lane to 225 feet of full-width storage and appropriate taper
- Construct a westbound right-turn lane with 150 feet of full-width storage and appropriate taper
- Extend the existing northbound left-turn lane to 225 feet of full-width storage and appropriate taper
- Extend the existing southbound left-turn lane to 300 feet of full-width storage and appropriate taper
- Construct a southbound right-turn lane with 200 feet of full-width storage and appropriate taper
- The above recommendations will require the traffic signal at the intersection to be modified.

Forestville Road at Access A

• Monitor Access A for potential signalization

The Initial phase with Improvements capacity analysis results is listed in Table 12.

With the recommended improvements in place, the level of service of the Burlington Mills Road & Forestville Road intersection improves from LOS F in both peak hours to LOS E in both peak hours. The eastbound left, westbound through, and southbound left movements still operate at LOS F in both peak hours but with reduced delays compared to the Intermediate Build without Improvements scenario, and there is now adequate storage to accommodate vehicles for these movements.

It should be noted that while the movement does not meet the requirements to study a protected-only phase in futureyear scenarios, the westbound left-turn was changed from permitted-only to protected-only as it resulted in significantly reduced delays and queues for the overall intersection, despite adding an extra phase to the signal.

The installation of a traffic signal at the intersection of Forestville Road and Access A during this phase of development would improve the LOS from an F to a C in both peak hours. The installation of a traffic signal is contingent upon the intersection meeting the warrants for installation of a traffic signal outlined in the Manual on Uniform Traffic Control Devices (MUTCD) and approved by NCDOT. Accordingly, it is recommended that the location be monitored for the installation of a traffic signal and that the design and construction of the signal be the responsibility of the applicant.

Table 12: Capacity Analysis Results for 2028 Intermediate Build with Improvements

	Intersection	Approach	Lane Group		Delay Se		el of vice DS)		95th %Queue (feet)		Max. Obs. Queue (feet)	
				AM	РМ	AM	РМ	AM	РМ	AM	PM	
		Overa		64.7	31.7	E	С					
		EB	LTR	12.7	23.9	В	С	214	526	422	1042	
B۶	Burlington Mills Road	WB	LTR	62.5	12.9	Е	В	1229	251	1902	156	
H:	Burlington Mills Road at Ligon Mill Road Burlington Mills Road at Forestville Road at Centaur Road / Access C Burlington Mills Road at Huntingcreek Drive Burlington Mills Road at Huntingcreek Drive	NB	L	119.7	55.3	F	E	145	86	299	156	
			TR	68.8	36.1	E	D	568	301	557	320	
		SB	L	194.6	79.1	F	E	236	158	300	299	
		05	TR	74	46.4	Е	D	608	374	1436*	761	
		Over	all	60	60.3	Е	E					
			L	117	97.5	F	F	349	516	362	565	
		EB	Т	73.8	69.4	Е	Е	307	326	368	466	
			R	20.2	27.1	С	С	34	75	234	248	
Dr			L	45.2	62.4	D	Е	141	194	325	297	
8	Burlington Mills Road	WB	Т	82.6	115.1	F	F	437	345	1046	694	
	, , , , , , , , , , , , , , , , , , ,		R	28.6	39.9	С	D	76	93	250	250	
			L	75	93.1	E	F	135	160	325	324	
		NB	TR	66.2	56.5	E	E	1147	1112	1853	172	
			L	120.5	129.5	 F	F	195	260	346	288	
		00	 Т			F D						
	Burlington Mills Road Access C Burlington Mills Road Burlington Mills Road Access C Burlington Mills Road Access C Burlington Mills Road Access C Burlington Mills Road Burlington Mills Road Access C Burlington Mills Road Access C Burlington Mills Road Burlington Mills Road Access C Burlington Mills Road Burlington Mills Road <td>SB</td> <td></td> <td>40.7</td> <td>38.2</td> <td></td> <td>D</td> <td>646</td> <td>733</td> <td>673</td> <td>690</td>	SB		40.7	38.2		D	646	733	673	690	
			R	11.7	4.8	B	A	168	60	300	300	
	Rurlington Mills Dard	EB	LTR	8.7	8.1	Α	Α	0	0	16	78	
STOP		WB	LTR	8.5	8.4	Α	Α	0	3	65	103	
		NB	LTR	29.6	20.2	D	С	35	15	64	56	
		SB	LTR	22.3	17	С	С	5	3	29	29	
	Burlington Mills Road	EB	LT	8.7	8.3	А	А	0	3	60	68	
STOP	, , , , , , , , , , , , , , , , , , ,	SB	LR	16.3	12.8	С	В	8	3	33	22	
	5	Over		70.8	44.3	E	D	Ű	0	00		
		Over			_	F	D	500	226	497	20,	
		FD	 Т	189.1	37.4			509	236		39	
		EB	-	40.4	18.1	D	В	61	22	457	96	
			R	35.7	11.9	D	В	205	26	266	147	
-0-			L	84.5	84.5	F	F	72	72	89	81	
	Burlington Mills Bood	WB	Т	79.6	79.6	E	E	83	83	106	107	
8	-		R	51.4	56.4	D	E	57	60	68	75	
			L	188.3	83.5	F	F	405	217	467	475	
		NB	Т	25.7	41.9	С	D	604	973	912	863	
			R	10.8	11.1	В	В	22	21	250	274	
			L	83.1	122.9	F	F	118	164	199	200	
		SB	Т	43.7	44.4	D	D	1098	836	1106*	725	
		30	R	7.1	7.6	A	A	122	115	935	210	
		Over				E		122	110	000	210	
		Over		69.9	19.8		В	4004	404	4005	0.44	
Pr	Forestville Road at	WB	T	70.9	16.5	E	B	1291	124	1085	240	
8;			R	17.6	21.4	B	С	229	168	438	299	
		NB	L	32.3	16.7	С	В	252	217	643	400	
		SB	R	102.7	24.5	F	С	935	375	792	28′	
		Over	all	16.7	22	В	С					
_		ED	Т	11.6	18.1	В	В	241	454	299	41(
8		EB	R	10.2	9.2	В	Α	126	132	211	317	
	US 401 Eastbound	NB	R	27.4	39.7	С	D	160	252	283	335	
		SB	L	23	25.9	С	С	134	148	261	427	
		Over		32.5	15.9	C	B					
8;	US 401 Westbound U-	WB	T	25.6	13.5	<u>с</u>	B	1094	269	1268*	274	
D	Turn											
		NB		77.7	22.6	E	C	507	187	331	305	
		Over		8.6	7.4	A	A	_				
		WB	L	34.6	33.7	С	С	96	74	129	104	
_	Ecrophille Dead at		R	29.4	30	С	С	38	31	65	44	
8	Forestville Road at Access A	NB	Т	8.8	6.1	А	Α	598	173	448	264	
	TULESS A		R	0	0.1	А	А	0	0	118	169	
		05	L	1.5	2.7	А	Α	1	10	54	70	
		SB	Т	4.3	7.3	А	Α	395	810	277	290	
STOP	Burlington Mills Road at Access B	NB	R	11.6	11.2	В	В	3	0	26	22	
STOP-					· · ·	-		ı		_ - •		

Traffic Analysis July 28, 2022

6.8 2029 NO BUILD ANALYSIS

In the 2029 No Build scenario, increases in traffic volumes due to the addition of future traffic growth increase delay across the network. The following observations are notable:

The Burlington Mills Road & Ligon Mill Road intersection operates at LOS E in the AM peak hour with significant queues on several approaches.

The intersection of Burlington Mills Road at Forestville Road operates at LOS E in both peak hours. Long queues are observed on the northbound and westbound through movements. Left turns on the eastbound, northbound, and southbound approaches operate at LOS F during both peak hours.

At the intersection of Burlington Mills Road and US 401 Business, LOS E is expected in the AM peak hour with a few movements operating at LOS F. This is typical of locations that are implementing urban design concepts such as those from U-6241 and the Wallbrook development.

The Forestville Road & US 401 westbound reduced conflict intersection now operates at LOS E in the AM peak hour. Similar to the 2026 scenarios, there are extensive queues for the westbound US 401 approaches in the AM peak hour.

The 2029 No Build capacity analysis results are listed in Table 13.

Table 13: Capacity Analysis Results for 2029 No Build Conditions

Intersection		Approach	Lane Group	De (sec./	lay / veh.)		el of vice DS)	95th % (fe	Queue et)	Que	Max. Obs. Queue (feet)	
				AM	РМ	AM	РМ	AM	РМ	AM	PM	
		Overa		70.3	32.7	E	С					
1 07		EB	LTR	14.3	26.8	В	С	238	551	418	1091	
	Burlington Mills Road	WB	LTR	80.8	16.7	F	В	1352	223	2247	208	
8	at Ligon Mill Road	NB	L	99.7	56.5	F	E	145	89	300	157	
	g		TR	67.6	34.8	E	С	583	300	755	319	
		SB	L	161.8	75.7	F	Е	241	159	300	300	
		30	TR	71.8	44	Е	D	629	372	1382*	1062	
		Over	all	62.5	62.2	E	E					
			L	117.8	90.4	F	F	375	505	415	574	
		EB	Т	66.7	65.7	E	E	301	308	(feet) AM PM 418 1091* 2247 2084 300 157 755 319 300 300 1382* 1062* 		
			R	21.2	28.1	С	С	42	70	232	250	
٦r			L	57.1	57.3	E	E	160	213	325	32!	
8	Burlington Mills Road	WB	Т	90.5	118	F	F	516	384			
	at Forestville Road		R	25.9	31.8	C	C	73	89			
			L	89.6	94.3	F	F	157	156			
		NB	TR	67.3	63.9	E	Ē	1229	1158			
		ļ	L	140.9	142.8	F	F	213	266			
	Burlington Mills Road at Centaur Road / Access C	6 D	<u> </u>									
		SB		42.9	40.5	D	D	697	766			
			R	11.9	7.2	B	A	179	106			
	Burlington Mills Road	EB	LTR	8.7	8.1	A	A	0	0	-		
STOP		WB	LTR	8.5	8.4	A	A	0	3	59	71	
	Access C	NB	LTR	30.3	20.4	D	С	35	15	77	64	
		SB	LTR	22.5	17.1	С	С	5	3	42	33	
	Burlington Mills Road	EB	LT	8.7	8.3	А	А	0	3	65	108	
STOP	at Huntingcreek Drive	SB	LR	16.5	12.9	С	В	8	3	36	21	
		Over	all	67.8	42.6	E	D					
			L	162	66.4	F	E	526	435	507	389	
		EB	Т	42.5	32.8	D	C	67	57			
		20	R	35.4	16.3	D	B	210	38			
			 L			F	F					
				87.5	84.5			75	72	65 108 36 21 5 507 389 478 98 273 155 82 86 110 108 86 68 9 458		
Qr	Burlington Mills Road	WB	<u>T</u>	86	79.6	F	E	88	83			
8;	at US 401 Business		R	55.9	38.3	E 	D	59	44			
			L	173.4	75.2	F	E	425	219			
		NB	Т	26.9	33.6	С	С	646	797			
			R	11	7.7	В	A	22	16	252	276	
			L	89.4	119.6	F	F	125	164	200	199	
		SB	Т	48.2	37.6	D	D	1194	687	1138	638	
			R	7.3	5.8	А	А	133	61	1037	150	
		Over	all	73.3	19.8	Е	В					
			Т	83.6	17.4	F	В	1416	137	1113	24	
8	Forestville Road at	WB	R	18.7	23.3	В	С	252	322			
-	US 401 Westbound	NB	L	33.8	16.2	C	B	268	214			
		SB	R	92.6	23.3	F	C	993	360			
		Over		17.5	23.3	B	C	000	000	001	00.	
		Over	T	11.7	23.2	B	C C	254	570	267	15	
<u>Ar</u>	Forestville Road at	EB										
8;	US 401 Eastbound		R	10.2	9.9	B	A	132	140	300 300 40 60 59 71 77 64 42 33 65 108 36 21 36 21 36 21 36 21 36 21 36 21 36 21 36 21 36 507 38 21 36 21 36 21 36 21 36 21 36 507 38 21 36 507 82 86 110 108 86 68 9 458 1037 156 2 438 1113 249 438 321 438 321 438 321 5 272 <		
		NB	R	29.8	37	С	D	174	248		0 157 5 319 0 300 2* 1062 2* 1062 5 574 0 480 2 250 5 325 41 653 0 250 4 325 33 222 7 392 2 874 0 300 0 201 33 222 7 392 2 874 0 300 0 600 0 711 7 389 3 155 2 276 0 108 5 389 3 156 0 108 3 156 1 357 2 276 0 108 3	
		SB		24.6	24.8	С	С	146	148	291	352	
Dr	US 401 Westbound U-	Over		35	16	D	В					
8;	Turn	WB	Т	27.8	13.8	С	В	1200	275	1270*	27:	
		NB	L	82.5	22.3	F	С	548	187	295	320	
		Over	all	9.1	7.5	А	А					
			L	37.8	33.7	D	С	102	74	130	108	
		WB	R	31.9	30	С	С	41	31	75	48	
Ø;	Forestville Road at	- <i>.</i> . –	Т	9	6.5	A	A	636	181			
ď	Access A	NB	 R	0	0.1	A	A	0	0			
			L	1.7	2.6	A	A	2	8			
		SB	 Т									
	Durlington Mills D		I	4.8	7.1	A	A	754	825	208	268	
STOP	Burlington Mills Road at Access B	NB	R	11.7	11.3	В	В	3	0	24	22	
									1			

Traffic Analysis July 28, 2022

6.9 2029 FULL BUILD ANALYSIS

In 2029 with the development fully built out, the network experiences an incremental change in delays due to the addition of traffic generated by the final phase of the proposed development. In large, operations are similar to that compared with the 2029 no build capacity analysis results as only two locations experience a degradation in LOS. Specifically, Access D in both peak hours increases one letter grade. That is, from LOS C to LOS D in the AM peak hour and from LOS B to LOS C in the PM peak hour. Forestville Road at Access A also experiences a degradation in LOS going from LOS A to LOS B in the AM peak hour.

This final phase adds Access C, a full-movement driveway, onto Burlington Mills across from Huntingcreek Drive. This intersection is projected to operate at LOS D in the AM peak hour and LOS C in the PM peak hour.

When warranted, the installation of a traffic signal is recommended at the intersection of Forestville Road and Access A as discussed in Section 6.7. This is contingent upon the intersection meeting the warrants for installation of a traffic signal outlined in the Manual on Uniform Traffic Control Devices (MUTCD) and approved by NCDOT. Accordingly, it is recommended that the location be monitored for the installation of a traffic signal and that the design and construction of the signal be the responsibility of the applicant.

The Full Build capacity analysis results are listed in Table 14.

Level of Max. Obs. Delay 95th % Queue Service Queue Lane (sec. / veh.) (feet) Intersection Approach Group (LOS) (feet) AM ΡM AM ΡM AM ΡM AM ΡM Overall 73.5 33.7 Е С 13.9 В С 433 EΒ LTR 28 238 563 1082* WB LTR 81.6 17.5 F В 1353 228 2193 2092 Burlington Mills Road L 118.8 56.5 F Е 153 89 299 177 at Ligon Mill Road NB Е D TR 70.3 35.5 598 306 658 323 F F L 198.7 82.7 250 161 300 300 SB Е TR 75 44 D 641 372 1359 941* Overall Е Е 65.2 64.3 130.8 97.7 F F 378 505 395 580 L EΒ Т 65.9 66.2 Е Е 305 336 370 609 R 20.9 27.5 С С 40 64 145 250 60.4 L 57.5 Е Е 159 207 325 311 箫 WB Т 95.5 117.3 F F 547 404 1225 633 Burlington Mills Road at Forestville Road R 25.8 30.5 С С 73 86 250 250 F F 133 324 L 92.6 87.6 124 325 NB TR 71.4 67.9 Е Е 1278 1190 2202 2036 L 140.9 137 F F 213 260 399 399 Т 42.4 699 SB 42.4 D D 810 839 818 В R 12.3 7.6 А 184 109 300 300 EΒ LTR А 8.2 А 0 0 57 8.8 55 **Burlington Mills Road** WB LTR 8.5 8.5 А А 0 3 49 107 at Centaur Road / STO NB LTR 29.4 20.8 D С 25 13 57 49 Access C SB LTR 23.6 17.9 С С 5 5 31 29 EΒ LTR 8.7 8.3 А А 0 3 54 106 WB LTR А А 0 3 78 8.5 8.3 28 **Burlington Mills Road** at Huntingcreek Drive D NB LTR 28.1 20.1 С 23 13 55 62 С С SB LR 20.2 15.9 13 5 40 31 Overall 69.3 43 Е D Е L 169.6 66 F 537 445 506 418 Т D С EΒ 43.3 31.9 68 54 487 156 R 37.5 161 D В 226 39 274 143 L 87.5 84.5 F F 75 72 88 85 Т F Е WB 86 79.6 88 83 117 106 箫 **Burlington Mills Road** R 55.9 Е D 44 74 38.4 59 67 at US 401 Business L 176.1 76.6 F Е 429 230 467 475 NB Т 26.9 33.8 С С 646 800 995* 820 R 11 7.8 В А 22 16 274 274 F F 125 L 89.4 124.1 164 200 200 Т 48.2 38 D D 1194 691 1149' 644 SB R 7.3 5.9 А А 134 63 1071 145 Overall 78.4 19.1 Е В Т 89.2 16 F В 1431 137 1187 258 WB Forestville Road at 읣 С R 19.5 21.2 В 259 223 438 305 US 401 Westbound NB 33.4 17.9 С В 274 236 718 L 727 344 SB R 100.8 21.7 F С 1044 777 297 Overall 17.5 23.2 В С

Table 14: Capacity Analysis Results for 2029 Full Build Conditions

		SB	L	24.6	24.4	С	С	146	148	305	338
		Over	all	35.1	16.1	D	В				
箫	US 401 Westbound U- Turn	WB	Т	27.9	138	С	В	1202	277	1276*	268
	run	NB	L	82.6	22.7	F	С	546	187	340	308
		Over	all	11.8	9.2	В	А				
		WB	L	37.3	34.6	D	С	132	97	169	129
	Essectille Desslet		R	29.7	29.3	С	С	50	38	83	70
铅	Forestville Road at Access A	NB	Т	12.2	7.5	В	Α	666	173	853	318
	10003371		R	0	0.1	Α	Α	0	0	167	187
		SB	L	2.1	4.1	А	А	2	11	104	165
		50	Т	6	9.4	А	А	512	839	298	325
STOP	Burlington Mills Road at Access B	NB	R	11.8	11.6	В	В	3	3	26	24
	* Q	ueue Exten	ds Off Si	mTraffic	Network	or Into I	Next Inte	rsection			

11.7

10.2

29.8

Т

R

R

EΒ

NB

Forestville Road at

US 401 Eastbound

읣

21.1

9.9

37

В

В

С

С

А

D

256

132

174

572

140

248

329

227

290

459

356

335

Recommendations July 28, 2022

7.0 RECOMMENDATIONS

Based on the findings of this study, specific improvements have been identified and should be completed as part of the proposed development.

7.1 INITIAL PHASE RECOMMENDATIONS

The following improvements are recommended to be constructed as part of the Initial phase of the development. These improvements are illustrated in Figure 19.

Burlington Mills Road at Ligon Mill Road

No improvements are recommended at this intersection

Burlington Mills Road at Forestville Road

No improvements are recommended at this intersection

Burlington Mills Road at Centaur Road / Access C

- Construct Access C as a full-movement access point
- Construct Access C with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Burlington Mills Road at Huntingcreek Drive

• No improvements are recommended at this intersection

Burlington Mills Road at US 401 Business

No improvements are recommended at this intersection

Forestville Road at Access A

- Construct Access A as a full-movement access point
- Construct Access A with one ingress and two egress lanes (one left-turn lane and one right-turn lane) with a driveway stem length of a minimum of 170 feet
- Construct a northbound Forestville Road right-turn lane with 100 feet of full-width storage and appropriate taper
- Construct a southbound Forestville Road left-turn lane with 100 feet of full-width storage and appropriate taper

Forestville Road at US 401

• No improvements are recommended at this intersection

Recommendations July 28, 2022

7.2 INTERMEDIATE PHASE RECOMMENDATIONS

Following the construction of the Initial phase and associated improvements, the following improvements are recommended to be constructed as part of the Intermediate phase of the development. These improvements are illustrated in Figure 19.

Burlington Mills Road at Ligon Mill Road

• No improvements are recommended at this intersection

Burlington Mills Road at Forestville Road

- Extend the existing eastbound Burlington Mills Road left-turn lane to 575 feet of full-width storage and appropriate taper
- Extend the existing westbound Burlington Mills Road left-turn lane to 225 feet of full-width storage and appropriate taper
- Construct a westbound Burlington Mills Road right-turn lane with 150 feet of full-width storage and appropriate taper
- Extend the existing northbound Forestville Road left-turn lane to 225 feet of full-width storage and appropriate taper
- Extend the existing southbound Forestville Road left-turn lane to 300 feet of full-width storage and appropriate taper
- Construct a southbound Forestville Road right-turn lane with 200 feet of full-width storage and appropriate taper
- The above recommendations will require the traffic signal at the intersection to be modified

Burlington Mills Road at Access B

- Construct Access B as a right-in/right-out access point
- Construct Access B with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Burlington Mills Road at Centaur Road / Access C

No improvements are recommended at this intersection

Burlington Mills Road at Huntingcreek Drive

No improvements are recommended at this intersection

Burlington Mills Road at US 401 Business

• No improvements are recommended at this intersection

Forestville Road at Access A

Monitor Access A for potential signalization

Forestville Road at US 401

• No improvements are recommended at this intersection

Conclusions July 28, 2022

7.3 FULL BUILD RECOMMENDATIONS

Following the construction of the Initial and Intermediate phases and associated improvements, the following improvements are recommended to be constructed as part of the Full Build phase of the development. These improvements are illustrated in Figure 19.

Burlington Mills Road at Ligon Mill Road

• No improvements are recommended at this intersection

Burlington Mills Road at Forestville Road

No improvements are recommended at this intersection

Burlington Mills Road at Access B

No improvements are recommended at this intersection

Burlington Mills Road at Centaur Road / Access C

No improvements are recommended at this intersection

Burlington Mills Road at Huntingcreek Drive / Access D

- Construct Access D as a full-movement access point
- Construct Access D with one ingress and one egress lane with a driveway stem length of a minimum of 100 feet

Burlington Mills Road at US 401 Business

• No improvements are recommended at this intersection


Forestville Road at Access A


• Monitor Access A for potential signalization

Forestville Road at US 401

• No improvements are recommended at this intersection







Lanes Signalized Intersection Stop-Controlled Intersection Improvement by Others Recommended Improvement - Initial Build Recommended Improvement - Intermediate Build Recommended Improvement - Full Build Monitor for Signalization - Intermediate Build Storage Length Figure is Not to Scale

Conclusions July 28, 2022

8.0 CONCLUSIONS

The results presented herein indicate that the proposed development will have an impact on the surrounding roadway network. These impacts are most pronounced at the intersection of Burlington Mills Road and Forestville Road. As a result, several improvements are recommended at the intersection. These improvements not only mitigate the development's impact on the intersection but also improve the Level of Service by a letter grade.

Other existing intersections in the study area? have improvements committed by other approved developments or public-funded projects. The results of this analysis show that these intersections experience minor increases in delay due to the proposed development. Accordingly, improvements are not recommended at these intersections.

The primary access point (Access A) on Forestville Road is anticipated to operate with high delays if it is left as a stop-controlled intersection, even with the addition of turn lanes on all approaches. The installation of a traffic signal would greatly improve operations but is contingent upon the intersection meeting the warrants for installation of a traffic signal outlined in the Manual on Uniform Traffic Control Devices (MUTCD) and approved by NCDOT. Accordingly, it is recommended that the location be monitored for the installation of a traffic signal and that the design and construction of the signal be the responsibility of the applicant.

All proposed driveways along Burlington Mills Road (Accesses B, C, and D) are expected to operate at an acceptable level of service in all scenarios and are not expected to have a significant impact on operations along Burlington Mills Road.

9.0 **REFERENCES**

¹ NCDOT Functional Classification Map,

http://ncdot.maps.arcgis.com/home/webmap/viewer.html?layers=029a9a9fe26e43d687d30cd3c08b1792

² 2020 NCDOT Average Daily Traffic Volumes,

https://ncdot.maps.arcgis.com/apps/webappviewer/index.html?id=964881960f0549de8c3583bf46ef5ed4

³ Trip Generation (11th Edition), Institute of Transportation Engineers (ITE), September 2021.

⁴ *Highway Capacity Manual 6th Edition: A Guide for Multimodal Mobility Analysis*. Washington D.C.: Transportation Research Board, 2016.

⁵ *NCDOT Capacity Analysis Guidelines*. North Carolina Department of Transportation (NCDOT), March 2022, <u>https://connect.ncdot.gov/resources/safety/Congestion%20Mngmt%20and%20Signing/Standards%20-</u> <u>%20Capacity%20Analysis%20Guidelines.pdf</u>

⁶ Draft NCDOT Capacity Analysis Guidelines: Best Practices. North Carolina Department of Transportation (NCDOT), March 2022,

https://connect.ncdot.gov/resources/safety/Congestion%20Mngmt%20and%20Signing/Best%20Practices%20-%20Capacity%20Analysis%20Guidelines.pdf

⁷ *Land Development Ordinance*. Town of Rolesville, June 1, 2021, <u>https://www.rolesvillenc.gov/code-ordinances</u>

Appendix July 28, 2022

APPENDIX

A link containing all relevant files is electronically sent with this report:

- NCDOT Scoping Checklist
- Site Plan
- Traffic Count Data
- Approved Development Information
- Traffic Volume Calculations
- Synchro and SimTraffic Files
- Traffic Signal Plans



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER GOVERNOR J. ERIC BOYETTE Secretary

August 26, 2022

Tom's Creek Development

Traffic Impact Analysis Review Report

Congestion Management Section

TIA Project:SC-2022-270Division:5County:Wake



Clarence B. Bunting, IV, P.E. Regional Engineer Daniel W. Collins, Design Engineer

Mailing Address: NC DEPARTMENT OF TRANSPORTATION TRANSPORTATION MOBILITY & SAFETY DIVISION 1561 MAIL SERVICE CENTER RALEIGH, NC 27699-1561 Telephone: (919) 814-5000 Fax: (919) 771-2745 Customer Service: 1-877-368-4968

Location: 750 N. GREENFIELD PARKWAY GARNER, NC 27529

Website: www.ncdot.gov

Tom's Creek Development

SC-2022-270	Roles	sville	Wake County					
Per your request, the Congestion Management Section (CMS) of the Transportation								
Mobility and Safety Division has completed a review of the subject site. The comments								
and recommendations contai	ned in this re	view are bas	ed on data for ba	ackground				
conditions presented in the Tra				e approval				
of the local District Engineer's Office and appropriate local authorities.								
Date Initially Received by CM	S 07/29/22	Date of Site F	Plan	03/31/22				

08/12/22 Date of Sealed TIA

07/28/22

Proposed Development

Date of Complete Information

The TIA assumes the development is completed by 2029 and consists of the following:

Land Use	Land Use Code	Size
Single Family Detached Housing	210	606 d.u

Trip Generation - Unadjusted Volumes During a Typical Weekday								
	IN	OUT	TOTAL					
AM Peak Hour	100	284	384					
PM Peak Hour	340	200	540					
Daily Trips			5,294					

General Reference

For reference to various documents applicable to this review please reference the following link: *https://connect.ncdot.gov/resources/safety/Pages/Congestion-Management.aspx* Once the driveway permit has been approved and issued, a copy of the final driveway permit requirements should be forwarded to this office. If we can provide further assistance, please contact the Congestion Management Section.

Improvements By Others


The analysis includes background improvements by others. If these improvements are not in place at the time of construction, the site should provide these improvements or analysis demonstrating mitigation is not necessary.

Signalization

We defer to the District Engineer, the Division Traffic Engineer, and the Regional Traffic Engineer for final decisions regarding signalization.

Phased Background Traffic

Please note that background analysis for each phase includes the site traffic from previously developed phases. Additional analysis files were submitted.





Tom's Creek Development SC-2022-270

	Existing Laneage
	Recommended Laneage
27777	Laneage Built By Others
-	NCDOT Recommendation
8	Existing Signal
	Signal Proposed By Others
8	Monitor For Signal
XXX	Storage
XXX	NCDOT Recommended Storage
<xxx> IPS</xxx>	Distance Between Intersections Internal Protected Stem Improvement by Others Initial Build Intermediate Build Full Build All Distances in Feet Drawing Not to Scale



TOWN OF ROLESVILLE PETITION FOR ANNEXATION

The items below are required in order to complete your application and shall be submitted when the application if filed.

- 1. A complete copy of the last deed of record for proof of ownership
 - 2. An annexation boundary plat/map for recordation at the Wake County Register of Deeds Office (mylar plat) prepared by a professional land surveyor showing the boundaries of the area or property for annexation into the Town of Rolesville.
 - 3. A complete copy of the written metes and bounds description based on the annexation boundary plat/map.

SECTION 1 - LOCATION

Is the area contiguous with the existing primary corporate limits? Satellite corporate limits is not primary. \square Yes or \square No Note: If the land is contiguous to any existing corporate limits, the proposed annexation boundary will include all intervening right-of-ways for streets, easements, and other areas as stated in North Carolina General Statute §160-131(1).

SECTION 2 – VESTED RIGHTS

NC General Statues require petitioners of both contiguous and non-contiguous annexations to file a signed statement declaring whether vested rights have been established in accordance with G.S. 160A-385.1 or 153A-344.1 for properties subject to the petition. Do you declare vested rights for the property subject to this petition? \Box Yes or \Box No

SECTION 3 - PROPERTY DETAILS

PIN Number	Real Estate ID Number	Deed Book Number	Page Number	Acreage To Be Annexed	Wake County Assessed Value
1748891680	0318100	DB 014427	PG 01034	172.03	\$ \$4,578,795
1758081893	0063677	DB 011146	PG 00339	33.81	\$ \$998,985
1748884104	0325091	DB 011180	PG 01815	17.10	\$ \$317,265

SECTION 4 - SIGNATURES AND VERIFICATION

We, the undersigned owners of the real properties contained in the metes and bounds description and plat/map attached hereto, respectfully request that the area described above be annexed and made part of the Town of Rolesville, North Carolina. By signing below, we acknowledge that all information is correct.

· If property owned by INDIVIDUALS (NOTE: All legal owners must sign including both husband and wife)

Earl F.	Shout	
Signature of Owner #1	C)

Signature of Owner #2

8-17-2022

Name

Date Signed

Date Signed

• If property owned by a COMPANY OR CORPORATION (NOTE: The company or corporation must be legally registered with the State of North Carolina – Office of the Secretary of State)

ESN	ΕL	LC

of Corporation EARLF. SHOAF E	l7. Shoop
Printed Name of Registered Agent Signature of R 343 South White Street, Wake Forest, NC 27587	Registered Agent
Address, State, Zip of Registered Office:	
County Elizabeth A. Howers a a where public for said County and State, do hereby certify that the Vitness my hand and efficient of the said County and State, do hereby certify that the NOTARY NOTARY MY COMMISSION EXPIRES 03.28.27 PUBLIC PUBLIC	e above signed individual(s) appeared before me this day and signed the formolog instrument. Notary Public My communication expires: 03.28.27



TOWN OF ROLESVILLE PETITION FOR ANNEXATION

The items below are required in order to complete your application and shall be submitted when the application if filed.

- 1. A complete copy of the last deed of record for proof of ownership
- 2. An annexation boundary plat/map for recordation at the Wake County Register of Deeds Office (mylar plat) prepared by a professional land surveyor showing the boundaries of the area or property for annexation into the Town of Rolesville.
- 3. A complete copy of the written metes and bounds description based on the annexation boundary plat/map.

SECTION 1 - LOCATION

Is the area contiguous with the existing primary corporate limits? Satellite corporate limits is not primary. \square Yes or \square No Note: If the land is contiguous to any existing corporate limits, the proposed annexation houndary will include all intervening right-of-ways for streets, easements, and other areas as stated in North Carolina General Statute §160-131(1).

SECTION 2 - VESTED RIGHTS

NC General Statues require petitioners of both contiguous and non-contiguous annexations to file a signed statement declaring whether vested rights have been established in accordance with G.S. 160A-385.1 or 153A-344.1 for properties subject to the petition. Do you declare vested rights for the property subject to this petition? \Box Yes or \boxtimes No

SECTION 3 - PROPERTY DETAILS

POGE LLC

PIN Number	Real Estate ID Number	Deed Book Number	Page Number	Acreage To Be Annexed	Wake County Assessed Value
1748891680	0318100	DB 014427	PG 01034	172.03	\$ \$4,578,795
1758081893	0063677	DB 011146	PG 00339	33.81	\$ \$998,985
1748884104	0325091	DB 011180	PG 01815	17.10	\$ \$317.265

SECTION 4 - SIGNATURES AND VERIFICATION

We, the undersigned owners of the real properties contained in the metes and bounds description and plat/map attached hereto, respectfully request that the area described above be annexed and made part of the Town of Rolesville, North Carolina. By signing below, we acknowledge that all information is correct.

• If property owned by INDIVIDUALS (NOTE: All legal owners must sign including both husband and wife)

Signature of Owner #1	Date Signed
Signature of Owner #2	 Date Signed

• If property owned by a COMPANY OR CORPORATION (NOTE: The company or corporation must be legally registered with the State of North Carolina – Office of the Secretary of State)

	Name
ANDREWL AMMONS	Al An
Printed Name of Registered Agent 8368 Six Forks Road, Suite 204, Raleigh, NC 2761	Signature of Registered Agent 5
Address, State, Zip of Registered Office:	\wedge
North Carolina, County	
1. Elin a berti Will Aunthow KS a Notary Public for said County and State, do he Witness no be Cand official Sculffit 19 17 day of AMAUST, 20 23	reby certify that the above signed inflividual(s) preared before mothingday and signed the foregoing instrument.
NOTARY THE	MULLAN
	Notary Chilic My commission expires: 03.28.27
03.28.27	
A PUBLIC ANIT	0
COUNT MININ	

ANX 22-07

BK011146PG00339

WAKE COUNTY, NC 233 LAURA M RIDDICK REGISTER OF DEEDS PRESENTED & RECORDED ON 12/16/2004 AT 11:41:56 STATE OF NORTH CAROLINA REAL ESTATE EXCISE TAX: \$694 BOOK:011146 PAGE:00339 - 00342

NORTH CAR	OLINA GEI	NERAL	WARRAN'	TY DEED	
Parcel Identifier No. 63677 By:	Verified by	~ .	_ County on the	day of	, 20
Mail/Box to: Box 204					
This instrument was prepared by: E.R.					
Brief description for the Index:					
THIS DEED made this	К	day of	Damber	, 20 <u>0</u>	⊈, by and between
GRANTOR			GRAN	TEE	
POGE, LLC			ESNE, LLC		
			(*a 50% und:	ivided inte	rest)
			316 Bay	tree fone	
			Raleigh .	tree have NC 27	609
Enter in appropriate block for each party:	name, address, and,	if appropriat			
The designation Grantor and Grantee as use singular, plural, masculine, feminine or net	ed herein shall includ	e said parties			
WITNESSETH, that the Grantor, for a valu and by these presents does grant, bargain, se the City of	able consideration pa	id by the Gra Grantee in f	ee simple [*] all that ce	rtain lot or narcel	of land situated in
SEE EXHIBIT A ATTACHED HERETC					
a 50% undivided interest					
The property hereinabove described was ac	quired by Grantor by	instrument 1	recorded in Book	11074 page	, 180-183
A map showing the above described proper					
NC Bar Association Form No. 3 @ 1076 P					

Printed by Agreement with the NC Bar Association - 1981

+ James Williams & Co., Inc. www.JamesWilliams.com

BK011146PG00340

2

TO HAVE AND TO HOLD the aforesaid lot or parcel of land and all privileges and appurtenances thereto belonging to the Grantee in fee simple.

And the Grantor covenants with the Grantee, that Grantor is seized of the premises in fee simple, has the right to convey the same in fee simple, that title is marketable and free and clear of all encumbrances, and that Grantor will warrant and defend the title against the lawful claims of all persons whomsoever, other than the following exceptions:

Subject to easements, rights of way, restrictions of record and 2004 ad valorem taxes.

IN WITNESS WHEREOF, the Grantor has duly executed the foregoing as of the day and year first above written.

POGE, LLC	Δ		(SEAL)
By:	ar Allow	-	(SEAL)
	BLACK INK		(SEAL)
Ву:	RE		(SEAL)
	I, the undersigned Notary Public of the County and State		
	A acknowledged the due execution of the foregoing instruction of the foreg	personally appeared before ment for the purposes therein express day of	ed. Witness my
	My Commission Expires:	Notary Public	
OTARL DTARL A COUNTY, N.	I, the undersigned Notary Public of the County and State <u>AADWWL</u> , <u>AMMONS</u> acknowledged that he is the <u>Makagu</u> a North Carolina or <u>corporation/I</u> pa rtnership (strike through the inapplicable), and that the he signed the forgoing instrument in its name on its Notarial stamp or seal this <u>1544</u> My Commission Expires: <u>2-3.08</u>	personally came before m of <u>7066</u> , UC mited liability company/general par y authority duly given and as the ac behalf as its act and deed. Witnes day of <u>Decembu</u>	tnership/limited t of each entity,
	State of North Carolina - County of VIIII I, the undersigned Notary Public of the County and State	aforesaid, certify that	•
	Witness my hand and Notarial stamp or seal this My Commission Expires:		,20
	SD	Notary Public	
	te(s) of	e Book and Page shown on the fir	
······································		Bistor of Docas	

NC Bar Association Form No. 3 © 1976, Revised © 1977, 2002 Printed by Agreement with the NC Bar Association - 1981 * James Williams & Co., Inc. www.JamesWilliams.com

BK011146PG00341

EXHIBIT A

BEGINNING at an existing iron pipe in the southern right of way of Burlington Mills Road, being the northeast corner of Herbert F. Faison Property (Deed Book 10986, Page 2004, Wake County Registry); thence with the Faison line south 0° 53 minutes 33 seconds east 416.19 feet to an iron pipe; thence south 89° 17 minutes 04 seconds west 234.59 feet to an existing iron pipe; thence south 0° 39 minutes 48 seconds east 124.39 feet to an existing iron pipe; thence south 89° 20 minutes 19 seconds west 330.37 feet to an existing iron pipe; thence south 15° 48 minutes 27 seconds west 115.81 feet to an existing iron pipe; thence north 84° 20 minutes 47 seconds west 599.08 feet to an existing iron pipe; thence south 09° 00 minutes 45 seconds west 1,229.37 feet to an existing iron pipe; thence south 89° 00 minutes 15 seconds east 590.45 feet to a bent axle; thence north 08° 39 minutes 21 seconds east 511.98 feet to an iron pipe; thence south 89° 46 minutes 10 seconds east 964.65 feet to an axle; thence north 01° 14 minutes 54 seconds west 59.88 feet to an iron pipe; thence north 01° 18 minutes 47 seconds west 255.38 feet to an iron pipe; thence north 01° 19 minutes 39 seconds west 195.03 feet to an iron pipe; thence north 01° 19 minutes 44 seconds west 399.16 feet to an iron pipe; thence north 89° 02 minutes 56 seconds east 206.09 feet to a point in the southern right of way of Burlington Mills Road; thence along with the southern right of way of Burlington Mills Road a curve to the right, having a radius of 515.68 feet, a length of 226.18 feet, and a chord bearing of north 54° 29 minutes 10 seconds west, a distance of 224.37 feet to an iron pipe set; thence with said right of way north 41° 55 minutes 16 seconds west 297.45 feet to an iron pipe set; thence with said right of way a curve to the left, having a radius of 663.20 feet, a length of 82.17 feet, and chord bearing of north 45° 28 minutes 14 seconds west, a distance of 82.12 feet to the point of beginning, and being all of Parcel 1, containing 34.928 acres, as shown on a survey entitled, "Boundary Survey for Ammons Development Group, Heritage/Trevisan Survey," dated October 7, 2004, prepared by Mulkey Engineers & Consultants.

See also plat recorded in Book of Maps 1997, Page 1970, Wake County Registry.



BOOK:011146 PAGE:00339 - 00342___

Yellow probate sheet is a vital part of your recorded document. Please retain with original document and submit for rerecording.



Wake County Register of Deeds Laura M. Riddick Register of Deeds

North Carolina – Wake (County		
The foregoing certificate_		H. Teaque	
			_

_____ Notary(ies) Public is (are) certified to be correct. This instrument and this certificate are duly registered at the date and time and in the book and page shown on the first page hereof.

Laura M Riddick, Register of Deeds 10 6 By: _

Assistant/Deputy Register of Deeds

This Document New Time Stamp # of Pages

22.004-7/11/03

This Customer Group

______ # of Time Stamps Needed

BK014427PG01034

WAKE COUNTY, NC 23 LAURA M RIDDICK REGISTER OF DEEDS PRESENTED & RECORDED ON 08/09/2011 AT 09:34:05 STATE OF NORTH CAROLINA REAL ESTATE EXCISE TAX: \$90 BOOK:014427 PAGE:01034 ~ 01036

HOLD FOR: Warren Jordan Shackleford, P.L.L.C. Box 204

PREPARED BY: Warren Jordan Shackleford, P.L.L.C., Ib 343 S. White Street, Wake Forest, NC 27587

TAX IDENTIFICATION #: 219552

REVENUE STAMP <u>\$ 90.00</u>

NORTH CAROLINA GENERAL WARRANTY DEED

This deed made this 26th day of July, 2011 by and between:

GRANTOR: VANESSA C. WHITNEY AND HUSBAND, STEVEN E. WHITNEY 590 White Oak Ridge Rd., Short Hills, NJ 07078

GRANTEE: POGE, LLC AND ESNE, LLC P.O. Box 1615, Wake Forest, NC 27588-1615

Grantor, for valuable consideration paid by Grantee, receipt of which is hereby acknowledged, does grant, convey and transfer unto Grantee in fee simple the property described as follows:

TOWNSHIP OF _____, COUNTY OF WAKE

BEING all of that 0.639 acre tract shown on plat entitled "Recombination Survey For POGE, LLC & ESNE, LLC", a copy of which is recorded in Book of Maps 2011, Page 665, Wake County Registry. This tract is bordered on the north by other land of Grantor, on the east by other land of Grantee, on the south by other land of Perry and on the west by the center line of Forestville Road.

The interest conveyed to POGE, LLC is a one half interest and the interest conveyed to ESNE, LLC is a one half interest in the above described property.

All or a portion of the property herein conveyed $_$ includes or \underline{x} does not include the primary residence of a Grantor.

BK014427PG01035

A so

TO HAVE AND TO HOLD the above described property and all privileges and appurtenances thereto belonging to the Grantee in fee simple.

Grantor covenants with Grantee, that Grantor is seized of the premises in fee simple, has the right to convey the same in fee simple, that title is marketable and free and clear of all encumbrances, and that Grantor will warrant and defend the title to the property against the lawful claims of all others except for the exceptions set out below.

Title to the property described herein is subject to the following exceptions:

1. Subject to the right of way of Forestville Road.

NN 20 IN WITNESS WHEREOF, Grantor has set his hand and seal, or if corporate, has caused this herry signed in its corporate name by a duly authorized officer. Vhitne (SP) Steven E. Whitney đ \mathbf{O} STATE O a Notary Public for the County of State of certify that Vanessa C. Whitney personally appeared before me this day and acknowledged the execution of the foregoing instrument. Witness my hand and official stamp or seal, this the of 3. dav Notary Public My Commission Expires XNiddl a Notary Public for the County of State certify that Steven E. Whitney personally appeared before me this day and acknowledged of the execution of the foregoing instrument. 2011. Witness my hand and official stamp or seal, this the _day of uΝ Notary Public 2013 My Commission Expires:

DEBORAH BROWN NOTARY PUBLIC OF NEW JERSEY Commission Expires 5/1/2013

POGE1615



.

BOOK:014427 PAGE:01034 - 01036

Yellow probate sheet is a vital part of your recorded document. Please retain with original document and submit for rerecording.




.

Wake County Register of Deeds Laura M. Riddick Register of Deeds

This Customer Group # of Time Stamps Needed This Document

_ New Time Stamp _ # of Pages

22.004-1/20/06



TOM'S CREEK ANNEXATION: LEGAL DESCRIPTION

Beginning at a point on the northern right of way line of Burlington Mills Road (a 60 foot public right of way); thence crossing said road, South 00°43'21" East a distance of 46.92 feet to a point; thence South 89°03'08" West a distance of 60.00 feet to an iron pipe, being the northeast corner of lot 1, as shown on book of maps 1983, page 1032; thence with said common line, South 89°03'39" West a distance of 187.22 feet to a an iron pipe; thence South 01°20'27" East a distance of 909.54 feet to an iron pipe, being a corner on the northern line of lands now of formally owned by the Ronald Gay Revocable Trust, as described in deed book 15275, page 1754; thence with said common line, North 89°46'12" West a distance of 964.93 feet to an iron pipe; thence South 08°38'57" West a distance of 511.94 feet to an iron pipe; thence North 88°59'41" West a distance of 1019.11 feet to an iron pipe; thence South 11°10'22" West a distance of 67.04 feet to an iron pipe; thence South 07°22'33" West a distance of 97.35 feet to an iron pipe; thence South 36°25'17" East a distance of 43.76 feet to an iron pipe; thence South 06°34'13" West a distance of 230.02 feet to an iron pipe; thence North 77°03'06" West a distance of 82.83 feet to a point; thence North 81°12'25" West a distance of 75.13 feet to a point; thence North 40°14'16" West a distance of 51.36 feet to a point, being the northeast corner of future common area "A", as shown on book of maps 2009, page 766; thence with said common line, North 42°57'03" West a distance of 65.28 feet to a point; thence North 44°16'05" West a distance of 120.33 feet to an iron pipe; thence North 70°43'54" West a distance of 186.82 feet to a point; thence South 80°13'05" West a distance of 193.30 feet to a point; thence North 83°14'58" West a distance of 211.03 feet to a point; thence North 36°02'02" West a distance of 382.28 feet to an iron pipe; thence North 68°25'41" West a distance of 57.67 feet to an iron pipe; thence North 01°28'10" East a distance of 286.16 feet to an iron pipe; thence North 89°55'54" West a distance of 1514.36 feet to an iron pipe on the eastern right of way line of Forestville Road (a 60 foot public right of way), passing through an iron pipe 24.99 feet before the end of the line; thence going across Forestville Road, South 89°54'41" West a distance of 60.37 feet to a point on the western of right of way line of said road; thence North 89°52'27" West a distance of 99.63 feet to a point on the eastern line of an open space lot, as shown on book of maps 2006, page 2455; thence with said common line, North 25°21'09" East a distance of 98.59 feet to an iron pipe; thence North 59°46'50" East a distance of 86.29 feet to an iron pipe on the western right of way line of Forestville Road; thence crossing Forestville Road, North 59°38'25" East a distance of 78.37 feet to an iron pipe on the eastern right of way line of said road, being the southwest corner of lands now or formally owned by Chester Hall, as described in deed book 15126, page 738; thence with said common line, North 59°44'06" East a distance of 44.33 feet to an iron pipe; thence North 33°55'46" East a distance of 456.11 feet to an iron pipe, being the southeast corner of the 1.05 acre tract as shown on book of maps 1984, page 1180; thence with said common line, North 15°01'05" East a distance of 160.64 feet to an iron pipe; thence North 80°14'37" West a distance of 293.14 feet to a point on the western right of way line of Forestville Road, passing through an iron pipe on the eastern right of way line of said road 59.90 feet before the end of the line; thence with the right of way line of said road, North 09°43'25" East a distance of 119.68 feet to a point; thence leaving said right of way line, South 79°14'30" East a distance of 303.79 feet to an iron pipe, being the southeastern corner of lot 2, as shown on book of maps 2011, page 665, passing through an iron pipe on the eastern right of way line of said road 244.11 feet before the end of the line; thence from the southeast corner of lot 2 with said common line, North 15°01'13" East a distance of 215.24 feet to an iron pipe; thence North 14°59'03" East a distance of 147.83 feet to an iron pipe, being the southeast corner of lot 1A, as shown on book of maps 2015, page 364; thence with said common line, North 10°16'58" East a distance of 545.13 feet to an iron

pipe, being the southeast corner of lands now or formally owned by Ricky Upchurch, as described in deed book 19101, page 210; thence with said common line, North 11°33'27" East a distance of 498.22 feet to an iron pipe on the eastern line of tract 2, as shown on book of maps 2008, page 316; thence with said common line, North 01°40'05" West a distance of 81.40 feet to an iron pipe, being the southeast corner of the 1.00 acre tract, as shown on book of maps 1983, page 1428; thence with said common line, North 00°47'30" West a distance of 199.02 feet to an iron pipe, being a corner on the southern line of lot 2, as shown on book of maps 2015, page 852; thence with said common line, South 89°01'55" East a distance of 1539.42 feet to an iron pipe on the southern line of lands now of formally owned by Cynthia Brown, et.al., as described in deed book 8488, page 1172; thence with said common line, South 89°57'48" East a distance of 177.78 feet to an iron pipe, being the northwest corner of lot 1 as shown on book of maps 2016, page 1918; thence with said common line, South 00°02'53" East a distance of 280.76 feet to an iron pipe; thence North 89°54'46" East a distance of 185.05 feet to an iron pipe; thence South 55°12'12" East a distance of 240.28 feet to an iron pipe, being a corner on the western line of the 5.00 acre tract, as shown on book of maps 1978, page 466; thence with said common line, South 34°48'09" West a distance of 398.52 feet to an iron pipe; thence South 55°16'40" East a distance of 299.72 feet to an iron pipe; thence North 34°50'47" East a distance of 756.71 feet to a point on the northern right of way line of Burlington Mills Road, passing through an iron pipe 60.04 feet before the end of the line; thence with said right of way line, South 57°04'24" East a distance of 748.89 feet to a point; thence with a curve to the left a radius of 1846.64 feet, an arc length of 160.08 feet, a chord bearing of South 59°40'11" East, a chord length of 160.03 feet to a point; thence leaving said right of way line, South 01°53'41" West a distance of 601.38 feet to an iron pipe on the western line of lots 2-4, as shown on book of maps 1980, page 1034, passing through an iron pipe on the southern right of way line of said road 534.89 feet before the end of the line; thence with said common line, South 02°05'19" West a distance of 61.24 feet to an iron pipe, being the northwest corner of lot 2, as shown on book of maps 2001, page 2256; thence with said common line, South 01°51'32" West a distance of 40.02 feet to an iron pipe, being a northeast corner of lot 1, as shown on book of maps 2015, page 2033; thence with said common line, North 89°12'34" West a distance of 298.87 feet to an iron pipe; thence South 04°47'52" West a distance of 263.29 feet an iron pipe; thence South 04°43'50" West a distance of 35.66 feet to an iron pipe; thence North 89°59'24" East a distance of 639.81 feet to an iron pipe; thence North 00°40'04" West a distance of 123.61 feet to an iron pipe; thence North 00°40'04" West a distance of 124.37 feet to an iron pipe, being the southwest corner of lands now or formally owned by Tammy Taylor, et.al., as described in deed book 3304, page 182; thence with said common line, North 89°16'36" East a distance of 234.62 feet to an iron pipe, being the southeast corner of lands now of formally owned Herbert Faison, et.al., as shown on book of maps 2017, page 1607; thence North 00°53'11" West a distance of 416.19 feet to an iron pipe on the southern right of way line of Burlington Mills Road; thence across said road, North 00°53'11" West a distance of 74.05 feet to a point on the northern right of way line of said road, passing through the corner in the center of said road 37.33 feet before the end of the line; thence with said right of way line, South 53°53'43" East a distance of 25.81 feet to a point; thence South 47°28'59" East a distance of 119.14 feet to a point; thence South 41°44'03" East a distance of 142.74 feet to a point; thence South 40°47'35" East a distance of 104.65 feet to a point; thence South 44°58'08" East a distance of 107.79 feet to a point; thence South 54°16'14" East a distance of 74.29 feet to a point; thence South 63°08'43" East a distance of 59.86 feet to a point; thence South 68°57'56" East a distance of 21.04 feet to the point and place of beginning; containing an area of 225.48 acres.

The above description excludes the family cemetery of the G.W. Wall family, as show on book of maps 1997, page 911. Being more particularly described as:

Commencing from an iron pipe, being the southwest corner of lot 1, as shown on plat book 2015, page 2033; thence South 68°38'02" East a distance of 380.31 feet to an iron pipe, the point of beginning; thence North 81°25'40" East a distance of 104.55 feet to a point; thence South 08°53'38" East a distance of 104.55 feet to an iron pipe; thence South 81°17'52" West a distance of 104.56 feet to an iron pipe; thence North 08°53'18" West a distance of 104.79 feet to the point and place of beginning, containing an area of 0.25 acres.

ATTACHMENT 10 - Annexation Certificate of Sufficiency

CERTIFICATE OF SUFFICIENCY

ANX22-07: Tom's Creek

To the Board of Commissioners of the Town of Rolesville, North Carolina:

I, <u>Robin E. Peyton</u>, Town Clerk, do hereby certify that I have investigated the attached petition and hereby make the following findings:

- a. The petition contains an adequate property description of the area(s) proposed for annexation.
- b. The area described in the petition is contiguous to the Town of Rolesville primary corporate limits as required by G.S. 160A-31.
- c. The petition is signed by all owners of real property lying in the area described therein.

In witness whereof, I have hereunto set my hand and affixed the seal of the Town of Rolesville, this 26th day of October 2022.



Robin C. Peyton

Robin E. Peyton Town Clerk