
Sheet 1-A For Index of Sheets Sheet 1-B For Conventional Symbols ROLESVILLE BEGIN PROJECT Century Farm Rd. (SR 2306) END PROJECT VICINITY MAP (NTS)


TOWN OF ROLESVILLE WAKE COUNTY


TOWN OF ROLESVILLE

LOCATION: EAST YOUNG STREET (PHASE B)

TYPE OF WORK: GRADING, DRAINAGE, SIDEWALK, MULTI-USE PATH, AND PAVEMENT MARKINGS








1. CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



PROJECT LENGTH

LENGTH OF PROJECT = 0.175 MI.


2018 STANDARD SPECIFICATIONS RIGHT OF WAY DATE: APRIL 1, 2019 LETTING DATE: MAY 15, 2020 TOWN OF ROLESVILLE CONTACT

Prepared for the North Carolina Department of Transportation in the Office of: A. MORTON THOMAS AND ASSOCIATES, INC. 6131 FALLS OF NEUSE ROAD, SUITE 106 • RALEIGH, NC 27609 (919) 855-9989 • NC LICENSE NO. F-1049 WWW.AMTENGINEERING.COM


DAVID A. SHINBARA, PE

PROJECT ENGINEER NICK RAMIREZ, PE PROJECT DESIGN ENGINEER

RAYMOND J. HAYES, PE NCDOT CONTACT AMY STEVENS



SIGNATURE:



GENERAL NOTES: 2018 SPECIFICATIONS

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

DRIVEWAYS:

INDEX OF SHEETS

SHEET

CONVENTIONAL SYMBOLS

ROADWAY DETAILS

SPECIAL DETAILS

ROADWAY SUMMARIES

DRAINAGE SUMMARIES

EROSION CONTROL PLANS

PAVEMENT MARKING PLANS

TRAFFIC MANAGEMENT PLANS

UTILITIES BY OTHERS PLANS

PLAN SHEET

PROFILE SHEET

CROSS-SECTIONS

INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS

PAVEMENT SCHEDULE AND TYPICAL SECTIONS

TITLE SHEET

SHEET NUMBER

1 A

1 B

2A - 1

2B - 1

2C-1

3B-1

3D - 1

UO-1

EC-1 THRU EC-5

PMP-1 THRU PMP-3

TMP-1 THRU TMP-2

X-1 THRU X-5

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3 FOOT RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

STREET TURNOUT:

STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE READII NOTED ON PLANS.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE:

CITY OF RALEIGH DUKE ENERGY PROGRESS AT&T SPECTRUM PSNC

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

CURB RAMPS

CURB RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS. CONSTRUCT ALL CURB RAMPS ACCORDANCE WITH STD 848.05 and/or 848.06.

UTILITIES (I.E. POWER POLES, LIGHT POLES, TELEPHONE AND CABLE PEDESTALS, ETC.) LOCATED WITHIN NEW SIDEWALK LIMITS TO BE RELOCATED BY RESPECTIVE UTILITY COMPANIES PRIOR TO SIDEWALK INSTALLATION UNLESS SHOWN OTHERWISE. COORDINATE WITH LOCAL UTILITY COMPANIES TO VERIFY UTILITY REALIGNMENT/RELOCATION WORK IS COMPLETE PRIOR TO START OF CONSTRUCTION.

ALL INDIVIDUAL TREES TO REMAIN UNLESS NOTED OTHERWISE ON PLAN OR AS DIRECTED BY ENGINEER AND APPROVED BY OWNER. SHRUBS IN PERMANENT EASEMENT TO BE REMOVED. SHRUBS IN TEMPORARY EASEMENT TO BE REMOVED ONLY AS NECESSARY FOR CONSTRUCTION. SHRUBS IN R/W TO BE REMOVED AS NEEDED AND COORDINATED WITH ENGINEER/OWNER.

TEMPORARILY REMOVE MINOR ITEMS AS REQUIRED FOR CONSTRUCTION. MINOR ITEMS SHALL INCLUDE, BUT ARE NOT LIMITED TO: EXISTING SIGNS, MAIL BOXES, AND STORM SEWER PIPES. REINSTALL ITEMS TO THEIR ORIGINAL CONDITION AT A LOCATION AS CLOSE TO ORIGINAL LOCATION AS PRACTICABLE.

APPROXIMATE LOCATION OF EXISTING UTILITIES ARE SHOWN ON DRAWINGS. NOTIFY UTILITY LOCATING SERVICE TO MARK LOCATION OF EXISTING UTILITIES AT LEAST 48 HOURS PRIOR TO COMMENCING CONSTRUCTION ACTIVITY. CONTRACTOR RESPONSIBLE FOR VERIFYING EXACT LOCATION OF THESE EXISTING UTILITIES. THE COST TO REPAIR THESE FACILITIES, IF DAMAGED, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

THE CONTRACTOR SHALL TAKE PRECAUTIONS NOT TO DISTURB EXISTING PROPERTY CORNER MARKERS. ALL DISTURBED PROPERTY CORNER MARKERS SHALL BE REPLACED BY A REGISTERED LAND SURVEYOR AT CONTRACTOR'S EXPENSE.

SIDEWALK TRANSITIONS SHALL NOT EXCEED 12:1 SLOPE PER ADA.

STAGING AREA SHALL BE DELINEATED WITH TREE PROTECTION FENCING AROUND EXISTING TREES.

SIDEWALK TO JOIN FLUSH W/ EXISTING OR PROPOSED CONCRETE DRIVES.

MAINTAIN ACCESS TO DRIVEWAYS AT ALL TIMES DURING CONSTRUCTION. DRIVEWAY IMPACTS ARE ANTICIPATED WITH THIS PROJECT AND ACCESS DURING CONSTRUCTION SHALL BE COORDINATED WITH THE OWNER.

TRANSITION AROUND WATER METERS, AS NECESSARY TO AVOID PLACING METER IN SIDEWALK.

METER TRANSITION LENGTH SHALL BE APPROXIMATELY 10'.

ADJUST WATER VALVES AS NECESSARY TO COORDINATE WITH SIDEWALK OR GRADE CHANGES.

GAS VALVES THAT REQUIRE ADJUSTMENT TO COORDINATE WITH SIDEWALK OR GRADE CHANGES MUST BE COORDINATED WITH GAS COMPANY DURING CONSTRUCTION.

LAND DISTURBANCE FOR PROJECT GREATER THAN 1 (ONE) ACRE. EROSION CONTROL PLAN APPROVAL IS REQUIRED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COMPLY WITH THE EROSION CONTROL REQUIREMENTS, DEVICES, MAINTENANCE, ETC. AS INDICATED ON THE PLANS.

E.YOUNG ST.PH II /Α ROADWAY DESIGN ENGINEER

SHEET NO.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.

2018 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:

TITLE

DIVISION 2 - EARTHWORK

200.02 Method of Clearing - Method II

225.02 Guide for Grading Subgrade - Secondary and Local DIVISION 3 - PIPE CULVERTS

300.01 Method of Pipe Installation

DIVISION 6 - ASPHALT BASES AND PAVEMENTS

654 01 Pavement Repairs

STD.NO.

DIVISION 8 - INCIDENTALS

840.19 Concrete Grated Drop Inlet Type 'D' - 12" thru 36" Pipe

840.24 Frames and Narrow Slot Sag Grates

840.28 Brick Grated Drop Inlet Type 'D' - 12" thru 36" Pipe

Concrete Junction Box - 12" thru 66" Pipe 840.31 Brick Junction Box - 12" thru 66" Pipe 840.32

840.45 Precast Drainage Structure

Brick Manhole - 12" thru 36" Pipe

Precast Manhole - 4', 5' and 6' Diameter

Precast Manhole with Masonry Base - 12" thru 42" Pipe 840.53

840.66 Drainage Structure Steps

840.72 Pipe Collar

846.01 Concrete Curb, Gutter and Curb & Gutter

848.04 Street Turnout

848.05 Curb Ramp - Proposed Curb & Gutter

852.01 Concrete Islands 1101.01 Work Zone Warning Signs

1101.02 Temporary Lane Closures

1110.01 Stationary Work Zone Signs

1110.02 Portable Work Zone Signs

1130.01 Drums

1150.01 Flagging Devices

1205 00 Pavement Markings

1205.07 Pavement Markings - Pedestrian Crosswalks

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
E.YOUNG ST.PH.II	IB

CONV	/ENTIONAL	PLAN	SHEET	SYMBOLS
CDO ADC	Note: Not to Scale	•	Subsurface Utili	

BOUNDARIES AND PROPERTY:		RAILROADS: Note: Not to S	Scale *S.
State Line —			++++++
County Line		Standard Gauge	CSX TRANSPORTATION
Township Line		RR Signal Milepost	MILEPOST 35
City Line		Switch —	SWITCH
Reservation Line		RR Abandoned	
Property Line		RR Dismantled	
Existing Iron Pin	<u>O</u> EIP		
Computed Property Corner	×	RIGHT OF WAY & PROJECT CO	ONTROL:
Property Monument	ECM	Secondary Horiz and Vert Control Point ——	
Parcel/Sequence Number	_	Primary Horiz Control Point —————	
Existing Fence Line	_	Primary Horiz and Vert Control Point	•
Proposed Woven Wire Fence		Exist Permanent Easment Pin and Cap ———	\Diamond
Proposed Chain Link Fence		New Permanent Easement Pin and Cap —	♦
Proposed Barbed Wire Fence		Vertical Benchmark	
Existing Wetland Boundary		Existing Right of Way Marker	\triangle
Proposed Wetland Boundary		Existing Right of Way Line	
Existing Endangered Animal Boundary		New Right of Way Line	$\frac{R}{W}$
Existing Endangered Plant Boundary		New Right of Way Line with Pin and Cap—	$\frac{R}{W}$
Existing Historic Property Boundary			w –
Known Contamination Area: Soil		New Right of Way Line with Concrete or Granite R/W Marker	-
Potential Contamination Area: Soil		New Control of Access Line with	
Known Contamination Area: Water		Concrete C/A Marker	
Potential Contamination Area: Water ———		Existing Control of Access	(0)
Contaminated Site: Known or Potential		New Control of Access	
BUILDINGS AND OTHER CULT		Existing Easement Line ————————————————————————————————————	——E——
		New Temporary Construction Easement –	———E———
Gas Pump Vent or U/G Tank Cap		New Temporary Drainage Easement ——	—— TDE ——
Sign —	_	New Permanent Drainage Easement ——	PDE
Well		New Permanent Drainage / Utility Easement	DUE
Small Mine	- ×	New Permanent Utility Easement ———	PUE
Foundation ————————————————————————————————————		New Temporary Utility Easement ———	TUE
Area Outline		New Aerial Utility Easement —————	——— AUE ———
Cemetery			
Building —		ROADS AND RELATED FEATUR	RES:
School	<u> </u>	Existing Edge of Pavement	
Church —		Existing Curb	
Dam —		Proposed Slope Stakes Cut ————	
HYDROLOGY:		Proposed Slope Stakes Fill —————	F
Stream or Body of Water ————————————————————————————————————		Proposed Curb Ramp	CR
Hydro, Pool or Reservoir ————————————————————————————————————		Existing Metal Guardrail	
Jurisdictional Stream		Proposed Guardrail —————	<u> T T T T</u>
Buffer Zone 1 ———————————————————————————————————		Existing Cable Guiderail	
Buffer Zone 2		Proposed Cable Guiderail	
Flow Arrow		Equality Symbol	
Disappearing Stream ————————————————————————————————————		Pavement Removal	
Spring —		VEGETATION:	
Wetland — — — — — — — — — — — — — — — — — — —	- <u>\</u>	Single Tree	- - ⇔
Proposed Lateral, Tail, Head Ditch ————	FLOW	Single Shrub	– භූ
False Sump ——————	-	-	


U.E. = Subsurface Utility Engineering	•	WATER
Hedge ———————————————————————————————————	_ ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	Wate
Woods Line	(;)(;)(;)(;)	Wate Wate
Orchard —	-	Wate
Vineyard ————————————————————————————————————	— Vineyard	U/G
EXISTING STRUCTURES:		U/G
MAJOR:		U/G
Bridge, Tunnel or Box Culvert	CONC	Above
Bridge Wing Wall, Head Wall and End Wall	-) CONC WW (Above
MINOR:		TV:
Head and End Wall		TV Pe
Pipe Culvert		TV To
Footbridge —	·	U/G
Drainage Box: Catch Basin, DI or JB	СВ	U/G
Paved Ditch Gutter		U/G
Storm Sewer Manhole		U/G
Storm Sewer	s	U/G U/G
UTILITIES:		U/G
POWER:		GAS:
Existing Power Pole	-	Gas \
Proposed Power Pole		Gas I
Existing Joint Use Pole	_	U/G
Proposed Joint Use Pole		U/G
Power Manhole	- P	U/G
Power Line Tower	_ 🖂	Above
Power Transformer	$\overline{\mathcal{M}}$	
U/G Power Cable Hand Hole	_	SANITA
H–Frame Pole		Sanit
U/G Power Line LOS B (S.U.E.*)		Sanit
U/G Power Line LOS C (S.U.E.*)	P	U/G
U/G Power Line LOS D (S.U.E.*)	P	Abov
TELEPHONE:		SS Fo
		SS Fo
Existing Telephone Pole		SS Fo
Proposed Telephone Pole		MISCE
Telephone Manhole		Utility
Telephone Pedestal		Utility
Telephone Cell Tower		Utility
U/G Telephone Cable Hand Hole		Utility
U/G Telephone Cable LOS B (S.U.E.*)		Utility
U/G Telephone Cable LOS C (S.U.E.*)		U/G
U/G Telephone Cable LOS D (S.U.E.*)		Unde
U/G Telephone Conduit LOS B (S.U.E.*)		A/G
U/G Telephone Conduit LOS C (S.U.E.*)		Geoe
U/G Telephone Conduit LOS D (S.U.E.*)		U/G
U/G Fiber Optics Cable LOS B (S.U.E.*)		Aban
U/G Fiber Optics Cable LOS C (S.U.E.*)		End o

U/G Fiber Optics Cable LOS D (S.U.E.*)—— TFO ——

WATER:	
Water Manhole	(W)
Water Meter —	
Water Valve	
Water Hydrant	
U/G Water Line LOS B (S.U.E*)	
U/G Water Line LOS C (S.U.E*)	
U/G Water Line LOS D (S.U.E*)	
Above Ground Water Line	
TV:	
TV Pedestal ————————————————————————————————————	
TV Tower —	\otimes
U/G TV Cable Hand Hole	
U/G TV Cable LOS B (S.U.E.*)	
U/G TV Cable LOS C (S.U.E.*)	
U/G TV Cable LOS D (S.U.E.*)	TV
U/G Fiber Optic Cable LOS B (S.U.E.*) ——	TV FO
U/G Fiber Optic Cable LOS C (S.U.E.*) ——	
U/G Fiber Optic Cable LOS D (S.U.E.*)	TV F0
GAS:	
Gas Valve	\Diamond
Gas Meter ———————————————————————————————————	\Diamond
U/G Gas Line LOS B (S.U.E.*)	
U/G Gas Line LOS C (S.U.E.*)	
U/G Gas Line LOS D (S.U.E.*)	
Above Ground Gas Line	
SANITARY SEWER:	
Sanitary Sewer Manhole	⊕
Sanitary Sewer Cleanout ————————————————————————————————————	<u> </u>
U/G Sanitary Sewer Line ————————————————————————————————————	
SS Forced Main Line LOS B (S.U.E.*) ———	
SS Forced Main Line LOS C (S.U.E.*)	
SS Forced Main Line LOS D (S.U.E.*)———	FSS FSS
MISCELLANEOUS:	
Utility Pole —	•
Utility Pole with Base —————	
Utility Located Object —	_
Utility Traffic Signal Box —————	
Utility Unknown U/G Line LOS B (S.U.E.*)	_
U/G Tank; Water, Gas, Oil —	
Underground Storage Tank, Approx. Loc. —	
A/G Tank; Water, Gas, Oil —————	
Geoenvironmental Boring	
U/G Test Hole LOS A (S.U.E.*)	*
	A A T 1 1D
Abandoned According to Utility Records —— End of Information ————	
LIIU OI IIIIOIIIIUIIOII —————————————————	E.O.I.


05662	
	PAVEMENT SCHEDULE (PRELIMINARY PAVEMENT DESIGN)
C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. APPROX. 2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E1	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.
J	PROP. 6" AGGREGATE BASE COURSE
R1	2'-6" CONCRETE CURB AND GUTTER
T	EARTH MATERIAL
U	EXISTING PAVEMENT
V	MILLING

PROJECT REFERENCE NO) .	SHEET NO.
E.YOUNG ST.PH	'.//	2A-1
ROADWAY DESIGN ENGINEER	P/	AVEMENT DESIGN ENGINEER
Decusioned by: Devid Shisted a 8427DF4DC88243B A. SHINBRANA 8/25/2021		
DOCUMENT NOT OUNLESS ALL SIGNA		



TYPICAL SECTION NO. 1

-L- STA. 16+82.05 TO 20+94.15 -MUP- STA. 10+00.00 TO 14+23.41




TYPICAL SECTION NO. 2

-L- STA. 16 + 55.51 TO 16 + 93.06


8/20/202| |-|Sinaleigh/16-0940.001 - Rolesville E Young St Side\05-CA


A. MORTON THOMAS AND ASSOCIATES, INC.
6131 FALLS OF NEUSE ROAD, SUITE 106 • RALEIGH, NC 27609
(919) 855-9989 • NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM




PROJECT REFERENCE NO. SHEET NO.

E.YOUNG ST.PH.// 2C-/









PROJECT REFERENCE NO. SHEET NO.

E.YOUNG ST.PH.// 3B-/


SUMMARY OF EARTHWORK


IN CUBIC YARDS


LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + 20%	BORROW	WASTE
-MUP- STA 10+00.00 TO -MPU- STA 14+10.00	22		192	178	
PROJECT TOTAL	22		192	178	
SAY	25		195	180	

A. MORTON THOMAS AND ASSOCIATES, INC.
6131 FALLS OF NEUSE ROAD, SUITE 106 • RALEIGH, NC 27609
(919) 855-9989 • NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM

COMPUTE	BY:			SM			[DATE: (08/11/202	21																																	PROJECT NO.	SHEE	.ET N
CHECKE	BY:							DATE:							N	OR'	TH	CA	ROL	INA	A DI	EPA	RT	MEN	TV C	OF '	TR	AN	SPORT	'AT	ION												East Young Street M	MUP 3E	کار 1-1
Note	Invert Ele	evation	ns indi	cated a	are for	Bid Purpos	ses only	y and sha	all not	be used	for pro	oject c	onstruc	tion st	takeou	t.				D]	IVIS	SIOI	1 O	F HI	IGH	WA	YS	i																<u> </u>	
	See "Sta	andard	Speci	ficatio	ns For	Roads and	Struct	ures, Sec	ction 3	300-5".				\boldsymbol{L}	<i>IST</i>	OF I	PIP.	ES, I	END	WA.	LLS	, ET	C. (FOR	PIP	ES A	48 I	INC	CHES &	UNI	DER))													
LINE & STATION	H	UCTURE NUMBER				E C	(RCP, C	Drainage CSP, CAAP, ∣		r PVC)			C. S.	PIPE	-		ı	R. C. PIPE CLASS III	.			R. C. I CLAS	PIPE		LS \$TD 838 11	OTHERWISE) NDWALLS		STRUCTURE	QUANTITIES OR DRAINAGE STRUCTURES NOTE: TOTAL LIN. FT. FOR PAY QUANTITY	I G AN	FRAME, GRATES, ND HOOD TD. 840.03	CONCRETE TRANSITIONAL	0.15 TD. 840.16	OR STD. 840.26 OR STD. 840.27	GRATE STD. 840.24 72 GRATES STD. 840.24	// 2 GRATES STD. 840.29	72, OK 31D. 040.33			N.	L. "B" STD. 840.72 PIPE PLUG STD. 840.71		ABBREVIATIONS C.A.A. CORRUGATE C.B. CATCH BASI C.S. CORRUGATE D.I. DROP INLET G.D.I. GRATED DR H.D.P.E. HIGH DENSI J.B. JUNCTION B	SIN TED STEEL ET PROP INLET SITY POLYETHYLENE	
	OFFSE	STR		Z	z												_								ENDWAL	NOTEC NOTEC		A P	SHALL BE A + (1.3 X B)	ID. 840		TD. 85,	TD. 84(840.18 840.19	ME W/	AME W	VER S'			N BAS	ARS CI		M.H. MANHOLE N.S. NARROW SL		
SIZE	-		NOIL	EVATIO	EVATIO	M 12 15 18	8 24 30	36 42 4	18	CAAP	发호		18 24 3	++	\perp	12 1	5 18 2	24 30 3	6 42 48	1:	12 15 18	8 24 30	36 4	12 48	- STO	(UNLESS		\perp	<u>А</u> В	OR ST		4 OR S	4 OR S	"STD.	3) FRA 3) FRA	AT) FR/ AT) FR/ 1 OR S	ND CO		× ×	PATIO	COLL/	NAL	P.V.C. POLYVINYL R.C. REINFORCE	L CHLORIDE	
THICKNESS OR GAUGE		FROM	TOP ELEVA	H INVERT ELE	H INVERT ELE	MINIMUM RE				DO NOT USE C DO NOT USE C DO NOT USE C	DO NOT USE H	.064	.064	079	.109										c	ey c	SY C	A MASONRY	19 7 10 10 10 10 10 10 10 10 10 10 10 10 10	8. STD. 8	GRATE TYPE	D.I. STD. 852.04	D.I. STD. 840.14	G.D.I. TYPE "A' G.D.I. TYPE "B' G.D.I. TYPE "D'	G.D.I. (N.S. SAC	G.D.I. (N.S. FLA J.B. STD. 840.3	M.H. FRAME AI ADJUST C.B.	ADJUST D.I. 15" C.S. ELBOV 18" C.S. ELBOV	24" C.S. ELBON 30" C.S. ELBON	ENERGY DISSI	CONCRETE CONCRETE	Y PIPE REMO	T.B.D.I. TRAFFIC BE. T.B.J.B. TRAFFIC BE. W.S. WIDE SLOT	EARING DROP INLET	
MUP 10+68	6 RT	0401	11.	11.	1 11	70																																			0.5526		KLW	ARRO	
		0401 0402		_	406.0 404.5	0.7	8 72		++		+					++	++				++	++					_	\perp	+++						+++	+++				++		++			
MUP 10+75	12 RT	0402	409.5																										1							1	1			#		丗			<u> </u>
MUP 11+50	14 RT	0403 0404 0403 0404	407.2		403.5	0.9	36	+++	++		\dashv	\dashv		++	++	++	++	+			++	++	++		\vdash	-	+	+	1	+	++	++	++	1	1	+	++		++	++		+			_
MUP 11+88	15 RT	0404	408.6																										1 1.6							1	1					廿			_
MUP 12+30	12 RT	0405 040	406.4		404.3	40			++		\dashv				++	++	++				++	++					+	+	1	+		+	++	1	1		++		-	++		+			
									$\downarrow \downarrow$																			1																	_
									++		+					++	++										+	+				++								+++		+			
																																								#					
				+				+++	++		+					++	++				++	++	++				+	+	+			+			+++		++			++		++			
																																								\bot		\Box			
				+					++		+				++	++	++				++	++					+	+			++	++	++		+++		++		+	++		+			—
																																													_
						+++			++		+			++		++	++				++	++					+	+	+++											++		+			_
									++							++	++										+	+				+								++					
																																													_
				1					++		+					++	++				++	++					+	+	+		-	++			+++				++	++		+			
																																													<u> </u>
			+	1		+++	++	+ + +	++		+		+	++	++	++	++	++			++	++		++		-	+	+	+++	\dashv	+	++	++		+++	+++	++			++		+			
																																								\bot					
				+		+++			++		+			+	++	++	++	+			++	++					+	+	+		++	++	++		+++		++		++	++		+			
				+		+++			++		\dashv			+	++	++	++				++	++					+	+	+	+	+	++	++	++	+++		++		++	++		+			_
																																										廿			
				+		+++			++		+			+	++	++	++				++	++					+	+	+	+	++	++	+	+++	+++		++		++	++		+			_
																												1																	_
			+	+		+++	++	+++	++	+	+	\dashv	+	++	++	++	++	++	+ +	++	++	++	++	++		+	+	+	+++	\dashv	++	++	++		+++	+++	++			++		+			
									$\downarrow \downarrow$					$\downarrow \downarrow$													士	\perp														丗			
		\vdash	+	+		+++	++	+++	++		+			++	++	++	++	+			++	++	++	+	++	_	+	+	+		+	++	++		+++	+++	++			++		+			—
									$\pm \pm$		丗																\perp	士														世			_
						+			$+\Gamma$		+		 	+-			+										\perp	\perp	+						+	111						+			_
																																													_
									$\bot \overline{\bot}$																				1 10			\prod	\bot							\bot					









STATE OF NORTH CAROLINA TOWN OF ROLESVILLE


PLAN FOR PROPOSED EROSION CONTROL





THIS PROJECT CONTAINS
EROSION CONTROL PLANS
FOR CLEARING AND
GRUBBING PHASE OF
CONSTRUCTION.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



F ROLESVILLE

GRAPHIC SCALE

O 50 100

PLANS

O 50 100

PROFILE (HORIZONTAL)

O 10 20

PROFILE (VERTICAL)

THESE EROSION AND SEDIMENT
CONTROL PLANS COMPLY WITH
THE REGULATIONS SET FORTH
BY THE NCG-010000 GENERAL
CONSTRUCTION PERMIT EFFECTIVE
APRIL 1, 2019 AND ISSUED BY
THE NORTH CAROLINA DEPARTMENT
OF ENVIRONMENT AND NATURAL
RESOURCES DIVISION OF WATER
RESOURCES.

Prepared in the Office of:



A. MORTON THOMAS AND ASSOCIATES, INC. 6131 FALLS OF NEUSE ROAD, SUITE 106 • RALEIGH, NC 27609 (919) 855-9989 • NC LICENSE NO. F-1049 WWW.AMTENGINEERING.COM

Designed by:

Rana Stansell, PE, CFM

3597

LEVEL III CERTIFICATION NO.


Reviewed in the Office of:

NCDEQ


3800 Barrett Drive Raleigh, NC 276091

Reviewed by:

8/20/2021 3 St Side/05-CAD/16-0940.001/Hydraulics/EROSION CONTROL/10



MATTING INSTALLATION DETAIL



STAPLES SHALL BE NO. 11 GAUGE STEEL WIRE FORMED INTO A "U" SHAPE WITH A MINIMUM THROAT WIDTH OF I STAPLES THAN 6 INCHES IN LENGTH.

5. MONITOR AND REPAIR MATTING AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.

INCH AND NOT LESS THAN 6 INCHES IN LENGTH.

SEQUENCE OF CONSTRUCTION

SUBMIT DOCUMENTATINO REQUIRED UNDER THE NPDES STORMATER PERMIT FOR CONSTRUCTION ACTIVITIES (NCG010000).

2. CONTACT NCDEQ LQS AT THE RALEIGH REGIONAL OFFICE AT 919–791–4200 TO SCHEDULE A PRE-CONSTRUCTION MEETING AT LEAST 48 HOURS PRIOR TO PROJECT ACTIVATION.

- 3. INSTALL TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE CLEARING AND GRUBBING PLAN SHEETS. CLEAR ONLY THE AREAS NECESSARY FOR INSTALLATION OF THE EROSION CONTROL MEASURES. CONTACT NCDEQ LQS AT THE RALEIGH REGIONAL OFFICE AT 919–791–4200 ONCE MEASURES ARE IN
- 4. LAND DISTURBANCE AND CONSTRUCTION MAY BEGIN ONCE CLEARING AND GRUBBING EROSION CONTROL MEASURES ARE IN PLACE.
- RETAIN A COPY OF THE EROSION AND SEDIMENT CONTROL (E&SC) PERMIT AND EROSION CONTROL PLANS ON SITE, PREFERABLY IN A PERMITS BOX, AND ACCESSIBLE DURING INSPECTION.
- 6. SELF-INSPECTIONS FOR EROSION AND SEDIMENTATION CONTROL MEASURES ARE TO BE PERFORMED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF EVERY RAIN EVENT OF GREATER THAN 1 INCH. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN MEASURES AS DESIGNED. ALL ESC MEASURES SHALL BE MAINTAINED AS SPECIFIED IN THE CONSTRUCTION DETAILS ON THIS PLAN. A RAIN GAUGE SHALL BE INSTALLED AT THE PROJECT SITE FOR MONITORING. COPIES OF THE INSPECTION REPORTS MUST BE KEPT ON SITE.
- 7. PREFORM GRADING OPERATIONS AND INSTALL PROPOSED DRAINAGE NETWORKS. ENSURE THAT EXISTING DRAINAGE SYSTEMS CONTINUE TO FUNCTION UNTIL THE PROPOSED SYSTEM IS INSTALLED. INSTALL FINAL EROSION CONTROL MEASURES PER THE FINAL EROSION CONTROL PLANS AS THE AREA IS CONSTRUCTED AND FINAL DRAINAGE AND GRADING IS IN PLACE.
- 8. PERMANENTLY STABILIZE ALL DISTURBED AREAS PAYING PARTICULAR ATTENTION TO THE FILL SLOPE ADJACENT TO THE WETLANDS. SITE STABILIZATION IS REQUIRED PRIOR TO FINAL APPROVAL. STABLIZE AREA IN ACCORDANCE WITH TIMEFRAMES INCLUDED IN THE EROSION CONTROL PLANS.
- 9. FINAL EROSION CONTROL MEASURES MAY NOT BE REMOVED UNTIL PERMANENT GROUND COVER HAS BEEN ESTABLISHED THROUGHOUT THE SITE.
- 10. WHEN THE PROJECT IS COMPLETE AND PERMANENT GROUND COVER IS ESTABLISHED, CONTACT NCDEQ LQS TO CLOSE OUT THE E&SC PLAN. AFTER NCDEQ LQS INFORMS THE PERMITTEE OF THE PROJECT CLOSE OUT, VIA INSPECTION REPORT, THE PERMITTEE SHAL VISIT DEQ.NC.GOV/NCG01 TO SUBMIT AN ELECTRONIC NOTICE OF TERMINATION (E-NOT).

GENERAL EROSION CONTROL NOTES

- EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AT ANY AREA USED FOR CONTRACTOR EQUIPMENT STAGING, MATERIALS LAYDOWN, AND SPOIL OR WASTE AREAS.
- 2. ALL SEDIMENT CONTAINMENT DEVICES MUST BE MAINTAINED UNTIL ALL UPGRADE DRAINAGE AREAS HAVE BEEN STABILIZED WITH THE ESTABLISHMENT OF PERMANENT VEGETATION.
- 3. ANY DEWATERING OF SEDIMENT CONTAINMENT DEVICES FOR MAINTENANCE, REMOVAL, OR CONVERSION PURPOSES IS TO BE DONE THROUGH A SILT BAG, TURBID WATER FROM EXCAVATIONS CANNOT BE PUMPED DIRECTLY TO THE STORM DRAIN SYSTEM BUT MUST BE FILTERED THROUGH A SILT BAG.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING AND MAINTAINING NEW GRASS DURING THIS PROJECT UNTIL THE NOTICE OF TERMINATION IS FILLED
- 5. ANY ACCIDENTAL RELEASE OF SEDIMENT FROM THE SITE SHALL BE CLEANED BY THE CONTRACTOR.
- 6. IT WILL BE THE CONTRACTORS RESPONSIBILITY TO KEEP CLEAN ALL STREETS DURING CONSTRUCTION. SEDIMENT TRACKED ONTO THE ROAD MUST BE CLEANED USING A DRY METHOD (E.G. NO WATER TRUCKS OR
- 7. THE CONTRACTOR MUST INSPECT THE PROJECT AND DOCUMENT THE INSPECTION AFTER INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROL MEASURES. CLEARING AND GRUBBING OF EXISTING GROUND COVER, COMPLETION OF ANY PHASE OF GRADING OF SLOPES OR FILLS, INSTALLATION OF STORM DRAINAGE FACILITIES, COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION.
- 8. ANY LAND CLEARING, CONSTRUCTION, OR DEVELOPMENT INVOLVING THE MOVEMENT OF EARTH SHALL BE IN ACCORDANCE WITH THE APPROVED ESC PLAN AND THAT THE SUPERINTENDENT IN-CHARGE OR CONTRACTOR SHALL BE ON SITE ON ALL DAYS WHEN CONSTRUCTION OR GRADING ACTIVITY TAKES PLACE.
- 9. ROLLED EROSION CONTROL PRODUCTS (NETS, BLANKETS OR MATS) MUST BE FREE OF PLASTIC OR SYNTHETIC MATERIALS, EVEN IF LABELED 'BIODEGRADABLE' OR 'PHOTODEGRADABLE' THESE PRODUCTS MUST BE MADE WITH NATURAL FIBERS SUCH AS JUTE (NOT POLY JUTE) STRAW, SISAL OR COIR.
- 10. GARBAGE IS TO BE DISPOSED OF PROPERLY. SPILLS GENERATED FROM EQUIPMENT ARE TO BE CLEANED UP IMMEDIATELY.
- TRENCH EXCAVATION MATERIAL TO BE PLACED ON HIGH SIDE OF TRENCH. ANY EXCESS EXCAVATED MATERIAL TO BE HAULED IMMEDIATELY OFF SITE AND DISPOSED OF AT APPROVED LOCATIONS. NO MATERIAL WILL BE STOCKPILED ON-SITE.
- 12. THE CONTRACTOR SHALL ONLY EXCAVATE THAT AMOUNT OF UTILITY AS CAN BE REMOVED AND REPLACED IN A SINGLE WORKING DAY AND SHALL BACKFILL OR COVER WITH STEEL PLATE ALL EXCAVATION AT THE END OF EACH WORKING DAY. NO OPEN UNCOVERED EXCAVATION WILL BE ALLOWED AFTER WORKING HOURS.
- 13. LOCATION OF CONCRETE WASHOUT TO BE SUBMITTED BY CONTRACTOR 14 DAYS PRIOR TO START OF CONSTRUCTION FOR APPROVAL BY ENGINEER AND INSPECTOR.

- PROJECT REFERENCE NO. SHEET NO. E.YOUNG ST.PH.II EC-3
- 20. EQUIPMENT AND TIRE WASHING IS PROHIBITED ON
- 21. ANY EQUIPMENT OR MATERIALS BEING BROUGHT TO THE CONSTRUCTION SITE MUST BE KEPT WITHIN THE PROJECT LIMITS.

THE CONSTRUCTION SITE.

22. ALL MILLINGS SHALL BE REMOVED FROM THE PROJECT SITE AND DISPOSED OF AT A NCDENR APPROVED

PROJECT REFERENCE NO. SHEET NO. E.YOUNG ST.PH.// EC-3A

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

<u>SECI</u>	ECTION E: GROUND STABILIZATION								
	Re	equired Ground Stabil	ization Timeframes						
Si	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations						
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None						
(b)	High Quality Water (HQW) Zones	7	None						
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed						
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed						
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope						

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
 Temporary Stabilization Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	 Permanent Stabilization Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls
	Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- 2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- 3. Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging offsite.
- 5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- 1. Maintain vehicles and equipment to prevent discharge of fluids.
- 2. Provide drip pans under any stored equipment.
- 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- 4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- 5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- 6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER. BUILDING MATERIAL AND LAND CLEARING WASTE

- 1. Never bury or burn waste. Place litter and debris in approved waste containers.
- 2. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- 3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- 4. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- . Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- 6. Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- 8. Dispose waste off-site at an approved disposal facility.
- 9. On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

- 1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- 4. Containment must be labeled, sized and placed appropriately for the needs of site.
- 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS


- 1. Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- 3. Monitor portable toilets for leaking and properly dispose of any leaked material.

 Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- 1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- 2. Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- 3. Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





CONCRETE WASHOUTS

- 1. Do not discharge concrete or cement slurry from the site.
- 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- 3. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- 4. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- 5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- 6. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- 7. Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- 8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- 1. Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- 2. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is
 possible or where they may spill or leak into wells, stormwater drains, ground water
 or surface water. If a spill occurs, clean area immediately.
- 4. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- 1. Create designated hazardous waste collection areas on-site.
- 2. Place hazardous waste containers under cover or in secondary containment.
- 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING



EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:							
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.							
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken. 							
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours	 Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken. 							
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 If visible sedimentation is found outside site limits, then a record of the following shall be made: Actions taken to clean up or stabilize the sediment that has left the site limits, Description, evidence, and date of corrective actions taken, and An explanation as to the actions taken to control future releases. 							
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.							
(6) Ground stabilization measures	After each phase of grading	 The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible. 							

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner described:

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation

In addition to the E&SC Plan documents above, the following items shall be kept on the site

and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This general permit as well as the certificate of coverage, after it is received.
- (b) Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- (c) All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that must be reported

Permittees shall report the following occurrences:

(a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if:

- They are 25 gallons or more,
- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or
- They are within 100 feet of surface waters (regardless of volume).
- (a) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (b) Anticipated bypasses and unanticipated bypasses.
- (c) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.


Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment	Within 24 hours, an oral or electronic notification.
deposition in a	Within 7 calendar days, a report that contains a description of the
stream or wetland	sediment and actions taken to address the cause of the deposition.
	Division staff may waive the requirement for a written report on a
	case-by-case basis.
	If the stream is named on the <u>NC 303(d) list</u> as impaired for sediment-
	related causes, the permittee may be required to perform additional
	monitoring, inspections or apply more stringent practices if staff
	determine that additional requirements are needed to assure compliance
	with the federal or state impaired-waters conditions.
(b) Oil spills and	Within 24 hours, an oral or electronic notification. The notification
release of	shall include information about the date, time, nature, volume and
hazardous	location of the spill or release.
substances per Item	
1(b)-(c) above	
(c) Anticipated	A report at least ten days before the date of the bypass, if possible.
bypasses [40 CFR	The report shall include an evaluation of the anticipated quality and
122.41(m)(3)]	effect of the bypass.
(d) Unanticipated	Within 24 hours, an oral or electronic notification.
bypasses [40 CFR	Within 7 calendar days, a report that includes an evaluation of the
122.41(m)(3)]	quality and effect of the bypass.
(e) Noncompliance	Within 24 hours, an oral or electronic notification.
with the conditions	Within 7 calendar days, a report that contains a description of the
of this permit that	noncompliance, and its causes; the period of noncompliance,
may endanger	including exact dates and times, and if the noncompliance has not
health or the	been corrected, the anticipated time noncompliance is expected to
environment[40	continue; and steps taken or planned to reduce, eliminate, and
CFR 122.41(I)(7)]	prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).
	 Division staff may waive the requirement for a written report on a case-by-case basis.




NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19







STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING AND SIGNING PLAN WAKE COUNTY

TIP NO.	SHEET NO.
E. YOUNG ST. PH. II	PMP-1
APPROVED:	
DATE:	
Document CAROLA Document State Document Stat	8/25/2021
DOCUMENT NOT CONSID	EDED EINAI

UNLESS ALL SIGNATURES COMPLETED

INDEX

SHEET NO.

DESCRIPTION

PAVEMENT MARKING PLAN TITLE AND

SCHEDULE SHEET

PMP-2 CRO

CROSSWALK PAVEMENT MARKING GUIDANCE DETAIL

PMP-3

PMP - 1

PAVEMENT MARKING DETAIL

PAVEMENT MARKING SCHEDULE

SYMBOL

T2

TΑ

DESCRIPTION

FINAL

PAVEMENT MARKINGS

WHITE STOPBAR

THERMOPLASTIC (4", 120 MILS)

THERMOPLASTIC (24", 120 MILS)

T8 WHITE 2' - 6'/SP MINI-SKIP
TC WHITE 10' SKIP
TD WHITE 3' - 9'/SP MINI-SKIP
TE WHITE SOLID LANE LINE
TH YELLOW SINGLE CENTER
TI YELLOW DOUBLE CENTER
TI THERMOPLASTIC (4", 90 MILS)

,

WHITE EDGE LINE

THERMOPLASTIC (8", 120 MILS)

TP YELLOW DIAGONAL TQ WHITE CROSSWALK LINE

THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)

UA LEFT TURN ARROW
UB RIGHT TURN ARROW
UC STRAIGHT ARROW
UE COMBO STRAIGHT/ RIGHT
UJ HELMETED BICYCLE SYMBOL
UK STRAIGHT ARROW, BIKE LANE

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME MARKING MARKER EAST YOUNG STREET THERMOPLASTIC N/A

B) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.

C) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

E) STOP BAR LOCATION AT NON-SIGNALIZED INTERSECTIONS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.

F) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON CONCRETE BRIDGE DECKS PRIOR TO PLACING (insert marking material) PAVEMENT MARKING MATERIAL.

UNLESS OTHERWISE SPECIFIED, HEATED-IN-PLACE THERMOPLASTIC MAY BE USED IN LIEU OF EXTRUDED THERMOPLASTIC FOR STOP BARS, SYMBOLS, CHARACTERS AND DIAGONALS. IF HEATED-IN-PLACE IS USED, IT SHALL BE PAID FOR USING THE EXTRUDED THERMOPLASTIC PAY ITEM.

H)

ALL BICYCLE LANE SYMBOLS SHALL BE HEATED-IN-PLACE THERMOPLASTIC.

SYMBOLS SHALL BE PAID FOR USING THE HEATED-IN-PLACE PAY ITEM.

SEE ROADWAY PLANS FOR ALTERNATE CURB RAMP DESIGNS WHEN INDICATED ON PAVEMENT MARKING DETAIL SHEETS.

ROADWAY STANDARD DRAWING


THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.06	PAVEMENT MARKINGS - LANE DROPS
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY
1253.01	RAISED PAVEMENT MARKERS - SNOWPLOWABLE

PLAN PREPARED BY: A. MORTON THOMAS & ASSOCIATES

David A. Shinbara, P.E. PROJECT ENGINEER

Mohammed Fallaha, P.E. DESIGN ENGINEER




OWN OF ROLESVILLE


GUIDANCE DETAIL FOR CROSSWALK MARKINGS

NOTES:

- 1. USE THE DETAILS ABOVE AND THE FOLLOWING NOTES FOR GUIDANCE IN PLACING CROSSWALK MARKINGS NOT STATIONED ON THE DETAIL SHEETS OR WHEN FIELD ADJUSTMENTS REQUIRED MOVING STATIONED MARKINGS AS DIRECTED BY THE ENGINEER. REFER TO NCDOT ROADWAY STANDARD DRAWINGS, MUTCD AND ADA STANDARDS FOR ADDITIONAL GUIDANCE.
- 2. THE CROSSWALK MARKINGS SHOWN ON THE ABOVE DETAILS ARE FOR REFERENCE ONLY. ONLY INSTALL CROSSWALK MARKINGS WHERE SHOWN ON THE DETAIL SHEETS OR AS DIRECTED BY THE ENGINEER. THE CROSSWALK MARKING TYPE, STANDARD OR HI-VISIBILITY, SHALL BE INSTALL AS SPECIFIED ON THE DETAIL SHEETS OR AS DIRECTED BY THE ENGINEER.
- 3. SET BACK DISTANCE FROM INSIDE CROSSWALK MARKING TO NEAREST EDGE OF TRAVEL IS 4' MIN.
- 4. BEYOND THE BOTTOM GRADE BRAKE, A CLEAR SPACE OF 4' X 4' MINIMUM SHALL BE PROVIDED WITHIN THE MARKINGS.
- 5. SINGLE DIAGONAL CURB RAMPS WITH FLARED SIDES SHALL HAVE A SEGMENT OF CURB 2 FEET LONG MINIMUM LOCATED ON EACH SIDE OF THE CURB RAMP AND WITHIN THE MARKED CROSSING, SEE DETAIL 'B'.
- 6. CURB RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE TO THE LATEST NCDOT ROADWAY STANDARD DRAWINGS.



DETAIL 'A'- DUAL CURB RAMPS



DETAIL 'B'- SINGLE DIAGONAL CURB RAMP

CROSSWALK PAVEMENT MARKING GUIDANCE DETAIL

. YOUNG ST. PH. II

APPROVED:

PMP-2

DocuSign Envelope ID: A7189532-ED09-469A-85F6-842F3BB05662 TIP NO. SHEET NO. PMP-3 . YOUNG ST. PH. II APPROVED: DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED RELOCATE — STOP SIGN R1 - 1 BEGIN CONSTRUCTION
-L- POT STA.12+00.00 STREET NAME
STREET NAME
STREET NAME
STREET NAME
SIGN (TYPE D)
- MUP - MULTI-USE PATH SIGN (TYPE D) -L- EAST YOUNG ST. RELOCATE TYPE D SIGN END CONSTRUCTION
-L- POT STA. 21+25.00 A. MORTON THOMAS AND ASSOCIATES, INC.
6131 FALLS OF NEUSE ROAD, SUITE 106 • RALEIGH, NC 27609
(919) 855-9989 • NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM

NOTE:
CONTRACTOR TO MAINTAIN EXIST. PAVEMENT MARKINGS, EXCEPT
WHERE THEY CONFLICT WITH PROPOSED MARKINGS AS SHOWN ABOVE.
CONFLICTING EXIST. PAVEMENT MARKINGS TO BE REMOVED BY
METHOD LEAST DAMAGING TO PAVEMENT.

PAVEMENT MARKING DETAIL

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TIME RESTRICTIONS

A) DO NOT CLOSE OR NARROW TRAVEL LANES AS FOLLOWS:

ROAD NAME

US 401, EAST YOUNG STREET

DAY AND TIME RESTRICTIONS

MONDAY - FRIDAY 6:00 A.M. TO 9:00 A.M. AND 4:00 P.M. TO 7:00 P.M.

B) DO NOT CLOSE OR NARROW TRAVEL LANES DURING HOLIDAYS AND SPECIAL **EVENTS AS FOLLOWS:**

ROAD NAME

US 401

EAST YOUNG STREET

HOLIDAY

- 1. FOR ANY UNEXPECTED OCCURRENCE THAT CREATES UNUSUALLY HIGH TRAFFIC VOLUMES, AS DIRECTED BY THE ENGINEER.
- 2. FOR NEW YEAR'S, BETWEEN THE HOURS OF 6:00 A.M. DECEMBER 31st TO 7:00 P.M. JANUARY 2ND. IF NEW YEAR'S DAY IS ON A FRIDAY, SATURDAY, SUNDAY, OR MONDAY THEN UNTIL 7:00 P.M. THE FOLLOWING TUESDAY.
- 3. FOR EASTER, BETWEEN THE HOURS OF 6:00 A.M. THURSDAY AND 7:00 P.M. MONDAY.
- 4. FOR MEMORIAL DAY, BETWEEN THE HOURS OF 6:00 A.M. FRIDAY TO 7:00 P.M. TUESDAY.
- 5. FOR INDEPENDENCE DAY, BETWEEN THE HOURS OF 6:00 A.M. THE DAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE DAY AFTER INDEPENDENCE DAY.
 - IF INDEPENDENCE DAY IS ON A FRIDAY, SATURDAY, SUNDAY OR MONDAY THEN BETWEEN THE HOURS OF 6:00 A.M. THE THURSDAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE TUESDAY AFTER INDEPENDENCE DAY.
- 6. FOR LABOR DAY, BETWEEN THE HOURS OF 6:00 A.M. FRIDAY AND 7:00 P.M. TUESDAY.
- 7. FOR THANKSGIVING DAY. BETWEEN THE HOURS OF 6:00 A.M. TUESDAY TO 7:00 P.M. MONDAY.
- 8. FOR CHRISTMAS, BETWEEN THE HOURS OF 6:00 A.M. THE FRIDAY BEFORE THE WEEK OF CHRISTMAS DAY AND 7:00 P.M. THE FOLLOWING TUESDAY AFTER THE WEEK OF CHRISTMAS.
- C) DO NOT CLOSE ROADS AS FOLLOWS:

ROAD NAME DAY AND TIME RESTRICTIONS

US 401 ANYTIME

EAST YOUNG STREET ANYTIME

D) DO NOT CONDUCT ANY HAULING OPERATIONS AGAINST THE FLOW OF TRAFFIC OF AN OPEN TRAVELWAY UNLESS THE HAULING OPERATION IS PROTECTED BY BARRIER OR GUARDRAIL OR AS DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- E) REMOVE LANE CLOSURE DEVICES FROM THE LANE WHEN WORK IS NOT BEING PERFORMED BEHIND THE LANE CLOSURE OR WHEN A LANE CLOSURE IS NO LONGER NEEDED, OR AS DIRECTED BY THE ENGINEER.
- F) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.
- G) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO AN UNDIVIDED FACILITY AND WITHIN 5 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO A DIVIDED FACILITY AND WITHIN 10 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

- H) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN A LANE OF TRAVEL OF AN UNDIVIDED OR DIVIDED FACILITY, CLOSE THE LANE ACCORDING TO THE TRAFFIC CONTROL PLANS, ROADWAY STANDARD DRAWINGS OR AS DIRECTED BY THE ENGINEER. CONDUCT THE WORK SO THAT ALL PERSONNEL AND/OR EQUIPMENT REMAIN WITHIN THE CLOSED TRAVEL LANE.
- I) DO NOT WORK SIMULTANEOUSLY WITHIN 15 FT ON BOTH SIDES OF AN OPEN TRAVELWAY RAMP OR LOOP WITHIN THE SAME LOCATION UNLESS PROTECTED WITH GUARDRAIL OR BARRIER.

PAVEMENT EDGE DROP OFF REQUIREMENTS

J) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF AS FOLLOWS:

BACKFILL DROP-OFFS THAT EXCEED 2 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.

BACKFILL DROP-OFFS THAT EXCEED 3 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

K) DO NOT EXCEED A DIFFERENCE OF 2 INCHES IN ELEVATION BETWEEN OPEN LANES OF TRAFFIC FOR NOMINAL LIFTS OF 1.5 INCHES. INSTALL ADVANCE WARNING "UNEVEN LANES" SIGNS (W8-11) IN ADVANCE AND A MINIMUM OF EVERY HALF MILE THROUGHOUT THE UNEVEN AREA.

TRAFFIC PATTERN ALTERATIONS

L) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- M) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- N) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

O) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

SHEET NO. PROJ. REFERENCE NO. E. YOUNG ST. PH. II TMP-01

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION


- P) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.
- Q) INSTALL BLACK ON ORANGE "DIP" SIGNS (W8-2) AND/OR "BUMP" SIGNS (W8-1) IN ADVANCE OF THE UNEVEN AREA, OR AS DIRECTED BY THE ENGINEER.

TRAFFIC CONTROL DEVICES

- R) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.
- S) SPACE CHANNELIZING DEVICES IN WORK AREAS NO GREATER THAN TWICE THE POSTED SPEED LIMIT (MPH), EXCEPT 10 FT ON-CENTER IN RADII, AND 3 FT OFF THE EDGE OF AN OPEN TRAVELWAY, WHEN LANE CLOSURES ARE NOT IN EFFECT. WHEN SKINNY DRUMS ARE ALLOWED, REFER TO SECTION 1180 OF STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES OR AS SHOWN IN THE PLANS.
- T) PLACE ADDITIONAL SETS OF THREE CHANNELIZING DEVICES PERPENDICULAR TO THE EDGE OF TRAVELWAY ON 500 FT CENTERS WHEN UNOPENED LANES ARE CLOSED TO TRAFFIC.

MISCELLANEOUS


- U) LAW ENFORCEMENT MAY BE USED TO MAINTAIN TRAFFIC THROUGH THE WORK AREA AND/OR INTERSECTIONS AS DIRECTED BY THE ENGINEER.
- V) IN THE EVENT A TIE-IN CANNOT BE MADE IN ONE DAY'S TIME, BRING THE TIE-IN AREA TO AN APPROPRIATE ROADWAY ELEVATION AS DETERMINED BY THE ENGINEER. PLACE BLACK ON ORANGE "LOOSE GRAVEL" SIGNS (W8-7) AND BLACK ON ORANGE "PAVEMENT ENDS" SIGNS (W8-3) AND RESPECTIVELY IN ADVANCE OF THE UNEVEN AREAS. USE DRUMS TO DELINEATE THE EDGE OF ROADWAY ALONG UNPAVED AREAS.
- W) ALL CURB RAMP LOCATIONS SHALL BE DERIVED FROM STATIONING SHOWN ON PAVEMENT MARKING PLANS OR AS DIRECTED BY THE ENGINEER IN COORDINATION WITH THE SIGNING AND DELINEATION UNIT.
- X) CONTRACTOR SHALL MAINTAIN SIDEWALK ACCESS AT ALL TIMES AS STATED IN THE PHASING. CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE TEMPORARY SIDEWALKS (CONCRETE, ASPHALT, OR OTHER SUITABLE MATERIAL AS APPROVED BY THE ENGINEER) AT ALL LOCATIONS WHERE THE OPEN PEDESTRIAN TRAVELWAY HAS BEEN REMOVED FOR CONSTRUCTION OPERATIONS (UTILITIES, DRAINAGE, ETC.).



DOCUMENT NOT CONSIDERED FINAL


UNLESS ALL SIGNATURES COMPLETED








deigh/16-0940,001- Rolesville E Young St Side\05-CAD\16-094

20/2021










(remove jumpers and set switches as shown)

ON OF F WD ENABLE (



1. Card is provided with all diode jumpers in place. Removal

of any jumper allows its channels to run concurrently.

2. Make sure jumpers SEL2-SEL5 are present on the monitor board.

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal

NOTES

heads flash in accordance with the Signal Plans.

2. Ensure that Red Enable is active at all times during normal operation. To prevent Red Failures on unused monitor channels, tie unused red monitor inputs 1,3, 4.5.6.7.8.9.11.13.14.15 & 16 to load switch AC+ per the

cabinet manufacturer's instructions. 3. Enable Simultaneous Gap-Out for all Phases.

4. Program phase 2 for Variable Initial and Gap Reduction.

5. Program phase 2 for Startup In Green.

6. Program phases 2 and 7 for Startup Ped Call.

7. Program phase 2 for Yellow Flash.

8. The cabinet and controller are part of the US 401 Bypass (Rolesville) Closed Loop System.

EQUIPMENT INFORMATION

CONTROLLER.....2070 SOFTWARE......ECONOLITE OASIS

CABINET MOUNT.....BASE

OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE LOAD SWITCHES USED.....S2,S2P,S4P,S7,S10,S13

PHASES USED......2,7,2PED,7PED OVERLAP "A".....NOT USED

OVERLAP "C".....NOT USED OVERLAP "D".....2+7

PROJECT REFERENCE NO. Sig 1

				SIC	ANE	L F	HEA	D I	100	K-l	JP	CHA	٩RT	1				
LOAD SWITCH NO.	SI	S2	S2P	S 3	S4	S4P	S5	S6	S6P	S7	S8	S8P	S 9	S10	S11	S12	S13	S14
PHASE	1	2	2 PED	3	4	7 [#] PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	NU	21,22	P21. P22	NU	NU	P71. P72	NU	NU	NU	71 ★	NU	NU	NU	72,73	NU	NU	71 ★	NU
RED		128												A124				
YELLOW		129								*								
GREEN		130																
RED ARROW																	A101	
YELLOW ARROW														A125			A102	
FLASHING YELLOW ARROW																	A103	
GREEN ARROW										124				A126				
4			113			104												
×			115			106												

NU = Not Used

* Denotes install load resistor. See load resistor installation detail this sheet.

See Phase 7 PED output programming detail on Sheet 2.

★ See pictorial of head wiring in detail this sheet.

INPUT FILE POSITION LAYOUT

(front view)

,	1	2	3	4	5	6	7	8	9	10	11	12	13	14
FILE U	SLOT EMPTY	ø 2/SYS 2A/S4 ø 2/SYS 2B/S5	SLOT EXPTY	SLOT EMPTY	SLOT EXPTY	SLOT EXPTY	SLOT EXPTY	SLOT EMPTY	SYS S6 SYS S7	SLOT EMPTY	SLOT EMPTY	Ø2PED OC ISOLATOR Ø7PED OC ISOLATOR	SLOT EMPTY	FS DC ISOLATOR ST DC ISOLATOR
FILE U "J" L	SLOT EMPTY	SLOT EMPTY	SLOT EXPTY	SLOT EXPTY	Ø 7 7A NOT USED	ø 7 7B ø 7 7C	SLOT EXPTY	SLOT EXPTY	SYS S8 NOT USED	SLOT EXPTY	SLOT EXPTY	PRE3 * 2 (h, Cord NOT USED	SLOT EMPTY	ω_10⊢ μΣμ⊢≻

EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE ST = STOP TIME PRE = PREEMPT

INPUT FILE POSITION LEGEND: J2L

FILE J

SLOT 2-

LOWER-

* INSTALL OPTICAL PREEMPTION SYSTEM ACCORDING TO MANUFACTURER'S INSTRUCTIONS AND ENGINEER'S APPROVED MOUNTING LOCATION.

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
2A/S4	TB2-5,6	I2U	39	1	2	2/SYS	Y	Υ			
2B/S5	TB2-7,8	I2L	43	5	12	2/SYS	Y	Υ			
* S6	TB6-9,10	19U	60	22	11	SYS					
* S7	TB6-11,12	I9L	62	24	13	SYS					
7.4	TB5-5,6	J5U	57	19	7	7	Y	Υ			15
7 A	-	J5U	57	19 ★	47	7	Y	Υ			
7B	TB5-9,10	J6U	42	4	8	7	Y	Υ			15
7C	TB5-11,12	J6L	46	8	18	7	Y	Υ			15
* S8	TB7-9,10	J9U	59	21	15	SYS					
PED PUSH BUTTONS											
P21,P22	TB8-4,6	I12U	67	29	PED 2	2 PED					
P71 . P72	TB8-5,6	I12L	69	31	PED 4	7 PED	│ ◆				


NOTE: INSTALL DC ISOLATORS IN INPUT FILE SLOT 112.

- * System detector only. Remove the vehicle phase assigned to this detector in the default programming.
- ★ See Input Page Assignment programming details on Sheet 3.

LOAD RESISTOR INSTALLATION DETAIL

(install resistor as shown below)

ACCEPTABLE VALUES VALUE (ohms) WATTAGE 1.5K - 1.9K 25W (min) 2.0K - 3.0K | 10W (min)



NC Dept of Transportation Division of Highways Final Drawing Date: 1/16/2020ITS & Signal Back Whit

-RP DISABLE

- WD 1.0 SEC

-GY ENABLE

—LEDguard

—FYA 1-9 **−FYA 3-10**

FYA 5-11

DENOTES POSITION

OF SWITCH

SF#1 POLARITY

-FYA COMPACT-


THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2390 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:



A. Morton Thomas and Associates, Inc. CONSULTING ENGINEERS 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM NCBELS LICENSE No. F-1049

FYA SIGNAL WIRING DETAIL

(wire signal head as shown)



NOTE

The sequence display for signal head 71 requires special logic programming. See sheet 2 for programming instructions.

COUNTDOWN PEDESTRIAN SIGNAL OPERATION

Countdown Ped Signals are required to display timing only during Ped Clearance Interval. Consult Ped Signal Module user's manual for instructions on selecting this feature.

Electrical Detail - Sheet 1 of 4

DOCUMENT NOT CONSIDERED FINAL **UNLESS ALL SIGNATURES COMPLETED**

ELECTRICAL AND PROGRAMMIN DETAILS FOR Prepared for the Offices of:

750 N.Greenfield Pkwy.Garner.NC 27529

US 401 NB (Louisburg Road)

SR 1003 (East Young Street) PLAN DATE: November 2019 REVIEWED BY: J O Deaton

PREPARED BY: M W Yalch REVIEWED BY: REVISIONS

SIGNATURE

SIG. INVENTORY NO. 05-2390

OVERLAP PROGRAMMING DETAILS

PAGE 2

PAGE 2

OVERLAP PROGRAMMING DETAIL FOR DEFAULT PHASING

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS). THEN '1' (VEHICLE OVERLAP SETTINGS).

PAGE 1: VEHICLE OVERLAP 'B' SETTINGS 12345678910111213141516 VEH OVL PARENTS: : VEH OVL NOT VEH: ; VEH OVL NOT PED: :

VEH OVL GRN EXT: : STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...N GREEN EXTENSION (0-255 SEC).....0 YELLOW CLEAR (O=PARENT.3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0 OUTPUT AS PHASE # (0=NONE, 1-16)....0

PRESS '+' TWICE

PRESS '+' ONE TIME

PAGE 1: VEHICLE OVERLAP 'D' SETTINGS 12345678910111213141516 PHASE: VEH OVL PARENTS: X X VEH OVL NOT VEH: ; VEH OVL NOT PED: ; VEH OVL GRN EXT: | STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW X GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...Y GREEN EXTENSION (0-255 SEC).....0 YELLOW CLEAR (O=PARENT.3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0 OUTPUT AS PHASE # (0=NONE, 1-16)....0

OVERLAP PROGRAMMING COMPLETE

OVERLAP PROGRAMMING DETAIL FOR ALTERNATE PHASING

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS). THEN '1' (VEHICLE OVERLAP SETTINGS). PRESS 'NEXT' TO ADVANCE TO PAGE 2.

PRESS '+' ONE TIME

NOTICE -PAGE 2: VEHICLE OVERLAP 'B' SETTINGS 12345678910111213141516 PHASE: VEH OVL PARENTS: | X VEH OVL NOT VEH: ; VEH OVL NOT PED: 1 VEH OVL GRN EXT: STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...N GREEN EXTENSION (0-255 SEC)...... YELLOW CLEAR (O=PARENT, 3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0 OUTPUT AS PHASE # (0=NONE, 1-16)....0

PRESS '+' TWICE

NOTICE -PAGE 2: VEHICLE OVERLAP 'D' SETTINGS PHASE: ¦12345678910111213141516 VEH OVL PARENTS: | VEH OVL NOT VEH: | VEH OVL NOT PED: VEH OVL GRN EXT: STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...Y GREEN EXTENSION (0-255 SEC)..... YELLOW CLEAR (O=PARENT.3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0

OUTPUT AS PHASE # (0=NONE, 1-16)....0

OVERLAP PROGRAMMING COMPLETE

PED 7 PROGRAMMING DETAIL

NOTICE GREEN FLASH

(program controller as shown below)

CHANGING OUTPUT ASSIGNMENTS

- 1. FROM MAIN MENU SELECT '6' (OUTPUTS). THEN '1' (OUTPUT ASSIGNMENTS)
- 2. ENTER 1 (PHASE 4 DW) FOR OUTPUT ASSIGNMENT #.
- 3. SCROLL DOWN TO 'PEDESTRIAN PHASE' AND ENTER 'Y' RECARDLESS OF DEFAULT PROGRAMMING!
- 4. ENTER '7' FOR 'SELECT PEDESTRIAN PHASE'. NO CHANGE NEEDED FOR 'SELECT COLOR'
- 5. BACKUP TO 'OUTPUT ASSIGNMENTS AND SETTINGS MENU: BY PRESSING THE 'ESC' BUTTON ON KEYBOARD.
- 6. SELECT '1' (OUTPUT ASSIGNMENTS)
- 7. ENTER 2 (PHASE 4 W) FOR OUTPUT ASSIGNMENT #.
- 8. REPEAT STEPS # 3 AND # 4.

CHANGING INPUT ASSIGNMENTS


- 1. FROM MAIN MENU SELECT '7' (DETECTORS), THEN '2' (PEDESTRIAN DETECTOR ASSIGNMENTS)
- 2. CYCLE TO PED DETECTOR #4 BY REPEATEDLY DEPRESSING '+' KEY
- 3. MODIFY PHASE ASSIGNED TO PED DETECTOR # 4 FROM PHASE 4 TO PHASE 7

PROGRAMMING COMPLETE

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)

- 1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1.2 AND 3.
- 2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).



LOGIC I/O PROCESSOR PROGRAMMING COMPLETE


OUTPUT REFERENCE SCHEDULE USE TO INTERPRET LOGIC PROCESSOR OUTPUT 39 = Overlap D Red OUTPUT 40 = Overlap D Yellow OUTPUT 41 = Overlap D Green

EMERGENCY VEHICLE PREEMPTION

PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #3.



Program Extend time on optical detector unit for 2.0 seconds.

NC Dept of Transportation Division of Highways Final Drawing Date: 1/16/2020 ITS & Signal South Asiat

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2390 DESIGNED: November 2019 SEALED: November 20, 2019 **REVISED:**

Electrical Detail - Sheet 2 of 4

DETAILS FOR

UNLESS ALL SIGNATURES COMPLETED US 401 NB (Louisburg Road)

SR 1003 (East Young Street) PLAN DATE: November 2019 | REVIEWED BY: J O Deaton

PREPARED BY: M W Yalch REVIEWED BY: REVISIONS INIT. DATE

07438 James O. Deaton 12/18/2019 SIGNATURE

SIG. INVENTORY NO. 05-2390

DOCUMENT NOT CONSIDERED FINAL

A. Morton Thomas and Associates, Inc.

Consulting Engineers 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687

E-MAIL MSURASKY@AMTENGINEERING.COM

NCBELS LICENSE No. F-1049

750 N.Greenfield Pkwy.Garner.NC 27529

ELECTRICAL AND PROGRAMMII

PROJECT REFERENCE NO. 44823 Sig. 1.3


INPUT PAGE 2 ASSIGNMENT PROGRAMMING DETAIL FOR ALTERNATE PHASING - LOOP 7A

(program controller as shown below)

NOTES: 1. THIS PROGRAMMING APPLIES FOR INPUT PAGE 2 ONLY. INPUT PAGE 1 WILL USE STANDARD DEFAULT SETTINGS. THIS PROGRAMMING IS NECESSARY FOR PROPER DETECTOR OPERATION DURING ALTERNATE PHASING OPERATION.

2. THIS PROGRAMMING REASSIGNS DETECTOR 47 TO INPUT #19 SO THAT THE DELAY ON LOOP 7A CAN BE REDUCED FROM 15 SECONDS TO 0 SECONDS.

FROM MAIN MENU PRESS '5' (INPUTS). THEN PRESS 'NEXT' TO GET TO INPUT PAGE '2'. PRESS THE '+' KEY UNTIL INPUT 19 IS REACHED.




PROGRAMMING COMPLETE

SPECIAL DETECTOR PROGRAMMING DETAIL - LOOP 7A (ALT.)

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS). THEN PRESS '1' FOR VEHICLE DETECTORS. PRESS THE '-' KEY TO GET TO VEHICLE DETECTOR #47.



NOTE: DETECTOR IS PROGRAMMED PER THE

CHART SHOWN ON SHEET 1.


INPUT FILE CONNECTION AND PROGRAMMING

NC Dept of Transportation Division of Highways Final Drawing Date: 1/16/2020 ITS & Signal 827 Wait

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2390 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:

A. MORTONTHOMAS AND ASSOCIATES, INC. Consulting Engineers 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM

NCBELS LICENSE No. F-1049



US 401 NB (Louisburg Road) SR 1003 (East Young Street)

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY:

07438 James O. Deaton 12/18/2019 SIGNATURE

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

REVISIONS SIG. INVENTORY NO. 05-2390

PROJECT	REFERENCE NO.	SHEET NO.
	44823	Sig. 1.4

ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING <u>COORDINATION</u> - SELECT ALL PAGE CHANGES (AS SHOWN BELOW) WITHIN COORDINATION PLAN PROGRAMMING.

TO RUN ALT. PHASING DURING <u>FREE RUN</u> - PROGRAM PAGE CHANGES (SHOWN BELOW) IN SEPARATE TIME OF DAY EVENTS. IF PAGE 1 IS USED, NO EVENT PROGRAMMING IS NECESSARY FOR THAT PARTICULAR PAGE.

PHAS I NG	INPUTS PAGE	OVERLAPS PAGE
ACTIVE PAGES REQUIRED TO RUN DEFAULT PHASING	1	1
ACTIVE PAGES REQUIRED TO RUN ALTERNATE PHASING	2	2

NOTE: PAGES NOT SHOWN (i.e. sequence, phase control, etc.) SHOULD REMAIN AS '1', OR AS DEFINED BY TIMING ENGINEER.

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY PAGE CHANGE EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN PAGE CHANGE EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING PAGE CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN THESE OVERLAP/INPUT PAGE CHANGES ACTIVATE TO CALL THE "ALTERNATE PHASING":

OVERLAPS PAGE 2: Modifies overlap parent phases for head 71 to run protected

turns only.

Reassigns an input and reduces delay INPUTS PAGE 2:

time on loop 7A to 0 seconds.

NC Dept of Transportation Division of Highways Final Drawing Date: ___1/16/2020

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2390 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:

Electrical Detail - Sheet 4 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMIN

750 N.Greenfield Pkwy.Garner.NC 27529

US 401 NB (Louisburg Road)

SR 1003 (East Young Street)

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY: REVISIONS


James O. Deaton 12/18/2019 40FF0AC450BD40F... SIGNATURE SIG. INVENTORY NO. 05-2390

A. MORTON THOMAS AND ASSOCIATES, INC. Consulting Engineers 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM NCBELS LICENSE No. F-1049

PROJECT REFERENCE NO. 44823 Sig. 2.0 OASIS 2070 LOOP & DETECTOR INSTALLATION CHART ALTERNATE PHASING 2 Phase DEFAULT PHASING INDUCTIVE LOOPS DETECTOR PROGRAMMING DEFAULT PHASING DIAGRAM EV PREEMPT PHASES Fully Actuated TABLE OF OPERATION TABLE OF OPERATION (Medium Priority) w/ EV Preemption PHASE PHASE US 401 Bypass (Rolesville) CLS (FT) STOPBAR SIGNAL SIGNAL Signal System #: 10552 FACE FACE 6X40 0 2-4-2 - 3 NOTES 6X40 0 2-4-2 - 3 ||| | - | - | - | | 6×40 | 0 | 2-4-2|-| 3 | Y | Y | 1. Refer to "Roadway Standard Drawings 32, 33 32,33 6A/S9 | 6X6 | 420 | EXIST | - | 6 | Y | Y | NCDOT" dated January 2018 and 6I, 62 6B/SIO 6X6 420 EXIST - 6 61,62 "Standard Specifications for Roads SII | 6X6 | 200 | EXIST | - | - | P3I, P32 | DW | W | DW | DF and Structures" dated January 2018. SI2 | 6X6 | 100 | 4 | - | - | - | - | - | PHASING DIAGRAM DETECTION LEGEND 2. Do not program signal for late night P6I, P62 P6I, P62 P63, P64 SI3 6X6 100 4 - - - - - flashing operation unless otherwise P63, P64 DETECTED MOVEMENT *Disable Delay during Alternate Phasing operation. directed by the Engineer. UNDETECTED MOVEMENT (OVERLAP) 3. Set all detector units to presence UNSIGNALIZED MOVEMENT W - Walk mode. \leftarrow - > PEDESTRIAN MOVEMENT SIGNAL FACE I.D. DW - Don't Walk 4. Omit "WALK" and flashing "DON'T DRK – Dark All Heads L.E.D. WALK" with no pedestrian calls. 5. Program pedestrian heads to ALTERNATE PHASING DIAGRAM countdown flashing "DON'T WALK" time only. 6. This intersection features an optical preemption system. Shown locations of optical detectors are conceptual only. P3I, P32 P6I, P62 7. Optical detector 10 calls PRE 3. 61,62 32,33 8. The Division Traffic Engineer will P63, P64 determine the hours of use for each phasing plan. 9. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values. 10. Closed loop system data: Metal Pole #1 Controller Asset #: 2236. 55 MPH -1% Grade US 401 (Louisburg Road) LEGEND **EXISTING** PROPOSED Traffic Signal Head Modified Signal Head US 401 (Louisburg Road) Cabinet for 05-2390 55 MPH +2% Grade Pedestrian Signal Head With Push Button & Sign Signal Pole with Guy ignal Pole with Sidewalk Guy Inductive Loop Detector OASIS 2070 EV PREEMPT Controller & Cabinet OASIS 2070 TIMING CHART Junction Box **FUNCTION** PRE 3 PHASE 2-in Underground Conduit Interval 1 – Dwell Green 255 **FEATURE** Right of Way 0.0* Interval 1 - Dwell Yellow Min Green 1 * Directional Arrow 0.0* Interval 1 – Dwell Red Metal Pole with Mastarm 2.0 6.0 Extension 1 * Interval 5 - Exit Green Type II Signal Pedestal 90 Max Green 1 * 25 0.0 Interval 5 - Yellow Directional Drill Yellow Clearance 3.0 5.3 0.0 Interval 5 - Red Optical Detector NC Dept of Transportation 2.6 1.1 Red Clearance Exit Phase(s) Division of Highways No U-Turn Sign (R3-4) 2.0 2.0 Red Revert MED "YIELD" Sign (R1-2) Walk 1 * Final Drawing Date: 1/16/2020 0 **Delay Time** N/A Curb Ramp Don't Walk 1 10 1∄ Min Green Before Pre Seconds Per Actuation 1.5 Ped Clear Before Pre 7 Max Variable Initial * 0.0* Yellow Clear Before Pre 15 Time Before Reduction DOCUMENT NOT CONSIDERED 0.0* Red Clear Before Pre FINAL UNLESS ALL Signal Upgrade Time To Reduce * 45 SIGNATURES COMPLETED 10 Dwell Min Time Minimum Gap 3.4 2 Dwell Max Time (Minutes) US 401 SB (Louisburg Road) Recall Mode MIN RECALL Ν **Enable Backup Protection** Vehicle Call Memory YELLOW Ped Clear Through Yellow SR 1003 (East Young Street) **Dual Entry** Omit Overlaps Simultaneous Gap Wake County Rolesville 043930 PLAN DATE: November 2019 REVIEWED BY: T. Kirk * Time defaults to time used for phase during normal operation
** Program Timing on Optical Detection Unit 50 N.Greenfield Pkwy,Garner,NC 27529 PREPARED BY: T. Wells Green for all other phases should not be lower than 4 seconds REVISIONS REVISIONS INIT. DATE Stopbar Locations For: Timotly" 8: 1 1/20/2019 US 401 SB (Louisburg Road) at SR 1003 (East Young Street) SCALE

SIG. INVENTORY NO. 05-2236

\$\$\$\$YSTIME\$\$\$\$\$ \$\$\$\$\$\$\$\$\$\$\$\$\$\$



- 2. Enable Simultaneous Gap-Out for all Phases.
- 3. Program phase 6 for Variable Initial and Gap Reduction.
- 4. Program phase 6 for Startup In Green.
- 5. Program phases 3 and 6 for Startup Ped Call.
- 6. Program phase 6 for Yellow Flash.
- 7. The cabinet and controller are part of the US 401 Bypass (Rolesville) Closed Loop System.

EQUIPMENT INFORMATION

CONTROLLER2070	
CABINET	
SOFTWAREECONOLITE OASIS	
CABINET MOUNTBASE	
OUTPUT FILE POSITIONS18 WITH AUX. OUTPUT FILE	
LOAD SWITCHES USEDS4.S8.S9.S12.AUX S2.AUX S5	
PHASES USED3,6,3PED,6PED	
OVEDLAD "A" NOT LICED	

OVERLAP "A".....NOT USED

OVERLAP "C".....NOT USED

LOAD SWITCH NO. S8 S9 S10 S11 S12 AUX CMU CHANNEL NO. PHASE NU 61,62 P61,P62, NU NU P31, P32 NU SIGNAL HEAD NO. A101 RED 135 YELLOW GREEN ARROW YELLOW A102 ARROW FLASHING YELLOW ARROW GREEN A103 ARROW

FYA SIGNAL WIRING DETAIL

OLB RED (A124) -

OLB YELLOW (A125)

OLB GREEN (A126) -

03 GREEN (118)

The sequence display for signal head 31 requires special

logic programming. See sheet 2 for programming instructions.

COUNTDOWN PEDESTRIAN SIGNAL OPERATION

Countdown Ped Signals are required to display timing only during

Ped Clearance Interval. Consult Ped Signal Module user's manual

(wire signal head as shown)

31

SIGNAL HEAD HOOK-UP CHART

NU = Not Used

- * Denotes install load resistor. See load resistor installation detail this sheet.
- # See Phase 3 PED output programming detail on Sheet 2.
- ★ See pictorial of head wiring in detail this sheet.

INPUT FILE POSITION LAYOUT

(front view)

,	1	2	3	4	5	6	7	8	9	10	11	12	13	14
	S L O	S	S	S	ø 3	ø 3	S	S	SYS	S	S		Ø6 PED	FS
FILE	Ť	P	P	ģ	3A	3B	Ď	ģ	S11	Ť	ģ	À	DC ISOLATOR	DC ISOLATOR
"I" ,	E M P	E M	E M p	E M P	NOT	ø 3	E M P	E M P	SYS	EMρ	E M P	E M P	Ø3PED	
L	T Y	T Y	T Y	T Y	USED	3C	T Y	T Y	S12	T Y	T Y	T Y	DC ISOLATOR	DC ISOLATOR
	S	ø6/SYS	S	s	S	S	S	S	SYS	S	s	PRE3	S	S
FILE U		6A/S9	L O T	þ	L D	D T	D T	þ	S13	D T		*		
"J" .	E M P	Ø6/SYS	E M	E M P	E M P	E M	E M P	E M P		E M	E M P	2 Ch. Card	E Mo	E M
Ľ	P T Y	l' l	P T Y	P T Y	P T Y	P T Y	P T Y	P T Y	NOT USED	P T Y	P T Y	NOT USED	P T Y	P T Y
Į	<u> </u>	6B/S10	Ÿ	<u> </u>	¥	Ý	Ÿ	,	USED	Ý	Ÿ	U3ED	Ý	<u> </u>

EDI MODEL 2018ECL-NC CONFLICT MONITOR

PROGRAMMING DETAIL

(remove jumpers and set switches as shown)

REMOVE DIODE JUMPERS 3-10, 3-12, 3-16, 6-10, 6-15, 10-12, 10-15, 10-16 AND 12-16.

COMPONENT SIDE

REMOVE JUMPERS AS SHOWN

2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.

4. Connect serial cable from conflict monitor to comm. port 1 of 2070

controller. Ensure conflict monitor communicates with 2070.

3. Ensure that Red Enable is active at all times during normal operation.

1. Card is provided with all diode jumpers in place. Removal

of any jumper allows its channels to run concurrently.

FS = FLASH SENSE ST = STOP TIME

> INPUT FILE POSITION LEGEND: J2L FILE J-

* INSTALL OPTICAL PREEMPTION SYSTEM ACCORDING TO MANUFACTURER'S INSTRUCTIONS AND ENGINEER'S APPROVED MOUNTING LOCATION.

LOAD RESISTOR INSTALLATION DETAIL

(install resistor as shown below)

SLOT 2 LOWER-

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
24	TB4-5,6	15U	58	20	3	3	Y	Υ			15
3A	-	I5U	58	20 ★	43	3	Y	Υ			
3B	TB4-9,10	I6U	41	3	4	3	Y	Y			15
3C	TB4-11,12	I6L	45	7	14	3	Y	Y			15
* S11	TB6-9,10	I9U	60	22	11	SYS					
* S12	TB6-11,12	I9L	62	24	13	SYS					
6A/S9	TB3-5 , 6	J2U	40	2	6	6/SYS	Y	Y			
6B/S10	TB3-7 , 8	J2L	44	6	16	6/SYS	Y	Y			
* S13	TB7-9,10	J9U	59	21	15	SYS					
PED PUSH BUTTONS										-	_
P61 , P62 , P63 , P64	TB8-7 , 9	I13U	68	30	PED 6	6 PED					
P31 , P32	TB8-8,9	I13L	70	32	PED 8	3 PED	—				

NOTE: INSTALL DC ISOLATORS IN INPUT FILE SLOT 113.

- * System detector only. Remove the vehicle phase assigned to this detector in the default programming.
- ★ See Input Page Assignment programming details on Sheet 3.

DOCUMENT NOT CONSIDERED FINAL **UNLESS ALL SIGNATURES COMPLETED**

Prepared for the Offices of:

750 N.Greenfield Pkwy.Garner.NC 27529

<u>NOTE</u>

US 401 SB (Louisburg Road) SR 1003 (East Young Street)

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY:

Division of Highways Final Drawing Date: 1/16/2020ITS & Signals Whit

REVISED:

A. Morton Thomas and Associates, Inc. Consulting Engineers

6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM NCBELS LICENSE No. F-1049

Electrical Detail - Sheet 1 of 4 ELECTRICAL AND PROGRAMMIN

DETAILS FOR

for instructions on selecting this feature.

REVISIONS

SIG. INVENTORY NO. 05-2236

PHASE 3 YELLOW FIELD TERMINAL (117)

ACCEPTABLE VALUES VALUE (ohms) WATTAGE 1.5K - 1.9K 25W (min) 2.0K - 3.0K | 10W (min)

NOTES:

EX.: 1A, 2A, ETC. = LOOP NO.'S

PRE = PREEMPT

WD ENABLE 🕥

SW2

-RP DISABLE

- WD 1.0 SEC

FSF#1 POLARITY

FYA COMPACT—

GY ENABLE

— LEDguard

-FYA 1-9

FYA 3-10 FYA 5-11

FYA 7-12 -

■ = DENOTES POSITION OF SWITCH

NC Dept of Transportation

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2236 DESIGNED: November 2019 SEALED: November 20, 2019

OVERLAP PROGRAMMING DETAILS

PAGE 2

PAGE 2

OVERLAP PROGRAMMING DETAIL FOR DEFAULT PHASING

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS). THEN '1' (VEHICLE OVERLAP SETTINGS).

PAGE 1: VEHICLE OVERLAP 'B' SETTINGS 12345678910111213141516 VEH OVL PARENTS: X X VEH OVL NOT VEH: ; VEH OVL NOT PED: : VEH OVL GRN EXT: : STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW X GREEN NOTICE GREEN FLASH SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...Y

GREEN EXTENSION (0-255 SEC).....0

OUTPUT AS PHASE # (0=NONE, 1-16)....0

YELLOW CLEAR (O=PARENT.3-25.5 SEC)..0.0

RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0

PRESS '+' TWO TIMES

PRESS '+' ONE TIME

PAGE 1: VEHICLE OVERLAP 'D' SETTINGS ¦12345678910111213141516 PHASE: VEH OVL PARENTS: | X VEH OVL NOT VEH: ; VEH OVL NOT PED: ; VEH OVL GRN EXT: | STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...N GREEN EXTENSION (0-255 SEC)...... YELLOW CLEAR (O=PARENT.3-25.5 SEC)..0.0 RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0 OUTPUT AS PHASE # (0=NONE, 1-16)....0

OVERLAP PROGRAMMING COMPLETE

OVERLAP PROGRAMMING DETAIL FOR ALTERNATE PHASING

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS). THEN '1' (VEHICLE OVERLAP SETTINGS). PRESS 'NEXT' TO ADVANCE TO PAGE 2.

PRESS '+' ONE TIME

NOTICE -PAGE 2: VEHICLE OVERLAP 'B' SETTINGS 12345678910111213141516 PHASE: VEH OVL PARENTS: | X VEH OVL NOT VEH: | VEH OVL NOT PED: 1 VEH OVL GRN EXT: STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...Y GREEN EXTENSION (0-255 SEC)...... YELLOW CLEAR (O=PARENT, 3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0 OUTPUT AS PHASE # (0=NONE, 1-16)....0

PRESS '+' TWO TIMES

NOTICE -PAGE 2: VEHICLE OVERLAP 'D' SETTINGS 12345678910111213141516 PHASE: VEH OVL PARENTS: | X VEH OVL NOT VEH: : VEH OVL NOT PED: VEH OVL GRN EXT: STARTUP COLOR: _ RED _ YELLOW _ GREEN FLASH COLORS: _ RED _ YELLOW _ GREEN SELECT VEHICLE OVERLAP OPTIONS: (Y/N) FLASH YELLOW IN CONTROLLER FLASH?...N GREEN EXTENSION (0-255 SEC)...... YELLOW CLEAR (O=PARENT,3-25.5 SEC)..0.0 RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0

OVERLAP PROGRAMMING COMPLETE

OUTPUT AS PHASE # (0=NONE, 1-16)....0

PED 3 PROGRAMMING DETAIL

(program controller as shown below)

CHANGING OUTPUT ASSIGNMENTS

- 1. FROM MAIN MENU SELECT '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS)
- 2. ENTER 17 (PHASE 8 DW) FOR OUTPUT ASSIGNMENT #.
- 3. SCROLL DOWN TO 'PEDESTRIAN PHASE' AND ENTER 'Y' REGARDLESS OF DEFAULT PROGRAMMING!
- 4. ENTER '3' FOR 'SELECT PEDESTRIAN PHASE'. NO CHANGE NEEDED FOR 'SELECT COLOR'
- 5. BACKUP TO 'OUTPUT ASSIGNMENTS AND SETTINGS MENU: BY PRESSING THE 'ESC' BUTTON ON KEYBOARD.
- 6. SELECT '1' (OUTPUT ASSIGNMENTS)
- 7. ENTER 18 (PHASE 8 W) FOR OUTPUT ASSIGNMENT #.
- 8. REPEAT STEPS # 3 AND # 4.

CHANGING INPUT ASSIGNMENTS


- ASSIGNMENTS)
- 2. CYCLE TO PED DETECTOR #8 BY REPEATEDLY DEPRESSING '+' KEY
- 3. MODIFY PHASE ASSIGNED TO PED DETECTOR # 8 FROM PHASE 8 TO PHASE 3

PROGRAMMING COMPLETE

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)

- 1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1. 2 AND 3.
- 2. FROM MAIN MENU PRESS '6' (OUTPUTS). THEN '3' (LOGICAL I/O PROCESSOR).



LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

OUTPUT REFERENCE SCHEDULE USE TO INTERPRET LOGIC PROCESSOR OUTPUT 47 = Overlap B Red OUTPUT 48 = Overlap B Yellow OUTPUT 49 = Overlap B Green

A. Morton Thomas and Associates, Inc.

6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687

E-MAIL MSURASKY@AMTENGINEERING.COM

NCBELS LICENSE No. F-1049


Consulting Engineers

EMERGENCY VEHICLE PREEMPTION

PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #3.



Program Extend time on optical detector unit for 2.0 seconds.

NC Dept of Transportation Division of Highways Final Drawing Date: 1/16/2020 ITS & Signal scountist

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2236 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:

Electrical Detail - Sheet 2 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMIN

750 N.Greenfield Pkwy.Garner.NC 27529

US 401 SB (Louisburg Road) SR 1003 (East Young Street)

James O. Deaton 12/18/2019

SIGNATURE

SIG. INVENTORY NO. 05-2236

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY: REVISIONS INIT. DATE

1. FROM MAIN MENU SELECT '7' (DETECTORS). THEN '2' (PEDESTRIAN DETECTOR

PROJECT REFERENCE NO. 44823 Sig. 2.3


INPUT PAGE 2 ASSIGNMENT PROGRAMMING DETAIL FOR ALTERNATE PHASING - LOOP 3A

(program controller as shown below)

NOTES: 1. THIS PROGRAMMING APPLIES FOR INPUT PAGE 2 ONLY. INPUT PAGE 1 WILL USE STANDARD DEFAULT SETTINGS. THIS PROGRAMMING IS NECESSARY FOR PROPER DETECTOR OPERATION DURING ALTERNATE PHASING OPERATION.

2. THIS PROGRAMMING REASSIGNS DETECTOR 43 TO INPUT #20 SO THAT THE DELAY ON LOOP 3A CAN BE REDUCED FROM 15 SECONDS TO 0 SECONDS.

FROM MAIN MENU PRESS '5' (INPUTS). THEN PRESS 'NEXT' TO GET TO INPUT PAGE '2'. PRESS THE '+' KEY UNTIL INPUT 20 IS REACHED.




PROGRAMMING COMPLETE


SPECIAL DETECTOR PROGRAMMING DETAIL - LOOP 3A (ALT.)

(program controller as shown below)

FROM MAIN MENU PRESS '7' (DETECTORS). THEN PRESS '1' FOR VEHICLE DETECTORS. PRESS THE '-' KEY TO GET TO VEHICLE DETECTOR #43.



NOTE: DETECTOR IS PROGRAMMED PER THE INPUT FILE CONNECTION AND PROGRAMMING CHART SHOWN ON SHEET 1.



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2236 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:

Electrical Detail - Sheet 3 of 4 ELECTRICAL AND PROGRAMMIN

DETAILS FOR

US 401 SB (Louisburg Road)

SR 1003 (East Young Street)

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY:

James O. Deaton 12/18/2019

A. Morton Thomas and Associates, Inc. Consulting Engineers 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM

DETECTOR PROGRAMMING COMPLETE

NCBELS LICENSE No. F-1049

750 N.Greenfield Pkwy.Garner.NC 27529

Prepared for the Offices of:

REVISIONS

INIT. DATE SIG. INVENTORY NO. 05-2236

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

PROJECT	REFERENCE NO.	SHEET	NO.
	44823	Sig	2.4

ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING <u>COORDINATION</u> - SELECT ALL PAGE CHANGES (AS SHOWN BELOW) WITHIN COORDINATION PLAN PROGRAMMING.

TO RUN ALT. PHASING DURING FREE RUN - PROGRAM PAGE CHANGES (SHOWN BELOW) IN SEPARATE TIME OF DAY EVENTS. IF PAGE 1 IS USED, NO EVENT PROGRAMMING IS NECESSARY FOR THAT PARTICULAR PAGE.

PHASING	INPUTS PAGE	OVERLAPS PAGE
ACTIVE PAGES REQUIRED TO RUN DEFAULT PHASING	1	1
ACTIVE PAGES REQUIRED TO RUN ALTERNATE PHASING	. 2	2

NOTE: PAGES NOT SHOWN (i.e. sequence, phase control, etc.) SHOULD REMAIN AS '1', OR AS DEFINED BY TIMING ENGINEER.

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY PAGE CHANGE EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN PAGE CHANGE EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING PAGE CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN THESE OVERLAP/INPUT PAGE CHANGES ACTIVATE TO CALL THE "ALTERNATE PHASING":

OVERLAPS PAGE 2: Modifies overlap parent phases for head 31 to run protected turns only.

INPUTS PAGE 2: Reassigns an input and reduces delay time on loop 3A to 0 seconds.

> NC Dept of Transportation Division of Highways Final Drawing Date: ___1/16/2020 ITS & Signed Stanit

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-2236 DESIGNED: November 2019 SEALED: November 20, 2019 REVISED:

Electrical Detail - Sheet 4 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



NCBELS LICENSE No. F-1049

A. Morton Thomas and Associates, Inc. Consulting Engineers 6131 FALLS OF NEUSE ROAD, SUITE 106, RALEIGH, NC 27609 TEL (919) 855-9989 FAX (919) 855-5687 E-MAIL MSURASKY@AMTENGINEERING.COM

ELECTRICAL AND PROGRAMMING DETAILS FOR: 750 N.Greenfield Pkwy.Garner.NC 27529

US 401 SB (Louisburg Road) SR 1003 (East Young Street)

PLAN DATE: November 2019 REVIEWED BY: J O Deaton PREPARED BY: M W Yalch REVIEWED BY: REVISIONS

SIG. INVENTORY NO. 05-2236