
SITE LOCATION MAP



PROJECT DESCRIPTION

THIS PROJECT IS LOCATED ON A 1.92 ACRE SITE, IN ROLESVILLE, NC. THE PROPERTY AS IT EXISTS IS AN UNDEVELOPED LOT. THE PROPOSED DEVELOPEMENT WILL BE AN AUTOMATED CAR WASH WITH ASSOCIATED

THIS PROPERTY IS LOCATED OUTSIDE OF ANY REGULATED FLOOD ZONES, ZONEX (OTHER AREAS), NAVD88,

SCALED FROM THE FIRM THE TOWN OF ROLESVILLE, NORTH CAROLINA PANEL NO. 3720175800K.

PARCEL ID: 1758479244


ZONING DISTRICT: GI (GENERAL INDUSTRIAL)

GENERAL NOTES

PROJECT SURVEY INFORMATION AND CONTRACTOR VERIFICATION REQUIREMENTS

- BOUNDARY, TOPOGRAPHIC, TREE, WETLAND DELINEATION, AND OTHER EXISTING CONDITIONS SHOWN ARE FROM SURVEY PREPARED BY MSP & ASSOCIATES LAND SURVEYING, INC. ALL ELEVATIONS ARE BASED ON NAVD88 DATUM.
- THE CONTRACTOR SHALL VERIFY THE EXISTING TOPOGRAPHIC WORK, EXISTING UTILITY LINE LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING WORK. SHOULD THE CONTRACTOR FIND ANY DISCREPANCIES ON THE DRAWINGS PRIOR TO BEGINNING WORK OR DURING CONSTRUCTION, THE ENGINEER SHALL BE NOTIFIED
- THE CONTRACTOR SHALL MAINTAIN AND BE SOLELY RESPONSIBLE FOR JOBSITE SAFETY.
- AN AUTOCAD BASE PLAN OF THIS DRAWINGS CAN BE PROVIDED TO THE CONTRACTOR UPON REQUEST. ENGINEER SHALL NOT BE RESPONSIBLE FOR ERRORS IN ELECTRONIC DATA.
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL PLANS AND COORDINATION WITH THE TOWN OF
- ROLESVILLE FOR LANE/ROAD CLOSURE AS NEEDED THROUGHOUT CONSTRUCTION. ALL SITE WORK TO BE PERFORMED IN CONFORMANCE WITH THE TOWN OF ROLESVILLE CODE OF ORDINANCE. MATERIAL SPECIFICATIONS ARE PROVIDED IN THE SPECIFICATIONS AND SPECIAL PROVISIONS SECTION.
- ALL UTILITY INSTALLATIONS, PUBLIC AND PRIVATE, SHALL BE PERFORMED IN CONFORMANCE WITH THE TOWN OF ROLESVILLE WATER AND SEWER POLICIES, PROCEDURES, STANDARDS AND SPECIFICATIONS.

SITE OVERVIEW



SCALE: 1" = 30'

SURVEYOR OWNER:

MSP & ASSOCIATES

LAND SURVEYING INC.

301 E. HILLCREST DR.

GREENVILEE, SC, 29609

PHONE: (864) 370-2232

PROJECT CONTACTS

EROSION CONTROL, STORMWATER AND FLOODPLAIN MANAGEMENT **APPROVED** EROSION CONTROL ☐ SEC-STORMWATER MGMT.□SWF-FLOOD STUDY ☐ SWF-

DEVELOPER: SHJ DEVELOPMENT, LLC 124 EAST THOMPSON STREET POST OFFICE DRAWER 311 THOMASTON, GA 30286 CONTACT: ALEX PERRY PHONE: 478-972-2418

GRAND PARK PROPERTIES, LLC 2636 WAIT AVENUE WAKE FOREST, NC 27587 CONTACT: GEORGE M. UPCHURCH, JR. PHONE: 919-996-3245

CIVIL ENGINEER & LANDSCAPE ARCHITECT: SOURCES: SEAMON WHITESIDE & ASSOCIATES, LLC 230 E PETERSON DR CHARLOTTE, NC 28217 CONTACT: TOMMIE LITTLE PHONE: 980-312-5450

UTILITY CONTACTS: CITY OF RALEIGH PUBLIC UTILITIES ONE EXCHANGE PLAZA, RALEIGH, NC 27601

Sheet List Table

C1.0	TITLESHEET
C1.1	LEGEND & REVISION NOTES
C2.1	SURVEY
C3.1	EXISTING CONDITIONS AND DEMO PLAN
C4.1	EROSION CONTROL PH I
C4.2	EROSION CONTROL PH II
C4.3	EROSION CONTROL PH III
C4.6	EROSION CONTORL NOTES
C4.4	EROSION CONTROL DETAILS
C4.5	EROSION CONTROL DETAILS
C5.1	SITE PLAN
C5.2	VEHICLE STACKING & TURNING MOVEMENT
C5.3	FIRE PROTECTION PLAN
C6.1	OVERALL GRADING AND DRAINAGE PLAN
C6.2	DRAINAGE PROFILES
C7.1	UTILITY PLAN AND PROFILES
C7.2	UTILITY PROFILES
C8.1	CONSTRUCTION DETAILS
C8.2	CONSTRUCTION DETAILS
C8.3	CONSTRUCTION DETAILS
C8.4	CONSTRUCTION DETAILS
C8.5	CONSTRUCTION DETAILS
D1.0	ADS STORMTECH
D1.1	ADS STORMTECH
D1.2	ADS STORMTECH
D1.3	ADS STORMTECH
D1.4	ADS STORMTECH
L1.0	LANDSCAPE PLAN
L1.1	PLANT SCHEDULE & DETAILS & NOTES

SITE DATA TABLE:

ADDRESS: 0 S MAIN STREET, ROLESVILLE, NC PROPERTY AREA: 1.92 ACRES PARCEL: 1758479244 **EXISTING USE: UNDEVELOPED** PROPOSED USE: CAR WASH WATERSHED: TOMS CREEK (MILL CREEK) RIVER BASIN: NEUSE

PROPERTY ZONING: GI (GENERAL INDUSTRIAL) BUILDING SETBACKS: FRONT (SE): CORNER (NE): SIDE (NW):

PERIMETER LANDSCAPE YARDS: NORTHEAST:

REQUIRED OPEN SPACE (5%) = 0.01 AC (4182 SF)

BUILDING:

BUILDING AREA: 3325 SF BUILDING HEIGHT: 21'-7"

SIDE (SW):

PRE VS. POST DEVELOPMENT AREA:

PRE-IMPERVIOUS AREA: 0.04 AC (2.08%) POST-IMPERVIOUS AREA: 1.30 AC (67.7%)

PARKING NOTE:

PARKING REQUIRED: 1 SPACE PER 400 SF GFA OR 5 SPACES MINIMUM = 5 SPACES

PARKING PROVIDED: EMPLOYEE SPACES: (4 MAX ON SHIFT)

VACUUM STALLS:


5 SPACES (1 ADA) 34 STALLS





GREENVILLE, SC SPARTANBURG, S 864.272.1272 CHARLOTTE, NC WWW.SEAMONWHITESIDE.COM





SW+ PROJECT: DRAWN BY: CHECKED BY:

REVISION HISTORY


TITLESHEET

C1.0


			DRAV	VINC	G LEG	END	NOTE: THIS LEGEND DOES N THE ORIGINAL FORMAT AS I	NOT APPLY TO 'EXISTING CONDITIONS' SHEET(S). THOS RECEIVED BY THE SURVEYOR	SE ARE SHOWN IN
BJECTS AND SYMBOLS	<u>EXISTING</u>	<u>NEW</u>	OBJECTS AND SYMBOLS Benchmark	EXISTING	<u>NEW</u>	<u>HATCH PATTERNS</u>		SWPP PLAN LEGEN	_
Right of Way Lot Line Adjoining Property Line			Sanitary Sewer Manhole Sanitary Sewer Manhole ID # Sanitary Sewer Cleanout	S N/A	MH # ⊗	Demo Existing Gravel		Turf Reinforcement Mat Sodding (See Turf and Grasses Specs)	TR) S
Easement Setback		(Same as Existing)	TYPE 1 Storm Drainage Structure (CI-1) Catch Basin (CB) Storm Drainage Junction Box (JB)			Demo Existing Trees		Temporary Seeding (See Schedule in EC Notes) Permanent Seeding (See Turf and Grasses Species)	(TS) (PS)
Sanitary Sewer (Gravity) Sanitary Sewer (Force Main) Water Line	ES	S FM	Yard Inlet (YI) Control Structure (CS) Storm Drainage Structure ID # Telephone Box	CS N/A	YI CS # N/A	Donas and Cidavarilla		Erosion Control Blanket (See Turf and Grasses Species) Concrete Washout Basin	(EC)
Curb & Gutter (Straight) Curb & Gutter (Roll)			Telephone Manhole Electrical Box Electrical Manhole	(T) E (E)	N/A N/A N/A	Proposed Sidewalk	4	Block & Stone Inlet Protection	
Previous Phase Storm Drain Pipe Storm Drain Pipe	(Width varies with size)	N/A (Width varies with size)	Power Pole Light Pole Fire Hydrant Assembly	\$ \$ \$	** #	Heavy Duty Concrete Pavement		Filter Fabric Inlet Protection Construction Entrance	
Drainage Flow Arrow Silt Fence, Standard Match Line	N/A ESF		Water Line Valve Water Line Reducer Sign		>	Standard Duty Concrete Pavement		Dandy Sack or Grate Gator Inlet Protection	
Drainage Basin Limits Conduit Natural Gas	N/A EC EG		ADA Accessible Parking Space Spot Elevation Drainage Basin Area	,×.×× N/A	X.XXAc	Asphalt Greenway			
Overhead Electrical Underground Electrical	EP	P	Parking Count ID # Revision ID #	N/A N/A	(2)	Area to be Permanently Stabilized			
Underground Telephone Fence Elevation Contour	X		Rip Rap at Pipe Outlet	N/A					
Revision Cloud (Encloses Revision)	N/A								



MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM








AL WAVE AUTO SP

SW+ PROJECT: 10772
DATE: 12/22/23
DRAWN BY: CPE
CHECKED BY: TLL


REVISION HISTORY

LEGEND & REVISION NOTES





MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM







DEMOLITION NOTES:

- 1. ALL DEMOLITION DEBRIS IS TO BE REMOVED FROM THE PROJECT SITE AND DISPOSED OF IN ACCORDANCE WITH APPLICABLE COUNTY, STATE, AND FEDERAL REGULATIONS.
- 2. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES BEFORE ANY WORK IS STARTED. ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCIES BETWEEN THE FIELD MARKINGS AND SURVEY.
- 3. NO LAND DISTURBING ACTIVITY PRIOR TO APPROVAL OF EROSION AND SEDIMENT CONTROL PLAN AND THE ISSUANCE OF THE LAND-DISTURBING PERMIT AT THE PRECONSTRUCTION MEETING.
- 4. CONTRACTOR TO REMOVE ALL TREES WITHIN LIMITS OF DISTURBANCE.

EXISTING UTILITY NOTE:

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING ANY WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR DUE TO THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.





SW+ PROJECT:

DRAWN BY:

CHECKED BY:


EXISTING

PLAN

CONDITIONS AND DEMO

REVISION HISTORY


12/22/23




- 3. PRE-CONSTRUCTION CONFERENCE TO BE CONDUCTED WITH THE WAKE COUNTY FIELD CONSULTANT (JEEVAN NEUPANE 919-819-8907) TO DISCUSS EROSION CONTROL MEASURE. FAILURE TO SCHEDULE SUCH CONFERENCE PRIOR TO ANY LAND DISTURBING ACTIVITY IS SUBJECT TO FINE. LDP WILL BE ISSUED AT THE PRECONSTRUCTION MEETING (ON-SITE). SITE SHOULD BE FLAGGED PRIOR TO PRE-CONSTRUCTION
- 4. INSTALL SILT FENCE, INLET PROTECTION, BERMS AND OTHER MEASURES AS SHOWN ON PLANS, CLEARING ONLY AS NECESSARY TO INSTALL THESE DEVICES.
- 5. CALL FOR ON-SITE INSPECTION BY WAKE COUNTY FIELD CONSULTANT (JEEVAN NEUPANE 919-819-8907). WHEN APPROVED, INSPECTOR GIVES CONTRACTOR THE ABILITY TO CLEAR AND GRUB SITE.
- 6. THE CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL
- 7. FOR PHASED EROSION CONTROL PLANS, CONTRACTOR SHALL MEET WITH EROSION CONTROL INSPECTOR PRIOR TO COMMENCING WITH EACH PHASE OF EROSION CONTROL MEASURES.
- 8. CONTRACTOR SHALL NOT ALLOW MORE THAN 0.25 ACRES OF DISTURBED AREA TO DRAIN TOWARDS 100LF OF SILT FENCE OR PERFORM GRADING IN A MANNER THAT ALLOWS SEDIMENT LADEN WATER TO FLOW LONGITUDINALLY ALONG SILT FENCE LINE. IF A LOW SPOT DEVELOPS ALONG GRADING NEAR SILT FENCE, CONTRACTOR SHALL COORDINATE WITH EROSION CONTROL INSPECTOR TO PLACE A SILT FENCE OUTLET IN OUTLET LOCATIONS.
- 9. CONTACT WAKE COUNTY FIELD CONSULTANT (JEEVAN NEUPANE 919-819-8907) UPON COMPLETION OF INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS PRIOR TO PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING.
- 10. UPON APPROVAL FROM WAKE COUNTY FIELD CONSULTANT (JEEVAN NEUPANE 919-819-8907), COMPLETE DEMOLITION OF ANY SITE FEATURES (PAVEMENT, CURB, ETC.), CLEARING AND GRUBBING, AND STRIP SITE OF TOP SOIL. ALL DEMOLISHED MATERIAL IS TO BE DISPOSED IN ACCORDANCE WITH APPLICABLE NORTH CAROLINA REGULATIONS. CONTRACTOR TO ENSURE ALL APPLICABLE DEMOLITION PERMITS HAVE BEEN ISSUED AND HAVE ORIGINALS OF THE SAME PRIOR TO COMMENCING DEMOLITION
- 11. CONTACT WAKE COUNTY FIELD CONSULTANT (JEEVAN NEUPANE 919-819-8907) UPON COMPLETION OF STRIPPING, THE STOCKPILING OF TOPSOIL, THE CONSTRUCTION OF TEMPORARY SEDIMENT AND EROSION CONTROL FACILITIES, DISPOSAL OF ALL WASTE MATERIAL, AND PREPARATION OF THE

INLET PROTECTION NOTE:

PROVIDE APPROPRIATE INLET PROTECTION FOR VARIOUS PHASES OF THE CONSTRUCTION . HARDWARE CLOTH AND GRAVEL PROTECTION SHALL BE PROVIDED FOR INLETS IN NON-PAVED AREA. WEEP FILTERS SHALL BE PROVIDED FOR INLETS IN PAVED AREAS.



/ PLANTINGS. ANY DISTURBED WHICH MIGHT OCCUR DUE TO THE CONTRACTOR'S AREA NOT ADDRESSED IN THE FAILURE TO EXACTLY LOCATE AND PRESERVE ANY LANDSCAPE PLANS SHALL BE AND ALL UNDERGROUND UTILITIES. PERMANENT SEEDED.




MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534

843.972.0710

864.272.1272

980.312.5450

ASSOCIATES, INC.



ROL

SW+ PROJECT: 12/22/23 DRAWN BY:

CHECKED BY: **REVISION HISTORY**

EROSION CONTROL PH I

LANDSCAPE PLANS SHALL BE

PERMANENT SEEDED.

0 10 20

SCALE: 1" = 20'

Know what's below.

AND ALL UNDERGROUND UTILITIES.



SW+ PROJECT: 12/22/23 DRAWN BY: CHECKED BY:


REVISION HISTORY

EROSION

CONTROL PH

PS

PERMANENT SOD



Know what's below.

Call before you dig.

PHASE III SEQUENCING:

2. BEGIN FINE GRADING AND INITIATE FINAL PAVING

NEUPANE 919-819-8907) FOR APPROVAL TO REMOVE APPLICABLE EROSION CONTROL MEASURES.


4. PERMANENTLY STABILIZE ANY REMAINING AREAS IN ACCORDANCE WITH THE PERMANENT SEEDING SCHEDULE AND

DRAINAGE, AND EROSION CONTROL FACILITIES, INCLUDING ESTABLISHED GROUND COVERS AND PLANTINGS, AND ALL

TOTAL SITE ACREAGE

1.92 ACRES

PERMANENT SEEDED.




	E&SC PLA	N LEGEND	
LIMITS OF DISTURBANCE		CONCRETE WASHOUT BASIN (SEE DETAIL)	CW
SILT FENCE, STANDARD	SF	SILT BAG INLET	
SILT FENCE OUTLET/RIP RAP APRON/RIP RAP BASIN & ROCK SEDIMENT TRAP		PROTECTION HARDWARE CLOTH AND	
CONSTRUCTION ENTRANCE		GRAVEL INLET PROTECTION	
PERMANENT SOD	PS	TEMPORARY SEEDING	TS

DISTURBED ACREAGE **2.02 ACRES EXISTING UTILITY NOTE:** THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY STABILIZATION NOTE: ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. PROVIDE FINAL STABILIZATION THE CONTRACTOR SHALL DETERMINE THE EXACT FOR ALL DISTURBED AREAS. LOCATION OF ALL EXISTING UTILITIES BEFORE REFER TO THE LANDSCAPE COMMENCING ANY WORK, AND AGREES TO BE PLAN FOR SPECIFIC MATERIALS FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES / PLANTINGS. ANY DISTURBED WHICH MIGHT OCCUR DUE TO THE CONTRACTOR'S AREA NOT ADDRESSED IN THE FAILURE TO EXACTLY LOCATE AND PRESERVE ANY LANDSCAPE PLANS SHALL BE AND ALL UNDERGROUND UTILITIES.


EROSION CONTROL PH

12/22/23




Temporary Seeding Schedule

SCALE: NOT TO SCALE



Pipe Outlet Riprap Protection with Calculations

SCALE: NOT TO SCALE



C4.4

SW+ PROJECT:

DRAWN BY:

CHECKED BY:

EROSION

CONTROL

DETAILS

REVISION HISTORY

12/22/23

MOUNT PLEASANT, SC

843.884.1667

GREENVILLE, SC

864.298.0534

SUMMERVILLE, SC

843.972.0710

SPARTANBURG, SC

864.272.1272

CHARLOTTE, NC

980.312.5450

WWW.SEAMONWHITESIDE.COM

SEAMON,

WHITESIDE &

ASSOCIATES, INC.

NO. C-2466

048282

NGINEER

SECTION A: SELF-INSPECTION Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record. Inspect (during normal business hours) (1) Rain gauge Daily rainfall amounts If no daily rain gauge observations are made during weekend o good working holiday periods, and no individual-day rainfall information i available, record the cumulative rain measurement for those up ttended days (and this will determine if a site inspection i needed). Days on which no rainfall occurred shall be recorded a "zero." The permittee may use another rain-monitoring dev approved by the Division. (2) E&SC At least once pe 2. Date and time of the inspection, 7 calendar days and within 24 3. Name of the person performing the inspection. Indication of whether the measures were operating event ≥ 1.0 inch in Description of maintenance needs for the measure. Description, evidence, and date of corrective actions taken. Identification of the discharge outfalls inspected, (3) Stormwater At least once per discharge 7 calendar days outfalls (SDCs) and within 24 Date and time of the inspection, 3. Name of the person performing the inspection, hours of a rain 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 24 hours 5. Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taker 7 calendar days of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has lef hours of a rain the site limits, Description, evidence, and date of corrective actions taken, and An explanation as to the actions taken to control future stream has visible increased turbidity from the construction wetlands onsite 7 calendar days and within 24 activity, then a record of the following shall be made: Description, evidence and date of corrective actions taken, and hours of a rain event > 1.0 inch in | 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit. (6) Ground After each phase 1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing measures activity, construction or redevelopment, permanen ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

SELE-INSPECTION, RECORDIFIEDING AND REPORTING

SELF-INSPECTION, RECORDKEEPING AND REPORTING SECTION C: REPORTING 1. Occurrences that Must be Reported

SECTION B: RECORDKEEPING

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

(a) Each E&SC measure has been installed Initial and date each E&SC measure on a copy and does not significantly deviate from the of the approved E&SC plan or complete, date locations, dimensions and relative elevations | and sign an inspection report that lists each E&SC measure shown on the approved E&SC shown on the approved E&SC plan. plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial (b) A phase of grading has been completed. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the nstruction phase. (c) Ground cover is located and installed Initial and date a copy of the approved E&SC

in accordance with the approved E&SC plan or complete, date and sign an inspection port to indicate compliance with approved ound cover specifications.

(d) The maintenance and repair omplete, date and sign an inspection report. requirements for all E&SC measures have been performed. e) Corrective actions have been taken Initial and date a copy of the approved E&S0 to E&SC measures. plan or complete, date and sign an inspection report to indicate the completion of the rrective action.

2. Additional Documentation to be Kept on Site In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

(a) This General Permit as well as the Certificate of Coverage, after it is received. (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records. 3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period

of three years after project completion and made available upon request. [40 CFR 122.41] PART II, SECTION G, ITEM (4)

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

(a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items, (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,

(c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,

(d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and

(f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Permittees shall report the following occurrences (a) Visible sediment deposition in a stream or wetland.

with the conditions

of this permit that

environment[40

CFR 122.41(I)(7)]

may endanger

 They are 25 gallons or more, They are less than 25 gallons but cannot be cleaned up within 24 hours, They cause sheen on surface waters (regardless of volume), or They are within 100 feet of surface waters (regardless of volume).

(c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

(e) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800)

Reporting Timeframes (After Discovery) and Other Requirements (a) Visible sediment • Within 24 hours, an oral or electronic notification. deposition in a • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sedimentrelated causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. (b) Oil spills and Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and hazardous location of the spill or release. substances per Item 1(b)-(c) above (c) Anticipated A report at least ten days before the date of the bypass, if possible ovpasses [40 CFR The report shall include an evaluation of the anticipated quality and L22.41(m)(3)] effect of the bypass. (d) Unanticipated Within 24 hours, an oral or electronic notification bypasses [40 CFR . Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.

Within 24 hours, an oral or electronic notification

continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6). Division staff may waive the requirement for a written report on a case-by-case basis.

Within 7 calendar days, a report that contains a description of the

including exact dates and times, and if the noncompliance has not

been corrected, the anticipated time noncompliance is expected to

noncompliance, and its causes; the period of noncompliance,

NORTH CAROLINA Environmental Quality

| EFFECTIVE: 04/01/19

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet

Required Ground Stabilization Timeframes Stabilize within th many calendar Timeframe variations Site Area Description days after ceasing land disturbance (a) Perimeter dikes. swales, ditches, and None perimeter slopes (b) High Quality Water (HQW) Zones If slopes are 10' or less in length and are (c) Slopes steeper than not steeper than 2:1, 14 days are -7 days for slopes greater than 50' in length and with slopes steeper than 4:1 7 days for perimeter dikes, swales, (d) Slopes 3:1 to 4:1 ditches, perimeter slopes and HQW -10 days for Falls Lake Watershed 7 days for perimeter dikes, swales, itches, perimeter slopes and HQW Zones (e) Areas with slopes -10 days for Falls Lake Watershed unless flatter than 4:1 I there is zero slope

may not apply depending on site conditions and the delegated authority having jurisdiction.

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the

techniques in the table below: Temporary Stabilization Temporary grass seed covered with straw or
 Permanent grass seed covered with straw or other mulches and tackifiers other mulches and tackifiers Hydroseeding Geotextile fabrics such as permanent soil Rolled erosion control products with or without temporary grass seed

reinforcement matting Hydroseeding Appropriately applied straw or other mulch
 Shrubs or other permanent plantings covered Plastic sheeting with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion

 Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

Permanent Stabilization

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures Apply flocculants at the concentrations specified in the NC DWR List of Approved

PAMS/Flocculants and in accordance with the manufacturer's instructions. Provide ponding area for containment of treated Stormwater before discharging

Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids. Provide drip pans under any stored equipment.
 - Identify leaks and repair as soon as feasible, or remove leaking equipment from the Collect all spent fluids, store in separate containers and properly dispose as

hazardous waste (recycle when possible). Remove leaking vehicles and construction equipment from service until the problem

has been corrected. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum product

to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

waters unless no other alternatives are reasonably available.

Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes. Locate waste containers at least 50 feet away from storm drain inlets and surface

Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.

Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if

containers overflow. Dispose waste off-site at an approved disposal facility.

9. On business days, clean up and dispose of waste in designated waste containers. PAINT AND OTHER LIQUID WASTE

Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available. Contain liquid wastes in a controlled area. Containment must be labeled, sized and placed appropriately for the needs of site.

Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

Do not dump paint and other liquid waste into storm drains, streams or wetlands.

offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.

Install portable toilets on level ground, at least 50 feet away from storm drains,

streams or wetlands unless there is no alternative reasonably available. If 50 foot

Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.


EARTHEN STOCKPILE MANAGEMEN

Show stockpile locations on plans. Locate earthen-material stockpile areas at leas 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably

Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile. Provide stable stone access point when feasible.

Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

> NORTH CAROLINA Environmental Quality



CONCRETE WASHOUTS

Do not discharge concrete or cement slurry from the site. Dispose of, or recycle settled, hardened concrete residue in accordance with local

and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.

Install temporary concrete washouts per local requirements, where applicable. If a alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.

Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.

Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow. Locate washouts in an easily accessible area, on level ground and install a stone

entrance pad in front of the washout. Additional controls may be required by the approving authority. Install at least one sign directing concrete trucks to the washout within the project

limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary

products, follow manufacturer's instructions. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout

HERBICIDES, PESTICIDES AND RODENTICIDES Store and apply herbicides, pesticides and rodenticides in accordance with label

Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.

Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

Create designated hazardous waste collection areas on-site. Place hazardous waste containers under cover or in secondary containment 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground. ASSOCIATES, INC.

MOUNT PLEASANT, SC

843.884.1667

GREENVILLE, SC

864.298.0534

 $\mathsf{SUMMERVILLE}$, SC

843.972.0710

SPARTANBURG, SC

864.272.1272

CHARLOTTE, NC

980.312.5450

WWW.SEAMONWHITESIDE.COM

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING **EFFECTIVE: 04/01/19**

SW+ PROJECT: DRAWN BY: CHECKED BY:


REVISION HISTORY

DETAILS

12/22/23

EROSION CONTROL

C4.5



MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC

> SEAMON, WHITESIDE & : ASSOCIATES, INC. NO. C-2466



SW+ PROJECT: 12/22/23 CHECKED BY: **REVISION HISTORY**

SITE PLAN

DO NOT ENTER SIGN

HANDICAP PARKING

SIGN

Know what's below.
Call before you dig.

0 10 20

SCALE: 1" = 20'

C5.1

PROPERTY ZONING: GI-CZ (GENERAL INDUSTRIAL - CONDITIONAL


0.04 AC (2.20%)

1.29 AC (70.88%)

1 SPACE PER 400 SF GFA OR 5 SPACES MINIMUM = 5 SPACES

34 STALLS

- CONTRACTOR SHALL CAREFULLY EXAMINE ALL DOCUMENTS AND THE CONSTRUCTION SITE TO OBTAIN FIRST HAND KNOWLEDGE OF
- VISUALLY APPEALING SURFACE WITH A MINIMUM TOPSOIL LAYER
- ALL STRIPING AND SIGNS SHALL CONFORM WITH THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES LATEST EDITION. PARKING STALL STRIPING TO BE WHITE WITH BLUE HANDICAPPED
- . ALL HANDICAP PARKING SPACED AND ACCESSIBLE ROUTE SHALL CONFORM WITH THE AMERICAN WITH DISABILITY ACT DESIGN
- DIMENSIONS AND CURVE RADII ARE GIVEN TO FACE OF CURB, WHERE CURB AND GUTTER IS SHOWN. OTHERWISE DIMENSIONS ARE GIVEN TO THE EDGE OF PAVEMENT. CONTRACTOR IS TO COORDINATE WITH THE ARCHITECTURAL PLANS AS TO THE



33.000ft 8.000ft 10.568ft 1.022ft 8.500ft 1.00s 48.500ft

Know what's below.

Call before you dig.

SCALE: 1" = 20'

0 10 20

MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710

SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450

WWW.SEAMONWHITESIDE.COM

WHITESIDE & : ASSOCIATES, INC. NO. C-2466



REVISION HISTORY

VEHICLE STACKING & TURNING MOVEMENT

C5.2



MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC

> CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM

864.272.1272





38.250ft 8.333ft 11.250ft 1.393ft 8.333ft 6.00s 45.00°

SW+ PROJECT: 12/22/23 DRAWN BY:

CHECKED BY: **REVISION HISTORY**


FIRE PROTECTION PLAN

0 10 20 SCALE: 1" = 20'

Know what's below.

Call before you dig.

C5.3



MOUNT PLEASANT, SC 843.884.1667

MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 www.seamonwhiteside.com

SEAMON,
WHITESIDE &
ASSOCIATES, INC.
NO. C-2466

OF AUTHORITICAL

OF AUTHO



L WAVE AUTO SPA

SW+ PROJECT: 10772
DATE: 12/22/23
DRAWN BY: CPE
CHECKED BY: TLL

CHECKED BY: TLL
REVISION HISTORY


OVERALL GRADING AND DRAINAGE PLAN


C6.1


EXAMPLE: A12.56ME MEANS THAT THE SURFACE OF NEW ASPHALT IS TO BE AT ELEVATION 12.56 WHICH


SHOULD MATCH THE ELEVATION OF THE EXISTING ASPHALT SURFACE AT THE JOINT

JUNCTION BOX
















SEAMONWHITES.

MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM





SAL WAVE AUTO SPA

SW+ PROJECT: 10772
DATE: 12/22/23
DRAWN BY: CPE
CHECKED BY: TLL

REVISION HISTORY

DRAINAGE PROFILES

C6.2

BACKFLOW PREVENTION NOTES


- L. REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTION ASSEMBLY AS APPROVED BY TOWN OF ROLESVILLE AND INSTALLED BY CONTRACTOR DURING CONSTRUCTION. ASSEMBLY TO INSTALLED ABOVE GROUND WITHIN INSULATED ENCLOSURE PER TOWN OF ROLESVILLE REQUIREMENTS. ENCLOSURE TO BE LOCATED OUT OF SETBACK.
- 2. THERE SHALL BE NO TAPS, PIPING BRANCHES, UNAPPROVED BYPASS PIPING, HYDRANTS, FIRE DEPT. CONNECTION POINTS OR OTHER WATER USING APPURTENANCES CONNECTED TO THE SUPPLY LINE BETWEEN ANY WATER METER AND ITS REQUIRED BACKFLOW PREVENTER.
- 3. EACH REQUIRED BACKFLOW PREVENTION ASSEMBLY IS REQUIRED TO BE TESTED BY AN APPROVED CERTIFIED TESTER PRIOR TO PLACING THE WATER SYSTEM IN SERVICE AND YEARLY THEREAFTER. SUBMIT PASSING TEST REPORTS TO TOWN OF ROLESVILLE. 4. DUCTILE IRON, COPPER, OR OTHER METALLIC PIPING (NO PVC) IS TO BE USED WITHIN 5 FEET OF ALL BACKFLOW PREVENTION
- 5. TAMPER SWITCHES SHALL BE INSTALLED ON THE FIRE LINE BACKFLOW PREVENTION. INSTALL 3/4" CONDUIT FROM FIRE LINE BACKFLOW ENCLOSURE/VAULT TO BUILDING ALARM SYSTEM INSIDE BUILDING. COORDINATE WITH ELECTRICAL DRAWINGS AND ALARM SYSTEM MANUFACTURER.

WATER SERVICE NOTES


- 1. 2" WATER METER FOR DOMESTIC SERVICE FURNISHED AND INSTALLED BY (CONTRACTOR/UTILITY) IN BELOW GRADE CONCRETE VAULT PREPARED BY CONTRACTOR IN ACCORDANCE WITH UTILITY DEPARTMENT STANDARDS. SEÉ DETAILS.
- 2. 3/4" WATER METER FOR IRRIGATION SERVICE FURNISHED AND INSTALLED BY (CONTRACTOR/UTILITY) IN BELOW GRADE CONCRETE VAULT PREPARED BY CONTRACTOR IN ACCORDANCE WITH UTILITY DEPARTMENT STANDARDS. SEE DETAILS.

STANDARD SEWER PLAN NOTES

- 1. FOR PROJECT SURVEY INFORMATION INCLUDING VERTICAL DATUM AND BENCHMARK LOCATIONS, SEE "PROJECT SURVEY INFORMATION AND CONTRACTOR VERIFICATION REQUIREMENTS" ON SHEET C1.0.
- 2. PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING EXISTING CONDITIONS, INCLUDING BUT NOT LIMITED TO TOPOGRAPHIC, TREE, STORM DRAINAGE FACILITIES, AND ALL UTILITIES. EXISTING UTILITIES SHOWN ARE APPROXIMATE AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ENGINEER. THEREFORE, THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE EXACT VERTICAL AND HORIZONTAL LOCATIONS OF ALL EXISTING UTILITIES. ANY DISCREPANCIES OR CONFLICTS IDENTIFIED DURING VERIFICATION OF EXISTING CONDITIONS AND UTILITIES SHALL BE REPORTED TO THE OWNER AND ENGINEER. ANY COSTS ASSOCIATED WITH CORRECTIVE WORK OR DAMAGES THAT ARE A RESULT OF THE CONTRACTOR NOT VERIFYING EXISTING CONDITIONS AND THE EXACT VERTICAL AND HORIZONTAL LOCATION OF ALL EXISTING UTILITIES WILL BE THE CONTRACTOR'S RESPONSIBILITY.
- 3. MANHOLE COVERS ARE NOT ALLOWED WITHIN CURB AND GUTTER AND ARE TO BE INSTALLED COMPLETELY WITHIN OR COMPLETELY OUT OF PAVED AREAS (INCLUDING SIDEWALKS).
- 4. SEWER MANHOLE CONES ADJACENT TO CURB AND/OR SIDEWALK RAMPS SHALL BE ROTATED TO LOCATE MANHOLE FRAME AND COVER AWAY FROM THE SIDEWALK RAMPS AND CURBS.
- 5. REFER TO THE SEWER AUTHORITY'S STANDARD NOTES, DETAILS, AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS AND PROCEDURES, INCLUDING WATERTIGHT MANHOLE LOCATIONS.
- 6. REFER TO SEWER DETAIL SHEETS AND SEWER PROFILE SHEETS FOR DETAILS AND ANY ADDITIONAL SEWER SYSTEM INFORMATION.



SCALE: 1" = 10'



ASSOCIATES, INC.

MOUNT PLEASANT, SC 843.884.1667

GREENVILLE, SC 864.298.0534

SUMMERVILLE, SC

843.972.0710

SPARTANBURG, SC

864.272.1272

CHARLOTTE, NC

980.312.5450

WWW.SEAMONWHITESIDE.COM



SW+ PROJECT: DATE: 12/22/23 DRAWN BY: CHECKED BY:


REVISION HISTORY


UTILITY PLAN AND **PROFILES**

EXISTING UTILITY NOTE:

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING ANY WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR DUE TO THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.







WWW.SEAMONWHITESIDE.COM



AL WAVE AUTO SPA ROLESVILLE, NC

SW+ PROJECT: 10772
DATE: 12/22/23
DRAWN BY: CPE
CHECKED BY: TLL

REVISION HISTORY


UTILITY PROFILES

EXISTING UTILITY NOTE:

AND ALL UNDERGROUND UTILITIES.


0 10 20 SCALE: 1" = 20'

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING ANY WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR DUE TO THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY




-0+25





C8.1



performance evaluation.

Trooper

Trooper

Grit Oil Interceptor

Grit Oil Interceptor Model GO

Sizes 500 thru 2000

DRN ENG DWG. NO.

3" PVC DRAIN FROM

RPCA CERTIFED PLANT

ELEVATION

Specifications

Engineering Data

CONCRETE:

DIFFUSION INLET
BAFFLE WEIR

Class I/II concrete with design strength of 4500 PSI at 28 days. Unit is of monolithic

with sectional riser to required depth.

REINFORCEMENT: Grade 60 reinforced with steel rebar conforming

Interceptor is structurally and hydraulically engineered conforming to Uniform Plumbing Code. Nominal total liquid capacity

and oil holding capacity as indicated. Recommended for flow rates

of 5 to 180 GPM (consult Park for proper sizing). Manufacturer

shall submit performance calculations for oil & water seperation certified by a licensed professional engineer. Field excavation and preparation shall be completed prior to delivery of interceptor.

resistant.

construction at floor and first stage of wall

to ASTM A615 on required centers or equal.

& lifting handles. All materials to be corrosion

1/4" thick nonskid floor plate, boltdown,

Access frame & cover shall be fabricated with min.

INT. COATING

PROJECT:

CUSTOMER:

ENGINEER:

ORDER #:

DATE 2018

GUARANTEED PERFORMANCE FOR CODE MAXIMUM OIL CONCENTRATION (SANITARY SEWER 400 PPM, STORM SEWER 15 PPM) © ParkUSA. ALL RIGHTS RESERVED.

— CORRELATOR PIT TO

CONVEYOR PIT

ENTRANCE DETAIL - REAR WHEEL PUSH

NOT TO SCALE

TECHNICAL CRITERIA

REAL-WHEEL PUSH - ENTRANCE


SHJ CONSTRUCTION GROUP


DATE OF PLANS

03/15/2023

NOT TO SCALE

MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM





SW+ PROJECT: 12/22/23 DRAWN BY: CHECKED BY: **REVISION HISTORY**

CONSTRUCTION DETAILS

C8.2

10' MULTI-USE PATH SECTION

(11) SCALE: NOT TO SCALE

24" ROLL CURB AND GUTTER
SCALE: NOT TO SCALE

N.C.D.O.T. STANDARD SPECIFICATIONS AND NORTH

PAVEMENT-MARKING

SCALE: NOT TO SCALE

CAROLINA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

MOUNT PLEASANT, SC LOWEST SIGN 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM

BOTTOM OF


----FACE

CAST-IN-PLACE

AND GUTTER

L CONCRETE CURB


SEAMON, WHITESIDE & ASSOCIATES, INC. NO. C-2466



SW+ PROJECT: 12/22/23 DRAWN BY: CHECKED BY: **REVISION HISTORY**

CONSTRUCTION **DETAILS**

C8.3



C8.4

12/22/23



843.884.1667
GREENVILLE, SC
864.298.0534
SUMMERVILLE, SC
843.972.0710
SPARTANBURG, SC
864.272.1272
CHARLOTTE, NC
980.312.5450
WWW.SEAMONWHITESIDE.COM





ME L. LINING

TIDAL WAVE AUTO S

SW+ PROJECT: 10772
DATE: 12/22/23
DRAWN BY: CPE
CHECKED BY: TLL

REVISION HISTORY

CONSTRUCTION DETAILS

PROJEC	CT INFORMATION
ENGINEERED PRODUCT MANAGER	
ADS SALES REP	
PROJECT NO.	





TWAS S MAIN ROLESVILLE, NC, USA

SC-160LP STORMTECH CHAMBER SPECIFICATIONS

- 1. CHAMBERS SHALL BE STORMTECH SC-160LP.
- 2. CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 4. CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- 5. THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- 6. CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- 7. REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 1.5"
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 400 LBS/FT/%. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- 8. ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
 - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
 - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- 9. CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-160LP SYSTEM

- STORMTECH SC-160LP CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A
 PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- 2. STORMTECH SC-160LP CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-160LP CONSTRUCTION GUIDE".
- 3. FOUNDATION STONE AND EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE; AASHTO M43 #3,357, 4, 467, 5, 56, OR 57.
- 4. THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- 5. THE DEPTH OF FOUNDATION STONE SHALL BE DETERMINED BASED ON THE SUBGRADE BEARING CAPACITY PROVIDED BY THE SITE DESIGN ENGINEER.
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES CONCERNING CHAMBER FOUNDATION DESIGN AND SUBGRADE BEARING CAPACITIES TO THE SITE DESIGN ENGINEER
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- 8. CHAMBERS SHALL BE INSTALLED "TOE TO TOE". NO ADDITIONAL SPACING BETWEEN ROWS IS REQUIRED.
- STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - STONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- 10. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

NOTES FOR CONSTRUCTION EQUIPMENT

- 1. THE USE OF CONSTRUCTION EQUIPMENT OVER SC-160LP CHAMBERS IS LIMITED:
 - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
 - NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-160LP CONSTRUCTION GUIDE".
 - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-106LP CONSTRUCTION GUIDE".
- 2. FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.


1	PROPOSED LAYOUT	PROPOSED ELEVA	ATIONS:				*INVERT ABOVE B	SASE OF CHAMBER		
	STORMTECH SC-160LP CHAMBERS	MAXIMUM ALLOWABLE GRADE (TOP OF PAVEME	NT/UNPAVED): 399.4		ITEM ON LAYOUT	DESCRIPTION	INVER	RT* MAX FLOW		
	STORMTECH SC-160LP END CAPS STONE ABOVE (in)		TRAFFIC): 391 12	2 2MANIFOLD		12" x 8" REDUCING CONCENTRIC MOLDED FITTINGS (12" PIPE)	-1.17		1	
6	STONE BELOW (in)	MINIMUM ALLOWABLE GRADE (TOP OF RIGID CO	DNCRETE PAVEMENT): 390.62	2		12" x 8" REDUCING CONCENTRIC MOLDED FITTINGS (8" PIPE) 18" x 8" ADS N-12 (18" PIPE)	0.96 -4.13		_	≤
40	STONE VOID INSTALLED SYSTEM VOLUME (CF)	MINIMUM ALLOWABLE GRADE (BASE OF FLEXIBL TOP OF STONE:	_E_PAVEMENT): 390.62 389.99	2 MANIFOLD 5	B	18" x 8" ADS N-12 (8" PIPE)	0.96	5"	J Z Sn	R S
8351	(PERIMETER STONE INCLUDED)	TOP OF SC-160LP CHAMBER: 8" x 8" BOTTOM MANIFOLD INVERT:	389.45	5 MANIFOLD	<u> </u>	8" x 8" BOTTOM MANIFOLD, MOLDED FITTINGS 15" x 8" ADS N-12 (15" PIPE)	0.96 -2.58		MAIN NC, USA	DRAWN: KH
	(BASE STONE INCLUDED)	8" ISOLATOR ROW PLUS INVERT:	1 300.5		0	15" x 8" ADS N-12 (8" PIPE)	0.96	5"	S H	품 공
	SYSTEM AREA (SF) SYSTEM PERIMETER (ft)	8" ISOLATOR ROW PLUS INVERT: 8" ISOLATOR ROW PLUS INVERT:		3 CONCRETE STRUCTURE 3 CONCRETE STRUCTURE		OCS (DESIGN BY ENGINEER / PROVIDED BY OTHERS)		3.4 CFS OUT	WAS	
0 10.0		8" BOTTOM CONNECTION INVERT:	388.53	3W/WEIR	F	(DESIGN BY ENGINEER / PROVIDED BY OTHERS)		4.4 CFS IN	TWA	
		18" x 8" BOTTOM MANIFOLD INVERT (8" PIPE): 15" x 8" BOTTOM MANIFOLD INVERT (8" PIPE):	388.53	3 CONCRETE STRUCTURE 3 W/WEIR	G	(DESIGN BY ENGINEER / PROVIDED BY OTHERS)		5.9 CFS IN	_ Z _ Z	
		12" x 8" BOTTOM MANIFOLD INVERT (8" PIPE): BOTTOM OF SC-160LP CHAMBER:	388.5	의CONCRETE STRUCTURE	н	(DESIGN BY ENGINEER / PROVIDED BY OTHERS)		0.7 CFS IN	1	#
		12" x 8" BOTTOM MANIFOLD INVERT (12" PIPE):	388.3	5 W/WEIR UNDERDRAIN		4" ADS N-12 DUAL WALL PERFORATED HDPE UNDERDRAIN		0.7 01 0 114	-	
		15" x 8" BOTTOM MANIFOLD INVERT (15" PIPE): 18" x 8" BOTTOM MANIFOLD INVERT (18" PIPE):	388.2 ² 388.1 ²	4		A ADO N-12 DONE WALL! EN ONNIED HID E ONDENDININ	I	I	-	DATE: PROJECT
		UNDERDRAIN INVERT:	387.99	5						A R
		BOTTOM OF STONE:	387.99	5						
	-			223.87' ———			-			
	<u> </u>			213.97'						2
				213.31						
	<u> </u>	 								
		 					† †			<u> </u>
	I									Į,
	' Carlo	 								× d
										2
		 								Ľ
		 								
										Σ
	/	+++								Ŭ
	/ 🚇									Ē
	_ / ' 📜									Z Z
	B	 					18.		© ⊆)TO
										
	c C						_ A 88 65.7		U	E ≷
	C H								, o	stem
	C H								0	System 54 - www
	C H								ָ בַּרָ .	er System
	C H I D								ָ בַּרָ .	mber System
	C H I D E								ָ בַּרָ .	:namber System
	C H I D E			. <u> </u>					ָ בַּרָ .	Chamber System 888-892-2694 www
	C H I D								ָ בַּרָ .	Chamber 888-892-26
	C H I D E								StormTe	40 Chamber System
	C H I D E								StormTe	Chamber 888-892-26
	C H I D E								StormTe	Chamber 888-892-26
	C H I D E								StormTe	Chamber 888-892-26
	C H I D E								StormTe	Chamber 888-892-26
	C H I D E								StormTe	Chamber 888-892-26
	C H I D E								StormTe	Chamber 888-892-26
	ISOLATOR ROW PLUS								StormTe	Chamber 888-892-26
									StormTe	Chamber 888-892-26
***	ISOLATOR ROW PLUS (SEE DETAIL/TYP 2 PLACES)	LIS125 WOVEN GEOTEXTILE OVER REDDING	NOTES MANIFOLD SIZE TO BE DETER	RMINED BY SITE DESIGN ENGIN	JEER SEE TE	CH NOTE #6 32 FOR MANIFOLD SIZING GUIDANCE	A A B 80.		StormTe	Chamber 888-892-26
	ISOLATOR ROW PLUS (SEE DETAIL/TYP 2 PLACES) PLACE MINIMUM 12.50' OF ADSPL STONE AND UNDERNEATH CHAM	LUS125 WOVEN GEOTEXTILE OVER BEDDING MBER FEET FOR SCOUR PROTECTION AT ALL	 MANIFOLD SIZE TO BE DETER DUE TO THE ADAPTATION OF 	RMINED BY SITE DESIGN ENGIN THIS CHAMBER SYSTEM TO SE	IEER. SEE TE	ECH NOTE #6.32 FOR MANIFOLD SIZING GUIDANCE.	A A B 80.	DARD MANIFOLD	StormTe	Chamber 888-892-26
	ISOLATOR ROW PLUS (SEE DETAIL/TYP 2 PLACES) PLACE MINIMUM 12.50' OF ADSPL		 MANIFOLD SIZE TO BE DETER DUE TO THE ADAPTATION OF COMPONENTS IN THE FIELD 				D COUPLE ADDITIONAL PIPE TO STANK		StormTe	20 40 Chamber
	ISOLATOR ROW PLUS (SEE DETAIL/TYP 2 PLACES) PLACE MINIMUM 12.50' OF ADSPL STONE AND UNDERNEATH CHAM		MANIFOLD SIZE TO BE DETER DUE TO THE ADAPTATION OF COMPONENTS IN THE FIELD. THE SITE DESIGN ENGINEER THIS CHAMBER SYSTEM WAS DETERMINING	MUST REVIEW ELEVATIONS AN DESIGNED WITHOUT SITE-SPE	ND IF NECES ECIFIC INFOR	SARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REQUENCED ON SOIL CONDITIONS OR BEARING CAPACITY. THE SITE	D COUPLE ADDITIONAL PIPE TO STAND JIREMENTS ARE MET. DESIGN ENGINEER IS RESPONSIBLE F	FOR	4640 TRUEMAN BLVD HILLIARD, OH 43026 1-800-733-7473	0 20 40 Chamber
	ISOLATOR ROW PLUS (SEE DETAIL/TYP 2 PLACES) PLACE MINIMUM 12.50' OF ADSPL STONE AND UNDERNEATH CHAM		 MANIFOLD SIZE TO BE DETER DUE TO THE ADAPTATION OF COMPONENTS IN THE FIELD. THE SITE DESIGN ENGINEER THIS CHAMBER SYSTEM WAS DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDED. 	MUST REVIEW ELEVATIONS AN B DESIGNED WITHOUT SITE-SPE PROVIDING THE BEARING CAP	ND IF NECES: ECIFIC INFOR PACITY OF TH		COUPLE ADDITIONAL PIPE TO STANDUREMENTS ARE MET. DESIGN ENGINEER IS RESPONSIBLE FOR DECREASED ONCE THIS INFORMATION.	FOR ON IS	4640 TRUEMAN BLVD HILLIARD, OH 43026 1-800-733-7473	TH 0 Chamber 1

ACCEPTABLE FILL MATERIALS: STORMTECH SC-160LP CHAMBER SYSTEMS

	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 14" (355 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}

DI EASE NOTE


- 1. THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- 2. STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- 3. WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- 4. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



NOTES:

- 1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 2. CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- 3. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 1.5"
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 400 LBS/FT/%. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.





SC-160LP ISOLATOR ROW PLUS DETAIL


INSPECTION & MAINTENANCE

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
 - A. INSPECTION PORTS (IF PRESENT)
 - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
 - A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 - A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
 - A.4. LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
 - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
 - B. ALL ISOLATOR PLUS ROWS
 - B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
 - B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
 - i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
 - ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
 - A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED
 - B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
 - C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

NOTES


- 1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
- 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.


ROLESVILLE, NC, USA
DRAWN: KH
CHECKED: N **TWAS S MAIN StormTech**® Chamber System 4640 TRUEMAN BLVD HILLIARD, OH 43026 1-800-733-7473 SHEET 4 OF 5





SC-160LP TECHNICAL SPECIFICATION

NTS









NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)
CHAMBER STORAGE

CHAMBER STORAGE
MINIMUM INSTALLED STORAGE*
WEIGHT

25.0" X 12.0" X 85.4" (635 mm X 305 mm X 2169 mm) 6.85 CUBIC FEET (0.19 m³)


16.0 CUBIC FEET (0.45 m³) 24.0 lbs. (10.9 kg)

*ASSUMES 6" (152 mm) ABOVE, 6" (152 mm) BELOW, AND STONE BETWEEN CHAMBERS WITH 40% STONE POROSITY.

PART#	STUB	Α
SC160EPP	6" (150 mm)	0.66" (16 mm)
SCIOUEPP	8" (200 mm)	0.80" (20 mm)
SC160EPP08	8" (200 mm)	0.96" (24 mm)

ALL STUBS ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

NOTE: ALL DIMENSIONS ARE NOMINAL



TWAS S MAIN

ROLESVILLE, NC, USA

DATE: DATE: DESCRIPTION

PROJECT #: CHECKED: NV

StormTech® Chamber System

540 I KUEMAN BLVD ILLIARD, OH 43026 800-733-7473



SHEET

5 OF 5

GENERAL NOTES:

- 1. SEE EROSION CONTROL PLANS PLANS [SHEETS C4.1 C4.3] FOR SILT FENCE LOCATIONS, TREE
- PROTECTION ZONES AND BARRICADES, AND ADDITIONAL NOTES AND DETAILS. 2. FOR TREE REMOVALS, PLEASE REFER TO SHEETS C3.1.
- 3. FOR REQUIRED TREE MITIGATION AND DEVELOPMENT INCHES PER THE TOWN OF ROLESVILLE ZONING
- ORDINANCE, PLEASE REFER TO SHEET L1.1 FOR PLANT SCHEDULE QUANTITY AND SIZES. 4. THE OVERALL PLANT QUANTITY FOR THE ENTIRE SITE CAN BE FOUND ON THE MASTER PLAN SCHEDULE,
- SEE SITE PLAN [C5.1] FOR SITE LABELS, INFORMATION AND DETAILS.
- CONTRACTOR TO CONTACT CIVIL ENGINEER OR LANDSCAPE ARCHITECT REGARDING ANY SITE WORK MODIFICATIONS FROM THESE PLANS PRIOR TO CHANGES IN THE FIELD. CONTACT: 980-312-5450

US HWY 401 / LOUISBURG ROAD (317 LF)							
	STREET BUFFER	PLANTINGS REQUIRED	PLANTINGS PROVIDED				
MINIMUM BUFFER WIDTH	30' MIN.						
CANOPY TREE	1 TREE PER 40 LF	1	1				
UNDERSTORY TREE*	2 TREES PER 40 LF	14	14				
*UNDERSTORY TREES SHALL BE USI			<u> </u>				

PLANT SCHED	ULE HWY 4	01 BUF	FER					
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	HEIGHT	SPREAD	SPACING	REMARKS
TREES								
	QUEP	1	QUERCUS PALUSTRIS / PIN OAK	2.5" CAL	8` MIN	4`-6`	AS SHOWN	FWF, SP
UNDERSTOR	Y TREES							
+	CERO	2	CERCIS CANADENSIS `OKLAHOMA` / OKLAHOMA REDBUD	1.5" CAL	8` MIN	8,	AS SHOWN	FWF, SP
Section of the sectio	CHIV	7	CHIONANTHUS VIRGINICUS / WHITE FRINGETREE	1.5" CAL	8` MIN	8,	AS SHOWN	FWF, SP
	MAGS	5	MAGNOLIA X SOULANGIANA / SAUCER MAGNOLIA	1.5" CAL	8, WIN	8.	AS SHOWN	MS, FWF, SP

GRAND PARK DRIVE (275 LF)						
	STREET BUFFER	PLANTINGS REQUIRED	PLANTINGS PROVIDED			
MINIMUM BUFFER WIDTH	10' MIN.					
CANOPY TREE	1 TREE PER 60 LF	5	6 (1 PROPOSED TREE, 5 EX. TREES TO REMAIN)			

PLANT SCHED	ULE GRAN	D PARK	DRIVE					
SYMBOL	CODE		BOTANICAL / COMMON NAME	SIZE	HEIGHT	SPREAD	SPACING	REMARK S
TREES		•			•			
$\overline{\bigcirc}$	QUEP	1	QUERCUS PALUSTRIS / PIN OAK	2.5" CAL	8. WIN	4`-6`	AS SHOWN	FWF, SP

OPEN SPACE

HAVE 3" OF DYED BROWN OR BLACK WOOD MULCH WITH EDGING AS

ALL RIVER ROCK SHALL BE 4"-6" MINIMUM IN DIAMETER AND SHALL BE

AN UNDERGROUND IRRIGATION SYSTEM, SHALL BE INSTALLED AND SHALL

COMPLY WITH ALL LOCAL MUNICIPAL CODES AND REGULATIONS AND ALSO COMPLY WITH THE LATEST NATIONAL ELECTRIC CODE RULES FOR

IF THERE IS NO PLANT BED AGAINST THE CAR WASH TUNNEL, VAC

HOUSE(S), OR DUMPSTER ENCLOSURE, THEN THERE SHALL BE A 18 INCH

REQUIRED. NO PINE STRAW MULCH WILL BE ALLOWED.

UNDERLAIN WITH LANDSCAPING FABRIC.


ALL ELECTRIC WORKS AND MATERIALS.

MINIMUM STRIP OF RIVER ROCK INSTALLED.

- SITE AREA = 79,279.2 SF OPEN SPACE REQUIREMENTS = 5% OF TOTAL SITE AREA
- OPEN SPACE REQUIRED = 3,964 SF OPEN SPACE PROVIDED = 4,293 SF

PLANT SCHE	DULE		
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME
TREES		_	
(D)	ACRO	3	ACER RUBRUM `OCTOBER GLORY` TM / OCTOBER GLORY MAPLE
	QUEP	6	QUERCUS PALUSTRIS / PIN OAK
UNDERSTO	RY TREES	·	
+	CERO	2	CERCIS CANADENSIS `OKLAHOMA` / OKLAHOMA REDBUD
**************************************	CHIV	7	CHIONANTHUS VIRGINICUS / WHITE FRINGETREE
	MAGS	5	MAGNOLIA X SOULANGIANA / SAUCER MAGNOLIA
SHRUBS			
•	ABES	33	ABELIA X GRANDIFLORA `SHERWOODII` / DWARF ABELIA
(·)	AZAF	22	AZALEA INDICA `FORMOSA` / FORMOSA AZALEA
) + }	ILCB	30	ILEX CORNUTA 'BURFORDII NANA' / DWARF BURFORD HOLLY
£+3	LCRR	27	LOROPETALUM CHINENSE RUBRUM `RUBY` / DWARF RUBY FRINGE FLOWE
GRASSES	1	-	•
+	MUHL	54	MUHLENBERGIA FILIPES / SWEETGRASS
GROUND C	OVERS		
	LMBB	422	LIRIOPE MUSCARI `BIG BLUE` / BIG BLUE LILYTURF
SOD/SEED	10 V	•	<u> </u>


SOD2 26,904 SF CYNODON DACTYLON `TIFTUF` / TIFTUF BERMUDA GRASS







MOUNT PLEASANT, SC 843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM





SW+ PROJECT: 10772 12/22/23 DRAWN BY: CHECKED BY: **REVISION HISTORY**

LANDSCAPE PLAN

L1.0

IT IS THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR TO VERIFY THAT EACH EXCAVATED TREE OR SHRUB PIT WILL PERCOLATE (DRAIN) PRIOR TO ADDING TOPSOIL AND INSTALLING TREES OR SHRUBS. THE LANDSCAPE CONTRACTOR SHALL FILL THE BOTTOM OF HOLES WITH SIX (6) INCHES OF WATER. THIS WATER SHOULD PERCOLATE WITHIN A TWENTY-FOUR (24) HOUR PERIOD. IF WATER DOESN'T PERCOLATE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLING PLANTS. SHOULD THE LANDSCAPE CONTRACTOR ENCOUNTER UNSATISFACTORY SURFACE OR SUBSURFACE DRAINAGE

ARCHITECT IN WRITING OF THE CONDITIONS PRIOR TO INSTALLING THE PLANTS. OTHERWISE, THE LANDSCAPE CONTRACTOR WARRANTS THAT THE PLANTING AREAS ARE SUITABLE FOR PROPER GROWTH AND DEVELOPMENT OF THE PLANTS TO BE INSTALLED THE LANDSCAPE CONTRACTOR WILL BE RESPONSIBLE FOR STAKING AND LAYOUT OF PLANTINGS ON THIS PROJECT. THE

JEOPARDIZE THE HEALTH AND VIGOR OF THE PLANTS, THE LANDSCAPE CONTRACTOR MUST ADVISE THE LANDSCAPE

CONDITIONS, SOIL DEPTH, LATENT SOILS, HARD PANS, STEAM OR OTHER UTILITY LINES OR OTHER CONDITIONS THAT WILL

LANDSCAPE ARCHITECT OR OWNER SHALL BE ADVISED WHEN STAKES ARE READY FOR INSPECTION ON VARIOUS PLANTING AREAS. ALL LAYOUT WORK SHALL BE INSPECTED AND APPROVED BY THE LANDSCAPE ARCHITECT AND OWNER PLANT MATERIAL QUANTITIES PROVIDED IN THE PLANT SCHEDULE ARE FOR REFERENCE ONLY AND THE LANDSCAPE

CONTRACTOR IS RESPONSIBLE FOR THE ACTUAL PLANT MATERIAL COUNTS. DISCREPANCIES BETWEEN QUANTITIES SHOWN ON THE PLANTING PLAN AND THOSE IN THE PLANT SCHEDULE SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT FOR CLARIFICATION. IF CLARIFICATION OF DISCREPANCIES FROM THE LANDSCAPE ARCHITECT IS NOT POSSIBLE, THEN QUANTITIES SHOWN ON THE PLANTING PLAN SHALL TAKE PRECEDENCE.

REQUIREMENTS FOR THE MEASUREMENTS, BRANCHING, GRADING, QUALITY, BALLING AND BURLAPPING OF PLANTS IN THE PLANT LIST SHOULD FOLLOW OR EXCEED THE STANDARDS CURRENTLY RECOMMENDED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC. IN THE AMERICAN STANDARD FOR NURSERY STOCKS (ANSI Z-60.1). UNLESS OTHERWISE SPECIFIED, ANY SIZE SPECIFIED SHALL BE CONSIDERED MINIMUM. MINIMUMS FOR HEIGHT, SPREAD, OR CALIPER SHALL TAKE PRECEDENT OVER A SPECIFIED CONTAINER SIZE.

ALL PLANTS SHALL HAVE A WELL FORMED HEAD WITH MINIMUM CALIPER, HEIGHT AND SPREAD OF THE SIDE BRANCHES AS SHOWN ON THE PLANT LIST. TRUNKS SHALL BE UNDAMAGED AND SHAPE SHALL BE TYPICAL OF THE SPECIES. MEASUREMENT OF CONIFER HEIGHT SHALL INCLUDE NOT MORE THAN FIFTY (50) PER CENT OF THIS YEARS' VERTICAL

GROWTH (TOP CANDLE). NO EXCAVATION OR PLANTING PIT SHALL BE LEFT UNATTENDED OVERNIGHT.

12. REMOVE BURLAP/STRAPPING AND WIRE BASKET FROM TOP 1/3 OF ROOT BALL ON TREES. 13. REMOVE PAPER, PLASTIC OR METAL AROUND ROOT BALLS OF SHRUBS.

14. DO NOT WRAP TREES.

15. WATER ALL PLANT MATERIAL IMMEDIATELY AFTER PLANTING.

16. TREE GUYING MATERIAL SHALL BE 'ARBOR-TIE' OR EQUIVALENT. 17. ALL PLANT BEDS TO BE MULCHED WITH 4" OF DOUBLE SHREDDED HARDWOOD MULCH UNLESS OTHERWISE SPECIFIED. 18. ALL AREAS OF PLANTING. INCLUDING AREAS OF GRASS SEEDING AND SOD. SHALL BE GRADED TO PROVIDE POSITIVE DRAINAGE AND SHALL BE PROVIDED APPROPRIATE SOIL FOR THE PROPOSED PLANTINGS, SEE SOIL NOTES.

ALL EXISTING VEGETATION WITHIN AREAS TO BE PLANTED, SODDED AND/OR SEEDED SHALL BE REMOVED PRIOR TO PLANTING, SODDING, AND SEEDING. ALL AREAS INDICATED TO BE GRASS SEED SHALL BE SEEDED PER GRASSING SPECIFICATIONS FOR PERMANENT STABILIZATION.

. ALL DISTURBED AREAS NOT SPECIFICALLY CALLED OUT ON THIS PLAN SHALL BE SEEDED PER THE PROVIDED SEEDING SCHEDULE. ALL DISTURBED NATURAL AREAS SHALL BE MULCHED (SEE MULCH SPECIFICATIONS). DRAINAGE TO BE PROVIDED FOR ALL ABOVE GROUND PLANTERS.

PLANTINGS SHALL BE PRUNED TO CONFORM WITH THE REQUIREMENTS OF ALL AUTHORITIES HAVING JURISDICTION, INCLUDING BUT NOT LIMITED TO THE CITY, COUNTY, STATE AND FEDERAL REQUIREMENTS.

THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING UP THE SITE AT THE COMPLETION OF THE PROJECT AND SHALL MAINTAIN THE SITE IN A REASONABLY NEAT AND CLEAN STATE THROUGHOUT THE INSTALLATION PROCESS. STREETS AND PAVED AREAS SHALL BE CLEANED REGULARLY TO REMOVE CONSTRUCTION MATERIALS AND OTHER DEBRIS RESULTING FROM WORK OF THE PROJECT.

REPLACEMENTS OF DEAD OR UNSATISFACTORY MATERIAL SHALL BE MADE AS SPECIFIED IN THE PLANT LIST. THE OWNER OR LANDSCAPE ARCHITECT SHALL INSPECT REPLACED PLANTS WHEN ALL REPLACEMENTS HAVE BEEN MADE. REPLACEMENTS ARE TO BE ALIVE AND IN A HEALTHY CONDITION WHEN THE REPLACEMENTS ARE COMPLETE. REPLACEMENTS ARE NOT SUBJECT TO AN ADDITIONAL GUARANTEE, BUT THE LANDSCAPE CONTRACTOR SHALL CONSULT WITH THE LANDSCAPE ARCHITECT ON REASON FOR PLANT DECLINE/DEATH AND HOW TO AVOID FUTURE INSTANCES.

SHOULD THE LANDSCAPE CONTRACTOR NOT MAKE REPLACEMENTS IN A SATISFACTORY AND TIMELY FASHION IN ACCORD WITH THE PLANTING NOTES, THE OWNER, AFTER PROPER NOTIFICATION TO THE LANDSCAPE CONTRACTOR MAY UTILIZE THE FUNDS OF THE RETAINAGE TO HAVE THE REPLACEMENTS MADE IN ACCORDANCE WITH THE SPECIFICATIONS BY ANOTHER CONTRACTOR.

FOR EACH UNAMENDED SOIL TYPE, FURNISH SOIL ANALYSIS AND A WRITTEN REPORT BY A QUALIFIED SOIL-TESTING LABORATORY STATING PERCENTAGES OF ORGANIC MATTER; GRADATION OF SAND, SILT, AND CLAY CONTENT; CATION EXCHANGE CAPACITY; SODIUM ABSORPTION RATIO; DELETERIOUS MATERIAL; BUFFER PH LEVELS; AND MINERAL AND PLANT-NUTRIENT CONTENT OF THE SOIL

A MINIMUM OF THREE REPRESENTATIVE SAMPLES SHALL BE TAKEN FROM VARIED LOCATIONS FOR EACH SOIL TO BE USED OR AMENDED FOR PLANTING PURPOSES.

LANDSCAPE CONTRACTOR SHALL SUBMIT TO LANDSCAPE ARCHITECT THE LAB RECOMMENDATIONS FOR SOIL TREATMENTS AND SOIL AMENDMENTS TO BE INCORPORATED, INDICATE LAB RECOMMENDATIONS IN WEIGHT PER 1000 SQ. FT. OR VOLUME PER CU. YD. FOR NITROGEN, PHOSPHORUS, AND POTASH NUTRIENTS AND ORGANIC AND INORGANIC SOIL AMENDMENTS TO BE ADDED TO PRODUCE PLANTING SOIL SUITABLE FOR HEALTHY, VIABLE PLANTS ALL SOILS USED FOR PLANTING SHALL BE PREPARED AS NECESSARY USING ORGANIC AND INORGANIC SOIL AMENDMENTS DEPTH VARIES. (SEE AND FERTILIZERS IN THE QUANTITIES RECOMMENDED IN THE SOIL ANALYSIS REPORT TO PRODUCE SATISFACTORY PLANTING SOIL FOR HEALTHY, VIABLE PLANTS, PLANTING SOILS SHALL HAVE A PH LEVEL BETWEEN 6.0 AND 7.0.

IN ALL PLANTING AREAS, SPREAD PLANTING SOIL TO A DEPTH OF 8 INCHES BUT NOT LESS THAN REQUIRED TO MEET FINISH GRADES AFTER NATURAL SETTLEMENT.

LANDSCAPE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS OF PROPOSED IRRIGATION SYSTEM TO LANDSCAPE ARCHITECT AND OWNER FOR ACCEPTANCE. LANDSCAPE CONTRACTOR TO SUPPLY AUTOMATIC IRRIGATION SYSTEMS, COMPLETE AND INSTALLED. SYSTEM TO INCLUDE ALL VALVES, PIPES, HEADS, FITTINGS, RAIN SENSOR, AND CLOCK AND TO PROVIDE 100% HEAD TO HEAD COVERAGE OF ALL NEW SODDED AND IMPROVED EXISTING GRASS AREAS, TREES, SHRUBS AND PLANTING BEDS. COORDINATE IRRIGATION WITH OWNER'S REPRESENTATIVE.

LANDSCAPE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FOR AUTOMATIC IRRIGATION SYSTEMS. LANDSCAPE CONTRACTOR SHALL PROVIDE ELECTRIC METER. BACKFLOW PREVENTER AND SERVICE IN ACCORDANCE WITH STATE AND LOCAL CODES FOR IRRIGATION SYSTEM. LOCATION OF METERS AND CONTROL PANELS FOR IRRIGATION SHALL BE APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION. COORDINATE WATER METER REQUIREMENTS WITH CIVIL ENGINEER.

LANDSCAPE CONTRACTOR TO PROVIDE DRIP IRRIGATION TO ALL ABOVE GROUND PLANTERS. IRRIGATION LINE TO BE INSTALLED BENEATH ADJACENT HARDSCAPE AS NECESSARY. IRRIGATION PIPING, SPRINKLERS, AND OTHER EQUIPMENT MAY BE SHOWN OUTSIDE OF LANDSCAPE AREAS ON DRAWING

FOR GRAPHIC CLARITY. ALL VALVE BOXES AND EQUIPMENT VAULTS SHALL BE LOCATED IN MULCH BEDS. NO IRRIGATION COMPONENTS, INCLUDING BUT NOT LIMITED TO, VALVE BOXES, CONTROL BOXES, BACKFLOW PREVENTERS, AND/OR RAIN SENSORS ARE ALLOWED TO BE INSTALLED WITHIN DEPARTMENT OF TRANSPORTATION

PLANT SCHEDULE NOTES

THE TECHNICAL SPECIFICATIONS ARE MADE A PART OF THESE PLANS AND SHALL BE CONSULTED BY THE LANDSCAPE CONTRACTOR. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING WORK AS SPECIFIED IN THE TECHNICAL SPECIFICATIONS AND ON THESE PLANS. THE LANDSCAPE CONTRACTOR SHALL NOTIFY THIS OFFICE OF ANY DISCREPANCIES PRIOR TO BEGINNING OR CONTINUING

THERE WILL BE NO SUBSTITUTIONS, DELETIONS OR ADDITIONS WITHOUT APPROVAL OF THIS OFFICE. SIZE OF PLANT MATERIALS SHALL CONFORM WITH THE CURRENT EDITION OF 'AMERICAN STANDARD FOR NURSERY STOCK' FOR NUMBER ONE GRADE NURSERY STOCK AS ADOPTED BY THE AMERICAN ASSOCIATION OF NURSERYMEN AND AMERICAN NATIONAL STANDARDS INSTITUTE.

GAL = GALLON CONTAINER

MS = MULTI-STEMMED TRUNK

HC = HURRICANE CUT

OC = ON-CENTER

RF = REFOLIATED

TYP = TYPICAL

SP = SPECIMEN MATERIAL


TF = TREE FORM HABIT

THE QUANTITIES ON THE SCHEDULE ARE ONLY A GUIDE. ALL QUANTITIES SHALL BE VERIFIED BY THE LANDSCAPE CONTRACTOR ON THE PLANTING PLAN.

B&B = BALLED & BURLAPPED

BR = BARE ROOT MATERIAL ESP = ESPALIER FTG = FULL TO GROUND CAL = TRUNK CALIPER (MIN) CON = CONTAINERIZED MATERIAL FWF = FULL WELL FORMED

Landscape Notes SCALE: NOT TO SCALE




1. SEE LANDSCAPE NOTES AND SPECIFICATIONS FOR FURTHER REQUIREMENTS RELATED TO THIS DETAIL.

2. EXCAVATE TRENCH BY HAND WITH SPADE.

CT = CLEAR TRUNK


3. ADD EXCESS SOIL TO ADJACENT PLANT BED AFTER PULLING BACK EXISTING MULCH. RAKE SOIL AND SMOOTH BEFORE MULCHING.

Lawn Edge Detail SCALE: NOT TO SCALE




1. SEE LANDSCAPE NOTES AND SPECIFICATIONS FOR FURTHER REQUIREMENTS RELATED TO THIS DETAIL

Tree in Poorly Drained Soil
SCALE: NOT TO SCALE



SEE LANDSCAPE NOTES AND SPECIFICATIONS FOR FURTHER REQUIREMENTS RELATED TO THIS DETAIL.

4 Shrub Planting - Modified Soil SCALE: NOT TO SCALE



SEE LANDSCAPE NOTES AND SPECIFICATIONS FOR FURTHER REQUIREMENTS RELATED TO THIS DETAIL. 2. SEE PLANT SCHEDULE FOR PLANT SPECIES, SIZE, AND SPACING DIMENSION.

3. SMALL ROOTS (1/2" OR LESS) THAT GROW AROUND, UP, OR DOWN THE ROOT BALL PERIPHERY ARE CONSIDERED A NORMAL CONDITION IN CONTAINER PRODUCTION AND ARE ACCEPTABLE HOWEVER THEY SHOULD BE ELIMINATED AT THE TIME OF PLANTING. ROOTS ON THE PERIPHERY CAN BE REMOVED AT THE TIME OF PLANTING.

4. THOROUGHLY TILL IN PLANTING SOIL MIXTURE AMENDMENTS TO DEPTH OF 8" IN ENTIRE GROUNDCOVER BED AREA. WORK SOIL TO LOOSE, UNIFORMLY FINE TEXTURE. 5. CONTRACTOR IS RESPONSIBLE FOR PROVIDING DRAINAGE FROM PLANTING HOLE/BEDS IF COMPACTED SOILS OR POORLY DRAINED SOIL IS ENCOUNTERED.

6. HAND-TAMP BACKFILL TO REMOVE VOIDS AND AIR POCKETS. WATER IMMEDIATELY AFTER PLANTING UNTIL NO MORE WATER IS ABSORBED.

Groundcover / Ornamental Grass Planting Detail SCALE: NOT TO SCALE



MANUFACTURER	BELSON OUTDOORS
PRODUCT	CBPB-6SB-BK
WEBSITE	BELSON.COM
MATERIAL	STEEL
COLOR	BLACK
FINISH	RIVER
MOUNTING	SURFACE MOUNT
REMARKS	INSTALL PER MANUFACTUREF SPECIFICATIONS
QUANTITY	1

SCALE: NOT TO SCALE



MANUFACTURER	BELSON OUTDOORS
PRODUCT	TF1953
WEBSITE	BELSON.COM
MATERIAL	PLASTIC
COLOR	CHARCOAL
FINISH	N/A
MOUNTING	N/A
REMARKS	ONE RECEPTACLE WILL HAVE RECYCLING DECAL AND THE OTHER WILL HAVE TRASH DECAL
QUANTITY	2

Trash And Recycling Receptacles

SCALE: NOT TO SCALE

SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	HEIGHT	SPREAD	SPACING	REMARK S
TREES								
(o	ACRO	3	ACER RUBRUM 'OCTOBER GLORY' TM / OCTOBER GLORY MAPLE	2.5" CAL	8` MIN	4`-6`	AS SHOWN	FWF, SP
	QUEP	4	QUERCUS PALUSTRIS / PIN OAK	2.5" CAL	8` MIN	4`-6`	AS SHOWN	FWF, SP
SHRUBS	<u>'</u>	•		•	•	•	•	•
$\langle \cdot \rangle$	AZAF	22	AZALEA INDICA `FORMOSA` / FORMOSA AZALEA	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
) + }	ILCB	30	ILEX CORNUTA 'BURFORDII NANA' / DWARF BURFORD HOLLY	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
GRASSES								
+	MUHL	54	MUHLENBERGIA FILIPES / SWEETGRASS	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
ROUND C	OVERS							
	LMBB	422	LIRIOPE MUSCARI 'BIG BLUE' / BIG BLUE LILYTURF	4" POT	8"-12"	8"-12"	24"	FWF, SP
PLANT SCHE	EDULE PERI	METER PLAN	TING					
SYMBOL	CODE C	QTY BOTA	NICAL / COMMON NAME	SIZE	HEIGHT	SPREAD	SPACING	REMARKS
SHRUBS					T		T	
• •	ABES 3	3 ABELI	A X GRANDIFLORA `SHERWOODII` / DWARF ABELIA	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
ራ . ኔ		I		_	1	1	1	1


{+} | LCRR | 27 | LOROPETALUM CHINENSE RUBRUM `RUBY` / DWARF RUBY FRINGE FLOWER | 3 GAL | 18"-24" | 18"-24" | AS SHOWN | FWF, SP

SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	HEIGHT	SPREAD	SPACING	REMARKS
TREES								
0	ACRO	3	ACER RUBRUM `OCTOBER GLORY` TM / OCTOBER GLORY MAPLE	2.5" CAL	8' MIN	4`-6`	AS SHOWN	FWF, SP
$\overline{\bigcirc}$	QUEP	6	QUERCUS PALUSTRIS / PIN OAK	2.5" CAL	8, WIN	4`-6`	AS SHOWN	FWF, SP
UNDERSTOR	Y TREES	•			•			•
+	CERO	2	CERCIS CANADENSIS 'OKLAHOMA' / OKLAHOMA REDBUD	1.5" CAL	8, WIN	8,	AS SHOWN	FWF, SP
S. O. S.	CHIV	7	CHIONANTHUS VIRGINICUS / WHITE FRINGETREE	1.5" CAL	8' MIN	8,	AS SHOWN	FWF, SP
	MAGS	5	MAGNOLIA X SOULANGIANA / SAUCER MAGNOLIA	1.5" CAL	8' MIN	8,	AS SHOWN	MS, FWF, S
SHRUBS	_	_			_			_
•	ABES	33	ABELIA X GRANDIFLORA `SHERWOODII` / DWARF ABELIA	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
	AZAF	22	AZALEA INDICA `FORMOSA` / FORMOSA AZALEA	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
7,4	ILCB	30	ILEX CORNUTA 'BURFORDII NANA' / DWARF BURFORD HOLLY	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
(+)	LCRR	27	LOROPETALUM CHINENSE RUBRUM 'RUBY' / DWARF RUBY FRINGE FLOWER	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
GRASSES	_							
+	MUHL	54	MUHLENBERGIA FILIPES / SWEETGRASS	3 GAL	18"-24"	18"-24"	AS SHOWN	FWF, SP
GROUND CO	VERS	•	•	•	•	•	•	•
		422	LIRIOPE MUSCARI 'BIG BLUE' / BIG BLUE LILYTURF	4" POT	8"-12"	8"-12"	24"	FWF, SP
SOD/SEED	_	_						_
	SOD2	26,904 SF	CYNODON DACTYLON 'TIFTUF' / TIFTUF BERMUDA GRASS	SOD	N/A	N/A	N/A	SP

Plant Schedule (6) SCALE: NOT TO SCALE

MOUNT PLEASANT, SC

843.884.1667 GREENVILLE, SC 864.298.0534 SUMMERVILLE, SC 843.972.0710 SPARTANBURG, SC 864.272.1272 CHARLOTTE, NC 980.312.5450 WWW.SEAMONWHITESIDE.COM





SW+ PROJECT: 12/22/23 DRAWN BY: CHECKED BY:

REVISION HISTORY

PLANT SCHEDULE & DETAILS & NOTES